


NorthRiver Midstream Inc.



**Non-Confidential**

# Emergency Response Plan

April, 2023



24-Hour Emergency Number  
1-844-667-8477

---

BCER Emergency Number  
1-800-663-3456

---

AER Emergency Number  
1-800-222-6514



**CORE  
EMERGENCY RESPONSE PLAN**

**Prepared by:**

**BLACK GOLD** Emergency  
Planners Inc.

**April, 2023**

**EMERGENCY RESPONSE PLAN  
MANUAL RECEIPT FORM**

Upon receipt of this Emergency Response Plan Manual, this Receipt Form must be completed and returned to the Supervisor, Emergency Management & Security in the Corporate Office. The Manual holder is responsible for ensuring that the Manual is kept current by inserting the latest revisions as they are issued.

**Recipient Name (please print):** \_\_\_\_\_

**Position:** \_\_\_\_\_

**Field Area Name, if applicable:** \_\_\_\_\_

**Date:** \_\_\_\_\_

**Signed:** \_\_\_\_\_

**ERP Number (from Distribution List):** \_\_\_\_\_

**Name of ERP:** \_\_\_\_\_

**Return signed copy to:** NorthRiver Midstream Inc.  
1400, 888 - 3rd St. SW  
Calgary, AB T2P 5C5

Phone: 587-747-6500

**Attention:**



**MANAGEMENT OF CHANGE REQUEST FORM****NorthRiver Midstream Inc.**Attn: [REDACTED]  
[REDACTED]  
[REDACTED]

Section Number: \_\_\_\_\_

Page Number: \_\_\_\_\_

Copies of revised pages attached:  yes  no

Description of Amendment:

---

---

---

---

---

---

---

---

---

---

Requested By: \_\_\_\_\_

Address: \_\_\_\_\_

---

---

Request Acknowledgement: \_\_\_\_\_

Request Numbered and Logged: \_\_\_\_\_

Correspondence Required: \_\_\_\_\_

Approved By: \_\_\_\_\_

Approval Date: \_\_\_\_\_

Revision Date: \_\_\_\_\_

Issue Date: \_\_\_\_\_

**MANAGEMENT OF CHANGE LOG**
**Annual Review Date: April 2023**
**Annual Update Due: April 2024**

Date Completed (DD/MM/YYYY)	Revision #	Section(s) Updated	Description	Revision <sup>1</sup>	Annual Update <sup>2</sup>	Date Inserted into ERP: DD/MM/YYYY	Signature
30/04/2023	New	All	New ERP Document	<input type="checkbox"/>	<input checked="" type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		

<sup>1</sup> **Revision:** An interim revision to the ERP when significant changes occur to Company personnel or infrastructure (drilling, facilities, pipelines). A revision does not replace the requirement for an annual update.

<sup>2</sup> **Annual Update:** A comprehensive update to all sections of the ERP. The entire document is reviewed and updated to ensure current distribution list, emergency telephone list, roles and responsibilities, mutual aid agreements, response agencies information, government support information, asset tables, safety equipment, and maps. In a Registered Site-Specific ERP, the stakeholder database is also verified, a hazard assessment is conducted, and area user contact information is updated.

---

**DISCLAIMER**

The Emergency Response Plan has been designed to provide a series of guidelines for responding to emergency situations. This plan identifies, defines and recommends actions for dealing with incidents that could impact facilities within the plan. This plan provides a logical and responsible approach to classifying and responding to incidents.

Verification of the information contained in this plan is the sole responsibility of NorthRiver. Black Gold Emergency Planners Inc. does not accept any liability arising from the implementation or use of this plan. The Emergency Response Plan must be available on site. Unauthorized reproduction is strictly prohibited.

This plan is administered by:



B5, 6020 – 2nd Street SE  
Phillips Park  
Calgary, AB T2H 2L8

Office: 403-216-7052  
Fax: 403-216-7053

**TABLE OF CONTENTS**

<b>TABLE OF CONTENTS .....</b>	<b>i</b>
<b>DISTRIBUTION LIST .....</b>	<b>1</b>
<b>1.0 EOC TELEPHONE LIST / ROLE ASSIGNMENT .....</b>	<b>1</b>
1.1 Corporate Contact List.....	1
<b>2.0 INTRODUCTION.....</b>	<b>1</b>
2.1 8 Step Initial Response Strategy .....	1
2.2 Emergency Response Plan Activation .....	2
2.3 Understanding the Situation .....	5
2.3.1 PEAR Response Priorities and Objectives.....	6
2.4 ICS Guidelines.....	7
2.4.1 Span of Control .....	7
2.4.2 Unity and Chain of Command .....	9
2.4.3 Transfer of Command .....	10
2.4.4 Five Steps of Transfer of Command .....	10
2.5 Scope .....	11
2.6 Purpose .....	11
2.7 Authority to Activate the ERP .....	12
2.8 Program Administration .....	12
2.9 Maintenance Schedule .....	13
2.10 Training and Testing the ERP .....	14
2.10.1 Orientation.....	15
2.10.2 Tabletop Exercise.....	15
2.10.3 Communication Exercise.....	15
2.10.4 Functional Exercise .....	15
2.10.5 Major Exercise.....	15
2.10.6 Training Cycle .....	16
<b>3.0 SITE INCIDENT COMMAND STRUCTURE - ROLES AND RESPONSIBILITIES .....</b>	<b>1</b>
3.1 Site Command Chart .....	1
3.2 First Responder .....	2
3.3 Incident Commander .....	3
3.4 Deputy Incident Commander.....	6
3.5 Operations Section Chief.....	9
3.6 Public Protection Group Supervisor .....	11
3.6.1 Roadblock Team .....	13
3.6.2 Rover Evacuation Team.....	15
3.6.3 Air Quality Monitoring Team.....	17
3.6.4 Reception Team .....	19
3.6.5 Telephone Team .....	21
3.7 On-Site Group Supervisor .....	23
3.7.1 Fire Control Team .....	25
3.7.2 Isolation/Repair Team .....	26
3.7.3 Spill Response Team .....	27
3.7.4 Security Team .....	29
3.7.5 Ignition Team.....	30
3.8 Staging Area Manager.....	32
3.9 Safety Officer.....	33

3.10	Liaison Officer.....	35
3.11	Information Officer.....	36
3.11.1	Scribe.....	38
3.12	Planning Section Chief.....	39
3.13	Logistics Section Chief.....	40
3.14	Finance/Admin Section Chief.....	41
<b>4.0</b>	<b>EOC INCIDENT COMMAND STRUCTURE - ROLES AND RESPONSIBILITIES .....</b>	<b>1</b>
4.1	EOC Command Chart.....	1
4.2	EOC Director.....	2
4.3	Operations and Technology Support.....	3
4.4	Regulatory / Government Liaison.....	5
4.5	Communications / Media.....	6
4.6	Business Impact Support.....	8
4.7	Admin Support.....	9
4.8	EHSS Support.....	10
<b>5.0</b>	<b>COMMAND CENTRES AND RESPONSE LOCATIONS.....</b>	<b>1</b>
5.1	On-Site Command Post (OSCP).....	1
5.2	Incident Command Post (ICP).....	1
5.3	Staging Area.....	1
5.4	Reception Centre.....	1
5.5	Helibase.....	2
5.6	Helispot.....	2
5.7	Emergency Operations Centre (EOC).....	2
5.7.1	Suggested Equipment and Supplies for the EOC.....	3
5.8	Government Command Posts.....	4
5.8.1	Regional Emergency Operations Centre (REOC).....	4
5.8.2	Municipal Emergency Operations Centre (MEOC).....	4
5.8.3	Government Emergency Operations Centre (GEOC).....	4
<b>6.0</b>	<b>CRISIS COMMUNICATION PLAN.....</b>	<b>1</b>
6.1	Purpose of the Crisis Communication Plan.....	2
6.2	Crisis Communication Policy.....	2
6.3	Crisis Communication Plan Objectives.....	2
6.4	Crisis Communication Audiences.....	2
6.5	Crisis Communication Process.....	2
6.5.1	24-Hour Emergency Number.....	2
6.5.2	Public Inquiry.....	3
6.5.3	Command Centre Communication Flow Diagram.....	4
6.6	Internal Communication and Command Centres.....	5
6.6.1	Internal Emergency Notification Flowchart.....	6
6.6.2	Communication at On-site Command Post.....	7
6.6.3	Communication at Incident Command Post.....	7
6.6.4	Communication at the Emergency Operations Centre (EOC).....	7
6.6.5	Communication with the Executives: President and Board of Directors.....	7
6.7	External Communication.....	8
6.7.1	External Notification Flow chart.....	8
6.7.2	Communication with Government/Regulatory.....	8
6.7.3	Communication with the Public.....	8
6.8	Media Communication.....	9

6.8.1	Media Crisis Communication Policy .....	9
6.8.2	Media Access to Emergency Site.....	10
6.8.3	Preliminary Holding Statement.....	10
6.8.4	General Guidelines.....	12
6.8.5	Media Release .....	14
6.8.6	Crisis Media Interview .....	14
6.8.7	News Conference Guidelines.....	15
6.8.8	Reporting.....	16
6.9	Social Media.....	16
6.10	Mutual Aid Agreements .....	16
6.11	Emergency Answering Procedures .....	17
6.11.1	General Evacuation Script.....	18
6.11.2	Shelter in Place Script .....	19
6.11.3	Urgent Evacuation Script.....	20
6.11.4	Notification Script .....	21
<b>7.0</b>	<b>RESPONSE ACTION PLANS .....</b>	<b>1</b>
7.1	Purpose .....	1
7.2	Incident Site Worker Protection .....	1
7.3	Personal Protective Equipment (PPE).....	1
7.4	Protection Levels .....	2
7.4.1	Levels of Responder Protection for Spill Response .....	2
7.5	Preparing a Health and Safety Plan .....	3
7.6	Health and Safety Plan.....	3
7.7	Public Safety and Protection .....	4
7.7.1	Public Notification Flowchart .....	5
7.8	Air Quality Monitoring .....	7
7.9	Determining the Response Zone Using Monitoring Equipment.....	7
7.9.1	Sour Gas Release from a Manned Operation .....	8
7.9.2	Sour Gas Release from an Unmanned Operation .....	8
7.10	Sour Gas Release .....	8
7.10.1	Sour Gas Release Site Safety.....	8
7.10.2	Safety of Response Operations .....	9
7.10.3	Action Plan Sour Gas Release.....	9
7.11	Sweet Gas (Hydrocarbon) Release.....	10
7.11.1	Flammability Limits.....	11
7.12	Hydrocarbon Exposure .....	11
7.12.1	Exposure to Heat Radiation (ignited hydrocarbon release).....	11
7.13	Entry Procedures into the EPZ .....	12
7.14	Roadblocks.....	12
7.14.1	Isolating the EPZ with Roadblocks.....	12
7.14.2	Suggested Roadblock Equipment .....	13
7.14.3	Setting up a Roadblock .....	13
7.15	Shelter in Place .....	18
7.15.1	General Shelter in Place Instructions .....	18
7.15.2	Post Shelter in Place Instructions.....	19
7.16	Liquids Release – Site/Facility.....	19
7.16.1	Liquid Release Site Safety .....	19
7.16.2	Action Plan for Liquids Release .....	19
7.17	Spill Contingency Plan.....	22

---

7.17.1	Spill Preparedness Risk Analysis	22
7.17.2	Seven Step Guideline for Spill Response	22
7.17.3	Company Spill Discovery and Response Actions	30
7.17.4	Spill Management Techniques	34
7.18	Electrical Incident Response	40
7.18.1	Methods of Contact Release for Electric Shock	40
7.18.2	Over Head Power Lines & Buried Cables	41
7.19	General Fire Response	41
7.19.1	Volunteer Fire Personnel	42
7.20	Facility Fires	42
7.20.1	Facility Fires Safety	42
7.20.2	Action Plan for Facility Fires	43
7.21	High Vapour Pressure (HVP) Release	45
7.21.1	HVP Product Release Monitoring	45
7.21.2	Ignition Considerations	45
7.21.3	Guideline for Igniting HVP Plume	46
7.22	Pressurized Fuel Fire	47
7.23	Propane or LPG Tank Fire	47
7.23.1	Boiling Liquid Expanding Vapour Explosion (BLEVE)	48
7.23.2	How big is the fireball from a Propane or LPG BLEVE?	48
7.23.3	Fire Fighting a BLEVE	50
7.24	Transportation Incident	50
7.24.1	Transportation Incident Safety	50
7.24.2	Action Plan for Transportation Incident	51
7.25	Product <i>Transportation</i> Incident	53
7.26	Hazardous Materials Incident	54
7.26.1	Hazardous Material Safety	54
7.26.2	Action Plan for Hazardous Material Incident	54
7.27	Injury/Fatality	56
7.27.1	Serious Injury/Fatality Safety	56
7.27.2	Action Plan for a Serious Injury/Fatality	56
7.27.3	Next of Kin Notification	60
7.28	Air Ambulance	60
7.28.1	Command and Control	60
7.28.2	Pre-Landing Checklist:	61
7.28.3	Landing Zone	61
7.28.4	Ground Operations	61
7.28.5	Loading and Unloading	61
7.28.6	Hazards and Special Situations	62
7.28.7	Approach Routes	62
7.29	Missing Worker	63
7.29.1	Response Plan for Missing Worker	63
7.30	Severe Weather Incidents	63
7.30.1	Severe Weather Safety	63
7.30.2	Wildfire	64
7.30.3	Tornadoes	65
7.30.4	Lightning	65
7.30.5	Floods	66
7.30.6	Seismicity	66
7.31	Wildlife	68

---

7.31.1	Wildlife Incidents and Mortalities .....	68
7.31.2	Wildlife Awareness .....	68
7.31.3	Working in wildlife habitat .....	68
7.31.4	Bears .....	68
7.31.5	Elk .....	70
7.31.6	Moose.....	70
7.32	Site Security .....	71
7.32.1	Safety .....	71
7.32.2	Response Plan for Site Security.....	71
7.33	Bomb Threat.....	72
7.33.1	Evaluating the Threat .....	72
7.33.2	Action Plan for Bomb Threat .....	72
7.33.3	Critical Event Decisions.....	72
7.33.4	Bomb Search Considerations.....	73
7.33.5	Bomb Search Procedures .....	73
7.33.6	Discovery of Suspect Device.....	73
7.33.7	No Suspected Devices Found.....	73
7.33.8	Explosion Occurrence .....	73
<b>8.0</b>	<b>POST EMERGENCY .....</b>	<b>1</b>
8.1	Overview.....	1
8.2	Responsibility .....	1
8.3	Critical Incident Stress Debriefing (CISD) .....	1
8.3.1	Key Reactions to Stress .....	2
8.4	Public Assistance and Support.....	2
8.5	Investigation .....	2
8.6	Clean Up and Repair .....	3
8.7	Post-Incident Notifications .....	3
8.8	Incident Documentation/Company Records .....	4
8.9	Post-Incident Debriefing and Incident Assessment .....	4
8.9.1	Session Guidelines.....	4
8.9.2	Site Response Team Debriefing Questions .....	5
8.9.3	EOC Team Debriefing Questions .....	6
8.10	Post-Incident Reports .....	8
8.11	Cause and Liability Report .....	9
8.12	Incident Investigations .....	9
8.12.1	Serious Injury/Fatality Investigations.....	10
8.12.2	Insurance Investigations.....	10
<b>9.0</b>	<b>JURISDICTIONAL REQUIREMENTS .....</b>	<b>11</b>
9.1	Spill & Release Reporting Requirements .....	12
9.2	ALBERTA .....	1
9.2.1	Assessment Matrix for Classifying Incidents .....	1
9.2.2	Notification Requirements for Key Government Agencies and Local Resources....	4
9.2.3	Spill Reporting .....	5
9.2.4	TDG Reporting – Alberta Environmental and Dangerous Goods Emergencies (EDGE) 6	
9.2.5	Flaring Reporting.....	8
9.2.6	Emergency Planning and Response Zones .....	9
9.2.7	Methods of Public Protection.....	10
9.2.8	Fire Hazard Order and NOTAM .....	16

9.2.9	Government Roles and Responsibilities .....	17
9.2.10	Alberta Pressure Equipment Incidents .....	25
9.2.11	Reporting Electrical Incidents .....	26
9.2.12	List of Abbreviations .....	26
<b>9.3</b>	<b>BRITISH COLUMBIA.....</b>	<b>1</b>
9.3.1	Incident Classification Matrix .....	1
9.3.2	Notification Requirements for Key Government Agencies and Local Resources....	8
9.3.3	Spill Reporting .....	9
9.3.4	Flaring .....	10
9.3.5	Emergency Planning and Response Zones .....	10
9.3.6	Methods of Public Protection.....	12
9.3.7	Drinking Water Emergency Contingency Plan .....	19
9.3.8	Closure Orders .....	21
9.3.9	Government Roles and Responsibilities .....	22
9.3.10	Technical Safety BC - Pressure Equipment .....	26
9.3.11	List of Abbreviations/Definitions .....	28
<b>9.4</b>	<b>CANADIAN FEDERAL GOVERNMENT.....</b>	<b>1</b>
9.4.1	Royal Canadian Mounted Police (RCMP) .....	1
9.4.2	Environment and Climate Change Canada .....	1
9.4.3	Department of Fisheries and Oceans (DFO).....	10
9.4.4	Public Safety Canada .....	10
9.4.5	Transport Canada – Transportation of Dangerous Goods .....	11
9.4.6	Transportation Safety Board .....	17
9.4.7	Health Canada .....	19
9.4.8	Public Health Agency of Canada.....	19
9.4.9	Indigenous Services Canada (ISC) .....	19
9.4.10	Indian Oil and Gas Canada .....	20
9.4.11	ERAC – A Not-For Profit Organization .....	21
<b>9.5</b>	<b>CANADA ENERGY REGULATOR .....</b>	<b>1</b>
9.5.1	Contact Information .....	2
9.5.2	Roles and Responsibilities .....	2
9.5.3	CER Definitions of Incident and Emergency .....	3
9.5.4	CER Event Reporting .....	4
9.5.5	Notifications and Preliminary Incident Reports.....	5
9.5.6	Detailed Incident Reports .....	6
9.5.7	Incident Costs.....	6
9.5.8	Published Manuals .....	7
<b>10.0</b>	<b>OPERATIONS .....</b>	<b>1</b>
10.1	Tupper Main Registered Supplement.....	1
10.1.1	Tupper Main Telephone Directory .....	2
10.1.2	Tupper Main Area Summary .....	7
10.1.3	Risk Assessment.....	9
10.1.4	Hazard Summary .....	13
10.1.5	Field Specific Response Actions .....	16
10.1.6	Command Centres .....	18
10.1.7	Equipment .....	19
10.1.8	Air Monitoring .....	22
10.1.9	Spill Support Services .....	23
10.1.10	Mutual Aid.....	27

10.1.11	Authority Roles Coordination .....	28
10.1.12	Public Summary.....	38
10.1.13	Stakeholder Data .....	45
10.1.14	Asset Data: Wells, Pipelines & Facilities .....	46
10.1.15	Maps .....	47
10.1.16	CEPA E2 Supplemental Plan .....	1
10.2	Tupper Main CER Regulated Pipeline.....	1
10.2.1	Contact Information .....	1
10.2.2	Tupper Main CER Telephone Directory .....	2
10.2.3	Area Summary .....	9
10.2.4	Public Summary .....	14
10.2.5	Risk Assessment.....	21
10.2.6	Spill Support Services .....	25
10.2.7	CER Regulated Assets.....	29
10.2.8	Supporting Information Table .....	29
10.2.9	Maps.....	29
10.3	Tupper West Registered Supplement .....	1
10.3.1	Tupper West Telephone Directory .....	2
10.3.2	Tupper West Area Summary .....	7
10.3.3	Risk Assessment.....	9
10.3.4	Hazard Summary .....	13
10.3.5	Field Specific Response Actions .....	17
10.3.6	Command Centres .....	19
10.3.7	Equipment .....	20
10.3.8	Air Monitoring .....	23
10.3.9	Spill Support Services .....	24
10.3.10	Mutual Aid.....	26
10.3.11	Authority Roles Coordination .....	27
10.3.12	Public Summary.....	33
10.3.13	Stakeholder Data .....	38
10.3.14	Asset Data: Wells, Pipelines & Facilities .....	39
10.3.15	Maps .....	40
<b>11.0</b>	<b>FORMS .....</b>	<b>42</b>
11.1	Initial emergency Response Forms .....	42
11.1.1	Form A1.....	42
11.2	Jurisdictional Forms.....	44
11.2.1	Alberta Forms.....	44
11.2.2	British Columbia Forms .....	10
11.3	ICS Forms .....	31
11.4	ERP Forms .....	55
11.5	Stakeholder Forms .....	63
11.6	Media Forms.....	67
<b>12.0</b>	<b>APPENDIX.....</b>	<b>1</b>
12.1	Properties of Hydrogen Sulphide (H <sub>2</sub> S).....	1
12.2	Properties of Sulphur Dioxide (SO <sub>2</sub> ).....	1
12.3	Legal Survey Description (LSD) Reference Tool (Alberta).....	2
12.4	National Topographic System (NTS) Reference Tool .....	3
12.5	HVP - Proposed EPZ Distances for Selected Diameters .....	4
12.6	Conversion Table .....	4

12.7	NATO Phonetic Alphabet .....	5
12.8	Glossary .....	5

**DISTRIBUTION LIST**

The following individuals will have a copy of this Emergency Response Plan for use as a reference document in the event of an emergency arising from Company operations.

**GOVERNMENT AGENCIES**

ERP Number	Name/Title	Agency	Core Plan	Registered Supplement	Partial	Field Name	ERP Type	Quick Ref
<b>Federal Government Agencies</b>								
GOV 01	Secretary of the Commission	Canada Energy Regulator	<input checked="" type="checkbox"/>	Confidential	<input type="checkbox"/>	Tupper Main / Tupper Main CER	Paper / Email	<input type="checkbox"/>
<b>BC Government Agencies</b>								
GOV 02	Public Protection & Safety Branch	BC Energy Regulator	<input checked="" type="checkbox"/>	Confidential	<input type="checkbox"/>	All	WEB / Paper	<input type="checkbox"/>
GOV 03	Manager, North East Regional Office	Emergency Management B.C.	<input checked="" type="checkbox"/>	Non-Confidential	<input type="checkbox"/>	All	Memory Stick	<input type="checkbox"/>
GOV 04	Protective Services Coordinator	Peace River Regional District (PRRD)	<input checked="" type="checkbox"/>	Non-Confidential	<input type="checkbox"/>	All	Email	<input type="checkbox"/>
GOV 05	Coordinator	Health Emergency Management BC, Northern Health	<input checked="" type="checkbox"/>	Non-Confidential	<input type="checkbox"/>	All	Email	<input type="checkbox"/>
<b>AB Government Agencies</b>								
GOV 06	ERP Department	Alberta Energy Regulator - Calgary	<input checked="" type="checkbox"/>	Confidential	<input checked="" type="checkbox"/>	Tupper Main / Tupper Main CER	Paper	<input type="checkbox"/>
GOV 07	Fire Chief	County of Grande Prairie No. 1	<input checked="" type="checkbox"/>	Non-Confidential	<input checked="" type="checkbox"/>	Tupper Main / Tupper Main CER	Memory Stick	<input type="checkbox"/>
GOV 08	Director, Environmental Public Health	Alberta Health Services - Zone 5 North	<input checked="" type="checkbox"/>	Non-Confidential	<input checked="" type="checkbox"/>	Tupper Main / Tupper Main CER	Email	<input type="checkbox"/>
GOV 09	NCO in Charge	RCMP - Beaverlodge	<input checked="" type="checkbox"/>	Non-Confidential	<input checked="" type="checkbox"/>	Tupper Main / Tupper Main CER	Memory Stick	<input type="checkbox"/>

**EOC COMMAND TEAM**

ERP Number	Name/Title	Company	Core Plan	Registered Supplement	Partial	Field Name	ERP Type	Quick Ref
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>

**SITE COMMAND TEAM**

ERP Number	Name/Title	Company	Core Plan	Registered Supplement	Partial	Field Name	ERP Type	Quick Ref
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	[REDACTED]	[REDACTED]	<input type="checkbox"/>
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	[REDACTED]	[REDACTED]	<input type="checkbox"/>
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	[REDACTED]	[REDACTED]	<input type="checkbox"/>
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	[REDACTED]	[REDACTED]	<input type="checkbox"/>
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	[REDACTED]	[REDACTED]	<input type="checkbox"/>

ERP Number	Name/Title	Company	Core Plan	Registered Supplement	Partial	Field Name	ERP Type	Quick Ref
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	[REDACTED]	[REDACTED]	<input type="checkbox"/>
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	[REDACTED]	[REDACTED]	<input type="checkbox"/>
[REDACTED]	[REDACTED]	[REDACTED]	<input type="checkbox"/>	[REDACTED]	<input type="checkbox"/>	[REDACTED]	[REDACTED]	<input type="checkbox"/>

**OTHER CONSULTANTS**

ERP Number	Name/Title	Company	Core Plan	Registered Supplement	Partial	Field Name	ERP Type	Quick Ref
N/A	Emergency Response Planner	Black Gold Emergency Planners Inc.	<input checked="" type="checkbox"/>	Confidential	<input type="checkbox"/>		WEB	<input type="checkbox"/>

**ERP Types**

Paper, WEB, Email, Memory Stick, CD, APP

**1.0 EOC TELEPHONE LIST / ROLE ASSIGNMENT**
**1.1 Corporate Contact List**

NorthRiver Midstream Inc.			
<b>Company Main Number</b> 587-747-6500			
<b>24-Hour Emergency Number</b> 1-844-667-8477			
Name	Position	Office	Cell
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

## 2.0 INTRODUCTION

### 2.1 8 Step Initial Response Strategy

Facility Incident	Pipeline Incident
When an incident occurs <b>at an operating facility</b> (gas plant, compressor station):	When a <b>call is received</b> that is reporting a gas leak, a sour gas odor, a vehicle accident (NRM or a 3rd party) an injury to NRM personnel, or a 3rd party, the Gas Controller should do the following
<b>1. Stop Work</b> <ul style="list-style-type: none"> <li>Make safe</li> <li>Secure the scene</li> </ul>	<b>1. Log the Call</b> <ul style="list-style-type: none"> <li>Keep an accurate log of the sequence of events</li> <li>Log the time the incident was reported to you</li> <li>Log the person(s) name and phone number that reported the incident</li> </ul>
<b>2. Alarm</b> <ul style="list-style-type: none"> <li>Sound the alarm</li> <li>Call for help</li> <li>Call 911</li> </ul>	<b>2. Get a Description</b> <ul style="list-style-type: none"> <li>Get an accurate description of the incident</li> <li>Get an accurate location of the incident</li> <li>Ascertain if NRM personnel are involved in the incident</li> </ul>
<b>3. Evacuate</b> <ul style="list-style-type: none"> <li>All non-essential personnel must evacuate to the muster point</li> </ul>	<b>3. Notify the Supervisor on Call</b> <ul style="list-style-type: none"> <li>Notify the Supervisor on call, or their designate of any details of the event</li> <li>Ensure all appropriate departments within NRM are notified of the event or incident as soon as possible, so the proper government and regulatory agencies can be notified in a reasonable period of time if necessary</li> </ul>
<b>4. Assess</b> <ul style="list-style-type: none"> <li>The on-site supervisors will take a head count</li> <li>Assess the hazards</li> <li>Assign roles – (search, rescue, first aid, transportation)</li> </ul>	<b>4. Dispatch Crew</b> <ul style="list-style-type: none"> <li>The supervisor for the area will dispatch a pipeline crew to investigate the event</li> </ul>
<b>5. Protect</b> <ul style="list-style-type: none"> <li>On site responders will don personal protective equipment</li> <li>Deploy site and public safety warning signs</li> <li>Non-essential personnel will be transported to a safe location</li> </ul>	<b>5. Assess and Report</b> <ul style="list-style-type: none"> <li>The crew will travel to the site to investigate and report back on their findings</li> <li>If the event is verified as an emergency, they will escalate to the Area Manager to activate the Emergency Response Plan</li> <li>ONE crew member will assume on scene <b>Incident Command Post</b> - until relieved.</li> </ul>
<b>6. Rescue</b> <ul style="list-style-type: none"> <li>Rescue team will search for, find and remove any casualties from the site to a safe location</li> </ul>	<b>6. Protect</b> <ul style="list-style-type: none"> <li>On site responders will don personal protective equipment</li> <li>Deploy site and public safety warning signs</li> <li>Non-essential personnel will be advised to move to a safe location</li> </ul>
<b>7. First Aid/Medical Aid</b> <ul style="list-style-type: none"> <li>Follow standard first aid protocols and coordinate transport of any casualties to medical aid.</li> <li>Provide information to Emergency Medical Services</li> </ul>	<b>7. Rescue/First Aid/Medical Aid</b> <ul style="list-style-type: none"> <li>Rescue team will search for, find and remove any casualties from the site to a safe location</li> <li>Follow standard first aid protocols and coordinate transport of any casualties to medical aid.</li> <li>Provide information to Emergency Medical Services</li> </ul>
<b>8. Escalate</b> <ul style="list-style-type: none"> <li>To area manager or director to determine the level of emergency.</li> <li>If this is a level 1 or 2 implement the Emergency Response Plan</li> </ul>	<b>8. Escalate</b> <ul style="list-style-type: none"> <li>To determine the level of emergency.</li> <li>If this is a level 1 or implement the Emergency Response Plan</li> </ul>

## 2.2 Emergency Response Plan Activation

The following outlines the steps to be followed when activating the ERP. This guide can be referred to for an understanding of the sequence of events and steps to be followed by responders. The details of how these steps are carried out can be found throughout the ERP document per the table of contents.

### Step 1 – Determine Level of Emergency

Area Supervisor/Manager is notified via phone of an incident. They will then determine the level of emergency.

If level 2 or 3 they will activate the emergency response plan.

- Alert / Minor
- Level 1 Emergency
- Level 2 Emergency
- Level 3 Emergency


Use the following resources:

- Section 9.1.1: AER Assessment Matrix - (Level of Emergency)
- Section 9.2.1: BCER Incident Classification Matrix - (Level of Emergency)

*Note: The BCER and the AER state that the licensee must use either the Incident Classification Matrix (BC) or the Assessment Matrix for Classifying Incidents (AB) to determine the Level of Emergency. If the incident overlaps more than one level, always choose the highest level.*

### Step 2 – Stand Up Incident Command System

- Supervisor assumes Incident Commander Role (IC)
- Assign Safety Officer (SO)
- Assign Liaison Officer (LO) – External Notification
- Assign Information Officer (IO)
- Determine if other roles are needed to establish the field response team – Consider site and scale
  - Deputy Incident Commander for large scale
  - Operations Section Chief
    - On-Site Group Supervisor
    - Public Safety Group Supervisor – (if the incident impacts the public)
  - Planning Section Chief
  - Logistics Section Chief
  - Finance, Admin Section Chief



### Step 3 – Internal Notification – IC to call/Emails Area Director and Director HSE

- Follow the Internal Emergency Notification Flowchart in Section 6.6.1 to determine who needs to be notified.
- Relay the information in the completed A1 Initial Emergency Report Form.
- Mobilize internal resources to the site, to the Incident Command Post (ICP), to the Emergency Operations Centre (EOC), or place them on standby as required.
- Area Directors will escalate to Senior Leadership Team and active the Emergency Operations Center (Fort St John or Dawson Creek with support from Calgary)
- Area Director or designate will assume EOC Director Role and support the IC

Use the following resources:

- Section 1: Initial Response EOC Telephone list
- Section 10: Initial Response Field Operations Telephone Directory
- Sections 3 & 4: Site and EOC Command Structure - Roles & Responsibilities
- Section 11: Forms (A1)

**Step 4 – External Notification – Liaison Officer**

- Follow the External Emergency Notification Flowchart in Section 6.7.1 to determine which external agencies need to be notified
- Regulatory agency to confirm the Level of Emergency
- 911 (Police, Fire, Ambulance)
- Health Authority/Health Services
- Local Authority (Cities, Towns, Villages, Counties, M.D.s, R.D.s, R.M.s, Special Areas, Reserves, etc.)
- Air Monitoring (at all levels of emergency)

**Use the following resources:**

- Section 6: Crisis Communication Plan
- Section 10 - Area Specific Information

**Step 5 - Incident Briefing – Information Officer/Safety Officer**Complete an **ICS 201 Incident Briefing Form**:

- Define incident details and an operational period (page 1).
  - Establish the On-Site Command Post (OSCP) and ICP.
- Document current incident objectives, strategies, and tactics.
- Prioritize objectives.
- Define initial Incident Command Structure.
- Identify required resources and when they'll be available.
- Identify Hazards and develop safety plan

**Use the following resources:**

- Section 2: Initial Response (ICS 201)
- Section 11: Forms (ICS 201)

**Step 6 – Activate Public Safety Measures****6.1 Activate Public Protection Measures - (Operations Section Chief)**

- Determine the hazard area; start with Emergency Planning Zone (EPZ) as default.
- Identify the affected surface developments and area users. (Houses, businesses, guides/outfitters, trappers, schools, other oil and gas operators, etc.)
- Determine the appropriate public protection measure for the affected surface developments and area users. (Evacuation, shelter-in-place and/or ignition)
- Coordinate evacuation outside of the EPZ with the local authority, if required.
- Utilize broadcast media to notify public outside of the EPZ in immediate evacuation situations.

**Use the following resources:**

- Section 2: Initial Response (Public Protection Measures Flowchart)
- Section 7: Response Action Plans (Public Safety and Protection)
- Section 7.7.1: Public Notification Flowchart
- Section 10: Area Specific Information (Map / EPZ calculation tables)

**6.2 Dispatch Rovers (Public Safety Group Supervisor)**

- Dispatch Rovers to patrol the EPZ.
- Follow safety procedures and have appropriate PPE.
- Search the EPZ for transients.
- Assist residences that require evacuation assistance.
- Investigate surface developments that are identified as vacant or those who were unable to contact.
- Post notices on all outside doors of empty surface developments, vehicles, etc.
- Record all contacts, communications and monitoring readings using the following forms: **ICS 214, A5, B3 & B5**.
- Monitor and record air quality readings using the following forms: **ICS 214 & A5**. (Smoke, plumes, wind,

etc.)

- Provide status updates to the Public Safety Group Supervisor at established intervals.

Use the following resources:

- Section 3: Site ICS - Roles & Responsibilities (Rovers)
- Section 11: Forms
- Section 10: Area Specific Information (Map)

### 6.3 Establish Telephone Team – (Public Safety Group Supervisor)

- Establish a Telephone Team to notify residents to evacuate or shelter-in-place as required.
- Notify special needs residents at a Level 1 Emergency and provide the option to evacuate voluntarily.
- Follow-up phone calls to address resident inquiries.
- Record all phone calls and communications using the following forms: ICS 214, B3, B6, B7, & B8.
- Regularly provide status updates to the Public Safety Group Supervisor.

Use the following resources:

- Section 3: Site ICS - Roles & Responsibilities (Telephoners)
- Section 11: Forms

### 6.4 Establish Roadblocks (Public Safety Group Supervisor)

- Follow safety procedures to safely establish roadblocks wherever a road intersects with the EPZ and advise vehicles to reroute.
- Record all vehicle encounters and air monitoring readings. Complete the following forms: ICS 214, A5, B3 & B4.
- Gain permission from the Public Safety Group Supervisor for response vehicles to enter the hazard area.
- Provide status updates to the Public Safety Group Supervisor at established intervals.

Use the following resources:

- Section 3: Site ICS - Roles & Responsibilities (Roadblocks)
- Section 11: Forms
- Section 10: Area Specific Information (Map)

### 6.5 Dispatch Air Monitors (Public Safety Group Supervisor)

- Dispatch Air Monitoring personnel to the nearest residence / public facility downwind of the incident.
- Follow safety procedures and have appropriate PPE.
- Monitor and record air quality readings using the following forms: ICS 214 & A5. (Smoke, plumes, wind, etc.)
- Provide status updates to the Public Safety Group Supervisor at established intervals.

Use the following resources:

- Section 3: Site ICS - Roles & Responsibilities (Air Monitors)
- Section 11: Forms

**6.6 Establish Reception Center for Impacted Residents and Stakeholders (Public Safety Group Supervisor)**

- If residents are evacuated, dispatch a Reception Centre Representative to the reception center location.
- Meet and register evacuated residents.
- Record contact information for those who choose to stay elsewhere. Complete the following forms: ICS 214, B1, B2 & C2.
- Regularly provide status updates to the Public Safety Group Supervisor (those who have arrived and those who have not yet arrived).

Use the following resources:

- Section 3: Site ICS - Roles & Responsibilities (Reception Centre Rep)
- Section 11: Forms

### 2.3 Understanding the Situation

The overarching priority of any emergency response is to manage the **People** aspects first, then the impact on the **Environment**, followed by protecting further company **Assets** within the vicinity of the event and protecting **Reputation** which would be based on potential social and financial impacts during the event.

The Incident Command Post (ICP) and the Emergency Operations Centre (EOC), as directed by the Incident Commander, will assess the situation using the following step.

Capture information relating to:

- Incident history and responses already taken
- Current response actions
- Response organizations that are activated

### 2.3.1 PEAR Response Priorities and Objectives


<b>P</b>	<b>PEOPLE</b> Preserve safety of human life, consider the safety of all people in the immediate area including your own.
	<input type="checkbox"/> Minimize impact of the incident on all personnel and local communities.
	<input type="checkbox"/> Ensure the safety and welfare of all responders.
	<input type="checkbox"/> Confirm status of employees and contractors.
	<input type="checkbox"/> Contact incident site to clarify field and headquarters responsibilities.
<b>E</b>	<b>ENVIRONMENT</b> Minimize adverse effects to the environment and property.
	<input type="checkbox"/> Conduct situation assessment of the incident.
	<input type="checkbox"/> Protect lives and the well-being of those people impacted by the environmental hazard.
	<input type="checkbox"/> Establish communications with the incident site response team(s).
	<input type="checkbox"/> Ensure the dispatch of appropriate equipment/personnel to control the environmental hazard.
	<input type="checkbox"/> Appoint technical and specialist assistance to eliminate/control environmental impacts.
	<input type="checkbox"/> Continually monitor control and containment.
	<input type="checkbox"/> Ensure compliance tracking for emissions levels, limits, or permit exceedances.
<input type="checkbox"/> Develop IAP in coordination with response team and agency/authority.	
<b>A</b>	<b>ASSETS</b> Protect Company's assets, stabilize the situation to prevent the event from worsening.
	<input type="checkbox"/> Determine potential impacts on other Company infrastructure.
	<input type="checkbox"/> Minimize impact of incident on Company assets and quickly restore normal business operations.
	<input type="checkbox"/> Evaluate and minimize impact on other Company assets.
	<input type="checkbox"/> Provide requested technical and legal assistance.
	<input type="checkbox"/> Assist in asset restoration and business recovery.
	<input type="checkbox"/> Protect the operational integrity of Company asset base.
	<input type="checkbox"/> Provide requested financial support.
<input type="checkbox"/> Establish communications with incident site response team(s).	
<b>R</b>	<b>REPUTATION</b> Minimize reputational and business impacts and maintain effective internal and external communications.
	<input type="checkbox"/> Determine lead position on assumption of incident responsibility.
	<input type="checkbox"/> Protect Company reputation.
	<input type="checkbox"/> Mitigate adverse publicity surrounding the incident to reduce impact to Company image.
	<input type="checkbox"/> Coordinate government interface.
	<input type="checkbox"/> Develop and implement communications plan.
	<input type="checkbox"/> Defend the reputation of our company with key external audiences.
	<input type="checkbox"/> Coordinate high level Company Management communications.
	<input type="checkbox"/> Coordinate discovery and litigation preparation.
	<input type="checkbox"/> Coordinate performance of incident investigation and reporting.
	<input type="checkbox"/> Establish key liaisons (e.g. media, investor relations).
<input type="checkbox"/> Monitor all type social media reporting on the emergency event (i.e. News agencies, social media, etc).	

## 2.4 ICS Guidelines


### 2.4.1 Span of Control

Span of Control is a term to describe how many resources can be directly managed by another person. Maintaining adequate Span of Control is very important and is most effective in a range from three to seven - a ratio of one to five reporting elements is recommended. If the number of reporting elements falls outside of these ranges, the expansion or consolidation of the organization is likely necessary.

This diagram shows effective Span of Control.




The following diagram shows Span of Control that is considered ineffective and possibly dangerous.



### Organization Flexibility

The Response Organization needs to be flexible and scalable where functions required to appropriately respond will determine the extent of the response organization. As needs arise or are reduced, the organization can easily adapt to the change. In the following diagram of a Response Organization only the named resources are currently active.




### 2.4.2 Unity and Chain of Command

Unity of Command means that every individual has a designated supervisor. There is a clear line of supervision.

Chain of Command means that there is a line of authority in the Response Organization with lower levels subordinate to, and connected to, higher levels. This achieves an orderly ranking of management positions in line of authority.

This diagram shows Unity and Chain of Command.



### Establishment and Transfer of Command

Command at an incident is initially established by the highest-ranking authority at the scene. Transfer of Command at an incident will take place for the following reasons:

- A more qualified person assumes control.
- The incident situation changes to where the authority is transferred to the jurisdictional authority because of legal requirement or good management sense.
- Normal turnover of personnel on long or extended incidents.

### Unified Command

Unified Command is a management process which allows all stakeholders who have jurisdictional or functional responsibility for the incident to jointly develop a common set of incident objectives and strategies.

This is accomplished without losing or giving up authority, responsibility or accountability.

Unified Command allows stakeholders who have legitimate responsibility at an incident to be part of the Incident Command function.

Under Unified Command the following always applies:

- The incident will function under a single, coordinated Incident Action Plan.
- One Operations Section Chief will have responsibility for implementing the Incident Action Plan.
- Only one On-Site Command Post will be established.

### 2.4.3 *Transfer of Command*

The process of moving the responsibility for incident command from one Incident Commander to another is called “transfer of command.”

During a command transfer, a role can be transferred during an incident for several reasons: as the incident grows a more qualified person may be required to take over as Incident Commander, or conversely where an incident reduces in size command can be passed down to free up highly qualified resources for other tasks. This can also occur when those involved in the ICP have exceeded a 12-hour day with no breaks and need to transfer command to other qualified individuals.

In the unlikely event of an incident larger, or more involved, than NorthRiver’s scope of management, there may be additional agencies involved, in which case incident control may be handed over to the most suitable commander.

### 2.4.4 *Five Steps of Transfer of Command*

There are five important steps in effectively assuming command of an incident in progress.

**Step 1:** The incoming Incident Commander should, if at all possible, personally perform an assessment of the incident situation with the existing Incident Commander.

**Step 2:** The incoming Incident Commander must be adequately briefed.

This briefing must be by the current Incident Commander and take place face-to-face if possible. The briefing must cover the following:

- Incident history (what has happened)
- Priorities and objectives
- Current plan
- Resource assignments
- Incident organization
- Resources ordered/needed
- Facilities established
- Status of communications
- Any constraints or limitations
- Incident potential
- Delegation of Authority

The ICS Form 201 is especially designed to assist in incident briefings. It is available in the Corporate ERP. It should be used whenever possible because it provides a written record of the incident as of the time prepared. The ICS Form 201 contains:

- Incident objectives.
- A place for a sketch map.
- Summary of current actions.
- Organizational framework.
- Resources summary.

The ICS 201 form is typically duplicated and distributed before the initial briefing of the Command and General Staff (or other responders, as appropriate). The following sections of the briefing form are provided to the Planning Section: "Map Sketch", "Current and Planned Actions, Strategies, and Tactics", "Current Organization", and "Resource Summary"

**Step 3:** After the incident briefing, the incoming Incident Commander should determine an appropriate time for transfer of command.

**Step 4:** At the appropriate time, notice of a change in incident command should be made to:

- Agency representatives.
- General Staff members (if designated).
- Command Staff members (if designated).
- All incident personnel.

**Step 5:** The incoming Incident Commander may give the outgoing Incident Commander another assignment on the incident. There are several advantages of this:

- The outgoing Incident Commander retains first-hand knowledge regarding the incident.
- This strategy allows the outgoing Incident Commander to observe the progress of the incident and to gain experience.

## 2.5 Scope

An emergency is any unexpected event that may result in a serious injury, loss of life, major property or environmental damage. This manual provides solutions to:

- Promote the safety of workers, responders, and the public.
- Promote the protection of the environment and reduce the magnitude of environmental impacts.
- Reduce the potential for destruction of goods and other property.
- Help responders quickly determine and initiate proper remedial actions.
- Reduce recovery times and costs.
- Make responders, industry, and the public more confident that emergencies will be properly managed.

Should communications fail, and the first responder is unable to make contact with a direct supervisor, the responder must be able and willing to take action to minimize the negative impact resulting from the incident. They should also know that they will be fully supported by their supervisors and the Company for whatever actions they deemed necessary to address the incident.

## 2.6 Purpose

Every ERP should be concise, well organized, and include enough detail to ensure quick access to critical information required during an emergency. Preparedness can shorten an initial period of confusion and reduce the impact of the emergency.

The ERP identifies common types of emergencies and helps personnel prepare an adequate response to the incident. These documents may include the following:

- **Core Plans** – These plans tend to be a more static document, with set processes, policies, and procedural authorities to activate plans, ICS structure, establishment of an emergency operations centres, corporate communications and information policies, ignition protocols, and processes for roadblocks, securing an incident site, preserving evidence, etc.
- Supplemental (field area)/Site Specific Plans
  - **Facilities, Fields, and Pipelines** – These supplemental (field area) plans are typically organized by operating area or when a large or unique facility

requires specialized training for an effective incident response. Supplemental (field area) ERPs generally contain site-specific information.

NorthRiver has no broadly available safety equipment and resources (i.e. equipment caches). For a list of all site-specific equipment and available resources please refer to the Supplemental (field area) /Site Specific ERP.

The emergency response community includes company personnel, local service providers, fire department, police, EMS, mutual aid responders, and other governmental agencies.

Serious emergencies can arise from many sources and can be difficult to manage. Emergency management incorporates prevention, preparedness, response, and recovery. It also involves a wide range of activities that prepare responders for incidents.

## 2.7 Authority to Activate the ERP

Any Employee or Contractor detecting an incident has the authority to activate and implement any part of the plan to prevent the emergency situation from escalating. An immediate notification process must be followed as part of the activation.

The Employee or Contractor detecting the incident has the responsibility to determine if the unplanned operational event has the potential to cause:

- A threat to worker or public health, and safety.
- Loss of property.
- A negative impact on the environment.
- A perception of risk by the public and neighbouring stakeholders.

If it is determined that there is an actual emergency situation (or the perception of an emergency by the public) the ERP must be activated, and appropriate response action taken to address the incident.

When the ERP is activated, it is of the utmost importance and urgency that the appropriate Company Personnel and government agencies are notified as outlined in this document.

## 2.8 Program Administration

The responsibility for maintaining this Emergency Response Plan (ERP) is as follows:

- The Supervisor, Emergency Management & Security is responsible for updating the company-wide sections of the manual. Any requests for revisions to these sections should be forwarded to the Supervisor, Emergency Management & Security for approval and implementation.
- The Supervisor, Emergency Management & Security is responsible for ensuring the ERP is reviewed by all personnel annually and immediately after any changes have been made to the manual.
- The appropriate field office is responsible for updating the Field Area Section of the manual and distributing to those on the distribution list.
- All manual recipients are responsible for ensuring that their assigned manuals are current.

Before any new or major modification to an existing facility is brought on-stream, relevant data will be added to the appropriate Field Area Section. It is the responsibility of the Supervisor, Emergency Management & Security to ensure that this data is included. Company personnel and contractors will attend ERP review meetings before major facility modifications are commissioned.

**2.9 Maintenance Schedule**

<b>Core Revisions</b>	<b>Semi-Annually</b>	<b>Annually</b>	<b>Every 2 Years</b>	<b>Every 3 Years</b>
Distribution List	X			
Emergency Telephone List	X			
ERP Roles and Responsibilities	X			
Mutual Aid Agreements, if applicable	X			
Response Agencies and Government Support	X			
<b>Non-Regulated Field Area</b>	<b>Semi-Annually</b>	<b>Annually</b>	<b>Every 2 Years</b>	<b>Every 3 Years</b>
Asset Tables		X		
Safety Equipment		X		
Map		X		
Orientation and Tabletop Training except in a year when a major exercise is held		X		
<b>Registered Site Specific</b>	<b>Semi-Annually</b>	<b>Annually</b>	<b>Every 2 Years</b>	<b>Every 3 Years</b>
Stakeholder Consultation - personal visit			X	
Stakeholder database verification - except in a year when a personal visit is completed		X		
Hazard Assessments		X		
Area users contact information		X		
Major Exercise Training				X

## 2.10 Training and Testing the ERP

Emergency response training is a required and regulated activity where NorthRiver personnel are to demonstrate that they are able to take action, solve problems, and make decisions in a team structure as if they are responding to a real emergency. The training should contain an appropriate balance between theoretical and practical hands on content and it should be structured so that each new skill builds upon those previously acquired.

Simulated emergency response exercises, such as a tabletop exercise, are essential in developing, maintaining and improving Emergency Response Plan programs. Exercises are particularly important for training and evaluating roles and responsibilities during an emergency. Testing or exercising enables critical aspects of the Emergency Response Plan to be examined in a structured way, simulating conditions to reveal mistakes and omissions so that they can be subsequently corrected without consequences.

The exercise scenario created must reflect a credible type of event for the location. When designing an exercise, the facilitator should ensure that the scenario reinforces any previous training, is simple enough that available resources are adequate and difficult enough to be challenging. The goal of the training is to provide maximum lessons learned and include a post-exercise evaluation with corrective actions.

An appropriate exercise design process is composed of four main steps:

- Planning the exercise.
- Holding the exercise.
- Evaluating the outcomes.
- Reporting on the outcomes.

The training should be designed to ensure that the following objectives are met:

- Appropriate assignment of personnel to fill the roles required to manage an efficient response.
- Effective communication amongst response personnel, agencies and support organizations.
- Accurate determination of the level of emergency.
- Worker and public safety considerations.
- Effective source control and incident mitigation.
- Coordinated and efficient response activities.
- Identification of gaps in the ERP and recommend changes to the document.
- Identification of additional training that may be required.

The Company will undertake training sessions on a regular basis for fulfilling functions defined in its ERP in accordance with CAN/CSA Z-731 and CSA Z-246 to ensure that responsible personnel retain competency in emergency response procedures. Personnel will be trained and capable of carrying out their responsibilities at all times. The Company will accomplish this by providing training sessions and response exercises.

---

**The various types of Emergency Response Plan Training are as follows:****2.10.1 Orientation**

Orientation training is designed to familiarize team members with emergency response, business continuity and crisis communications plans. Orientation of newcomers to emergency response operations can be completed without the demands of a Tabletop Exercise or Major Exercise.

**2.10.2 Tabletop Exercise**

As described in CAN/CSA-Z-731 and CSA Z-246, an informal exercise generally used to review resource allocations and roles and responsibilities of personnel and to familiarize personnel with emergency operations.

Tabletop exercises are discussion-based sessions where team members meet in an informal, classroom setting to discuss their roles during an emergency and their responses to a particular emergency situation. A facilitator guides participants through a discussion of one or more scenarios. The duration of a tabletop exercise depends on the audience, the topic being exercised, and the exercise objectives. Many tabletop exercises can be conducted in a few hours, so they are cost-effective tools to validate plans and capabilities.

**2.10.3 Communication Exercise**

These exercises are considered expanded tabletop exercises and focus on the internal and/or external communication required during an incident. The scope of these exercises can vary greatly and may include public protection radio communication, internal telephone communication, as well as external agency communication.

**2.10.4 Functional Exercise**

Functional exercises allow personnel to validate plans and readiness by performing their duties in a simulated operational environment. Functional exercises are designed to exercise specific team members, procedures, and resources (e.g. communications, warning, notifications and equipment set-up) but they do not typically include outside agencies or stakeholders.


**2.10.5 Major Exercise**

As described in CAN/CSA-Z731 and CSA Z-246, an exercise involving emergency response agencies and the licensee that entails the deployment of all resources required to test the licensee's ERP. It is intended to provide a realistic simulation of an emergency response.

A Major Exercise is as close to the real thing as possible. It takes place on location using the equipment and personnel that would be called upon in a real event. Major exercises are conducted in conjunction with public agencies and regulatory authorities. They often include participation from local stakeholders.


The licensee must notify the appropriate Regulatory Authority 30 days in advance of a scheduled exercise and invite the local authority or any other government department or agency to participate and/or observe at Major Exercises.

2.10.6 Training Cycle



### 3.0 SITE INCIDENT COMMAND STRUCTURE - ROLES AND RESPONSIBILITIES

#### 3.1 Site Command Chart



### 3.2 First Responder

The First Responder is the first person at the incident location. If properly trained and qualified, the First Responder will be responsible for the following checklist.

Location	On-Site
<b>Evacuate (Protect yourself)</b>	<input type="checkbox"/> Remain calm. <input type="checkbox"/> Get to a safe area away from the hazard. <input type="checkbox"/> Direct others to a safe area.
<b>Sound the Alarm</b>	<input type="checkbox"/> Alert other personnel on-site. <input type="checkbox"/> Call for help (your supervisor or control room, as appropriate). <input type="checkbox"/> Activate mutual aid and emergency services, as required.
<b>Assess Incident</b>	<input type="checkbox"/> Resist the urge to rush in, others cannot be helped if you are injured. <input type="checkbox"/> Gather at muster stations and conduct a head count. <input type="checkbox"/> Consider wind direction. <input type="checkbox"/> Identify exposure to environments that may be toxic, flammable, explosive, or otherwise harmful. <input type="checkbox"/> Ensure personnel understand hazards and control actions.
<b>Protect</b>	<input type="checkbox"/> Assume on-site ICS duties until relieved, refer to Incident Commander checklist. <input type="checkbox"/> Take action to shutdown, isolate, control, or contain incident. <input type="checkbox"/> Don personal protective equipment. <input type="checkbox"/> Control entry into hazardous area. <input type="checkbox"/> Secure the area. <input type="checkbox"/> Release non-essential on-site personnel.
<b>Rescue Operations</b>	Only if safe to do so: <input type="checkbox"/> Rescue victim to safe area.
<b>Medical Aid</b>	<input type="checkbox"/> Revive victim. <input type="checkbox"/> Administer first aid, maintain ongoing care and confirm emergency services have been dispatched.
<b>Continue Response</b>	<input type="checkbox"/> Continue to implement ICS response actions.

Forms	
<input type="checkbox"/>	ICS 214 – Activity Log

### 3.3 Incident Commander

The Incident Commander assumes responsibility for the implementation and management of emergency response procedures at the incident site. Even if other functions are not filled, an Incident Commander will always be designated.

The Incident Commander role should be assigned to the most experienced company supervisor or representative near the incident site. The Incident Commander has the responsibility to establish the Incident Command Post and manage the implementation of a safe and effective tactical response.

The Incident Commander is responsible for all response functions until he/she delegates those response activities.

INCIDENT COMMANDER	
<b>Location</b>	
<input type="checkbox"/>	Incident Command Post.
<b>Confers With</b>	
<input type="checkbox"/>	EOC Operations and Technical Support
<b>Gives Direction To</b>	
<input type="checkbox"/>	Operations Section Chief.
<input type="checkbox"/>	Planning Section Chief.
<input type="checkbox"/>	Logistics Section Chief.
<input type="checkbox"/>	Finance/Admin Section Chief.
<input type="checkbox"/>	Safety Officer.
<input type="checkbox"/>	Liaison Officer.
<input type="checkbox"/>	Information Officer (Scribe).
<b>Situation Assessment</b>	
<input type="checkbox"/>	Consider evacuating non-essential personnel to safety and place them on standby to fill public protection roles.
<input type="checkbox"/>	Dispatch trained and appropriately equipped personnel (preferably in pairs) to investigate.
<input type="checkbox"/>	If the situation assessment confirms that company assets are involved, activate the ERP and establish Incident Command.
<input type="checkbox"/>	If the incident involves another company's asset, ensure that their personnel are notified. Maintain contact with the responsible operating company until they arrive on scene.
<input type="checkbox"/>	Contact the person who reported the incident and advise them of the result of the situation assessment.
<input type="checkbox"/>	Notify appropriate company personnel.
<input type="checkbox"/>	Assess the situation using the appropriate matrix for classifying incidents.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Develop an initial response strategy that adheres to the PEAR emergency response priorities. These response priorities are protecting people, environment, assets and reputation.
<input type="checkbox"/>	Establish method of communications with EOC Operations and Technical Support.
<input type="checkbox"/>	Schedule regular briefings with EOC Operations and Technical Support.
<input type="checkbox"/>	Evaluate resource requirements and advise EOC Operations and Technical Support.
<input type="checkbox"/>	For an incident that is not impacting public safety, consider public notification as a courtesy.
<input type="checkbox"/>	Ensure Regulatory Authority notification according to the applicable requirements.
<input type="checkbox"/>	Refer to the Notification Requirements for Key Government Agencies and Resources in the Jurisdictional section of this document.
<b>Level 1</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Determine the Operational Period.
<input type="checkbox"/>	Complete the ICS 201 – Incident Briefing Form.
<input type="checkbox"/>	Facilitate Objectives Meeting with Section Chiefs. Determine the objectives for the incident and communicate them between activated command posts.

INCIDENT COMMANDER

### INCIDENT COMMANDER

**INCIDENT COMMANDER**

<input type="checkbox"/>	Facilitate Command and General Staff Meeting, as required. Identify safety hazards and immediate safety actions to be taken to protect against the hazards.
<input type="checkbox"/>	Request resources, personnel and equipment to address emergency situation.
<input type="checkbox"/>	Take steps to protect personnel, the public, and the environment.
<input type="checkbox"/>	Direct on-site operations; take steps to control the incident (e.g. shutdown, isolate, depressurize) to protect the property.
<input type="checkbox"/>	Initiate first aid, as required.
<input type="checkbox"/>	Ensure that a head count and personnel accountability record is maintained for the duration of the incident.
<input type="checkbox"/>	Immediately report any suspected threats of violence, sabotage, or terrorism.
<input type="checkbox"/>	Report worker exposure exceeding allowable limits.
<input type="checkbox"/>	Develop Incident Action Plan in coordination with the Section Chiefs. Ensure all objectives have been assigned to someone for action.
<input type="checkbox"/>	Develop Incident Action Plan in coordination with the Section Chiefs.
<input type="checkbox"/>	Secure the scene and restrict access to authorized personnel only.
<input type="checkbox"/>	Initiate on-site monitoring.
<input type="checkbox"/>	Establish an Incident Command Post and communications with other Command Centres.
<input type="checkbox"/>	Define the boundaries of the response zones and identify the boundaries on the area map.
<input type="checkbox"/>	Ensure that the Operations Section Chief evaluates how many members of the public could be inside the response zones.
<input type="checkbox"/>	Initiate stakeholder notification within the EPZ of the incident.
<input type="checkbox"/>	Ensure Operations Section Chief initiates a transient survey of the area.
<input type="checkbox"/>	Dispatch Mobile Air Monitoring Unit to the incident scene.
<input type="checkbox"/>	For an incident with the potential of odours, smoke, or hazardous airborne release initiate monitoring at nearest downwind occupied location.
<input type="checkbox"/>	Discuss actions, media / resource requirements and conditions with EOC Operations and Technical Support.
<input type="checkbox"/>	Delegate responsibilities to Company personnel and contract support resources.
<input type="checkbox"/>	Assign roles to personnel as appropriate for the size and complexity of the incident.
<input type="checkbox"/>	Notify police in the event of an industrial fatality or motor vehicle incident.
<input type="checkbox"/>	If the incident involves a pressure vessel notify the designated Company Chief Inspector.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Reassess level of emergency and confer with the EOC Operations and Technical Support in the event of a change.
<input type="checkbox"/>	Determine the potential for the incident to escalate
<input type="checkbox"/>	Ensure the Operations Section Chief has established site security and is working to address source control.
<input type="checkbox"/>	Secure response zones and set up roadblocks, if required.
<input type="checkbox"/>	Establish a sign-in post/station as required.
<input type="checkbox"/>	Evacuate non-essential personnel.
<input type="checkbox"/>	Initiate first line emergency services such as firefighters, police, ambulance, safety, or oil spill contractors.
<input type="checkbox"/>	Dispatch helicopter, if required, to survey area, transport supplies and/or assist with control measures.
<input type="checkbox"/>	If the emergency has the potential to require ignition, ensure a qualified Ignition Team is chosen, duties are discussed, and ignition equipment is on-site.
<input type="checkbox"/>	Evaluate ignition criteria and communicate with the Operations Section Chief, EOC Operations and Technical Support and applicable Regulatory Authority regarding ignition decision.
<input type="checkbox"/>	Establish a Unified Command structure with government agencies at the Incident Command Post, if necessary.
<input type="checkbox"/>	Ensure field responders are promptly notified of any status updates.
<input type="checkbox"/>	Continually reassess the situation and the risk to life and safety.
<b>Level 3</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Reassess the level of emergency and confer with the EOC Operations and Technical Support in the event of a change.
<input type="checkbox"/>	Confer with EOC Operations and Technical Support to discuss additional control measures.
<input type="checkbox"/>	Determine if ignition criteria have been met.

INCIDENT COMMANDER	
<input type="checkbox"/>	Consult with EOC Operations and Technical Support and applicable Regulatory Authority, if possible. Initiate ignition procedures as required
<input type="checkbox"/>	Determine the need for Planning Section Chief, Logistics Section Chief, and Finance/Admin Section Chief and activate as required.
<input type="checkbox"/>	Expand the response zones if monitoring indicates it is necessary.
<input type="checkbox"/>	Ensure Operations Section Chief has established an appropriate staging area and is providing resource support.
<input type="checkbox"/>	Update previous contacts if there is a change of status.
<b>Deactivation</b>	
<input type="checkbox"/>	Where applicable, commence reclamation activities once the spill has been isolated and the area has been secured.
<input type="checkbox"/>	Coordinate the removal of the impacted waste material and dispose of the waste to an approved facility.
<input type="checkbox"/>	Obtain a sufficient number of samples of the remediated site to demonstrate containment.
<input type="checkbox"/>	Downgrade the emergency in consultation with the EOC Operations and Technical Support and the applicable Regulatory Authority.
<input type="checkbox"/>	Ensure all appropriate government agencies are notified of the stand-down of the emergency.
<input type="checkbox"/>	Ensure any notified media are updated of the stand-down of emergency.
<input type="checkbox"/>	Ensure all affected stakeholders are notified of the stand-down of emergency.
<input type="checkbox"/>	Ensure the Operations Section Chief coordinates the ventilation of all residences and businesses as required and that monitoring for gas pockets continues to take place.
<input type="checkbox"/>	Ensure evacuee expenses and damage claims are collected.
<input type="checkbox"/>	Ensure post-incident reports are completed and submitted, if applicable.
<input type="checkbox"/>	Ensure all members of the Emergency Response Team and other key participants are invited to the debriefing.
<input type="checkbox"/>	Conduct post-incident debriefing.
<input type="checkbox"/>	Assess the physical and emotional health of responders and make recommendations for Critical Incident Stress Debriefing.

INCIDENT COMMANDER

Forms	
<input type="checkbox"/>	ICS 201 – Incident Briefing
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Notification Record

Note: A comprehensive Incident Action Plan should, as a minimum, include ICS Forms 201, 202, 203, and 207.

### 3.4 Deputy Incident Commander

The Deputy Incident Commander assists the Incident Commander as needed in the delegation and execution of critical emergency response actions. The Deputy Incident Commander role is only required should the scope of the incident require this additional manpower or the length of the incident is expected to go beyond a reasonable days efforts requiring relief.

The three primary reasons to designate a Deputy Incident Commander are to:

- Perform specific tasks as requested by the Incident Commander.
- Perform the incident command function in a relief capacity (e.g., to take over for the next operational period). In this case, the Deputy will assume the primary role.
- Represent an Assisting Agency that may share jurisdiction or have jurisdiction in the future.

The Deputy Incident Commander must be qualified to fulfill the incident command role (ICS 200, ICS 300). The Deputy Incident Commander reports directly to the Incident Commander however authority lies with the Incident Commander for all response functions until he/she delegates those response activities.

DEPUTY INCIDENT COMMANDE	
<b>Location</b>	
<input type="checkbox"/>	Incident Command Post.
<b>Confers With</b>	
<input type="checkbox"/>	Incident Commander
<b>Gives Direction To (as directed by the Incident Commander)</b>	
<input type="checkbox"/>	Operations Section Chief.
<input type="checkbox"/>	Planning Section Chief.
<input type="checkbox"/>	Logistics Section Chief.
<input type="checkbox"/>	Finance/Admin Section Chief.
<input type="checkbox"/>	Safety Officer.
<input type="checkbox"/>	Liaison Officer.
<input type="checkbox"/>	Information Office (Scribe).
<b>Situation Assessment</b>	
<input type="checkbox"/>	Consider evacuating non-essential personnel to safety and place them on standby to fill public protection roles.
<input type="checkbox"/>	Dispatch trained and appropriately equipped personnel (preferably in pairs) to investigate.
<input type="checkbox"/>	If the situation assessment confirms that company assets are involved, activate the ERP and establish Incident Command.
<input type="checkbox"/>	If the incident involves another company's asset, ensure that their personnel are notified. Maintain contact with the responsible operating company until they arrive on scene.
<input type="checkbox"/>	Contact the person who reported the incident and advise them of the result of the situation assessment.
<input type="checkbox"/>	Notify appropriate company personnel.
<input type="checkbox"/>	Assess the situation using the appropriate matrix for classifying incidents.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Develop an initial response strategy that adheres to the PEAR emergency response priorities. These response priorities are protecting people, environment, assets and reputation.
<input type="checkbox"/>	Establish method of communications with the EOC Operations and Technical Support
<input type="checkbox"/>	Schedule regular briefings with the EOC Operations and Technical Support
<input type="checkbox"/>	Evaluate resource requirements and advise EOC Operations and Technical Support
<input type="checkbox"/>	For an incident that is not impacting public safety, consider public notification as a courtesy.
<input type="checkbox"/>	Ensure Regulatory Authority notification according to the applicable requirements.
<input type="checkbox"/>	Refer to the Notification Requirements for Key Government Agencies and Resources in the Jurisdictional section of this document.

DEPUTY INCIDENT COMMANDER

**DEPUTY INCIDENT COMMANDER**
**Level 1**

- Continue with previous actions.
- Determine the Operational Period.
- Complete the ICS 201 – Incident Briefing Form.
- Facilitate Objectives Meeting with Section Chiefs. Determine the objectives for the incident and communicate them between activated command posts.
- Facilitate Command and General Staff Meeting, as required. Identify safety hazards and immediate safety actions to be taken to protect against the hazards.
- Request resources, personnel and equipment to address emergency situation.
- Take steps to protect personnel, the public, and the environment.
- Direct on-site operations; take steps to control the incident (e.g. shutdown, isolate, depressurize) to protect the property.
- Initiate first aid, as required.
- Ensure that a head count and personnel accountability record is maintained for the duration of the incident.
- Immediately report any suspected threats of violence, sabotage, or terrorism.
- Report worker exposure exceeding allowable limits.
- Develop Incident Action Plan in coordination with the Section Chiefs. Ensure all objectives have been assigned to someone for action.
- Develop Incident Action Plan in coordination with the Section Chiefs.
- Secure the scene and restrict access to authorized personnel only.
- Initiate on-site monitoring.
- Establish an Incident Command Post and communications with other Command Centres.
- Define the boundaries of the response zones and identify the boundaries on the area map.
- Ensure that the Operations Section Chief evaluates how many members of the public could be inside the response zones.
- Initiate stakeholder notification within the EPZ of the incident.
- Ensure Operations Section Chief initiates a transient survey of the area.
- Dispatch Mobile Air Monitoring Unit to the incident scene.
- For an incident with the potential of odours, smoke, or hazardous airborne release initiate monitoring at nearest downwind occupied location.
- Discuss actions, media requirements, resource requirements and conditions with EOC Operations and Technical Support.
- Delegate responsibilities to Company personnel and contract support resources.
- Assign roles to personnel as appropriate for the size and complexity of the incident.
- Notify police in the event of an industrial fatality or motor vehicle incident.
- If the incident involves a pressure vessel notify the designated Company Chief Inspector.

**Level 2**

- Continue with previous actions.
- Reassess level of emergency and confer with the EOC Operations and Technical Support in the event of a change.
- Determine the potential for the incident to escalate
- Ensure the Operations Section Chief has established site security and is working to address source control.
- Secure response zones and set up roadblocks, if required.
- Establish a sign-in post/station as required.
- Evacuate non-essential personnel.
- Initiate first line emergency services such as firefighters, police, ambulance, safety contractors, or oil spill contractors.
- Dispatch helicopter, if required, to survey area, transport supplies and/or assist with control measures.
- If the emergency has the potential to require ignition, ensure a qualified Ignition Team is chosen, duties are discussed, and ignition equipment is on-site.
- Evaluate ignition criteria and communicate with the Operations Section Chief, EOC Operations and Technical Support and applicable Regulatory Authority regarding ignition decision.
- Establish a Unified Command structure with government agencies at the Incident Command Post, if necessary.
- Ensure field responders are promptly notified of any status updates.
- Continually reassess the situation and the risk to life and safety.

DEPUTY INCIDENT COMMANDER

<b>DEPUTY INCIDENT COMMANDER</b>	
<b>Level 3</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Reassess the level of emergency and confer with the EOC Operations and Technical Support in the event of a change.
<input type="checkbox"/>	Confer with EOC Operations and Technical Support to discuss additional control measures.
<input type="checkbox"/>	Determine if ignition criteria have been met.
<input type="checkbox"/>	Consult with EOC Operations and Technical Support and applicable Regulatory Authority, if possible. Initiate ignition procedures as required
<input type="checkbox"/>	Determine the need for Planning Section Chief, Logistics Section Chief, and Finance/Admin Section Chief and activate as required.
<input type="checkbox"/>	Expand the response zones if monitoring indicates it is necessary.
<input type="checkbox"/>	Ensure Operations Section Chief has established an appropriate staging area and is providing resource support.
<input type="checkbox"/>	Update previous contacts if there is a change of status.
<b>Deactivation</b>	
<input type="checkbox"/>	Where applicable, commence reclamation activities once the spill has been isolated and the area has been secured.
<input type="checkbox"/>	Coordinate the removal of the impacted waste material and dispose of the waste to an approved facility.
<input type="checkbox"/>	Obtain a sufficient number of samples of the remediated site to demonstrate containment.
<input type="checkbox"/>	Downgrade the emergency in consultation with the EOC Operations and Technical Support and the applicable Regulatory Authority.
<input type="checkbox"/>	Ensure all appropriate government agencies are notified of the stand-down of the emergency.
<input type="checkbox"/>	Ensure any notified media are updated of the stand-down of emergency.
<input type="checkbox"/>	Ensure all affected stakeholders are notified of the stand-down of emergency.
<input type="checkbox"/>	Ensure the Operations Section Chief coordinates the ventilation of all residences and businesses as required and that monitoring for gas pockets continues to take place.
<input type="checkbox"/>	Ensure evacuee expenses and damage claims are collected.
<input type="checkbox"/>	Ensure post-incident reports are completed and submitted, if applicable.
<input type="checkbox"/>	Ensure all members of the Emergency Response Team and other key participants are invited to the debriefing.
<input type="checkbox"/>	Conduct post-incident debriefing.
<input type="checkbox"/>	Assess the physical and emotional health of responders and make recommendations for Critical Incident Stress Debriefing.
<b>Forms</b>	
<input type="checkbox"/>	ICS 201 – Incident Briefing
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Notification Record
Note: A comprehensive Incident Action Plan should, as a minimum, include ICS Forms 201, 202, 203, and 207.	

DEPUTY INCIDENT COMMANDER

### 3.5 Operations Section Chief

The Operations Section Chief is responsible for the direction and coordination of all incident tactical operations and resources. Initially the Operations Section Chief consists of those few resources first assigned to an incident (these resources will initially report directly to the Incident Commander until the Operations Section Chief is assigned).

OPERATIONS SECTION CHIEF	
<b>Location</b>	
<input type="checkbox"/>	Location not pre-determined.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Incident Commander.
<b>Confers With</b>	
<input type="checkbox"/>	Section Chiefs, if applicable.
<input type="checkbox"/>	Safety Officer
<b>Gives Direction To</b>	
<input type="checkbox"/>	On-Site Group Supervisor.
<input type="checkbox"/>	Public Protection Group Supervisor.
<input type="checkbox"/>	Staging Area Manager.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Establish method of communications with the Incident Commander and provide support as required.
<input type="checkbox"/>	Schedule regular briefings with the Incident Commander.
<input type="checkbox"/>	Designate Public Protection Group Supervisor and On-Site Group Supervisor, as required.
<b>Level 1</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Establish On-Site Command Post.
<input type="checkbox"/>	Facilitate Tactics Meeting with the Safety Officer, Logistics Section Chief, and Finance/Admin Section Chief. Discuss how the objectives will be met. Review strategy and required resources to satisfy the objectives.
<input type="checkbox"/>	Prepare the ICS 215 – Operational Planning Worksheet with assistance from the Safety Officer and Logistics Section Chief or EOC Logistics Support. Document all decisions made during the Tactics Meeting concerning resource assignments and needs for the next operational period. Share completed ICS 215 with all Staff.
<input type="checkbox"/>	Prepare the ICS 204 – Assignment List, obtain sign-off from the Planning Section and approval from Incident Commander prior to dissemination as part of the Incident Action Plan.
<input type="checkbox"/>	Distribute approved Incident Action Plan to the Incident Commander.
<input type="checkbox"/>	Participate in the Operations briefing.
<input type="checkbox"/>	Implement Incident Action Plan in coordination with the Incident Commander, On-Site Group Supervisor, Public Protection Group Supervisor, and Staging Area Manager.
<input type="checkbox"/>	Identify EPZ boundaries.
<input type="checkbox"/>	Evaluate how many stakeholders could be inside the EPZ. Account for residents, businesses, First Nations persons, trappers, guide/outfitters, grazing lessees, transients, highways, waterways, railroads / public facilities.
<input type="checkbox"/>	Determine applicable public protection method.
<input type="checkbox"/>	Direct Public Protection Group Supervisor to initiate area resident notifications.
<input type="checkbox"/>	Determine what methods of communication are available to the Team Directors and Team Leaders and schedule regular briefings.
<input type="checkbox"/>	Provide any required voluntary evacuation assistance to residents identified as having special needs.
<input type="checkbox"/>	Review the topographical information, weather data, and weather forecast information.
<input type="checkbox"/>	Ensure an appropriate air quality monitoring strategy is employed.
<input type="checkbox"/>	Develop a roadblock strategy.
<input type="checkbox"/>	Determine resource requirements.
<input type="checkbox"/>	Provide direction to the On-Site Group Supervisor to address fire control, isolation, equipment damage, repair, spill response, site security, and waste management, as required.

OPERATIONS SECTION CHIEF

**OPERATIONS SECTION CHIEF**
**OPERATIONS SECTION CHIEF**

<input type="checkbox"/>	Assess the requirements for on-site safety supervision, personnel, equipment, and other contract services.
<input type="checkbox"/>	Coordinate with the Logistics Section Chief (if assigned) to obtain equipment and resources.
<input type="checkbox"/>	Compile and display incident information.
<input type="checkbox"/>	Assign roles to personnel as appropriate for the size and complexity of the incident.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Direct Public Protection Group Supervisor to review EPZ boundaries.
<input type="checkbox"/>	Direct Public Protection Group Supervisor to initiate shelter and/or evacuation procedures.
<input type="checkbox"/>	Ensure transient surveys are completed.
<input type="checkbox"/>	Ensure mobile environmental and/or air quality monitoring is taking place.
<input type="checkbox"/>	Ensure roadblocks are established.
<input type="checkbox"/>	When required, dispatch a Staging Area Manager to establish and coordinate operations at the Staging Area. The Staging Area must be located outside the EPZ and near the emergency site.
<input type="checkbox"/>	Evaluate ignition criteria and communicate with the Incident Commander regarding ignition decision.
<input type="checkbox"/>	Ensure field responders are promptly notified of any status updates.
<input type="checkbox"/>	Continually reassess the situation and the risk to life and safety.
<b>Level 3</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Confirm with Public Protection Group Supervisor that all members of the public in the EPZ have been evacuated and/or sheltered.
<input type="checkbox"/>	Ensure Public Protection Group Supervisor has established a protocol for resident updates and evacuees are provided with updated information.
<input type="checkbox"/>	Maintain security.
<input type="checkbox"/>	Evaluate monitoring data and expand planning zone if required.
<input type="checkbox"/>	Review Ignition Criteria to determine if any one of the conditions have been met and coordinate with the Incident Commander.
<b>Deactivation</b>	
<input type="checkbox"/>	Discuss downgrading of emergency with Incident Commander once it has been determined that the incident site is controlled.
<input type="checkbox"/>	Notify all responders once the decision to downgrade the emergency has been made.
<input type="checkbox"/>	If a serious injury or death has occurred, the scene must be left as undisturbed as possible until the appropriate authorities can complete a site investigation.
<input type="checkbox"/>	Ensure that the Public Protection Group Supervisor ventilates residences/businesses as required and that monitoring for gas pockets continues to take place.
<input type="checkbox"/>	Ensure that the Public Protection Group Supervisor notifies all evacuees that the emergency has been downgraded.
<input type="checkbox"/>	Ensure that the Public Protection Group Supervisor assists evacuees in returning to their residences/businesses as required.
<input type="checkbox"/>	Ensure that the Public Protection Group Supervisor collects all Resident Expense Claims forms.
<input type="checkbox"/>	Participate in post-incident debriefing held by Incident Commander.
<input type="checkbox"/>	Participate in any Critical Incident Stress Debriefing, as required.

<b>Forms</b>	
<input type="checkbox"/>	ICS 204 – Assignment List
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 215 – Operational Planning Worksheet (to be completed with support from Site Safety Officer and Site Logistics Section Chief or EOC Logistics Chief)
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Status Board

### 3.6 Public Protection Group Supervisor

The Public Protection Group Supervisor is responsible for initiating and managing public protection measures. Working closely with air quality monitoring, evacuation and roadblock personnel, the Public Protection Group Supervisor ensures the efficient notification and/or evacuation of residents, businesses, industrial operators and transients.

PUBLIC PROTECTION GROUP SUPERVISOR	
<b>Location</b>	
<input type="checkbox"/>	Location not pre-determined.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Operations Section Chief.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Roadblock Team.
<input type="checkbox"/>	Rover/Evacuation Team.
<input type="checkbox"/>	Air Quality Monitoring Team.
<input type="checkbox"/>	Reception Team.
<input type="checkbox"/>	Telephone Team.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Determine operating location and setup as necessary.
<input type="checkbox"/>	Determine what job aids your position may require.
<input type="checkbox"/>	Review ERP map.
<b>Level 1</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Establish communication with the Operations Section Chief.
<input type="checkbox"/>	Proceed to On-Site Command Post.
<input type="checkbox"/>	Review the Public Protection requirements.
<input type="checkbox"/>	Record the wind direction and speed.
<input type="checkbox"/>	Review EPZ inventory.
<input type="checkbox"/>	As required, activate the following positions: Roadblock Team, Rover/Evacuation Team, Air Quality Monitoring Team, Reception Team, and Telephone Team.
<input type="checkbox"/>	Establish and maintain reporting cycles with all of the Public Protection Team Leaders.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Ensure the Telephone Team contacts residents to evacuate by phone.
<input type="checkbox"/>	Designate Reception Centre.
<input type="checkbox"/>	Dispatch Reception Team to the Reception Centre.
<input type="checkbox"/>	Ensure the Rover Evacuation Team contacts residents in person.
<input type="checkbox"/>	Ensure the EPZ has been evacuated in a timely fashion, and roadblocks are in place to isolate the EPZ.
<input type="checkbox"/>	Ensure EPZ has been checked for transients and that they are evacuated as required.
<input type="checkbox"/>	Ensure air quality monitoring occurs downwind, with priority being directed to the nearest unevacuated residence or areas where people may be present.
<input type="checkbox"/>	Record all air quality monitoring results from the Air Quality Monitoring Team.
<input type="checkbox"/>	Ensure field responders are promptly notified of any status updates.
<input type="checkbox"/>	Continually reassess the situation and the risk to life and safety.
<input type="checkbox"/>	Review information from the Roadblock, Rover Evacuation, Air Quality Monitoring and Telephoner Teams.
<input type="checkbox"/>	At pre-determined intervals, report status and discuss responses with Operations Section Chief.

PUBLIC PROTECTION GROUP SUPERVISOR

PUBLIC PROTECTION GROUP SUPERVISOR	
<b>PUBLIC PROTECTION GROUP SUPERVISOR</b>	<b>Level 3</b>
	<input type="checkbox"/> Continue with previous actions.
	<input type="checkbox"/> Update the Operations Section Chief of status
	<input type="checkbox"/> Ensure Rover Evacuation Team has successfully evacuated the EPZ.
	<input type="checkbox"/> Ensure the Roadblock Team maintains roadblocks as required.
	<input type="checkbox"/> Ensure the EPZ is being monitored effectively by the Air Quality Monitoring Team.
	<input type="checkbox"/> Ensure Telephone Team is providing ongoing status updates to impacted stakeholders.
	<input type="checkbox"/> Ensure Reception Team has a record of all evacuees.
	<b>Deactivation</b>
	<input type="checkbox"/> Ensure all evacuees are notified of the downgrading of the level of emergency.
	<input type="checkbox"/> Ensure residences/businesses are ventilated as required and that monitoring of gas pockets continues to take place.
	<input type="checkbox"/> Ensure evacuees are assisted in returning to their residences/businesses as necessary.
	<input type="checkbox"/> Ensure evacuee's evacuation expenses and damage claims are collected.
	<input type="checkbox"/> Participate in the post-incident debriefing held by the Incident Commander.
	<input type="checkbox"/> Participate in any Critical Incident Stress Debriefing as required.

Forms	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	Stakeholder Contact Record
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Status Board

### 3.6.1 Roadblock Team

The Roadblock Team has the responsibility to secure the perimeter of the EPZ through road closures and monitoring in coordination with the local police, local authority, or road maintenance personnel.

ROADBLOCK TEAM	
<b>Location</b>	
<input type="checkbox"/>	Location not pre-determined.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Public Protection Group Supervisor.
<b>Confers With</b>	
<input type="checkbox"/>	Public Protection Team.
<b>Gives Direction To (via Roadblock Team)</b>	
<input type="checkbox"/>	Road Traffic.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Review the ERP map.
<input type="checkbox"/>	Obtain safety equipment including SCBA, H <sub>2</sub> S and LEL monitors (handheld instruments), barricade tape and radio communication, as required.
<input type="checkbox"/>	Obtain roadblock kit, if not nearby arrange to have it brought to you.
<input type="checkbox"/>	Ensure a sufficient supply of appropriate forms.
<input type="checkbox"/>	Review vehicle requirements to carry out your assignment.
<input type="checkbox"/>	Fill vehicle fuel tank.
<b>Level 1</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Establish communication with the Public Protection Group Supervisor.
<input type="checkbox"/>	Determine if there are roads and how many lead into a Planning Zone.
<input type="checkbox"/>	Assess weather conditions in and around the area of emergency.
<input type="checkbox"/>	Implement Incident Action Plan in coordination with the Public Protection Group Supervisor.
<input type="checkbox"/>	As required, dispatch roadblock teams to their assigned roadblock locations using a safe route.
<input type="checkbox"/>	Contact the RCMP, local police, and/or local authority to inform them of the location of roadblocks. The authority contacted will be dependent on whether the roadway is a numbered highway, urban roadway, or rural road. Provide them with sufficient information regarding the incident and allow them to determine if they choose to take control of the roadblock.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Establish roadblocks at required sites to secure identified EPZ.
<input type="checkbox"/>	Engage the four-way flashers on your vehicle and don illuminated traffic vest so you are visible to traffic.
<input type="checkbox"/>	Do not completely block the road, leave at least one lane open.
<input type="checkbox"/>	Take air quality monitoring readings periodically for your safety and reposition as necessary.
<input type="checkbox"/>	Record any incoming and outgoing vehicles and equipment.
<input type="checkbox"/>	Ask the residents leaving the EPZ to proceed to the designated Reception Centre.
<input type="checkbox"/>	Update the Public Protection Group Supervisor of status at scheduled intervals.
<b>Level 3</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Report any significant or unusual activities.
<b>Deactivation</b>	
<input type="checkbox"/>	Ensure all roadblock equipment is cleaned and returned to its proper location.
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in any Critical Incident Stress Debriefing as required.

ROADBLOCK TEAM

**Note:** The licensee has the responsibility to protect the public by activating roadblocks. Restricting access to the hazard area will remain under the authority of the applicable agency (i.e. police, RCMP, fire department, road maintenance contractor, regulatory authority, etc). If someone insists on going through the roadblock, ask him or her for emergency contact numbers, this may encourage the driver to stop.

Forms	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	Roadblock Checkpoint Record
<input type="checkbox"/>	Environmental Monitoring Record

### 3.6.2 Rover Evacuation Team

The Rover Evacuation Team is responsible for identifying and evacuating all members of the public within the response zones. He/she provides support to those who need evacuation assistance by checking residences, businesses (where no phone contact has been made), trappers, Guide/Outfitters, transients, and seasonal and casual area users.

ROVER EVACUATION TEAM	
<b>Location</b>	
<input type="checkbox"/>	Location not pre-determined.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Public Protection Group Supervisor.
<b>Confers With</b>	
<input type="checkbox"/>	Public Protection Team.
<b>Gives Direction To (via Rover Evacuation Team)</b>	
<input type="checkbox"/>	Residents.
<input type="checkbox"/>	Businesses.
<input type="checkbox"/>	Trappers.
<input type="checkbox"/>	Guide/Outfitters.
<input type="checkbox"/>	Transients.
<input type="checkbox"/>	Seasonal and casual area users.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Review the ERP map.
<input type="checkbox"/>	Obtain safety equipment including SCBA, H <sub>2</sub> S and LEL monitors (handheld instruments) and radio communication, as required.
<input type="checkbox"/>	Ensure a sufficient supply of appropriate forms.
<input type="checkbox"/>	Review vehicle requirements to carry out your assignment.
<input type="checkbox"/>	Fill vehicle fuel tank.
<input type="checkbox"/>	Review product release rates, wind direction, and safest egress routes.
<b>Level 1</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Establish communication with the Public Protection Group Supervisor.
<input type="checkbox"/>	Review the boundaries of the response zones.
<input type="checkbox"/>	Evaluate how many members of the public could be inside the EPZ and the response zones. Account for residents, businesses, First Nations persons, trappers, guide/outfitters, grazing lessees, and transients.
<input type="checkbox"/>	Identify highways, waterways, railroads, airports, campgrounds, hiking trails, etc. where stakeholders may be located.
<input type="checkbox"/>	Assess weather conditions in and around the area of the emergency. Determine if weather conditions could impact or impede emergency response efforts.
<input type="checkbox"/>	Identify the required number of Rovers and prepare to dispatch.
<input type="checkbox"/>	Implement Incident Action Plan in coordination with the Public Protection Group Supervisor.
<input type="checkbox"/>	Commence transient survey.
<input type="checkbox"/>	Advise members of the public identified as having special needs of the incident. Provide evacuation assistance if requested.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Report any observations or issues which may negatively impact evacuations.
<input type="checkbox"/>	Take air quality monitoring readings periodically for your safety.
<input type="checkbox"/>	Ensure all public locations are visited and evacuated.
<input type="checkbox"/>	When contacting stakeholders, identify yourself, speak slowly and confidently.
<input type="checkbox"/>	Document time of arrival.

ROVER EVACUATION TEAM

<b>ROVER EVACUATION TEAM</b>	
<b>ROVER EVACUATION TEAM</b>	<input type="checkbox"/> Account for all members of the household, business or dwelling. Inquire as to the whereabouts of anyone not present.
	<input type="checkbox"/> Review the condition of stakeholders and identify any special requirements.
	<input type="checkbox"/> Relay travel time and directions to the reception centre using safe egress routes.
	<input type="checkbox"/> Check all fields and vacant locations to ensure that they are empty.
	<input type="checkbox"/> Post a Notice of Evacuation on all doors of each unoccupied residence and business, on each outbuilding and the windshield of each unattended vehicle within the evacuated zones.
	<input type="checkbox"/> Expand transient survey if EPZ is increased.
	<input type="checkbox"/> Update the Public Protection Group Supervisor of status at scheduled intervals.
	<b>Level 3</b>
	<input type="checkbox"/> Continue with previous actions.
	<input type="checkbox"/> Ensure EPZ has been evacuated.
	<input type="checkbox"/> Update the Public Protection Group Supervisor of status at scheduled intervals.
	<b>Deactivation</b>
	<input type="checkbox"/> Continue to monitor for gas pockets.
	<input type="checkbox"/> Assist evacuees in returning to their residences/businesses as required.
	<input type="checkbox"/> Ventilate residences/businesses as required.
<input type="checkbox"/> Provide Company phone number in the event of additional concerns or questions.	
<input type="checkbox"/> Participate in the post-incident debriefing held by the Incident Commander.	
<input type="checkbox"/> Participate in any Critical Incident Stress Debriefing, as required.	

<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Stakeholder Contact Record
<input type="checkbox"/>	Notice of Evacuation

### 3.6.3 Air Quality Monitoring Team

The Air Quality Monitoring Team uses air quality monitoring equipment and personnel to identify and track the extent of the plume associated with a gas release to atmosphere.

AIR QUALITY MONITORING TEAM	
<b>Location</b>	
<input type="checkbox"/>	Location not pre-determined.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Public Protection Group Supervisor.
<b>Confers With</b>	
<input type="checkbox"/>	Public Protection Team.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Mobile air quality monitoring unit.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Review ERP map, product release rates, wind direction, and safest egress routes.
<input type="checkbox"/>	Review stakeholder locations and proximity to urban developments.
<input type="checkbox"/>	Obtain radio communication equipment, as required.
<input type="checkbox"/>	Verify operational condition and appropriateness of plume monitoring equipment.
<input type="checkbox"/>	Ensure a sufficient supply of appropriate forms.
<input type="checkbox"/>	Review vehicle requirements to carry out your assignment.
<input type="checkbox"/>	Fill vehicle fuel tank.
<b>Level 1</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Establish communication with the Public Protection Group Supervisor.
<input type="checkbox"/>	Implement Incident Action Plan in coordination with the Public Protection Group Supervisor.
<input type="checkbox"/>	If safe to do so, perform air quality monitoring with hand-held aspirating detectors until mobile air quality monitoring unit arrives.
<input type="checkbox"/>	Confirm dispatch of the mobile air quality monitoring unit, if required.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Track the plume perimeter and record measured concentration.
<input type="checkbox"/>	Where a release has the possibility of being sustained, the EPZ must be redefined using mobile monitoring vehicles equipped with devices to continuously measure and record wind speed, directions and concentrations.
<input type="checkbox"/>	Air quality monitoring must occur downwind with priority being directed to the nearest un-evacuated residence or area where people may be present.
<input type="checkbox"/>	If the EPZ includes a portion of an urban density development, mobilize sufficient air quality monitoring units so that one unit will be dedicated to the urban density development.
<input type="checkbox"/>	In coordination with the Public Protection Group Supervisor, provide monitored information to applicable Regulatory Authority, local authority, local health authority and environmental authority on a regular basis throughout the emergency.
<input type="checkbox"/>	Update the Public Protection Group Supervisor of status at scheduled intervals.
<b>Level 3</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Ensure the EPZ is being monitored effectively.
<input type="checkbox"/>	Provide Air Quality Monitoring Record reports to the Public Protection Group Supervisor.
<input type="checkbox"/>	Update the Public Protection Group Supervisor of status at scheduled intervals.

AIR QUALITY MONITORING TEAM

AIR QUALITY MONITORING TEAM	
<b>AIR QUALITY MONITORING</b>	<b>Deactivation</b>
	<input type="checkbox"/> Collect and submit all reports and documents to the Public Protection Group Supervisor.
	<input type="checkbox"/> Determine from the Public Protection Group Supervisor if your position will require any follow up actions before you leave the scene.
	<input type="checkbox"/> Participate in the post-incident debriefing held by the Incident Commander.
	<input type="checkbox"/> Participate in the Critical Incident Stress Debriefing as required.

Forms	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	Environmental Monitoring Record

### 3.6.4 Reception Team

The Reception Team is responsible for establishing a Reception Centre at a suitable location outside the EPZ and addressing the concerns and immediate needs of evacuated stakeholders.

RECEPTION TEAM	
<b>Location</b>	
<input type="checkbox"/>	Reception Centre.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Public Protection Group Supervisor.
<b>Confers With</b>	
<input type="checkbox"/>	Public Protection Team.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Evacuated stakeholders.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Prepare reception centre kit (pen, paper, area phone book, registration forms, and title badges).
<b>Level 1</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Identify appropriate Reception Centre.
<input type="checkbox"/>	Contact reception centre to make necessary arrangements.
<input type="checkbox"/>	Implement Incident Action Plan in coordination with the Public Protection Group Supervisor.
<input type="checkbox"/>	Proceed to designated Reception Centre and prepare facility to receive evacuees if evacuation is probable.
<input type="checkbox"/>	Set up communication with the Public Protection Group Supervisor.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Receive evacuees and record names of evacuees who arrive at the Reception Centre.
<input type="checkbox"/>	Receive school children who live inside the EPZ whose school buses have been redirected to the Reception Centre. Children must be supervised until they are picked up by their parents or guardians.
<input type="checkbox"/>	If necessary, arrange for a school administrator to come to the Reception Centre.
<input type="checkbox"/>	Address evacuees' immediate needs for food and housing.
<input type="checkbox"/>	Provide information to the evacuees on the status of the incident.
<input type="checkbox"/>	Record details of temporary destinations and contact numbers when evacuees leave the Reception Centre.
<input type="checkbox"/>	Discuss immediate expense issues.
<input type="checkbox"/>	Relay concerns regarding requirements for ongoing care of livestock to the Public Protection Group Supervisor, if applicable.
<input type="checkbox"/>	Provide support to evacuees who may be emotionally upset.
<input type="checkbox"/>	Update the Public Protection Group Supervisor of status at scheduled intervals.
<b>Level 3</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Verify with Public Protection Group Supervisor that all members of the public have been evacuated.
<input type="checkbox"/>	Continue with status updates for residents and other concerned members of the public.
<input type="checkbox"/>	Update telephone contacts for evacuees as required.
<input type="checkbox"/>	Update the Public Protection Group Supervisor of status at scheduled intervals.
<b>Deactivation</b>	
<input type="checkbox"/>	Advise evacuees that they may return to their residences and arrange any assistance.
<input type="checkbox"/>	Collect and document all evacuation expense claims, provide copies to the Finance/Admin Section Chief and/or Business Impact Support, if activated.
<input type="checkbox"/>	Provide Company phone number in the event of additional concerns or questions.
<input type="checkbox"/>	Participate in post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.

RECEPTION TEAM

<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	Evacuee Expense Claim Form
<input type="checkbox"/>	Reception Centre Registration Form

### 3.6.5 Telephone Team

The Telephone Team is responsible for contacting impacted stakeholders to provide updates regarding any emergency situation when necessary. Communication will be facilitated using the appropriate scripts as a guide.

TELEPHONE TEAM	
<b>Location</b>	
<input type="checkbox"/>	Location not pre-determined.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Public Protection Group Supervisor.
<b>Confers With</b>	
<input type="checkbox"/>	Public Protection Team.
<b>Gives Direction To (via Telephone Team)</b>	
<input type="checkbox"/>	Area Stakeholders.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Review the ERP map.
<input type="checkbox"/>	Assemble required telephone team forms.
<input type="checkbox"/>	Review area stakeholder list and phone numbers, if applicable.
<input type="checkbox"/>	Review the Communication Plan scripts.
<input type="checkbox"/>	Identify appropriate space and communication devices to facilitate stakeholder telephone notification, if required.
<b>Level 1</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Implement Incident Action Plan in coordination with the Public Protection Group Supervisor.
<input type="checkbox"/>	Standby and prepare to initiate stakeholder telephone notification.
<input type="checkbox"/>	Prepare evacuation or shelter-in-place phone messages based on direction from the Public Protection Group Supervisor. Use scripts in the manual for consistent wording and clarity.
<input type="checkbox"/>	Notify stakeholders and other area users inside the EPZ so they may choose whether to voluntarily evacuate.
<input type="checkbox"/>	An automated telephone notification system can be used but prepare to follow-up the automated system with personal contact from the Telephone Team.
<input type="checkbox"/>	Record all details of contacts using the Stakeholder Contact Record for documentation.
<input type="checkbox"/>	Advise the Public Protection Group Supervisor about stakeholders requiring assistance.
<input type="checkbox"/>	Update the Public Protection Group Supervisor of status.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Contact stakeholders and other area users in EPZ and advise them to evacuate.
<input type="checkbox"/>	Confirm the location of the Reception Centre so coordination with stakeholders can occur.
<input type="checkbox"/>	If school is in session, contact impacted schools and school bus authorities. This contact is not to be made by an automated telephone system.
<input type="checkbox"/>	Coordinate with the Reception Team and request a school administrator assist with the effective management of the students and parents at the Reception Centre.
<input type="checkbox"/>	Document and track the status of stakeholders who have evacuated or sheltered.
<input type="checkbox"/>	Update the Public Protection Group Supervisor of status at scheduled intervals.
<b>Level 3</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Continue phoning stakeholders who have been unreachable.
<input type="checkbox"/>	Remain on standby to assist with telephone calls as required.
<input type="checkbox"/>	Update the Public Protection Group Supervisor of status at scheduled intervals.

TELEPHONE TEAM

TELEPHONE TEAM	
<b>TELEPHONE TEAM</b>	<b>Deactivation</b>
	<input type="checkbox"/> As instructed by the Public Protection Group Supervisor, advise all evacuees that they may return.
	<input type="checkbox"/> Ensure a post-incident telephone message is communicated to the public impacted by the emergency.
	<input type="checkbox"/> Collect and submit all reports and documents to the Public Protection Group Supervisor.
	<input type="checkbox"/> Participate in the post-incident debriefing held by the Incident Commander.
	<input type="checkbox"/> Participate in the Critical Incident Stress Debriefing as required.

Forms	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Stakeholder Contact Record

### 3.7 On-Site Group Supervisor

The On-Site Group Supervisor is responsible for establishing the On-Site Command Post and coordinating personnel and equipment to address control, containment and recovery from the incident.

ON-SITE GROUP SUPERVISOR	
<b>Location</b>	
<input type="checkbox"/>	On-Site Command Post.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Operations Section Chief.
<b>Confers With</b>	
<input type="checkbox"/>	Public Protection Group Supervisor.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Fire Control Team.
<input type="checkbox"/>	Isolation/Repair Team.
<input type="checkbox"/>	Spill Response Team.
<input type="checkbox"/>	Site Security Team.
<input type="checkbox"/>	Ignition Team.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Identify hazards.
<input type="checkbox"/>	Attend to medical needs.
<input type="checkbox"/>	Request emergency medical services, as required.
<input type="checkbox"/>	Isolate the scene.
<b>Level 1</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Establish communication with the Operations Section Chief.
<input type="checkbox"/>	Discuss the incident situation and actions to be taken with the Operations Section Chief.
<input type="checkbox"/>	Release non-essential personnel.
<input type="checkbox"/>	Isolate the immediate area until the Public Protection Group Supervisor assumes this responsibility.
<input type="checkbox"/>	Activate appropriate Source Control Team Leaders to address the incident.
<input type="checkbox"/>	Ensure all on-site personnel follow the appropriate safe work procedures.
<input type="checkbox"/>	Ensure all on-site personnel have the appropriate training and personal protective equipment.
<input type="checkbox"/>	Assess the requirements for on-site safety supervision, equipment, and personnel.
<input type="checkbox"/>	Coordinate on-site responses to gain control, shutdown, isolate, and depressure equipment, as required.
<input type="checkbox"/>	Review dangerous conditions near the incident site. For example fuel leaks, toxic gas releases, oxygen deficiency, BLEVE, ignition sources, and chemical leaks.
<input type="checkbox"/>	Build dykes with available materials to stop leaks from travelling off-lease or into waterways.
<input type="checkbox"/>	Evaluate ignition criteria and communicate with the Operations Section Chief regarding ignition decision.
<input type="checkbox"/>	Obtain spill samples as required and monitor environment for adverse effects.
<input type="checkbox"/>	Record and report all readings at established intervals to the Operations Section Chief.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Update the Operations Section Chief of status.
<input type="checkbox"/>	Continue spill sampling.
<input type="checkbox"/>	Ensure field responders are promptly notified of any status updates.
<input type="checkbox"/>	Continually reassess the situation and the risk to life and safety.
<input type="checkbox"/>	In conjunction with the Operations Section Chief, choose a qualified ignition team, discuss ignition duties, and check ignition equipment in advance of meeting any ignition criteria.
<input type="checkbox"/>	Confirm with the Operations Section Chief that you have the authority to ignite, if required.

ON-SITE GROUP SUPERVISOR

ON-SITE GROUP SUPERVISOR	
ON-SITE GROUP SUPERVISOR	<b>Level 3</b>
	<input type="checkbox"/> Continue with previous actions.
	<input type="checkbox"/> Update the Operations Section Chief of status at scheduled intervals.
	<input type="checkbox"/> Initiate ignition procedure if ignition criteria have been met (upon consultation with Operations Section Chief).
	<b>Deactivation</b>
	<input type="checkbox"/> Ensure site is safe.
	<input type="checkbox"/> Ensure the incident site is not disturbed until all necessary site investigations have been completed by the appropriate authority.
	<input type="checkbox"/> Ensure all work areas, safety equipment, machinery, and tools are cleaned, repaired, and returned to their proper location.
	<input type="checkbox"/> Ensure that on-site personnel and equipment including contracted services are decontaminated before leaving the incident site.
	<input type="checkbox"/> Complete and submit all documents to the Operations Section Chief.
	<input type="checkbox"/> Participate in the post-incident debriefing held by the Incident Commander.
	<input type="checkbox"/> Participate in any Critical Stress Incident Debriefing, as required.

Forms	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Spill/Release Written Report Form

### 3.7.1 Fire Control Team

The Fire Control Team is responsible for coordinating the fire suppression efforts with the local fire department, industrial firefighting contractors, and the On-Site Team members.

FIRE CONTROL TEAM	
<b>Location</b>	
<input type="checkbox"/>	On-Site Command Post.
<b>Takes Direction From</b>	
<input type="checkbox"/>	On-Site Group Supervisor.
<b>Confers With</b>	
<input type="checkbox"/>	Local Fire Department.
<input type="checkbox"/>	Industrial Firefighters.
<input type="checkbox"/>	On-Site Team.
<b>Gives Direction To</b>	
<input type="checkbox"/>	On-Site Fire Control Personnel.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Inventory number, type and location of fire extinguishers.
<input type="checkbox"/>	Proactive notification to local Fire Department.
<input type="checkbox"/>	Establish communication with the On-Site Group Supervisor.
<input type="checkbox"/>	Determine classification of fire.
<input type="checkbox"/>	Implement Incident Action Plan in coordination with the On-Site Group Supervisor.
<input type="checkbox"/>	Request assistance from local Fire Department or Industrial Firefighters.
<input type="checkbox"/>	Use a fire extinguisher only when it can be done safely.
<input type="checkbox"/>	Contain fire until fire department or additional firefighting resources arrive.
<b>Deactivation</b>	
<input type="checkbox"/>	Ensure site is safe.
<input type="checkbox"/>	Ensure all work areas, safety equipment, machinery, and tools are cleaned, repaired, and returned to their proper location.
<input type="checkbox"/>	Complete and submit all documents to the On-Site Group Supervisor.
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in any Critical Stress Incident Debriefing, as required.
<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log

FIRE CONTROL TEAM

### 3.7.2 Isolation/Repair Team

The Isolation/Repair Team is responsible for emergency shutdown, isolation, depressurization, troubleshooting, and repair efforts with the On-Site isolation/repair personnel and the On-Site Team members.

ISOLATION/REPAIR TEAM	
<b>Location</b>	
<input type="checkbox"/>	On-Site Command Post.
<b>Takes Direction From</b>	
<input type="checkbox"/>	On-Site Group Supervisor.
<b>Confers With</b>	
<input type="checkbox"/>	On-Site Team.
<b>Gives Direction To</b>	
<input type="checkbox"/>	On-Site isolation/repair personnel.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Identify hazards involved.
<input type="checkbox"/>	Account for all personnel on-site.
<input type="checkbox"/>	Evacuate immediate work area.
<input type="checkbox"/>	Go to muster point.
<input type="checkbox"/>	When possible confirm situation with back-up personnel.
<input type="checkbox"/>	Determine if situation requires isolation and/or emergency shutdown of an individual piece of equipment.
<input type="checkbox"/>	Determine if situation requires complete shutdown of facility.
<input type="checkbox"/>	Contact the On-Site Group Supervisor for further instructions and provide the exact location of the incident.
<input type="checkbox"/>	Implement Incident Action Plan in coordination with the On-Site Group Supervisor.
<b>Deactivation</b>	
<input type="checkbox"/>	Ensure site is safe.
<input type="checkbox"/>	Ensure all work areas, safety equipment, machinery, and tools are cleaned, repaired, and returned to their proper location.
<input type="checkbox"/>	Complete and submit all documents to the On-Site Group Supervisor.
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in any Critical Stress Incident Debriefing, as required.
<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix

ISOLATION/REPAIR TEAM

### 3.7.3 Spill Response Team

The Spill Response Team is responsible for coordinating spill, containment, and clean-up efforts to minimize impairment to the environment, human health, or property.

SPILL RESPONSE TEAM	
<b>Location</b>	
<input type="checkbox"/>	On-Site Command Post
<b>Takes Direction From</b>	
<input type="checkbox"/>	On-Site Group Supervisor.
<b>Confers With</b>	
<input type="checkbox"/>	On-Site Team.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Spill Responders.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Collect date, time, name, and contact numbers from the person who reports the spill.
<input type="checkbox"/>	Dispatch initial responders to incident site.
<input type="checkbox"/>	Establish site control.
<input type="checkbox"/>	Analyze the situation.
<input type="checkbox"/>	Establish a muster point.
<input type="checkbox"/>	Identify the type and volume of spill product.
<input type="checkbox"/>	Report the incident to the On-Site Group Supervisor.
<input type="checkbox"/>	Implement spill response objectives in coordination with the On-Site Group Supervisor.
<b>Level 1</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Dispatch spill responders and equipment to the incident site.
<input type="checkbox"/>	Control all access to the incident site.
<input type="checkbox"/>	Identify the contamination zone, support zone, and equipment staging area.
<input type="checkbox"/>	Identify an emergency signal, escape routes, and meeting location for response personnel.
<input type="checkbox"/>	Place a wind indicator at appropriate locations.
<input type="checkbox"/>	Establish an entry and exit checkpoint at the periphery of the incident site.
<input type="checkbox"/>	Monitor weather conditions that could hinder the spill response.
<input type="checkbox"/>	Identify area stakeholders and environmental sensitivities.
<input type="checkbox"/>	Identify designated spill control points.
<input type="checkbox"/>	Initiate containment and recovery operations.
<input type="checkbox"/>	Develop a waste management plan.
<input type="checkbox"/>	Develop sampling and analysis strategy.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Establish a bulletin board.
<input type="checkbox"/>	Post site safety plan, SDS, crew roster sheets, status reports, and other relevant information.
<input type="checkbox"/>	Obtain radios and megaphones to direct communications on-site.
<input type="checkbox"/>	Establish first aid station in a visible area with appropriate facilities and supplies.
<input type="checkbox"/>	Establish a decontamination area where responders can remove contaminated clothing, wash up, and return clean equipment.
<input type="checkbox"/>	Create diagrams of response strategies, e.g. trenching berm, setting up a boom, blocking a culvert, etc.

SPILL RESPONSE TEAM

SPILL RESPONSE TEAM	
<b>SPILL RESPONSE TEAM</b>	<b>Level 3</b>
	<input type="checkbox"/> Continue with previous actions.
	<b>Deactivation</b>
	<input type="checkbox"/> Ensure site is safe.
	<input type="checkbox"/> Ensure all work areas, safety and spill equipment, machinery, and tools are cleaned, repaired, and returned to their proper location.
	<input type="checkbox"/> Complete and submit all documents to the On-Site Group Supervisor.
	<input type="checkbox"/> Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/> Participate in any Critical Stress Incident Debriefing, as required.	

Forms	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Spill/Release Written Report Form

### 3.7.4 Security Team

The Security Team is responsible for the security of the site and establishing boundaries to prevent unauthorized entry.

SECURITY TEAM	
<b>Location</b>	
<input type="checkbox"/>	On-Site Command Post.
<b>Takes Direction From</b>	
<input type="checkbox"/>	On-Site Group Supervisor.
<b>Confers With</b>	
<input type="checkbox"/>	On-Site Team.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Security Personnel.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Investigate and report a security breach that has the potential to impact people, property, or the environment.
<input type="checkbox"/>	Monitor and ensure security of the site.
<input type="checkbox"/>	Develop security guidelines for the site and potentially affected area.
<input type="checkbox"/>	Establish communication with the On-Site Group Supervisor at scheduled intervals.
<input type="checkbox"/>	Implement Incident Action Plan in coordination with the On-Site Group Supervisor.
<input type="checkbox"/>	Establish a security perimeter.
<input type="checkbox"/>	Control access to the incident site of non-essential personnel.
<input type="checkbox"/>	Report any significant or unusual activities immediately to the On-Site Group Supervisor.
<b>Deactivation</b>	
<input type="checkbox"/>	Complete and submit all documents to the On-Site Group Supervisor.
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in any Critical Stress Incident Debriefing, as required.
<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Roadblock Checkpoint Record

SECURITY TEAM

### 3.7.5 Ignition Team

The Ignition Team is responsible for reviewing pre-ignition considerations, preparing ignition equipment and assembling a trained ignition team in the event that ignition criteria is met.

IGNITION TEAM	
<b>Location</b>	
<input type="checkbox"/>	On-Site Command Post.
<b>Takes Direction From</b>	
<input type="checkbox"/>	On-Site Group Supervisor in coordination with the Site Operations Section Chief and Incident Commander.
<b>Confers With</b>	
<input type="checkbox"/>	On-Site Team.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Ignition Team Members.
<b>Alert/Minor</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Consider safety and health risks to emergency personnel.
<input type="checkbox"/>	Consider proximity of release to public areas.
<input type="checkbox"/>	Consider availability of air monitoring equipment and personnel.
<input type="checkbox"/>	Consider detectable concentrations of H <sub>2</sub> S and/or flammable gases near the source of the release and within the EPZ.
<input type="checkbox"/>	Consider weather conditions.
<input type="checkbox"/>	Consider duration of the release and potential volume.
<input type="checkbox"/>	Consider impacts to livestock.
<input type="checkbox"/>	Consider impacts to other values at risk including property, timber, or infrastructure.
<b>Level 1</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Establish communication with the On-Site Group Supervisor.
<input type="checkbox"/>	Implement Incident Action Plan in coordination with the On-Site Group Supervisor.
<input type="checkbox"/>	Review ignition procedures.
<input type="checkbox"/>	Review ignition criteria.
<input type="checkbox"/>	Review flare gun manufacturer's loading instructions and specifications.
<input type="checkbox"/>	Prepare ignition equipment.
<input type="checkbox"/>	Review training of ignition team members.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Assemble an adequate ignition team, ideally containing four members but never fewer than two members so that there is at least one person for rescue backup.
<input type="checkbox"/>	Carry out pre-ignition planning.
<input type="checkbox"/>	Monitor the area for combustible gas.
<input type="checkbox"/>	Erect windsock and streamers, if time permits.
<input type="checkbox"/>	If it is not an urgent situation and time permits, consultation with the On-Site Group Supervisor, Operations Section Chief, Incident Commander, EOC Operations and Technical Support, and Regulatory authorities should be made regarding ignition.
<b>Level 3</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Assemble an adequate ignition team, ideally containing four members but never with fewer than two members so that there is one person for rescue backup.
<input type="checkbox"/>	Carry out pre-ignition planning.
<input type="checkbox"/>	Monitor the area for combustible gas.
<input type="checkbox"/>	If time permits, consultation with the On-Site Group Supervisor, Operations Section Chief, Incident Commander, EOC Operations and Technical Support, and Regulatory authorities should be made regarding ignition.

IGNITION TEAM

IGNITION TEAM	
<b>IGNITION TEAM</b>	<b>Deactivation</b>
	<input type="checkbox"/> Ensure all work areas, safety equipment, machinery and tools are cleaned, repaired and returned to their proper location.
	<input type="checkbox"/> Complete and submit all documents to the On-Site Group Supervisor.
	<input type="checkbox"/> Participate in the post-incident debriefing held by the Incident Commander.
	<input type="checkbox"/> Participate in any Critical Stress Incident Debriefing, as required.

Forms	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	Stakeholder Contact Record
<input type="checkbox"/>	Environmental Monitoring Record

### 3.8 Staging Area Manager

The Staging Area Manager oversees and controls the movement of equipment, services, and personnel at the staging area.

STAGING AREA MANAGER	
<b>Location</b>	
<input type="checkbox"/>	Location not pre-determined.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Operations Section Chief.
<b>Confers With</b>	
<input type="checkbox"/>	On-Site Team.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Contractors and suppliers.
<b>Alert/Minor</b>	
<input type="checkbox"/>	No assigned duties during an alert/minor.
<b>Level 1</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Proactively review area map to identify potential staging areas near the incident site and outside of the EPZ.
<input type="checkbox"/>	Ensure potential staging area has an adequately sized site that is stable and level with suitable access roads.
<input type="checkbox"/>	Ensure potential staging area has no entry problems such as narrow approach ways, gates, power lines, etc.
<input type="checkbox"/>	Ensure potential staging area has adequate communication reception.
<b>Level 2</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Ensure approval has been obtained from landowner.
<input type="checkbox"/>	Establish a staging area.
<input type="checkbox"/>	Erect staging area information and directional signs to the staging area, if required.
<input type="checkbox"/>	Flag the perimeter of the staging area.
<input type="checkbox"/>	Obtain an office trailer and emergency lighting, if required.
<input type="checkbox"/>	Advise the Operations Section Chief about the location and directions to the staging area.
<input type="checkbox"/>	Respond to Operations Section Chief's request for resources.
<input type="checkbox"/>	Coordinate and maintain a log of personnel and services.
<input type="checkbox"/>	Maintain a copy of the ICS 211 - Check-In List, provide a completed copy of all resources that are available, in use, and out of service to the Operations Section Chief and EOC Business Impact Support.
<b>Level 3</b>	
<input type="checkbox"/>	Continue with previous actions.
<input type="checkbox"/>	Continue coordinating staging area operations support requirements until incident is concluded.
<b>Deactivation</b>	
<input type="checkbox"/>	Demobilize or move staging area in accordance with incident demobilization plan.
<input type="checkbox"/>	Remove all equipment and supplies and coordinate clean-up of the staging area.
<input type="checkbox"/>	Participate in post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in any Critical Incident Stress Debriefing, as required.
<b>Forms</b>	
<input type="checkbox"/>	ICS 211 – Check-In List
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix

STAGING AREA MANAGER

### 3.9 Safety Officer

The role of the Safety Officer is to develop and recommend measures for assuring the safety of all personnel, as well as to assess and anticipate hazardous situations. The Safety Officer reviews the site Incident Action Plan for safety concerns and discontinues any operation which threatens the health and safety of responders.

SAFETY OFFICER	
<b>Location</b>	
<input type="checkbox"/>	Incident Command Post.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Incident Commander.
<b>Confers With</b>	
<input type="checkbox"/>	Section Chiefs.
<input type="checkbox"/>	Liaison Officers.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Operations Section Chief.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Continually evaluate risks and identify hazardous situations associated with the incident.
<input type="checkbox"/>	Assertively make safety concerns known to the Incident Commander.
<input type="checkbox"/>	Exercise emergency authority to stop and prevent unsafe acts.
<input type="checkbox"/>	Prepare ICS 215A – Incident Action Plan Safety Analysis, collaborate with the Operations Section Chief in the development of the ICS 215A.
<input type="checkbox"/>	Confirm all workers have required training before they are dispatched to the incident.
<input type="checkbox"/>	Prepare ICS 206 – Medical Plan for the operational period. To be provided to all Command and General Staff as part of the Incident Action Plan (IAP).
<input type="checkbox"/>	Prepare ICS 208 - Safety Message / Plan for the operational period - can be included as part of the IAP.
<input type="checkbox"/>	Review the complete Incident Action Plan for safety implications.
<input type="checkbox"/>	Complete safety message for operation period on the Incident Action Plan.
<input type="checkbox"/>	Conduct responder safety orientations, if required.
<input type="checkbox"/>	Ensure the proper use of personal protective equipment.
<input type="checkbox"/>	Ensure that responder personnel are taking appropriate actions; safe work procedures, proper grounding, bonding procedures, working in teams, etc.
<input type="checkbox"/>	Ensure workers who show signs of stress, fatigue or adverse symptoms are demobilized and sent for treatment, if necessary.
<input type="checkbox"/>	Recommend alternatives for activities which are considered to be unsafe.
<input type="checkbox"/>	Ensure incident casualties receive first aid and ongoing care.
<input type="checkbox"/>	If any serious injuries occur, ensure the incident scene remains undisturbed, if possible, until there has been a thorough investigation.
<input type="checkbox"/>	Investigate accidents that have occurred within the incident area.
<input type="checkbox"/>	Document all injuries and on-site medical treatments.
<input type="checkbox"/>	Review and approve the medical plan if implemented.
<input type="checkbox"/>	Ensure safe and adequate lighting is in place as required.
<input type="checkbox"/>	Ensure only intrinsically safe radios are used in the incident area.
<input type="checkbox"/>	Ensure that nobody, including contract personnel, works alone.
<input type="checkbox"/>	Participate in planning meetings.
<input type="checkbox"/>	Continue to follow up and maintain safety responsibilities.
<b>Deactivation</b>	
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.

SAFETY OFFICER

<b>Forms</b>	
<input type="checkbox"/>	ICS 206 – Medical Plan
<input type="checkbox"/>	ICS 208 – Safety Message / Plan
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 215A – Incident Action Plan Safety Analysis
<input type="checkbox"/>	Environmental Monitoring Record

### 3.10 Liaison Officer

The Liaison Officer interfaces with field government agency representatives who arrive at the Incident Command Post. The objective of the Liaison Officer is to ensure there is collaborative communication with the field government agency representatives and to report communications to the Incident Commander.

LIAISON OFFICER	
<b>Location</b>	
<input type="checkbox"/>	Incident Command Post.
<input type="checkbox"/>	Government Emergency Operations Centre (Level 2 and 3).
<b>Takes Direction From</b>	
<input type="checkbox"/>	Incident Commander.
<b>Confers With</b>	
<input type="checkbox"/>	Section Chiefs.
<input type="checkbox"/>	Safety Officer.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Receive briefing from Incident Commander.
<input type="checkbox"/>	Evaluate which government agencies have jurisdiction inside the planning zone.
<input type="checkbox"/>	In coordination with the Incident Commander, ensure Regulatory Authority notification according to the applicable requirements.
<input type="checkbox"/>	Refer to the Notification Requirements for Key Government Agencies and Resources in the Jurisdictional section of this document.
<input type="checkbox"/>	Determine which government and regulatory notifications have been completed.
<input type="checkbox"/>	Receive representatives from the Regulatory Authority, the local authority, and local regional health authority, at the Incident Command Post, if they arrive on-scene.
<input type="checkbox"/>	Coordinate the flow of information to and from the government agencies who are present.
<input type="checkbox"/>	Update the Incident Commander.
<input type="checkbox"/>	Travel to the Government Emergency Operations Centre, if necessary.
<b>Deactivation</b>	
<input type="checkbox"/>	Participate in post-incident debriefing held by Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.
<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Status Board

LIAISON OFFICER

### 3.11 Information Officer

The Information Officer will develop a communication strategy to ensure information and releases are appropriate, consistent, accurate, and timely. He/she implements the communication plan, providing media information support and serving as the dissemination point for all media releases.

The Information Officer ensures the affected public receives ongoing information about emergency status, relief programs, and services.

INFORMATION OFFICER	
<b>Location</b>	
<input type="checkbox"/>	Emergency Operations Centre.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Incident Commander
<b>Confers With</b>	
<input type="checkbox"/>	Section Chiefs.
<input type="checkbox"/>	Liaison Officer.
<input type="checkbox"/>	EOC Director
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Prepare telephone response for Company receptionists.
<input type="checkbox"/>	Contact the Emergency 24-hour number attendant, if applicable and/or the Company Field Office to ensure all media enquiries are directed to the Information Officer.
<input type="checkbox"/>	Monitor communication issues and incorporate into communications plan.
<input type="checkbox"/>	Ensure communication channels are established and maintained with appropriate stakeholders.
<input type="checkbox"/>	Assess media impacts and ensure concerns are clearly identified.
<input type="checkbox"/>	Prepare all media responses with the assistance of the Incident Commander/EOC Director.
<input type="checkbox"/>	Establish media notification schedules.
<input type="checkbox"/>	Ensure all media releases are approved by the applicable Regulatory Authority prior to release.
<input type="checkbox"/>	Organize news conferences.
<input type="checkbox"/>	Dispatch personnel to field locations, media information centres and/or Government Emergency Operations Centre, if applicable.
<input type="checkbox"/>	Ensure all other external requests are redirected to the appropriate recipient.
<b>Deactivation</b>	
<input type="checkbox"/>	If required, continue media and public interaction.
<input type="checkbox"/>	Upon direction from the Liaison Officer in coordination with the Regulatory Authority, prepare a media statement regarding the downgrade of the emergency.
<input type="checkbox"/>	Participate in post-incident debriefing held by Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.
<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix

INFORMATION OFFICER

Use this template following the onset of an incident.

<b>EMERGENCY COMMUNICATION PLANNING TEMPLATE</b>	
<b>EMERGENCY COMMUNICATION PLANNING TEMPLATE</b>	<input type="checkbox"/> Identify the Communication Team.
	<input type="checkbox"/> Activate Communication Team.
	<input type="checkbox"/> Communication Team meets to assess the situation and develop communication strategies
	<input type="checkbox"/> Information Officer meets with Incident Commander/EOC Director to determine the response and message.
	<input type="checkbox"/> Communication Team prepares initial internal and external communication statements.
	<input type="checkbox"/> Ensure communication statements and strategy are reviewed and approved by Incident Commander.
	<input type="checkbox"/> Information Officer delivers initial internal and external messages in coordination with the applicable Regulatory Authority.
	<input type="checkbox"/> Communication Team updates company website information regarding the emergency.
	<input type="checkbox"/> Communication Team coordinates meetings with media and delivers approved messages.
	<input type="checkbox"/> Communication Team obtains regular status reports from Incident Commander.
	<input type="checkbox"/> Communication Team prepares and distributes status reports regularly on the communication situation.
	<input type="checkbox"/> Communication Team prepares and delivers regular updates to stakeholders, government agencies and other relevant entities.
	<input type="checkbox"/> Communication Team prepares and delivers messages on resolution of the emergency.
	<input type="checkbox"/> Communication Team provides ongoing updates to internal and external parties as the situation is resolved.
	<input type="checkbox"/> Communication Team is advised by Incident Commander that the emergency is over.
	<input type="checkbox"/> Communication Team stands down once the emergency has been resolved.
	<input type="checkbox"/> Communication Team prepares, and issues post-incident reports as needed to internal and external parties.
<input type="checkbox"/> Communication Team conducts post-incident review of and revision to the Crisis Communication Plan.	

### 3.11.1 Scribe

The Scribe provides documentation and administrative assistance to the Incident Command Post. This includes the recording of meeting minutes, information filing, and reproduction tasks. If required, a Scribe may be assigned to solely maintain a written record of the incident response.

<b>SCRIBE</b>	
<b>Location</b>	
<input type="checkbox"/>	Incident Command Post.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Incident Commander.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Maintain a chronological summary of the incident response activities.
<input type="checkbox"/>	Record names of personnel in each assigned response position and their location utilizing ICS 211 – Check-In List and ICS 207 – Incident Organization Chart.
<input type="checkbox"/>	Record control and containment measures.
<input type="checkbox"/>	Record environmental monitoring information.
<input type="checkbox"/>	Record injuries, deaths, and missing persons.
<input type="checkbox"/>	Record phone calls.
<input type="checkbox"/>	Record decisions.
<input type="checkbox"/>	Record actions.
<input type="checkbox"/>	Record status of the public protection actions.
<input type="checkbox"/>	Collect documentation from response team members.
<input type="checkbox"/>	Maintain a consistent system for organizing the data.
<b>Deactivation</b>	
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.

**SCRIBE**

<b>Forms</b>	
<input type="checkbox"/>	ICS 207 – Incident Organization Chart (may be completed by Site Planning Section Chief, if assigned)
<input type="checkbox"/>	ICS 211 – Check-In List
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	Environmental Monitoring Record
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Status Board

### 3.12 Planning Section Chief

The Planning Section Chief is responsible for strategic planning, evaluating and processing information for use in the development of the Incident Action Plan. Disseminating information can be in the form of the Incident Action Plan, formal briefings, or status board displays.

PLANNING SECTION CHIEF	
<b>Location</b>	
<input type="checkbox"/>	Incident Command Post.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Incident Commander.
<b>Confers With</b>	
<input type="checkbox"/>	Section Chiefs.
<input type="checkbox"/>	Liaison.
<input type="checkbox"/>	Safety Officer.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Section Chiefs.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Prepare the ICS 202 – Incident Objectives Form following each Command and General Staff Meeting. Obtain sign-off from Incident Commander prior to dissemination as part of the Incident Action Plan.
<input type="checkbox"/>	Prepare for the Planning Meeting, Review ICS 215 – Operational Planning Worksheet developed in the Tactics Meeting. Review ICS 215A – Incident Action Plan Safety Analysis – prepared by the Safety Officer.
<input type="checkbox"/>	Assess current operations effectiveness and resource efficiency, gather information to support incident management decisions.
<input type="checkbox"/>	Facilitate Planning Meeting with Command and General Staff. Review. Validate the operational plan as proposed by the Operations Section Chief.
<input type="checkbox"/>	Prepare the ICS 203 – Organization Assignment List with information on all positions currently activated, include the names of personnel staffing each position. ICS 203 serves as part of the Incident Action Plan.
<input type="checkbox"/>	Compile the complete Incident Action Plan to include ICS 202 – Incident Objectives, ICS 203 Organization Assignment List, ICS 204 – Assignment List, ICS 206 Medical Plan and possibly ICS 208 Safety Message Plan.
<input type="checkbox"/>	Distribute Incident Action Plan to the Incident Commander for approval prior to disseminating to Command and General Staff.
<input type="checkbox"/>	Assess the current situation and prepare an incident response strategy considering “what if” scenarios.
<input type="checkbox"/>	Assemble information and propose alternative strategies.
<input type="checkbox"/>	Compile and display incident information on the Status Board.
<input type="checkbox"/>	Using the information contained within the ICS 203 – Organization Assignment List, continuously monitor and update ICS 207 – Incident Organization Chart.
<input type="checkbox"/>	In a prolonged incident, ensure site response strategies are considered. Develop the ICS 209 – Incident Status Summary, as required.
<b>Deactivation</b>	
<input type="checkbox"/>	Develop plan for demobilization. Utilize ICS 221 – Demobilization Check-Out Form.
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.

PLANNING SECTION CHIEF

Forms	
<input type="checkbox"/>	ICS 202 – Incident Objectives
<input type="checkbox"/>	ICS 203 – Organization Assignment List
<input type="checkbox"/>	ICS 207 – Incident Organization Chart
<input type="checkbox"/>	ICS 209 – Incident Status Summary (to be completed following a significant incident)
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 221 – Demobilization Check-Out
<input type="checkbox"/>	ICS 230 – Daily Meeting Schedule

### 3.13 Logistics Section Chief

The Logistics Section Chief assists the response effort by procuring equipment and support services.

LOGISTICS SECTION CHIEF	
<b>Location</b>	
<input type="checkbox"/>	Incident Command Post.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Incident Commander.
<b>Confers With</b>	
<input type="checkbox"/>	Section Chiefs.
<input type="checkbox"/>	Liaison Officer.
<input type="checkbox"/>	Safety Officer.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Section Chiefs.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Develop and implement Incident Action Plan in coordination with the Section Chiefs and Incident Commander.
<input type="checkbox"/>	Procure supplies.
<input type="checkbox"/>	Procure transportation services.
<input type="checkbox"/>	Procure equipment.
<input type="checkbox"/>	Procure manpower.
<input type="checkbox"/>	Procure communications systems.
<input type="checkbox"/>	Procure oil spill contractor/cooperative services.
<input type="checkbox"/>	Procure catering services for the responders.
<input type="checkbox"/>	In a prolonged incident, identify and obtain accommodations for responders.
<b>Deactivation</b>	
<input type="checkbox"/>	Notify all services and suppliers of the stand-down of the incident.
<input type="checkbox"/>	Forward all data related to the incident to the Incident Commander.
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.
<b>LOGISTICS SECTION CHIEF</b>	
<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix

### 3.14 Finance/Admin Section Chief


The Finance/Admin Section Chief is responsible for tracking cost, time compensation and claims. This role, when filled by field personnel, is to provide financial administrative support to the EOC.

FINANCE SECTION CHIEF	
<b>Location</b>	
<input type="checkbox"/>	Incident Command Post.
<b>Takes Direction From</b>	
<input type="checkbox"/>	Incident Commander.
<b>Confers With</b>	
<input type="checkbox"/>	Section Chiefs.
<input type="checkbox"/>	Liaison Officer.
<input type="checkbox"/>	Safety Officer.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Obtain briefings from the Incident Commander.
<input type="checkbox"/>	Account for costs.
<input type="checkbox"/>	Track time.
<input type="checkbox"/>	Adhere to procurement procedures.
<input type="checkbox"/>	Track compensation and claims.
<input type="checkbox"/>	Attend planning meetings.
<input type="checkbox"/>	Submit reports and expense claims to the EOC Financial Department.
<b>Deactivation</b>	
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.
<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	Evacuee Expense Claim Form

FINANCE SECTION CHIEF

## 4.0 EOC INCIDENT COMMAND STRUCTURE - ROLES AND RESPONSIBILITIES

### 4.1 EOC Command Chart



## 4.2 EOC Director

The EOC Director is responsible for coordination of response efforts from corporate to support the Field Response Team (FRT) and for efforts to ensure business continuity during the incident. The EOC Director coordinates the actions upon request of the Incident Commander. The EOC Director is the main link between the Field Response Team and the Emergency Support Team and is the main informant for the Emergency Support Team.

EOC DIRECTOR	
<b>Location</b>	
<input type="checkbox"/>	Emergency Operations Centre.
<b>Confers With</b>	
<input type="checkbox"/>	Corporate Executive Team.
<b>Gives Direction To</b>	
<input type="checkbox"/>	EOC Leaders.
<input type="checkbox"/>	Regulatory / Government Liaison.
<input type="checkbox"/>	Communications / Media.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Advise the Corporate Executive Team.
<input type="checkbox"/>	In consultation with EOC Operations and Technology Support, develop and implement a comprehensive response plan for the incident.
<input type="checkbox"/>	Evaluate EOC Operations and Technology Support's actions.
<input type="checkbox"/>	Make EOC Operations and Technology Support aware of external expertise and services that can be provided.
<input type="checkbox"/>	Ensure personnel and expertise from Engineering, Human Resources, and Legal are available as required to support the incident response activities.
<input type="checkbox"/>	Confirm the status of the incident.
<input type="checkbox"/>	Estimate the maximum impact and duration of the incident.
<input type="checkbox"/>	Determine the impact on the public.
<input type="checkbox"/>	Determine business continuity issues.
<input type="checkbox"/>	Advise on corporate responsibilities.
<input type="checkbox"/>	Advise on any internal company policies.
<input type="checkbox"/>	Identify agencies (government and regulatory) with jurisdiction related to the incident.
<input type="checkbox"/>	If incident escalates ensure that the Regulatory / Government Liaison Officer role is filled.
<input type="checkbox"/>	Ensure that Regulatory / Government Liaison Officer is coordinating communication between government agencies and company personnel as required.
<input type="checkbox"/>	Ensure ongoing internal communication, as appropriate.
<input type="checkbox"/>	Approve major capital financial support as required.
<input type="checkbox"/>	Advise and support Communications / Media regarding media and public statements.
<b>Deactivation</b>	
<input type="checkbox"/>	Ensure the Regulatory / Government Liaison Officer, in coordination with the Regulatory Authority agree that there is consensus to downgrade emergency.
<input type="checkbox"/>	Ensure the Regulatory / Government Liaison Officer has notified all previously contacted government agencies of the decision to downgrade the emergency.
<input type="checkbox"/>	Ensure all records and reports are gathered in their original state, for accurate post-incident review.
<input type="checkbox"/>	Ensure all EOC Team Members are notified.
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.
<input type="checkbox"/>	Approve final release of incident reports in coordination with the legal department.
<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log.

EOC DIRECTOR

### 4.3 Operations and Technology Support

Operations and Technology Support is the main link between Site Command, the Emergency Operations Centre and is the main informant for the EOC Director. Operations and Technology Support speaks directly with the Incident Commander.

Operations and Technology Support provides operational, public safety, planning and logistics advice and support to assist the Incident Commander with developing an effective field Incident Action Plan (IAP).

OPERATIONS AND TECHNOLOGY SUPPORT	
<b>Location</b>	
<input type="checkbox"/>	Emergency Operations Centre.
<b>Takes Direction From</b>	
<input type="checkbox"/>	EOC Director.
<b>Confers With</b>	
<input type="checkbox"/>	EOC Leaders.
<input type="checkbox"/>	Regulatory / Government Liaison.
<input type="checkbox"/>	Communications/Media.
<b>Gives Direction To</b>	
<input type="checkbox"/>	Incident Commander.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Establish method of communications with the Incident Commander.
<input type="checkbox"/>	Schedule regular briefings with the Incident Commander.
<input type="checkbox"/>	Dedicate a phone line to the Incident Commander.
<input type="checkbox"/>	Confer with the Incident Commander to ascertain the level of emergency.
<input type="checkbox"/>	Activate the EOC.
<input type="checkbox"/>	Appoint EOC team members.
<input type="checkbox"/>	Complete the EOC team and site command team assignment charts.
<input type="checkbox"/>	Schedule regular briefings with the EOC team members and clarify objectives as necessary.
<input type="checkbox"/>	Ensure the Status Board and ICS 234 - Work Analysis Matrix are prominently displayed in the EOC.
<input type="checkbox"/>	Develop Incident Action Plan in coordination with the EOC team members and Incident Commander.
<input type="checkbox"/>	Ensure public protection and responder safety issues are being addressed.
<input type="checkbox"/>	Discuss actions with the Incident Commander and provide support until situation is normalized.
<input type="checkbox"/>	Verify the boundaries of the emergency response planning zones.
<input type="checkbox"/>	Discuss shelter and/or evacuation plan, as required.
<input type="checkbox"/>	Discuss transient surveys plan, as required.
<input type="checkbox"/>	Discuss mobile air quality monitoring plan, as required.
<input type="checkbox"/>	Discuss the area isolation and roadblock plan, as required.
<input type="checkbox"/>	Discuss Fire Hazard Order/Closure Order and NOTAM (Notice to Airmen) if necessary.
<input type="checkbox"/>	Verify that adequate containment and recovery measures are initiated.
<input type="checkbox"/>	Evaluate which government agencies have jurisdiction inside the emergency response zones.
<input type="checkbox"/>	In coordination with the Incident Commander, ensure Regulatory Authority notification according to the applicable requirements.
<input type="checkbox"/>	Refer to the Notification Requirements for Key Government Agencies and Resources in the Jurisdictional section of this document.
<input type="checkbox"/>	Designate Regulatory / Government Liaison and direct him/her to communicate with Regulatory Authority, environmental agency, health authority, local authority, occupational health and safety authority, and pressure vessel authority.
<input type="checkbox"/>	Ensure Regulatory Authority notification according to the applicable requirements.
<input type="checkbox"/>	Ensure the applicable reporting form has been completed and submitted to the applicable Regulatory Authority.

OPERATIONS AND TECHNOLOGY SUPPORT

**OPERATIONS AND TECHNOLOGY SUPPORT**
**OPERATIONS AND TECHNOLOGY SUPPORT**

<input type="checkbox"/>	Ensure confirmation of the level of emergency with Regulatory Authority.
<input type="checkbox"/>	Notify the applicable Regulatory Authority if the public or media has been contacted.
<input type="checkbox"/>	Evaluate ignition criteria and communicate with the Incident Commander and applicable Regulatory Authority regarding ignition decision.
<input type="checkbox"/>	Ensure other required government authorities have been notified (e.g. environmental agency, local health authority, local authority, occupational health and safety authority, and pressure vessel authority).
<input type="checkbox"/>	Ensure monitoring data is being provided to the appropriate regulatory agencies via the Regulatory/Government Liaison.
<input type="checkbox"/>	Assess the potential for media interest and the need to notify Communications/Media or Information Officer.
<input type="checkbox"/>	Direct media communication to Communications/Media or Information Officer.
<input type="checkbox"/>	Ensure communication with all previously contacted agencies is maintained throughout the incident duration at set frequencies, until the incident is downgraded.
<input type="checkbox"/>	Assess corporate responsibility with regards to health, environment, community, and business impacts including joint venture partner notification.
<input type="checkbox"/>	Keep the EOC Director and Corporate Executive Team advised of ongoing events.
<input type="checkbox"/>	Discuss business continuity concerns with EOC Director.
<input type="checkbox"/>	Assess the incident situation with regards to both short and long-term implications.
<input type="checkbox"/>	For prolonged incidents, ensure provisions for relieving and rotating staff on a regular basis.
<b>Deactivation</b>	
<input type="checkbox"/>	In consultation with the Incident Commander and the applicable Regulatory Authority, downgrade the emergency.
<input type="checkbox"/>	In consultation with the applicable Regulatory Authority, ensure the Fire Hazard Order/Closure Order and NOTAM are lifted, if necessary.
<input type="checkbox"/>	Ensure all appropriate agencies previously notified of the emergency are notified of the stand-down of the emergency.
<input type="checkbox"/>	Ensure all evacuees are notified of the stand-down of the emergency.
<input type="checkbox"/>	In consultation with Communications/Media, ensure the media is notified of the stand-down of emergency.
<input type="checkbox"/>	Confirm with the Incident Commander that all evacuees are being assisted in returning to their residences/businesses.
<input type="checkbox"/>	Ensure follow-up meetings are held with affected residents/landowners.
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Ensure Critical Incident Stress Debriefing for responders is coordinated by the Human Resources Department.
<input type="checkbox"/>	Participate in any Critical Incident Stress Debriefing.

<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Notification Record
<input type="checkbox"/>	Status Board

#### 4.4 Regulatory / Government Liaison

Provides regulatory guidance and advice to the EST as well as to be a liaison between responding government agencies and the company. The Regulatory / Government Liaison is responsible for providing support to the field Liaison Officer

REGULATORY/GOVERNMENT LIAISON	
<b>Location</b>	
<input type="checkbox"/>	Emergency Operations Centre.
<input type="checkbox"/>	Government Emergency Operations Centre (Level 2 and 3).
<b>Takes Direction From</b>	
<input type="checkbox"/>	EOC Director.
<b>Confers With</b>	
<input type="checkbox"/>	EOC Leaders.
<input type="checkbox"/>	Communications/Media.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Receive briefing from Operations and Technology Support.
<input type="checkbox"/>	Evaluate which government agencies have jurisdiction inside the planning zone and response zones.
<input type="checkbox"/>	In coordination with the EOC Operations Chief, ensure Regulatory Authority notification according to the applicable requirements.
<input type="checkbox"/>	Refer to the Notification Requirements for Key Government Agencies and Resources in the Jurisdictional section of this document.
<input type="checkbox"/>	Determine which government and regulatory notifications have been completed.
<input type="checkbox"/>	Develop a communication strategy with those government agencies who need to be contacted.
<input type="checkbox"/>	Address inquiries from and obtain information required by the government agencies.
<input type="checkbox"/>	Fill out and submit the forms as provided by the applicable government and/or Regulatory Authority.
<input type="checkbox"/>	Coordinate the flow of communication to and from the government agencies.
<input type="checkbox"/>	Coordinate the use of expertise and resources available through the government agencies.
<input type="checkbox"/>	Travel to the Government Emergency Operations Centre, if necessary.
<input type="checkbox"/>	Update all previous contacts of change in status.
<b>Deactivation</b>	
<input type="checkbox"/>	In coordination with the Regulatory Authority ensure that there is consensus to downgrade the emergency.
<input type="checkbox"/>	Notify all previously contacted government agencies of the decision to downgrade the emergency.
<input type="checkbox"/>	Participate in post-incident debriefing held by Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.

REGULATORY/GOVERNMENT LIAISON

Forms	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	Government/Regulatory Reporting Form
<input type="checkbox"/>	Status Board

#### 4.5 Communications / Media

Communications / Media will develop a communication strategy to ensure information and releases are appropriate, consistent, accurate, and timely. He/she implements the communication plan, providing media information support and serving as the dissemination point for all media releases.

Communications / Media ensures the affected public receives ongoing information about emergency status, relief programs, and services.

COMMUNICATIONS / MEDIA	
<b>Location</b>	
<input type="checkbox"/>	Emergency Operations Centre.
<b>Takes Direction From</b>	
<input type="checkbox"/>	EOC Director.
<b>Confers With</b>	
<input type="checkbox"/>	EOC Leaders.
<input type="checkbox"/>	Regulatory / Government Liaison.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Prepare telephone response for Company receptionists.
<input type="checkbox"/>	Contact the Emergency 24-hour number attendant, if applicable and/or the Company Field Office to ensure all media enquiries are directed to the field Information Officer.
<input type="checkbox"/>	Monitor communication issues and incorporate into communications plan.
<input type="checkbox"/>	Ensure communication channels are established and maintained with appropriate stakeholders.
<input type="checkbox"/>	Assess media impacts and ensure concerns are clearly identified.
<input type="checkbox"/>	Prepare all media responses with the assistance of the EOC Director.
<input type="checkbox"/>	Establish media notification schedules.
<input type="checkbox"/>	Ensure all media releases are approved by the applicable Regulatory Authority prior to release.
<input type="checkbox"/>	Organize news conferences.
<input type="checkbox"/>	Dispatch personnel to field locations, media information centres and/or Government Emergency Operations Centre, if applicable.
<input type="checkbox"/>	Ensure all other external requests are redirected to the appropriate recipient.
<b>Deactivation</b>	
<input type="checkbox"/>	If required, continue media and public interaction.
<input type="checkbox"/>	Upon direction from the Regulatory/Government Liaison in coordination with the Regulatory Authority, prepare a media statement regarding the downgrade of the emergency.
<input type="checkbox"/>	Participate in post-incident debriefing held by Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.
<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix

COMMUNICATIONS / MEDIA

Use this template following the onset of an incident.

<b>EMERGENCY COMMUNICATION PLANNING TEMPLATE</b>	
<b>EMERGENCY COMMUNICATION PLANNING TEMPLATE</b>	<input type="checkbox"/> Identify the Communication Team.
	<input type="checkbox"/> Activate Communication Team.
	<input type="checkbox"/> Communication Team meets to assess the situation and develop communication strategies
	<input type="checkbox"/> Communications / Media meets with EOC Director to determine the response and message.
	<input type="checkbox"/> Communication Team prepares initial internal and external communication statements.
	<input type="checkbox"/> Ensure communication statements and strategy are reviewed and approved by EOC Director.
	<input type="checkbox"/> Field Information Officer delivers initial internal and external messages in coordination with the applicable Regulatory Authority.
	<input type="checkbox"/> Communication Team updates company website information regarding the emergency.
	<input type="checkbox"/> Communication Team coordinates meetings with media and delivers approved messages.
	<input type="checkbox"/> Communication Team obtains regular status reports from EOC Director.
	<input type="checkbox"/> Communication Team prepares and distributes status reports regularly on the communication situation.
	<input type="checkbox"/> Communication Team prepares and delivers regular updates to stakeholders, government agencies and other relevant entities.
	<input type="checkbox"/> Communication Team prepares and delivers messages on resolution of the emergency.
	<input type="checkbox"/> Communication Team provides ongoing updates to internal and external parties as the situation is resolved.
	<input type="checkbox"/> Communication Team is advised by EOC Director that the emergency is over.
	<input type="checkbox"/> Communication Team stands down once the emergency has been resolved.
	<input type="checkbox"/> Communication Team prepares, and issues post-incident reports as needed to internal and external parties.
<input type="checkbox"/> Communication Team conducts post-incident review of and revision to the Crisis Communication Plan.	

#### 4.6 Business Impact Support

The role of business impact support is to identify and work to mitigate all of the negative impacts of the incident on the business as well as to provide business advice and support. Business Impact Support provides support to the company in the areas of finance / accounting, legal, marketing, risk management and insurance.

BUSINESS IMPACT SUPPORT	
<b>Location</b>	
<input type="checkbox"/>	Emergency Operations Centre.
<b>Takes Direction From</b>	
<input type="checkbox"/>	EOC Director.
<b>Confers With</b>	
<input type="checkbox"/>	EOC Leaders.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Review the Incident Action Plan for business impact implications.
<input type="checkbox"/>	Determine the severity and impact of business interruption to the company; loss of service, supply chain interruptions, catastrophic loss of critical infrastructure, etc.
<input type="checkbox"/>	Establish which critical services/functions may be required for the response to the emergency.
<input type="checkbox"/>	Identify the critical functions that need to be reinstated within 24-hours or are time-dependent; IT recovery, supply chain, procurement, vendors, etc.
<input type="checkbox"/>	Aim to maintain the Company's minimum level of service.
<b>Deactivation</b>	
<input type="checkbox"/>	Implement business/disaster/IT recovery procedures.
<input type="checkbox"/>	Acquire the additional resources necessary for restoring business operations.
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing if required.
<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix

BUSINESS IMPACT SUPPORT

#### 4.7 Admin Support

Admin Support provides administrative and technical support to the company in the areas of human resources, information technology, travel, security and reception.

ADMIN SUPPORT	
<b>Location</b>	
<input type="checkbox"/>	Emergency Operations Centre.
<b>Takes Direction From</b>	
<input type="checkbox"/>	EOC Director.
<b>Confers With</b>	
<input type="checkbox"/>	EOC Leaders.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Assess the current situation and support the Incident Action Plans as necessary
<input type="checkbox"/>	Gather specialists (Human Resources, IT, Environmental, Security or Travel) required for the response.
<input type="checkbox"/>	Ensure incident information is documented, current, and disseminated to the supporting team.
<input type="checkbox"/>	Utilize the Status Board, ICS 234 – Work Analysis Matrix and Response Organizational Chart.
<b>Deactivation</b>	
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.

ADMIN SUPPORT

Forms	
<input type="checkbox"/>	ICS 202 – Incident Objectives
<input type="checkbox"/>	ICS 203 – Organization Assignment List
<input type="checkbox"/>	ICS 207 – Incident Organization Chart
<input type="checkbox"/>	ICS 214 – Activity Log
<input type="checkbox"/>	ICS 221 – Demobilization Check-Out
<input type="checkbox"/>	ICS 234 – Work Analysis Matrix
<input type="checkbox"/>	ICS 230 – Daily Meeting Schedule

#### 4.8 EHSS Support

Health, Safety & Environment Support is responsible for providing Health, Safety & Environmental support to the Field Response Team.

EHSS SUPPORT	
<b>Location</b>	
<input type="checkbox"/>	Emergency Operations Centre.
<b>Takes Direction From</b>	
<input type="checkbox"/>	EOC Director.
<b>Confers With</b>	
<input type="checkbox"/>	EOC Leaders.
<input type="checkbox"/>	Incident Commander.
<b>All Levels</b>	
<input type="checkbox"/>	Document all activities utilizing the ICS 214 – Activity Log.
<input type="checkbox"/>	Provide guidance to the EOC team and Field Response Team in terms of Health, Safety and Environmental Support and Resources.
<input type="checkbox"/>	Develop and implement Incident Action Plan in coordination with the EOC Leaders.
<b>Deactivation</b>	
<input type="checkbox"/>	Participate in the post-incident debriefing held by the Incident Commander.
<input type="checkbox"/>	Participate in the Critical Incident Stress Debriefing as required.
<b>EHSS SUPPORT</b>	
<b>Forms</b>	
<input type="checkbox"/>	ICS 214 – Activity Log

## 5.0 COMMAND CENTRES AND RESPONSE LOCATIONS

To coordinate response efforts, the Company and Government will establish various Command Centres to facilitate required actions. These centres represent the location of specific members of the response team and may be set up temporarily (in a vehicle for example) or long-term (field or head office) depending on the nature of the emergency and the availability of a facility. The following Command Centres would be established as required depending upon the nature and seriousness of the incident.

### 5.1 On-Site Command Post (OSCP)

The On-Site Command Post is at 'ground zero' and will be located as close to the actual incident site as possible given safety concerns. This location is where the On-Site Group Supervisor would manage actions to control and mitigate the situation and coordinate subsequent remedial activities.

The On-Site Command Post is the focal point for control and containment activities as well as communications to the Incident Command Post. The Incident Command Post and On-Site Command Post can be located at the same place.

### 5.2 Incident Command Post (ICP)

The Incident Command Post is the location from which the Incident Commander oversees all incident operations. Key field response activities, including public safety actions, are coordinated from this centre. It must have the appropriate equipment and resources, including good communication equipment, to manage the emergency. The ICP will be established near the site of the emergency but outside of the hazard area. Often the Incident Command Post is located in the closest company office, a nearby facility or building. It may be combined with the Regional Emergency Operations Centre.

### 5.3 Staging Area

The decision to establish a staging area will be made by the Operations Section Chief as directed by the Incident Commander. The staging area is a control point for regulating the flow of equipment and services.

The Staging Area is used for the initial drop off of heavy equipment and large numbers of personnel used in an emergency response. This will greatly aid the efficiency and preparedness of all equipment movement into the EPZ when required. Resources in the Staging Area need to be ready for deployment within five minutes from the incident site, if at all possible. When establishing the Staging Area, ensure that it has adequate entrance and exit routes and is on a paved surface, if possible.

### 5.4 Reception Centre

Reception Centres are established in order to provide a safe place for people within an established EPZ, including employees, contractors, and site visitors, to evacuate to during an emergency. Local authorities may have predetermined reception centre locations identified within their Municipal Emergency plan. Early contact with the local authority will ensure a coordinated response between the municipality and Company. A company representative will be assigned to travel to the Reception Centre and coordinate activities along with the Local Authority's representative.

Services provided include registration and inquiry, emergency food services, emergency clothing services, emergency lodging services, and personal services. Arrangements for accommodation, reimbursement of daily expenses and temporary care of evacuated property are managed through the centre.

A Reception Centre is usually required if five or more households are evacuated.

### 5.5 Helibase

A Helibase is a location where aircraft are maintained and fuelled. If helicopter evacuation is or may be a requirement, the helicopter services may be placed on standby at a Level 1 Emergency.

### 5.6 Helispot

The Helispot is the temporary location where the helicopter can land to load or unload evacuees, equipment, and supplies. Rover/Evacuation personnel will be located at each Helispot to assist evacuees including non-essential employees, contractors, and site visitors.

### 5.7 Emergency Operations Centre (EOC)

Significant emergencies impact a business in many ways including reputation loss, regulatory non-compliance, the incurring of legal liabilities, financial loss, etc. During a Hierarchy 2 emergency the EOC Team will assemble and provide support to the affected location.

The EOC is the principal site of response coordination to support the Incident Commander. This is the centre where head office support activities are coordinated, it includes Company representatives with adequate authority, technical, and media relations skills. It is the location where personnel formulate strategies and action plans to manage regional emergency response issues.

The EOC is equipped with the tools, accessibility and space to accommodate the EOC Team and support personnel.

### 5.7.1 Suggested Equipment and Supplies for the EOC

<b>Office Equipment and Supplies</b>	
<input type="checkbox"/> Pens/Pencils	<input type="checkbox"/> Appropriate batteries for all equipment
<input type="checkbox"/> Felt-tip markers	<input type="checkbox"/> Appropriate printer cartridges
<input type="checkbox"/> Dry erase markers	<input type="checkbox"/> Envelopes of various size
<input type="checkbox"/> Coloured grease pencils	<input type="checkbox"/> Light bulbs
<input type="checkbox"/> Pencil sharpeners	<input type="checkbox"/> Paper for flip charts
<input type="checkbox"/> Staples/staplers	<input type="checkbox"/> String
<input type="checkbox"/> Staple removers	<input type="checkbox"/> Photocopy/printer paper
<input type="checkbox"/> Scissors	<input type="checkbox"/> Identification tags/name plates
<input type="checkbox"/> Scotch tape/tape dispenser	<input type="checkbox"/> EOC forms
<input type="checkbox"/> Notepads	<input type="checkbox"/> Laminated Status Board
<input type="checkbox"/> Calculator(s)	<input type="checkbox"/> Laminated ICS 234 – Work Analysis Matrix
<input type="checkbox"/> Elastic bands	<input type="checkbox"/> Clocks
<input type="checkbox"/> File folders	<input type="checkbox"/> Waste baskets/recyclable containers
<input type="checkbox"/> In/Out boxes	<input type="checkbox"/> Stamps (“For Action”, “Completed”, “Approved”)
<input type="checkbox"/> Map tacks/thumb tacks	<input type="checkbox"/> Flashlights
<b>Communications Equipment</b>	
<input type="checkbox"/> Telephones	<input type="checkbox"/> Telephone Conference Unit (Polycom)
<input type="checkbox"/> Phone/computer cables	<input type="checkbox"/> Computers/laptops with networking capability
<input type="checkbox"/> Power boards	<input type="checkbox"/> LCD projector/screen
<input type="checkbox"/> Extension cords	<input type="checkbox"/> Overhead projector
<input type="checkbox"/> Television/DVD player	<input type="checkbox"/> AM/FM radios
<input type="checkbox"/> Digital cameras/video camera	<input type="checkbox"/> Fax machine
<input type="checkbox"/> Memory card(s)/disc(s)/tape(s) for cameras	<input type="checkbox"/> Photocopier
<b>Furnishings</b>	
<input type="checkbox"/> Workstation desks/tables	<input type="checkbox"/> Filing cabinet(s)
<input type="checkbox"/> Conference table(s)	<input type="checkbox"/> Whiteboard(s)
<input type="checkbox"/> Map stand	<input type="checkbox"/> Cork boards
<input type="checkbox"/> Chairs	<input type="checkbox"/> Flip chart stands
<input type="checkbox"/> Bookshelf(ves)	<input type="checkbox"/> Coat rack/hangers
<b>Reference Materials</b>	
<input type="checkbox"/> Updated EOC floor plan	<input type="checkbox"/> Contingency plans
<input type="checkbox"/> Checklists (operational guidelines)	<input type="checkbox"/> Local, area, and regional maps
<input type="checkbox"/> Updated contact/supplier/media lists	<input type="checkbox"/> Aerial photos
<input type="checkbox"/> Current phone/email lists	<input type="checkbox"/> Resource inventories
<input type="checkbox"/> Emergency Response Plans (with extras)	<input type="checkbox"/> CANUTEC guide
<input type="checkbox"/> OHS Standards	<input type="checkbox"/> TDG Regulations
<b>Store Supplies and Dispensary</b>	
<input type="checkbox"/> Paper towels	<input type="checkbox"/> Facial tissue/Kleenex
<input type="checkbox"/> First aid kit	
<b>Food Service Areas</b>	
<input type="checkbox"/> Coffee/tea	<input type="checkbox"/> Pitchers
<input type="checkbox"/> Kettle/tea pot	<input type="checkbox"/> Glasses/paper cups
<input type="checkbox"/> Coffee maker filters/coffee pot	<input type="checkbox"/> Refrigerator/freezer
<input type="checkbox"/> Mugs	<input type="checkbox"/> Stove
<input type="checkbox"/> Food preparation/serving equipment	<input type="checkbox"/> Dishwashing supplies
<input type="checkbox"/> Eating utensils/dinner plates	<input type="checkbox"/> Storage cabinets
<input type="checkbox"/> Food supplies	<input type="checkbox"/> Garbage bags
<input type="checkbox"/> Water	

## 5.8 Government Command Posts

### 5.8.1 Regional Emergency Operations Centre (REOC)

If it is taking a considerable amount of time to bring an emergency under control or if the external support requirements are substantial, the appropriate government agency will establish a REOC in the area.

The REOC is a single operations centre that is established in a suitable location to manage the larger aspects of the emergency and it is managed jointly by government and industry staff. The Regulatory Authority encourages the combination of industry and municipal responses into a single REOC if possible.

This centre has two functions:

1. To provide a central location for addressing the demands and coordinating the services of various government agencies.
2. To provide a centre for public and media interaction.

If a REOC is established, the Company will dispatch a Liaison to the centre to represent the company's view on management, technical, and public affairs issues. The REOC may be combined with a Company command post in order to centralize personnel.


### 5.8.2 Municipal Emergency Operations Centre (MEOC)

The MEOC is activated by the Local Director of Disaster Services to support the local authority's emergency response. The MEOC can assess the capability of Municipal Government services and other available resources necessary to support the emergency response.

### 5.8.3 Government Emergency Operations Centre (GEOC)

If the incident affects more than one local authority, provincial/state involvement may necessitate the need for activation of a GEOC.

## 6.0 CRISIS COMMUNICATION PLAN



## 6.1 Purpose of the Crisis Communication Plan

A crisis communication plan provides policies and procedures for the coordination of communication within the organization and between the organization and any applicable outside agencies (e.g. the media, regulatory agencies, customers, suppliers, stakeholders, and the public) in the event of an emergency or controversial issue.

## 6.2 Crisis Communication Policy

The Company will conduct all aspects of response to a crisis with transparency, timeliness, and honesty and will strive to implement effective communication channels between the Company and all stakeholders in the event of a critical incident.

All communication is designed from the following perspectives:

- Comply with all applicable laws and regulations; making use of industry standards and best practices where appropriate.
- Accept accountability of the operation, of its assets, and the conduct of its employees, contractors, and consultants.
- Communicate openly with all stakeholders.

## 6.3 Crisis Communication Plan Objectives

The Communication Plan Objectives are as follows:

- To factually assess the situation and determine whether a communication response is warranted.
- To assemble personnel who will make recommendations on appropriate responses.
- To implement immediate action to:
  - Identify those parties who should be informed about the situation.
  - Communicate facts about the crisis.
  - Minimize rumours.
  - Restore order and/or confidence.

## 6.4 Crisis Communication Audiences

Important audiences for the Company during an emergency event includes employees, contractors, residents, businesses, visitors, stakeholder organizations, all levels of government, media, and the general public who are considered to be at risk. Priority in messaging will be given to those considered at greatest risk.

## 6.5 Crisis Communication Process

To be effective, emergency response requires timely and efficient communication. The appropriate Company personnel and government/regulatory agencies must be informed of the potential for a serious incident (or the occurrence of a significant event requiring emergency support and response). Notification of a potential incident can occur in several ways: through external stakeholders, through detection by field personnel or through Company reception/ 24-hour emergency number.

Regardless of whether all information is available at the time, the Information Officer should produce a media statement in a timely manner indicating that the situation is under investigation.

### 6.5.1 24-Hour Emergency Number

The Company must establish a 24-hour emergency number for stakeholders to report an operational emergency such as smoke, fire, odours, or spills. This number appears on all facility,

well, and pipeline crossing signs. The Company must ensure that incoming calls to the 24-hour emergency number initiate immediate action.

The 24-hour emergency number may be managed by a Call Centre which provides a 24-hour a day, 7 days a week live answering service to notify Company personnel based on a pre-defined call-down list.


During an emergency, the Information Officer must contact the Emergency 24-hour number attendant to ensure all media enquiries are directed appropriately.

#### **6.5.2 Public Inquiry**

Calls to the Company main switchboard are first directed to the EOC where support staff will screen and collect information from all inquiries. EOC support staff will then pass all incoming information requests or issues to the Information Officer. The Information Officer, in conjunction with the EOC Director, will evaluate all incoming requests for action and response and either handle the requests directly or forward the requests onto the Incident Commander or the Corporate Executive Team to handle.

The appropriate notifications must start immediately when declaring an emergency incident. See Communication Flow diagram for notification and reporting flow process.

6.5.3 Command Centre Communication Flow Diagram



## 6.6 Internal Communication and Command Centres

Effective command, control, and coordination of the incident is dependent on situational awareness gained from fully functioning communication processes and systems. This not only applies between the responders and the On-site Command Post, but also across the entire response effort. The Incident Command Post and the Emergency Operations Centre function as communication hubs and it is important that the relationship and function of each centre is understood.


Internal communications are those between the incident site, company response team members, and other contract emergency resources.

Equipment includes telephones, two-way radios, computer networks, as well as company and response plan contact lists. Outside resources should be procured to assist with the equipment needs. Any site-specific radio and communication infrastructure existing within an area owned either by the Company or through mutual aid should be integrated into the response communication plan. Specific telephone lines may be identified for incoming and outgoing purposes and specific locations may be set up as communication centres with designated media personnel. Roadblock, monitoring, and rover crews also utilize the communication equipment to report conditions and actions, on an ongoing basis, to the Incident Commander or a designate.

An organized, efficient and effective collection of these resources and procedures are considered an incident communication system. It is this system that captures and relays information and orders so that effective decision-making and action can occur throughout the emergency management structure.

The different types of response centres in the emergency communication system are described below.

### 6.6.1 Internal Emergency Notification Flowchart



### ***6.6.2 Communication at On-site Command Post***

The On-site Command Post is the primary emergency response location. It is located a safe distance away from the incident but close enough to facilitate site emergency response operations and communication. If necessary, this could be at a Company Facility or Mutual Aid Operator's Field Office.

### ***6.6.3 Communication at Incident Command Post***

The Incident Command Post is typically located at a nearby facility or field office and provides oversight, support, and coordination of regional (vs. site) response activities. Emergency Response activities at the Incident Command Post include the management of impacts to employees, stakeholders and operations.

The Incident Command Post will need to collect relevant tactical information to make a strategic picture of what is happening. Communication of this information from the On-site Command Post/ Incident Command Post is critical as it enables the Incident Commander to communicate a strategic picture to the Emergency Operation Centres.

This accurate strategic picture will assist the EOC to maintain strategic situational awareness of the event allowing senior decision makers to identify and respond appropriately to issues occurring at regional, national, and international levels.

### ***6.6.4 Communication at the Emergency Operations Centre (EOC)***

During an emergency which requires a Hierarchy 2 communication level, the Emergency Operations Centre will assemble and provide support to the affected location. This may include the aspect of various support sections (e.g. Legal, Information, Finance, etc.) responding to the Incident Command Post.

### ***6.6.5 Communication with the Executives: President and Board of Directors***

During an emergency which requires a Hierarchy 3 communication level, the President and Board of Directors should be notified because significant incidents impact business in many ways including, reputation loss, regulatory compliance, the incurring of legal liabilities, financial loss, etc.


Concurrent with notification to the EOC of the incident, the EOC Director will confirm that the Corporate Executive Team will be the primary conduit for Board notification.

The Corporate Executive Team will notify the Board of the incident and commit to providing updates as the incident evolves.

## 6.7 External Communication

### 6.7.1 External Notification Flow chart

**Prior to commencing contact of the agencies below, make sure a completed A1 Initial Emergency Report Form is available and at hand for reference.**



### 6.7.2 Communication with Government/Regulatory

A key component of the plan is to establish and maintain effective two-way communication with government departments and regulatory agencies that have legislated responsibilities for emergency management within their jurisdiction.

### 6.7.3 Communication with the Public

Public communication can be done in person or by phone. The Company must provide the public with timely emergency information that addresses what actions, if any, are to be taken by the public (for example - shelter in place or evacuate). For extended emergency situations, scheduled information sessions should be conducted to keep the public and affected community updated on the incident (including environmental, health, or safety information).

The following information must be disseminated to the public at the onset of and during an incident:

To those evacuated or sheltered - at onset	To those evacuated or sheltered - during	To the general public - during
<ul style="list-style-type: none"> <li>Type and status of the incident.</li> <li>Location and proximity of the incident to people in the vicinity.</li> <li>Public protection measures to follow, evacuation instructions, and any other emergency response measures to consider.</li> <li>Actions being taken to respond to the situation, including anticipated time period.</li> <li>Contacts for additional information.</li> </ul>	<ul style="list-style-type: none"> <li>Description of the products involved and their short-term and long-term effects.</li> <li>Effects the incident may have on people in the vicinity.</li> <li>Areas impacted by the incident.</li> <li>Actions the affected public should take if they experience adverse effects.</li> </ul>	<ul style="list-style-type: none"> <li>Type and status of the incident.</li> <li>Location of the incident.</li> <li>Areas impacted by the incident.</li> <li>Description of the products involved.</li> <li>Contacts for additional information.</li> <li>Actions being taken to respond to the situation, including anticipated time period.</li> </ul>

## 6.8 Media Communication

In times of crisis, the public forms their opinions from various media sources. It is critical the company uses all available platforms to relay information to the public.

### 6.8.1 Media Crisis Communication Policy

Media releases should be coordinated with the applicable Regulatory Authority prior to release to ensure consistency and accuracy of information. The EOC Director will delegate the Information Officer role to interact with the Regulatory Authority and other applicable government agencies.

It is expected that the designated Information Officer will interact with the media in a timely, open and honest manner.

When dealing with members of the press, Company representatives must:

- Demonstrate professionalism at all times.
- Be available for comment and response.
- Be timely and respect the increasingly fast pace of the news cycle.
- Be completely transparent.
- Provide only truthful and accurate information being mindful of the Company's continuous disclosure obligations and restrictions.
- Provide available point of contact for follow-up inquiries.
- Never comment on issues outside of your area of expertise.

Generally, other Company personnel are not permitted to make any verbal or written public statements regarding Company operational matters or events (e.g. accidents, spills, injuries) unless approved by the Information Officer.

Company goals are to:

- Limit public statements to only those that are deemed necessary.
- Make public statements solely from the Company's Head office.
- Present a unified and accurate corporate image to the community.
- Provide correct information to the public.
- To be in compliance with applicable laws, rules and regulations.

If approached by the media for an interview:

- Politely check and record credentials of media, news photographers, and public officials.
- Remember you are always “on-the-record” with the media.
- Assure the media that a Company representative will address their questions at a later time.
- All media inquiries at the emergency site must be forwarded to the Information Officer who is authorized to supply the media with a brief initial statement.
- Use the following statement as a guideline, never lie or say “no-comment”.

Hello, my name is \_\_\_\_\_ (state your name).

“We are currently dealing with the situation at hand to ensure the safety of persons, property and the environment. The matter is being investigated. A statement will be released by the Company once the facts have been determined. If you would like to leave your contact information with me, I will promptly pass it on to someone who will contact you and provide you with information as it becomes available.”

Name of Media Individual: \_\_\_\_\_

Media Organization: \_\_\_\_\_

Telephone Number: \_\_\_\_\_

### **6.8.2 Media Access to Emergency Site**

Company safety procedures apply to everyone on-site. Therefore, to ensure the safety the media will not be allowed on-site unless otherwise agreed to by Senior Management. No objection should be made of the media filming or photographing the event provided they do so in a safe place, off the property.

The following information provides some additional guidelines when dealing with the media and public reactions.

### **6.8.3 Preliminary Holding Statement**

A preliminary holding statement is a brief description of a critical situation. The statement is intended to be the first information that contains the key messages from the Company to the public, prior to any media release. It includes a brief description of the situation, including who was involved, what occurred and any other critical information. It is not meant to replace a media release or a press conference. The preliminary holding statement will be regularly updated by the Information Officer with the most current key points or messages from the company.

The preliminary holding statement should be provided to all telephone operators in the case of a crisis. The statement should be faxed or emailed to the Incident Commander and On-Site Group Supervisor as soon as approved so that the field location can communicate the same messages as Head Office. By having one consistent statement for all callers, the amount of conjecture, personal opinion and speculation is removed from the media contact.

Where a Preliminary Holding Statement is required by the media, the Statement shall contain:

<b>Nature of Emergency:</b>	General description of what happened. Do not give an opinion of the cause. Do not speculate. Use non-technical language.
<b>Where, When:</b>	Location of the site from the nearest major centre and the time the incident began.
<b>Injuries/Fatalities/Damages:</b>	No opinions shall be given as to the extent of damage or injuries. State the number of people receiving treatment. No names are to be released until after permission has been granted by the next-of-kin.
<b>Status:</b>	Indicate the nature of the situation: what is being done and by whom.
<b>When to Expect More Information:</b>	The Information Officer, or alternate, will issue further information to the media. Ongoing media attention focused at the emergency site shall be referred to the Information Officer.

**Sample Preliminary Holding Statement**

Name of Media Representative: _____ Organization they work for: _____ Date: _____ Time (0-2400 hrs): _____
At approximately _____ (Time, am/pm) today, NorthRiver Midstream Inc. experienced a _____ (Fire/Explosion/Gas Release) at its _____ facility located approximately _____ kilometres (east/west/north/south) of _____ (Nearest Town/City).
There are no injuries associated with this incident.  or  There are injuries associated with this incident. However, the numbers, names, and conditions of those injured have not yet been confirmed for release.
The cause of this incident is not yet known, and no estimate of damage is available. However, NorthRiver Midstream Inc. is directing emergency procedures at this time and steps are being taken by NorthRiver Midstream Inc. to control this incident.
For additional information about this incident, please call: _____. NorthRiver Midstream Inc. at _____.

**6.8.4 General Guidelines**

- Be proactive in advising media of the situation to ensure consistent and appropriate communication to the public.
- Establish an agreed upon schedule for updating the media on a timely basis.
- Coordinate media communication with the Government Emergency Operation Centres if established.
- Return media calls promptly and courteously.
- Restrict comments to indisputable facts and brief descriptions of what is being done.
- Keep messages consistent.
- Record names and numbers for media contacts (so you can provide subsequent contact and updates).

The questions that should be answered are:

- What, where and when did it happen?
- Who was involved? (not providing any names)
- Why did it happen? Do not respond until you have facts – otherwise we are investigating the cause.
- What is the status of the situation?
- When will more information be expected?
- Which Government agencies were notified/are on the scene?
- Plus, any other relevant facts that will dispel rumour, speculation and fear.

DO	DO NOT
<ul style="list-style-type: none"> <li>• Ensure individuals present for any media communication are authorized to be there.</li> <li>• Provide factual information quickly. A reporter will be on the next news broadcast regardless. It is in the Company's best interest that he/she has the facts and not just speculation and comments from others.</li> <li>• Have one person locally and one at the head office as designated spokespersons (all others will defer questions to them).</li> <li>• Keep your commitments. If you say you will check something, ensure you do.</li> <li>• If there is an important development, provide an information update immediately.</li> <li>• Show yourself as caring and concerned.</li> <li>• Reinforce that the Company has active safety, prevention, and response programs.</li> <li>• As soon as the Company can confirm, provide:               <ul style="list-style-type: none"> <li>○ Estimate of when production or flow can be resumed.</li> <li>○ Estimate of clean-up details (e.g. cost, time frame).</li> <li>○ After notification of families, names of those injured.</li> </ul> </li> <li>• Keep your answers brief.</li> <li>• Maintain strong eye contact with those asking questions. Wandering or averted eyes will make you seem dishonest.</li> <li>• Immediately provide the Information Officer with details of what you have said.</li> <li>• Keep a record of all media representatives' organizations and when you talk with them.</li> <li>• Politely correct reporters who have carried inaccurate information.</li> </ul>	<ul style="list-style-type: none"> <li>• Never use the term "no comment." Those two words arouse suspicion. If you don't have the answer, say for example "I don't have that information now, but it is currently being investigated".</li> <li>• Do not speculate or guess.</li> <li>• Do not place blame on anyone – or accept any blame. Do not prejudge the situation by agreeing with any statement (e.g. you heard the driver was speeding).</li> <li>• Do not accuse anyone of negligence.</li> <li>• Do not discuss anything "off the record".</li> <li>• Do not discuss liability.</li> <li>• Do not get flustered by hostile questions: control any anger you may want to return.</li> <li>• Do not play favourites with reporters. Be consistent with the information you provide.</li> <li>• Do not ask to see or hear a reporter's story to check it before it goes. Do, however, make yourself available to confirm facts.</li> <li>• Do not answer hypothetical questions. Comment that the question is hypothetical and that every effort is being made to contain the situation.</li> <li>• Do not fall victim to the either/or question. Repeat your facts.</li> <li>• Do not repeat the reporter's negative or colourful words (e.g. deadly) even to deny them and do not accept or make comparison to other publicized situations.</li> </ul> <p style="text-align: center;"><b>Do not allow yourself to be positioned in front of a blowout for an interview or photograph but do try to find an interesting backdrop that you control.</b></p>

Public reaction to a crisis moves through four stages:

1. **Curiosity** This is the need (or want) to know stage.
2. **Concern** People want to know how it affects them, their community or region.
3. **Anxiety** If the Company does not seem to be informing a concerned public, anxiety sets in. People worry about their health and the environment.
4. **Anger/Fear** Emotions focus on the perceived threat to people’s self-interest. Anger is directed in many directions, especially towards the Company and Government.

### 6.8.5 *Media Release*

A media release is a communication directed at members of the news media for the purpose of announcing something ostensibly newsworthy. Typically, they are faxed or e-mailed to assignment editors and journalists at newspapers, magazines, radio stations, television stations or television networks.

The media release starts with the most important information first (who, what, where, when, why). This is followed by additional information that may be important with supporting details. It ends with contact information. The objective of each media release is to build or maintain the Company’s reputation and public support. The release should emphasize company values, convey empathy to show the public that the Company is concerned and is taking responsibility for the situation. Include only facts that can be confirmed and emphasize resolve of the company to get answers or rectify the problem.

The Media Release contains three core messages that form the basis of all public incident communications.

The Company’s primary concern is to ensure the safety of all those affected by the incident, to work closely and cooperatively with all agencies involved and to address any environmental impacts.	A core message of empathy
The Company is putting its full effort into bringing the impact of the incident under control. As more information becomes available it will keep all stakeholders informed.	A core message of commitment and candor
Incident prevention comprises an integral part of the Company’s job in all its facilities. However, specific details of how the incident occurred will be subject to a full investigation and it is not appropriate for the Company’s to either comment or speculate on this at this time.	A core message of competence

### 6.8.6 *Crisis Media Interview*

Crisis interviews are intended to communicate that the Company:

- Has control over the situation.
- Is familiar with the crisis situation and has the knowledge to handle and resolve problem.
- Takes accountability for the situation and attempts to instill trust with the public in handling the crisis.

During crisis media interviews, the messages should be simple, without jargon and conducted in a slow and clear manner with action points repeated. An interviewee should listen with empathy and invoke conviction and compassion through tone of voice.

Before conducting an interview always review, revise, and rehearse. Ensure information is confirmed and factual, that key messages are well prepared, that the interviewee is comfortable in the chosen location for the interview, and that all the background information supports key points.

When asked a question by a media interviewer, the interviewee should take time to assess whether he or she has the authority to answer the question or the expertise (adequate subject matter knowledge) to answer question. If so, then frame your response with these 3 key points in mind:

- What is the answer – avoid extended preamble and get to the point succinctly.
- How did you derive this answer – use 2-3 supporting points to substantiate your answer.
- Opportunity – select the best key message for the audience to build trust and confidence for company's actions.

Remember the keys to effective crisis media relations are:

- Accuracy of information.
- Speed of release of information.
- Empathy and openness builds trust with stakeholders.

#### **6.8.7 News Conference Guidelines**

When you notify the media of news conferences be sure to define what kind of event you are having. News conferences are held to announce something for the first time.

- Do not call unnecessary news conferences, if it's not worth their time, the media will only be angered. If holding a news conference, try to tell media in advance some details that you will be announcing.
- Gauge the size of your crowd carefully when reserving a room; it is better to have too much than too little space. Make sure microphones, chairs, lighting, and water are in place at least 30 minutes prior to the event.
- Decide format in advance – who will introduce speakers, who decides when questions/answer period ends, and other details.
- Decide in advance whether handouts are needed. If speaker is giving a talk for which there is a text, you may want to wait and hand out material after the talk, so media will stay and listen. However, it's advisable to tell the media you will provide a text of the speech, so they are not irritated by having to take unnecessary notes.
- Check to see what else is happening in your organization or the community before scheduling a press conference.
- Consider whether you need to let other organizations and agencies know you are having a news conference. You may wish to invite others to attend or participate in your event.
- Decide who will maintain control at the news conference, who will decide where cameras are set up, and who sits where.
- Try to plan the length of the news conference but be flexible.
- Consider the time of the news conference. If you want to make the noon, 6 PM or 11 PM news, you need to allow time for crews to travel and edit tape.
- If you are going to set restrictions on an event such as limited photo access, try to put the restrictions in writing and communicate to the media at least 24-hours in advance.

### 6.8.8 Reporting

Regular status updates or status reports provided during the emergency response will be the responsibility of the Information Officer in consultation with the EOC Director. Reports should be provided to the agencies at defined intervals or as frequently as updates are required. Reporting intervals may be adjusted as the situation develops. Reporting will continue until the emergency has been declared over and the response effort has stood down.

Specifically, the Communication Plan establishes a guideline for the following core communication expectations:

Communication	Suggested Timeline
Notifications to internal staff and regulators	As per EOC Director
Initial written public holding statement	Within 1 hour of EOC team activation for a Level 2 or 3 crisis
Media release	Within 2 hours of EOC team action for a Level 3 crisis
Media appearance (if required) and spokesperson preparation	Within 3 hours of communication team activation for a Level 3 crisis
News conference (if required)	Prior to 4 PM if possible
Formal updates – media release, continuous disclosure obligations	Every 4-6 hours or as situation warrants

### 6.9 Social Media

The use of social media, (Facebook, Twitter, Reddit, etc.) to communicate with the public can be a very efficient and effective form of communication during an incident. With the release of one small statement the Company can potentially notify a large segment of the population.

Social media provides a form of two-way communication with the public during an emergency situation. Social media provides the ability to directly see how a situation is affecting people and gives the opportunity to respond to them, keeping them informed, preventing panic, and keeping rumors at bay. By following keywords and hashtags, the Company is able to easily monitor what the community is saying about the incident and respond accordingly.

It should be noted that news organizations are increasingly monitoring social media as a way to find news stories; in some cases, finding out about events before a company.

During an emergency in the Information Officer should appoint an assistant to monitor social media. The designated person can employ a web program such as HootSuite to monitor several social media feeds at once.

### 6.10 Mutual Aid Agreements

A wide range of emergencies may occur that have an impact on neighbouring stakeholders. In this event, multiple parties may want to provide assistance during the emergency.

It must be agreed upon prior to any type of third party response that NorthRiver will remain the primary emergency responder, and that any assistance provided by third parties must be under the supervision of a NorthRiver representative. Furthermore, the party providing mutual aid must comply with all applicable NorthRiver policies and applicable government regulations.

If another Area Operator provides assistance, the principal behind this assistance should remain as follows:

- Companies or individuals providing assistance are to provide the support outside the lease boundary. The focus will be to provide the manpower and support

required for roadblock crews, rovers, resident contact, and evacuation coordination as required by NorthRiver requesting the assistance.

- Third party responders will report to the Incident Commander or other coordinating position in the area.
- Individuals providing assistance retain the right to withdraw the assistance should his/her personal safety be jeopardized.

### 6.11 Emergency Answering Procedures

When answering telephone calls listen to the person on the other end of the line carefully. You need to determine whether this is an emergency situation or not. Try to get the following information, repeat it back for clarification.

- Record the time of day.
- Make sure you ask and log the following information:
  - The person's name.
  - The person's phone number.
  - The exact location of the person calling.
  - Directions to the caller's home/incident site.
  - The exact location of the potential emergency.
  - The extent of injuries or damage.
  - Wind direction.
  - Nature of emergency.
- Please tell the caller to call \_\_\_\_\_ (collect) if their situation changes or gets worse.
- Call the Company representative for that area and relay all the information. Fax, or scan and email, a copy of the recorded information to the responder.

Please remember how important this information is as you will have to relay it to a Company representative.

If the person calling is agitated, try to keep them on the line long enough to get this information. Let them know a Company representative will be dispatched to check out the incident and will contact them with further information.

**6.11.1 General Evacuation Script**

<p>Ensure you are speaking with the correct person. Record answers to your questions on a separate sheet of paper. Speak slowly, calmly and clearly.</p>
<p>Mr./Mrs. _____, this is _____ of NorthRiver Midstream Inc. calling.</p> <p>I am phoning you because we are experiencing some _____ problems at the nearby _____ property.</p> <p>This situation does not pose any immediate threat, but we want you to be aware of it in case the situation gets worse.</p> <p>If it does, we will call back and ask you to go to the _____ reception centre. Would you need any help in getting to the _____?</p> <p>I will be calling back, in any event, to give you an update.</p> <p>If you have any questions, please phone me, collect, at _____.</p> <p>If at all possible, please avoid the use of your telephone, so we can call you again quickly with further information.</p> <p>Thank you.</p>

**Immediately report, to the Telephone Team Leader, the names of all residents not contacted.**

### 6.11.2 Shelter in Place Script

Telephone message for Residences/Businesses inside the EPZ where it is initially deemed unsafe to evacuate.

Ensure you are speaking with the correct person.  
Record answers to your questions on a separate sheet of paper.  
Speak slowly, calmly and clearly.

Mr./Ms. \_\_\_\_\_, this is \_\_\_\_\_ from NorthRiver Midstream Inc. calling. We are experiencing a gas leak, which has created a vapour cloud (plume) that may be toxic or cause a serious fire and explosion near your home. NorthRiver Midstream Inc. is currently responding to the emergency. For your safety it is essential that you and your family/associates, remain sheltered indoors, preferably at the upper levels in your house until we can evacuate you safely or until the situation is under control and this serious hazard no longer exists.

Please take the following actions immediately:

1. Gather everyone in the house and close all windows and doors.
2. Extinguish all potential sources of ignition, including open flames.
3. Do not smoke.
4. Turn off the electrical power at your switch box.
5. If possible, plug any fresh air intakes or vents to your home, or furnace.
6. Move to the upper levels of your house.
7. Use a portable radio and stay tuned to a local station for public information.

**Do not leave your house or attempt to start any vehicle until NorthRiver Midstream Inc. advises you that the area is safe.**

Do you understand what I have just told you?

A Company representative or the local police will come to your house as soon as the fire and explosion hazard no longer exists.

If at all possible, please avoid the use of your telephone, so we can call you again quickly with further information.

If you have urgent questions, please call NorthRiver Midstream Inc. at \_\_\_\_\_\*

**The Telephone Team Leader will designate the phone number at the time of the incident.**

Thank You

### 6.11.3 Urgent Evacuation Script

Ensure you are speaking with the correct person.  
Record answers to your questions on a separate sheet of paper.  
Speak slowly, calmly and clearly.

Mr./Ms. \_\_\_\_\_, this is \_\_\_\_\_ of NorthRiver Midstream Inc. calling. I want to tell you about a/the serious \_\_\_\_\_ we are experiencing at our \_\_\_\_\_ location.

The wind is carrying the escaping gas to the north/south/east/west.

**YOU ARE IN NO IMMEDIATE DANGER.**

However, as a safety precaution, we want you to leave your premises and go right away to the reception centre located at \_\_\_\_\_.

How many people are currently at your home?

Are there any medical considerations or other special concerns that could affect your safe evacuation?

Do you have transportation? If not, please stay indoors and close all windows and doors. We will send one of our drivers and vehicles to get you right away.

If you have transportation, please take the north/south/east/west route, which will take you safely out of the endangered area. You can then travel by \_\_\_\_\_ to get to the reception centre.

**Read the following paragraph only during school hours:**

We have contacted the schools and have arranged to hold students at the school.  
You may pick them up there or would you like to have us take them to the reception centre?  
What are your children's names and which school are they at?

It is very important for us to know where you are and where you can be contacted both during and after the evacuation. Please report to the reception centre to confirm your accommodations and other support you may need.

Any concerns you have regarding livestock, pets, or property will be addressed by our representatives at the reception centre.

Please try not to use your telephone as it may tie up the lines and prevent us from calling other residents.

**Immediately report, to the Telephone Team Leader, the names of all residents not contacted.**

#### 6.11.4 Notification Script

Ensure you are speaking with the correct person.  
Speak slowly, calmly and clearly.

Mr./Ms. \_\_\_\_\_, this is \_\_\_\_\_ of NorthRiver Midstream Inc. calling. I am calling with an important message.

NorthRiver Midstream Inc. has an emergency near your location, which does not affect your safety; REPEAT, does not affect your safety. You are in no danger at this time; NorthRiver Midstream Inc. is notifying you for informational purposes only.

**Repeat: You are in no danger at this time; we are notifying you for informational purposes only.**

If you would like to voluntarily evacuate, please go to the Reception Centre located at the \_\_\_\_\_.

For further information, please contact NorthRiver Midstream Inc.'s 24-hour emergency number at 1-844-667-8477.

## 7.0 RESPONSE ACTION PLANS

### 7.1 Purpose

The following examples of emergency response actions have been developed to provide a guide for response personnel. They should be reviewed and (if applicable) implemented as part of a specific emergency response.

The Site Command and Emergency Operations Command staff may follow these guidelines to protect worker and public safety.

### 7.2 Incident Site Worker Protection

To ensure that workers take the appropriate actions in the event of an emergency they should be properly trained and familiar with the Company emergency response strategy. This includes the following:

#### Actions:

- Ensure familiarity with egress routes and the muster point.
- Know where the safety equipment is located (fire extinguishers, first aid kits, gas monitoring equipment, and personal protective equipment).
- Understand how to initiate a site evacuation by sounding an alarm.
- If required, assist with a head count at the muster point and identify any missing personnel.
- Provide medical aid to an injured worker.
- Ensure that there is an accounting system in place for on-site personnel.

### 7.3 Personal Protective Equipment (PPE)

All responders should be properly equipped with PPE in their role as first responders at a Company site. In prolonged emergency response situations, a critical role of the Site Logistics Section Chief is to ensure that adequate quantities of all types of equipment and clothing are available for response personnel including essential spare parts (e.g. additional air bottles, bunker gear etc.). Local suppliers of safety equipment should be pre-identified.

#### Respiratory Protection

Supplied-Air Breathing Apparatus (SABA) supplies air from air carts rather than breathing ambient air. The most common type of supplied-air apparatus is the Self-Contained Breathing Apparatus (SCBA) for example, Scott Air Packs, which supplies air from tanks carried on the responder's back with a full face-piece. SABA and SCBA represent the highest level of respiratory protection available.

The following general guidelines can assist in the selection of proper respiratory protection for responders:

- SCBA should be used by initial responders (i.e. the first responders to enter the planning zone or immediate area of the spill), especially if the levels of concentration are unknown but suspected to be high, or if there is the possibility of oxygen deficiency (e.g., confined spaces). One of the key roles of the initial responders will be to take accurate vapour concentration measurements to determine the actual level of risk to follow-up responders.
- Air-purifying (e.g. organic cartridge) respirators can be used when the levels of vapour concentration are confirmed by gas testing to be safely below the level for

the chemical involved, and the situation has stabilized (e.g., vapours are starting to be dispersed by wind, or have been suppressed using foam).

**Note:** All responders should be trained in the proper use of respiratory protection equipment. Final selection of respirators should always be based on accurate, ongoing measurements of vapour concentration levels at and around the spill site (especially downwind).

### Protective Clothing

Recommended protective clothing requirements are outlined in Safety Data Sheets (SDS) which are published for all products.

Chemicals can pass through protective clothing through three processes:

- **Penetration** occurs when the liquid or vapour passes through seams or small openings in the clothing.
- **Degradation** is the deterioration or breakdown of the clothing material caused by the action of the chemical.
- **Permeation** is the process by which molecules of liquid or gas move through clothing material. Permeation is regarded as the most useful measure of the level of protection afforded by different clothing materials.

## 7.4 Protection Levels

There are four general levels of responder protection, which are recognized in both the U.S. and Canada. These are outlined in the table below.

- For solvents and Styrene, initial responders will probably require Level B protection until vapour concentration levels have been confirmed. Follow-up responders should have Level C protection.
- For certain specialty chemicals like Phenol, Level A protection may be required depending on the nature and location of the incident.

### 7.4.1 Levels of Responder Protection for Spill Response

Protection Level	Situation	Protective Equipment
<b>A</b>	Entry into unknown or high levels of skin-permeating chemicals.	SCBA and totally-encapsulated or gas-tight suit.
<b>B</b>	High concentrations – no skin-permeating chemicals present.	SCBA and chemical resistant clothing and gloves, boots.
<b>C</b>	Known levels of non-permeating chemicals.	Air-purifying respirator, liquid-repellent clothing, gloves, boots, safety goggles/glasses, and hard hat.
<b>D</b>	Chemicals well below danger levels.	Coveralls, gloves, boots, safety goggles or glasses, hard hat.

## 7.5 Preparing a Health and Safety Plan

The Health and Safety Plan for a hazardous material spill highlights the critical information about the product, physical location of the spill and other incident-specific conditions required by responders to respond safely to the incident, as well as appropriate safety rules and precautions that will be enforced at the scene.

In most circumstances, the Health and Safety Plan for a specific incident should be prepared by a Site Safety Officer at the scene who is in a position to conduct a thorough, accurate hazard assessment.

The Health and Safety Plan should be concise, and written in clear, non-technical language to ensure understanding by responders.

The Health and Safety Plan outlines the key hazards associated with the incident, and the safety procedures and precautions that are to be enforced during the response. As the response progresses, the Health and Safety Plan should be updated on a regular basis to reflect changing conditions at or near the scene of the incident.

The Incident Commander is responsible for reviewing the Health and Safety Plan. The Site Operations Section Chief and On-Site Group Supervisor are responsible for implementing and enforcing the safety requirements of the plan throughout the response.

## 7.6 Health and Safety Plan

### *Product Specific Information*

**Product Hazards:**

- Poisonous or toxic.
- Flammability.
- Corrosive.

**Health Hazards and Risks:**

- By ingestion.
- By direct contact, skin.
- By inhalation.

**Critical Behaviours and Properties (as required by the situation):**

- Vapours heavier or lighter than air?
- Sinks, floats, dissolves or evaporates in water?

**Other:****Risk of Fire or Explosion:**

- Flash Point.
- Lower Explosive Limit (LEL).
- Upper Explosive Limit (UEL).

**Exposure Limits  
(ACGIH – if other specify):**

- TLV-TWA.
- TLV-STEL.
- TLV-C.

---

### *Responder Safety and Protection*

**Responder Qualifications/Training Requirements:**

---

**Recommended Level of Personal Protective Equipment (PPE):**

- Level A (specify equipment).
- Level B (specify equipment).
- Level C (specify equipment).

**First Aid Measures:**

---

### Site-Specific Information

#### Drawing, map or sketch of the incident site showing:

- Key topographical features (e.g., buildings, natural features).
- Initial Isolation Zone.
- Protective Action Zone.
- Potential Downwind Evacuation Zone.
- Wind Direction.
- Real and potential vapour monitoring points.
- Security Access Points (if applicable).
- First Aid stations (if applicable).
- Command Centre and Staging Areas (if applicable).

#### Note key features of the location that might affect the safety of responders.

#### Describe proximity to:

- Populated areas (e.g. residential or commercial).
- Bodies of water (e.g. lakes, rivers, streams, ocean).
- Environmentally-sensitive areas.

### 7.7 Public Safety and Protection

In most foreseeable situations, the responsibility for public safety and protection following an emergency incident will be the responsibility of the local authorities including one or more of the following:


- Police.
- Fire Department.
- Municipal Emergency Planners and Responders.
- Public Health officials.


Actions taken may range from nothing if no public risk is perceived, to notification or public warnings, public health alerts, and full or partial evacuation of certain areas around the incident site.

Company personnel will support this process by providing whatever information is required about Company emissions and their related properties and hazards to enable the authorities to reach the most appropriate decision given the circumstances at the time. Such information may include:

- Physical and chemical properties.
- Toxicological properties and risks.
- Critical physical parameters such as flash point, explosive limits, exposure limits, etc.
- Physical properties and behaviour following a spill on land, water, or in vapour form.

### 7.7.1 Public Notification Flowchart





### Notification and Evacuation Requirements Outside of the HPZ

For a sour gas release, the licensee must continuously assess and act on the need to expand the evacuation area based on the monitored levels of H<sub>2</sub>S and SO<sub>2</sub>. In the absence of monitored readings, responders should advise the residents to Shelter-in-Place.

H <sub>2</sub> S Requirements		SO <sub>2</sub> Requirements	
1-10 ppm	Individuals who requested notification so that they can voluntarily evacuate before any exposure to H <sub>2</sub> S or SO <sub>2</sub> must be notified.	1-5 ppm	Individuals who requested notification so that they can voluntarily evacuate before any exposure to H <sub>2</sub> S or SO <sub>2</sub> must be notified.
10 ppm and above (1-hour average)	Local conditions must be assessed and all persons must be advised to evacuate and/or shelter.	5 ppm and above	Local conditions must be assessed and all persons must be advised to evacuate and/or shelter.
<i>Note: H<sub>2</sub>S Evacuation Level – when downwind monitoring at the nearest unevacuated residence, outside the Hazard Planning Zone, indicates a level of 10 ppm, evacuation procedures will be initiated if safe to do so.</i>			

## 7.8 Air Quality Monitoring

At a Level 1 Emergency, Mobile Air Quality Monitoring equipment and qualified operating personnel will be dispatched to the Emergency Planning Zone and placed downwind to gather the ambient air quality data required to support public safety actions.

Air Quality Monitoring equipment will be used to:

- Track the plume.
- Determine if ignition criteria are met.
- Determine whether evacuation and/or sheltering criteria have been met, particularly beyond the EPZ.
- Assist in determining when the emergency can be downgraded.
- Determine roadblock locations.
- Determine concentrations in areas being evacuated to ensure that evacuation is safe.

Downwind Mobile Air Quality Monitoring Requirements		
Level 1 Emergency	Level 2 Emergency	Level 3 Emergency
Deploy unit(s) to area of release and commence mobile air quality monitoring.	Continue mobile air quality monitoring. Request additional air quality monitoring unit(s) if required.	Continue mobile air quality monitoring. Request additional air quality monitoring unit(s) if required.

## 7.9 Determining the Response Zone Using Monitoring Equipment

Response personnel required to determine the extent of the response zones with handheld monitoring equipment must take the following precautions to protect their safety:

- Use the buddy system.
- Equip each responder with reliable H<sub>2</sub>S detection and respiratory protective equipment.
- Establish and maintain communication with the Incident Command Post.
- If walking a pipeline right-of-way, walk a safe distance apart staying within visual and audible contact. As the lead responder monitors for H<sub>2</sub>S, the backup responder will maintain communication and be prepared to rescue.

### Detection

- Portable 3 or 4-head gas monitor.
- Mobile Air Monitor Units.

### Record all information

- Concentrations in ppm.
- Location and time of readings.
- Wind speed and direction.

### Communication and Documentation

- Report all information to Public Protection Group Supervisor or Site Operations Section Chief.
- Notify Roadblock Personnel and Response Teams of changes.

### 7.9.1 Sour Gas Release from a Manned Operation

For critical sour wells, if the EPZ includes a portion of an urban density development or urban centre, there must be a minimum of two mobile air quality monitors: one to monitor the boundary of the urban density development or urban centre and the other to track the plume. The licensee must also:

- Ensure that one unit is in the area during drilling and/or completions, testing, and workover operations in potentially critical sour zones.
- Ensure that the other unit is dispatched if it is evident that well control measures are deteriorating, and that sour gas release is likely to occur.
- Prior to conducting operations in the sour zone, determine where the monitoring equipment is located and what the estimated travel time is to the well site.

For critical sour wells whose EPZ does not include a portion of an urban density development or urban centre and for all noncritical sour wells, the licensee must:

- Dispatch mobile air quality monitoring unit(s) when it is evident that well control measures are deteriorating and that a sour gas release is likely to occur.
- Prior to conducting operations in the sour zone, determine where the monitoring equipment should be located and what the estimated travel time is to the well site.

Air quality monitoring occurs downwind, with priority being directed to the nearest un-evacuated residence or area where people may be present.

The licensee is expected to provide monitored H<sub>2</sub>S and SO<sub>2</sub> information on a regular basis throughout a sour gas emergency to the environmental agency, the applicable Regulatory Authority, local health authority, and other local authorities.

### 7.9.2 Sour Gas Release from an Unmanned Operation

If the licensee is notified of a release by an alarm or by a reported odour, the source of the release must be investigated, and air quality monitoring units sent out upon confirmation of the release location.

## 7.10 Sour Gas Release

### 7.10.1 Sour Gas Release Site Safety

- Communicate with all workers the potential presence of H<sub>2</sub>S, SO<sub>2</sub> and LEL levels.
- Immediately initiate atmospheric monitoring of H<sub>2</sub>S, SO<sub>2</sub> and LEL levels.
- Designate a safe muster location based on the extent of the Sour Gas release.
- Initial immediate evacuation of all non-essential personnel.
- Identify areas of the site with confirmed or potential H<sub>2</sub>S, SO<sub>2</sub> and LEL levels.
- Complete a site roll call to account for the safe location of all personnel that were on site prior to the event occurrence.
- Identify any unaccounted-for personnel.
- Attempt to remove or control all ignition sources, where ignition would threaten safety of workers.
- Perform search and rescue for site personnel unaccounted for or overcome by H<sub>2</sub>S and SO<sub>2</sub>.
- Continue to provide atmospheric monitoring of H<sub>2</sub>S, SO<sub>2</sub> and LEL levels to ensure the safety of the Muster Location and emergency responder staging position.

### 7.10.2 Safety of Response Operations

- Ensure personnel that assist with release control operate only within their specific:
  - Levels of training.
  - Capability.
  - Experience.
- Personnel remaining in proximity to H<sub>2</sub>S and SO<sub>2</sub> exposures shall be provided with and shall wear the appropriate PPE and SCBA appropriate to the exposure hazard.
- Ensure that any personnel utilizing SCBA have been properly trained and fitted.
- Monitor and provide control of the operating time of site personnel working in SCBA.
- Establish a decontamination station prior to assigning personnel to enter areas in proximity to H<sub>2</sub>S and SO<sub>2</sub>, for the safe and timely decontamination of any exposed personnel.

### 7.10.3 Action Plan Sour Gas Release

- Attempt to stop the release of Sour Gas, when safe to do so.
- Notify local emergency response agencies.
- Notify potentially exposed residential or public areas.
- Determine and implement public protection actions.
- Maintain air monitoring for H<sub>2</sub>S and SO<sub>2</sub>.
- Activate the Site Command and EOC Command for support.
- Assist emergency response agencies in organizing area evacuations and access restrictions.

### Request Emergency Response Agencies

- Call 911.
  - Request Fire Department, Emergency Medical Responders, and Police.
  - In the event of potential exposure to a sour gas release off-site
- Request that the local Emergency Management Representative and local police agency respond.
- Maintain air monitoring for levels of H<sub>2</sub>S and SO<sub>2</sub>.
- Designate a safe staging position for responding resources.

### Brief Emergency Responders

- Provide emergency responders with an SDS for H<sub>2</sub>S and SO<sub>2</sub>.
- Brief emergency responders on:
  - Event timeline.
  - Nature of the release; dynamic - static.
  - Hazards of the release; flammable, corrosive, toxic, asphyxia.
  - Status of personnel accountability; search and rescue profile.
  - Other uncontrolled facility hazards.
  - Status of the release control operation.
  - Status of other operating personnel within the facility.
- Identify the number of injured/exposed people due to any inhalation hazard.
- Identify the uncontrolled sources of ignition.
- Identify any confined spaces.
- Identify any low-lying areas where H<sub>2</sub>S and SO<sub>2</sub> may pool.

### 7.11 Sweet Gas (Hydrocarbon) Release

The effectiveness of the following guidelines depends on the judgment exercised by all personnel. To extinguish hydrocarbon fires and prevent further explosions, it is necessary to do at least one of the following:

1. **Remove fuel** by isolating the section of equipment on fire and pumping out or depressurizing the flammable material.
2. **Remove oxygen** by the use of steam, chemicals, foam, dry powder, or CO<sub>2</sub> extinguishers. If the fire is small, the flames can be smothered with a fire blanket, new tarpaulin, or sand.
3. **Cool fuel** so that it no longer produces vapors using water where possible (as a fog) to extinguish fires or as a coolant for equipment, tanks, support columns, etc. or use to provide a protective shield while the fire is being extinguished by foam, chemicals, or power extinguishers.

#### Response Actions:

- Understand the type of product and its immediate hazards.
- Establish an evacuation route and muster point for workers at the site.
- Shut in all known fuel sources. Do not extinguish a leaking gas flame unless the leak can be stopped.
- Shut off high voltage power supplies to equipment in fire-affected area.
- Shut off fuel to heaters near to or downwind of the fire.
- Observe surrounding area for other possible re-ignition sources and if safe to do so take appropriate steps to eliminate these hazards.
- Dissipate static electrical charges on bodies of all personnel in area. Grounding may be accomplished by holding onto a metal structure for ten seconds with bare hands.
- Approach the site from an upwind or crosswind direction.
- Ensure an appropriate on-site and off-site air monitoring strategy is employed.
- Monitor the area for LEL.
- Monitor local weather conditions. Weather conditions such as temperature inversions, fog and wind may affect plume dispersions.
- Do not use water jet. For a small fire, use dry chemical, CO<sub>2</sub>, water spray, or foam. For a large fire, use water spray, fog, or foam. Beware of electrical hazards.
- Move containing vessels from the fire area if this can be done without risk.
- Cool containing vessels with flooding quantities of water until long after fire is out.
- Keep unauthorized personnel away.

### 7.11.1 Flammability Limits

Monitored Flammability Limits (% of LFL)	Comments and Typical Actions
10% of the LFL (LFL/10)	This concentration represents a level at which industry response personnel should leave the area or don fire protective clothing if continuing to work in this environment or if approaching the source of a release.
50% of the LFL (LFL/2)	A concentration level at which ignition and flame propagation through a dispersing plume may be possible due to the non-homogenous nature of dispersion in the atmosphere (i.e., concentration fluctuations). A meteorologically weighted distance to this criterion (as calculated using quantitative hazard analysis methods) is often used as the basis for establishing emergency planning zones for flammable substances. If measured by air monitoring, this concentration represents a level at which public protection measures such as removal of ignition sources, shelter-in-place or evacuation may be warranted.
100% of the LFL (LFL)	A concentration level at which (in the presence of an ignition source) ignition and flame propagation through the dispersing plume is highly probable. Extreme caution should be exercised, and emergency response personnel should withdraw from the area.

Adapted from Best Management Practices, Emergency Air Monitoring, Canadian Association of Petroleum Producers, March 2014

### 7.12 Hydrocarbon Exposure

Exposure to flame (delayed ignition of a hydrocarbon gas release). Direct exposure to flame occurs when ignition of a flammable gas cloud in the environment is delayed. If ignited, a flame front will move from the point of ignition, through the gas, to the source.

For planning purposes, the flammable region of the plume is assessed by estimating the concentration of fuel in air as the gas is transported and dispersed from the release site. The lower flammable limit (LFL) is the lowest concentration at which the fuel will support combustion in the presence of an ignition source. While hydrocarbon gases cannot burn below the LFL, the distance to one half of the LFL (LFL/2) is used as a conservative basis for establishing the boundaries of the flammable region. For emergency response purposes, responders will use monitors to determine where a flammable gas exists.

Direct exposure to flame can result in third degree burns or death. If you detect a hydrocarbon release, extinguish and reduce all ignition sources and, if possible, move away from the area on foot in a cross-wind direction away from the source. If you cannot leave the area on foot or are uncertain about the source of a release or the wind direction, please shelter indoors.

#### 7.12.1 Exposure to Heat Radiation (ignited hydrocarbon release)

Exposure to thermal radiation can result from a:

- Pool fire or refers to the burning of liquid hydrocarbon at the surface of a liquid hydrocarbon pool (e.g. burning of an oil pool).
- Jet fire: refers to the burning of liquid or gas at the point of the release into the atmosphere (e.g. the flame on the tip of a butane torch).

A number of criteria are used to evaluate the effects to people of heat exposure. These include:

- Thermal Radiation: a measure of the instantaneous level of heat radiation received at a location near a release.
- Thermal Load: a measure of the cumulative heat received at a location near a release and is a better measure of the overall impact to people.

These effects of heat exposure are summarized for these criteria in the tables below.

### Thermal Radiation

Radiation Intensity (kW/m <sup>2</sup> )	Damage to Equipment	Exposure to People
4	Sufficient to cause pain to personnel if unable to reach cover within 20 seconds; blistering of the skin (second degree burns); 0% lethality.	
12.5	Minimum energy required for piloted ignition of wood; melting of plastic tubing.	1% lethality in 1 minute. First-degree burns in 10 seconds.
25	Minimum energy required to ignite wood at indefinitely long exposures (non-piloted).	1% lethality in 30 seconds. Significant injury in 10 seconds.
37.5	Sufficient to cause damage to process equipment.	100% lethality in 1 minute. 1 % lethality in 10 seconds.

World Bank (1985) in Guidelines for Chemical Process Quantitative Risk Analysis, Center for Chemical Process Safety of the American Institute of Chemical Engineers, 1989.

### Thermal Load

Harm Caused	Thermal Dose Units (TDU) (kW/m <sup>2</sup> ) <sup>4/3</sup> s
Pain	86 to 103
First Degree Burns	80 to 130
Second Degree Burns	240 to 350
Third Degree Burns	870 to 2600

Health & Safety Laboratory, 2004

For the purposes of establishing HPZs, the maximum distance to a thermal load of 342 (kW/m<sup>2</sup>)<sup>4/3</sup> s is applied.

#### 7.13 Entry Procedures into the EPZ

- Only authorized personnel may enter the response zones.
- Use the "Buddy System" when required.
- Keep in contact with the Incident Commander using two-way radio or mobile telephone.
- Schedule reports every 10 to 15 minutes while in the response zones.
- Wear personal protective equipment (PPE).
- Continuously monitor the concentration of combustible gas (LEL) in the area.

#### 7.14 Roadblocks

##### 7.14.1 Isolating the EPZ with Roadblocks

The response zones are to be isolated by roadblocks to prevent entry of non-essential personnel. Roadblocks are to be established and manned by the Company or contract personnel with possible assistance from the police and/or local disaster services.

An ongoing situation may require the activation of additional contract safety personnel to provide relief at the roadblocks.

When contacting additional roadblock personnel, the following information must be provided:

- The nature, location and extent of the response zones.
- Suggestions on where to establish roadblocks.
- The current weather conditions (such as wind speed and direction).
- The estimated number of people living in the response zones.
- The name, telephone number and location of the Incident Commander.

Each roadblock location should have access to the following equipment:

- Road barricades.
- Radio or mobile communication equipment.
- Personal protective equipment.
- Flares and/or strobe lights.
- Area map.
- Roadblock checklist.
- Air Monitoring detection equipment.

This equipment is available from local contract safety companies.

#### **7.14.2 Suggested Roadblock Equipment**

- H<sub>2</sub>S, LEL, CO, O<sub>2</sub> detection equipment (handheld instruments).
- High-visibility reflective vests.
- Communication equipment.
- Poisonous gas signs.
- Road barriers.
- ERP maps.
- Reflective triangles or cones.
- Flashlights (with batteries).
- Appropriate forms, such as air monitoring record and roadblock log of people leaving and entering the PAZ.
- Handheld stop signs.
- Personal protective equipment.
- Flares and/or flashing lights.
- First aid equipment.
- SCBA.
- Pens.
- Portable rotating emergency lights.
- Waterproof bag.
- Caution tape.
- Rain suit.

The permit holder must ensure that company equipment is operational meets industry standards.

#### **7.14.3 Setting up a Roadblock**

- Park vehicle on an angle across the lane, activating four-way flashers and roof-mounted rotating beacon.
- Put on a reflective vest.
- Take a reading with your handheld monitor for H<sub>2</sub>S and lower explosive limit (LEL), ensuring your roadblock is not too close to the edge of the EPZ. Record readings on the Air Quality Monitoring Log.
- Notify the Public Protection Group Supervisor once your roadblock is set up.
- Continue to monitor and record H<sub>2</sub>S and LEL levels at scheduled intervals. Report to the Public Protection Group Supervisor at scheduled intervals.
- Maintain roadblock until the emergency is over and the stand down declaration is given or until relieved by other roadblock personnel.


To give motorists time to prepare to come to a stop, it is recommended that the roadblock personnel setup all available reflective triangles 100 metres apart, at a minimum distance of 200 metres before the roadblock.

*Roadblock Statement*

Hello, my name is \_\_\_\_\_ (state your name).  
I am representing NorthRiver Midstream Inc.. NorthRiver is presently experiencing control problems ahead. This situation is serious enough to warrant restricted access beyond this point and therefore I am requesting you take an alternate route.


**Note:** Confirm evacuation route and evacuation orders with Public Protection Group Supervisor prior to directing traffic on an alternate route

### Primary Roadblock – Single Lane Roads




Secondary roadblock locations might be established to facilitate re-routing traffic around the hazard area. All diverted traffic would be re-routed to the secondary roadblock locations.

### Primary Roadblock – Multi-Lane/Divided Highway



In this scenario, the roadblock will be set up prior to the arrival and assistance from either the Provincial Authority responsible for primary highways or the Police. Secondary roadblock locations must be established to facilitate re-routing around the EPZ area. All diverted traffic would be re-routed to the secondary roadblock locations.

*Secondary Roadblock – Placement Schematic*



-  Primary roadblock to cordon off the EPZ.
-  Secondary roadblock to reroute traffic on busy roads.
-  Detour route.



## 7.15 Shelter in Place

Shelter in Place is an acceptable public safety action when there is no advanced warning to the incident, or the release is of a short duration (several minutes to half an hour).

Studies have predicted that the indoor concentration of toxic and flammable gases is significantly lower than the expected outdoor concentration levels.

Sheltering will be considered the primary protective measure in limited circumstances when:

- There is not enough time or warning to safely evacuate the public immediately.
- Stakeholders are waiting for evacuation assistance.
- There is a sour gas release of limited duration.
- The location of the release has not been identified.
- The public would be at a higher risk if they were evacuated.

### 7.15.1 General Shelter in Place Instructions

The following steps should be communicated to the public if individuals are asked to shelter in place:

- Immediately gather everyone indoors and stay inside.
- Close and lock all windows and outside doors.
  - If convenient, tape the gaps around the exterior door frames.
- Extinguish indoor wood burning fires.
  - If possible, close flue dampers.
- Turn off appliances or equipment that either:
  - Blows out or uses indoor air, such as:
    - Bathroom and kitchen exhaust fans.
    - Built-in vacuum systems.
    - Clothes dryers.
    - Gas fireplaces.
    - Gas stoves.
  - Sucks in outside air, such as:
    - Heating ventilation and air conditioning (HVAC) systems for apartments, commercial or public facilities.
    - Fans for heat recovery ventilators or energy recovery ventilators (HRV/ERV).
- Turn down furnace thermostats to the minimum setting and turn off air conditioners.
- Leave open all inside doors.
- Avoid using the telephone, except for emergencies, so that you can be contacted by emergency response personnel.
  - Call the Company emergency number that you have been provided:
    - If you are experiencing symptoms or smelling odours (so that we can address your concerns and adjust our response priorities).
    - If you have contacted fire, police or ambulance (so that we can coordinate our response).
- Stay tuned to local radio and television for possible information updates.
- Even if you see people outside, do not leave until instructed by response personnel.
- If you are unable to follow these instructions, please notify the Company's emergency response personnel.

### **7.15.2 Post Shelter in Place Instructions**

Once the emergency situation has been corrected you will receive a communication from the emergency response personnel. Advise the residents/area users/stakeholders to:

- Ventilate the building.
- Open all windows and doors.
- Turn on indoor fans.
- Turn on the furnace.
- Avoid remaining inside during this time (if possible) as the outdoor air may be fresher.
- Once the building is ventilated, return all heating, ventilating and other equipment to normal.

## **7.16 Liquids Release – Site/Facility**

### **7.16.1 Liquid Release Site Safety**

- Activate the site evacuation alarm and establish safety zones to protect workers, residents and public. Reference EPZ map or utilize Emergency Response Guidebook for zoning guidance.
- Where the spill/release is flammable, eliminate any sources of ignition and monitor for Lower Explosive Limits.
- Reference SDS for released material's properties (located in the site office, drilling floor, etc.):
  - Exposures considerations.
  - Handling precautions.
  - Personal Protective Equipment.
  - Clean-up measures.
- Assess the specific hazards associated with exposure and response to the spill.
- Ensure that all site personnel are accounted for.
- Ensure all workers in proximity to the spill, are monitored to ensure their personal safety.
- Countermeasures must only be initiated where hazardous material exposure can be controlled within training levels of workers.

### **7.16.2 Action Plan for Liquids Release**

- Where available consult the site-specific or field area section for an overview of spill potentials and environmental receptors including water bodies and streams.
- Contain release to the site recovering as much spilled material as possible.
- Protect surface water-bodies, groundwater and other sensitive environmental receptors in the area.
- Notify Company management and notify local emergency response agencies.
- Rapid mobilization of response contractors and any additional technical support.
- Establish decontamination procedures prior to commencing recovery efforts.

### **Evacuate and Restrict Access**

- Evacuate personnel from the facility when required by the scale of the spill.
- Request through 911 roadblocks and or evacuation of residents where indicated.
- Provide facility security at the access points to the facility to:
  - Restrict access to areas in proximity to the spill.
  - Maintain accountability of the personnel on site.
- Initiate the notification and access control to exposed or threatened public areas off-site.
- Coordinate roadblocks.

**Identify the Released Material**

- Identify the spilled product:
  - Chemical Name.
  - Common name.
  - Class.
  - Type.
  - UN/DOT Number.
- Reference the product's SDS identifying:
  - The flammability of the spilled product.
  - PPE requirements for proximal exposures and handling of the spilled product.
  - Released materials reaction with organic materials.
- Immediately report the release event to the line supervisor, providing all known information available.

**Identify the Release Parameters**

- Identify the source of the release.
- Identify and remove any known potential ignition sources for the spilled product within the Planning Zones.
- Initiate monitoring of any flammable or combustible material:
  - Identify and monitor elevated LEL areas.
- Identify:
  - The likely spill exposure area.
  - Velocity and volume of the release.
  - Potential to erode or overcome site containment features.
  - The potential worst-case scenarios.
- Consider discontinuing operations for larger dynamic release events.

**Identify the Release Exposures**

- Reference available site documents.
- Identify the release exposure to the Spill Retention Basins (SRBs).
- Identify the release exposure to Environmental receptors (e.g. water bodies, streams, ground areas with high permeability, marshes, etc.).
- Identify any public or resident exposures.

**Identify the External Resources Required**

- Responding agencies.
- Technical personnel.
- Manpower.
- Equipment.
- Specialized materials.

**Report Incident Information to the Incident Command Post**

- Event timeline.
- Material released.
- Hazards and exposures generated from the released material.
- Volume of release.
- Volume-rate of release.
- Likely total volume of release.
- Worst case release volume.
- Off-site areas of release sensitivity.
- Current release control actions.
- Planned release control actions.
- External resource support required.

### Initial Countermeasures

- All response personnel shall wear appropriate PPE.
- Provide a decontamination station for responders and initial containment personnel.
- Stop the flow of product at the source if safe to do so:
  - Close Isolation Valves.
  - Shutdown Transfer Pumps.
  - Transfer materials from leaking tanks into available and compatible undamaged storage tanks, vacuum trucks or lined secondary containment areas.
- Attempt control of the release by:
  - Confining the released materials to on-site areas.
  - Utilize absorbent booms and pads to contain and clean-up smaller release events.
  - Directing the release away from and limiting the negative exposure or spill accumulation in or around critical site facilities and components.
- Utilize the Spill Retention Basins (SRBs) as release control points:
  - Immediately plug off/cap the discharge pipes.
  - Block off drainage ditches, culverts and discharge pipes with sandbags, earthen dikes, and other available materials.
- Where containment is not possible, attempt to divert the release in a direction that may:
  - Allow for containment.
  - Use natural containment (topography).
  - Provide an outfall away from waterways.
  - Limit exposure of sensitive areas.
  - Limit public exposure.
- Adequately monitor Facilities for:
  - Leaks, pressure build-up, and gas generation.
  - Valve, pipe and equipment ruptures.
- Where a material release has entered waterway and cannot be contained, attempt to create control points:
  - In the event that the released material is lighter than water, create a dam with an underflow water passage to allow clean water flow while retaining and controlling the released material at the dam location.
  - In the event that the released material is heavier than water, create a dam with overflow water passage past the dam to allow clean water flow while retaining and controlling the released material at the dam location.

### Management of Recovery Operations

- Track and document the areas outside the fence line, with regard to:
  - Release volume.
  - Proximity/exposure monitoring.
  - Control actions – time-based record.
  - Clean-up actions – time-based record.
- Initiate soil sampling and regulatory communication about remediation as maybe required.
- Recover surface fluids and contaminated soil.
- Fence-off release areas to protect people and wildlife until reclamation is complete.

- Contaminated material must be placed in appropriate impermeable storage (steel tank, lined containment area, etc.), sampled and disposed of at an approved licensed disposal facility.
- Plan adequate storage and disposal of any recovered/ contaminated product.
- Follow approved Transportation of Dangerous Goods (TDG) regulations when shipping recovered /contaminated materials.

### 7.17 Spill Contingency Plan

The purpose of this Spill Contingency Plan is to define procedures for responding to discharges of petroleum or refined products that flow offsite and/or that impact surface water features such as drains, wetlands, ponds, or creeks.

The objective of the procedures described in this Spill Contingency Plan is to protect the public, Company personnel, and other responders during spills or releases and clean-up operations. In addition, the Spill Contingency Plan is intended to minimize damage to the environment, natural resources, and facility installations from a discharge.

This Spill Contingency Plan describes the responsibilities and procedures for responding to a petroleum or refined products discharge and performing clean-up operations.

#### 7.17.1 Spill Preparedness Risk Analysis

The risk analysis is the identification of potential spill sources and product types from a company's operations, the potential hazards that could result from an uncontrolled release and the determination of the vulnerability of an area should a spill occur. The possibility that a spill could occur under all conditions in a given area must be anticipated. In terms of spills, higher risk operations are often linked with having facilities and/or transporting products in close proximity to the public and environmentally sensitive area including those areas that have surface water.

A typical risk analysis of a company's operations includes the following components:

- An evaluation of products handled in terms of their characteristics during an uncontrolled release as well as their impact on people, property and the environment.
- Familiarization with the environmental sensitivities around facilities and in areas where the products are handles and/or transported.
- Compliance with legal and company requirements (i.e. laws and regulations, industry standards, policies, procedures and guidelines).
- Review of construction and maintenance procedures.
- Evaluation of the spill prevention program.
- Review of the company emergency response plan and spill contingency plan.
- Evaluation of the overall company's response capability for each area of operation.

#### 7.17.2 Seven Step Guideline for Spill Response

For specific spill volume thresholds and reporting requirements, see the applicable Jurisdictional Section in this ERP.

### *Step 1 – Collect and Document Spill Reporting Information*

One of the first steps in a spill response will be to collect and document spill-reporting information. This emergency response plan has a spill report form that can be used to collect critical information. Ensure that staff are familiar with the spill report form and know who to pass information on to. Information documented on the spill report form will be used to notify initial spill responders, company contacts and where appropriate, government and land contacts. It is important to ensure that a contact number is recorded for the person that reports the spill and that there is follow-up contact with that person. Typical information on a spill report form includes:

- Person reporting and contact numbers.
- Operator, company and/or licensee information.
- Date and time of incident.
- Type and volume of the spilled product (product identification number if available).
- Incident cause.
- Incident location and site description.
- Safety concerns.
- Environmental issues.
- Level of emergency.
- Public concerns issues.
- Spill response activities.
- Contact information.

Responder tools will depend on the types of spills. If an employee has been identified as having a spill response role, it is important that he/she has quick access to initial response tools including:

- An emergency response plan or key information (e.g. contact lists, resource lists, access and control point maps) extracted from the plan.
- Communications equipment.
- Appropriate personnel protective equipment including a personal and/or electronic monitor (gas detector).
- Recording equipment (e.g. notebook, pens, and camera).
- Portable barriers and/or hazard warning ribbon.
- A compass and measuring equipment (e.g. topofil, tape measurer).
- Personal items (e.g. water, extra clothing, snacks, etc.).
- Wind indicators (e.g. portable windsocks, Teflon tape).

In addition, it may be of value to have access to some basic spill containment and sampling equipment including:

- Shovel.
- Rubber mat and/or plastic to cover storm and/or sewer drains and plywood to block culverts.
- Sorbent booms.
- Basic patching equipment for container leaks.
- Sampling equipment and containers.
- Quantabs for assessing salinity at produced water spills.

### *Step 2 – Dispatch Initial Responders to the Incident Site*

Following the notification of the incident dispatch initial responders to the spill site to:

- Verify that there is a spill.
- Gain site control.
- Assess the incident.
- Make appropriate contacts.
- Develop an incident action plan.
- Isolate the leak.
- Initiate containment and recovery if safe to do so.

On route to the site, responders should consider how they would safely approach the area to minimize exposure. In general, the site should be approached from upwind and from high ground if possible, with appropriate PPE and detection equipment.

Three important things for responders to remember during the initial response are:

1. To protect the lives and well-being of spill responders.
2. Initial responders must only attempt what they are capable of doing safely.
3. Sounding the alarm with a call for help should be anticipated.

#### **HELP! Where from?**

- Internal resources.
- Other companies.
- Government agencies.
- Fire departments.
- Police.
- Ambulance.
- Contractors.
- Spill specialists.

It will be important that the response team have pre-determined organizational structure with a spill response team leader and that each member clearly understands his/her role. The initial response team should be organized so that they work in pairs (buddy system) prior to taking any action on-site. Good, clear communications within the initial response team is critical. If additional help is required, the initial responders should identify a practical meeting location that can be used as a staging area for manpower and equipment.

### *Step 3 – Arriving at the Spill Site – Site Control*

One of the most critical steps once the responders arrive on the incident scene is for them to take control of the site. It is essential to keep all personnel out of the hazardous area until the identification of the nature and degree of hazards is known, and the initial assessment completed. This includes not only hazards from the spilled material but other physical hazards such as power lines, etc. Although no two spills are the same and not all of the assessment information is immediately available, the following general sequence of site control techniques is common during a disciplined spill response:

- Verify who is in command.
- Identify the emergency planning zone which is the area of greatest concern related to the hazards associated with the event.
- Secure all non-essential personnel from the emergency planning zone and identify the emergency planning zone with ribbon and/or barricades if possible.
  - This step could include the evacuation of a large number of people and outside assistance will likely be required.

- Identify an entry and exit checkpoint at the periphery of the emergency planning zone to regulate the flow of personnel and equipment.
- Control all access to the emergency site by adding a contamination reduction zone which is a transitional or buffer area and a support zone which is a clean area for the On-Site Command Post (OSCP), equipment, staging, etc.
- Identify a safe area within the contamination reduction zone to remove contamination from response personnel, their clothing, and equipment.
- Eliminate all potential ignition sources if safe to do so.
- Identify an emergency signal, escape routes, and a meeting location for response personnel.
- Place wind indicators at appropriate locations.
- Ensure responders understand the issues related to site management and understand their role.

If there is an injury at the spill site when the responders arrive it may be necessary to provide primary care to the injured persons until medical professionals arrive. In remote areas, it may be advantageous to consult with a physician via radio or phone and provide care for the injured during the transferring of the injured to medical professionals. It is extremely important that responders do not take an unreasonable risk when attempting a rescue operation at the incident site.

#### *Step 4 – Situation Analysis*

Following their arrival on-site, the response team will conduct an assessment of the spill, sometimes referred to as a situation analysis. The analysis can be broken down into smaller components as follows:

- What is the problem?
- What variables can affect it?
- What are the potential losses and critical issues?
- What is needed to protect response personnel?

#### **The Problem?**

Analyzing the problem means looking at the quantity and nature of the material, type and behavior of the container and stage of incident.

- Identify the spilled substance.
- Identify of the hazards associated with the uncontrolled release.

#### **Sources of Information Include:**

**Operator Knowledge:** The owner of the spilled material is a good source of information related to product identification, characteristics of the material and typical hazards associated with an uncontrolled release. The owner also has access to Safety Data Sheets (SDS) and an emergency response plan.

**Shipping Documents:** If the spill is linked to a transport vehicle, shipping documents or a waste manifest will be in the road vehicle within reach of the driver (i.e. seat or door pocket). The shipping document will outline contact information, a description of good carried, quantity of goods and an emergency response telephone number.

**Safety Marks/Labeling:** Placards (250 mm x 250 mm) used to identify loads over 450 litres, labels (100 mm x 100 mm) used to identify product in smaller containers and safety marks provide visual clues related to the identification and hazards associated with the spilled product. An international system of safety marks that responders should be familiar with includes:

- **Class Number:** Eight classes of dangerous goods are identified including; Class 1-Explosives, Class 2-Gases, Class 3-Flammable Liquids, Class 4-Flammable Substance, Class 5-Oxidizers/Organic Peroxides, Class 6-Toxic/Infectious Substances, Class 7-Radioactives, Class 8-Corrosives, Class 9-Miscellaneous
- **Colour:** The color of the safety mark will also provide clues as to the type and hazard associated with the material; for example, red indicates that the product is flammable.
- **Number:** A United Nations (UN) number, a four-digit number has been assigned to all dangerous goods; for example, gasoline is UN 1203, diesel fuel is UN 1202, and crude oil is UN 1267.
- **Container Identification:** The size and shape of the container involved in an uncontrolled release can also provide responders with a visual clue related to that container's contents.

**Emergency Response Guidebooks:** These guides help the responder identify the material by listing all of the United Nations (UN) numbers and linking the number with the name of the material and/or listing the materials in alphabetical order. The guidebook also provides a general guideline on potential hazards, public safety issues and emergency response considerations for each of the materials listed in the book. In addition, the guide includes initial isolation and protective action distances that can be used to zone a spill site (i.e. flammable liquids isolate spill for at least 25 to 50 meters in all directions).

**Computer databases:** Countries maintain emergency response telephone numbers where the responder can obtain specific information regarding the spilled substance.

In terms of quantity, responders should be concerned with both the amount of product spilled and the amount that could be spilled. The type, condition and behavior of the container will help responders estimate spill volumes and forecast potential problems.

Variables That Affect the Spill:

There are three primary variables that have an impact on a spill including the location of the spill, the time the spill occurs, and weather conditions. It is important to remember that no two spills are the same and that these variables can affect the spill in many different combinations.

### Spill Location

The spill location will likely have the greatest impact on the number and complexity of issues that a response team is faced with. The following are typical examples of how location can affect the spill's impact:

- **Populated versus Unpopulated areas:** Spills in remote areas will likely have less impact on the general public, as opposed to the same incident occurring in a populated area. Remote areas usually have their own unique characteristics that can present challenges to the responsible party (i.e. communications problems, resource availability, equipment access, exposure to wild animals, etc.).
- **Spills in Surface Water versus Land Based Spills:** Spills that migrate into surface water are much more complex to deal with than land-based spills. The issues become more complex when there is a current carrying the product downstream, particularly when there are downstream water users and the stream or river is abundant in fish and wildlife.
- **Land Uses:** It is not uncommon for there to be several land uses associated with a spill incident. The more land uses affected by the spill, the more issues the response team is usually faced with.

- **Spill Site Characteristics:** The soil structure, vegetation types, presence of storm, and sewer drains, topography, and man-made structures at a spill site are just a few of the potential site characteristics that can have an impact on the incident.

### **Time**

The time of day, day of the week and month of the year all have an impact on the issues related to the incident. For example, a spill that occurs in the middle of the night will probably have a delay in the overall response.

### **Weather Conditions**

Weather conditions can help or hinder the conditions at a spill incident. Wind can have major effect on downwind exposures, it can change directions in a matter of seconds and move spill vapours into highly sensitive areas. In some cases, stronger winds can disperse vapours and reduce the flammable range and toxicity of a hydrocarbon plume migrating from the incident site. Strong winds also have the potential to blow debris around the site and cause dead standing timber to fall. In the absence of wind, vapours can pool in low areas in and around the spill site. Wind can also affect the movement of a spilled substance on surface water by increasing or decreasing the spreading rate and pushing the substance in a downwind direction.

Temperature may have an effect on the behavior of a spilled substance and can reduce or increase vaporization rates. In addition, temperature extremes can present health risks to responders such as heat stress, hypothermia and exposure to lightning strikes. Travel time for responders can also be influenced by weather conditions.

Winter conditions present their own unique problems such as product mixed with or under ice and snow, short days, cold temperatures, equipment limitations, etc.

### **Identification of Potential Losses and Critical Issues**

Generally potential losses resulting from a spill include:

- Health and welfare of people linked with the incident including the spill response team.
- Health and welfare of domestic animals, fish and wildlife.
- Damage to property and equipment.
- Negative impact to the environment.
- Impact on a company's image.
- Costs incurred from losses and response activities.

It is important to identify all land uses and stakeholders that are or could be affected by the spill. In some jurisdictions, a list of land uses can be obtained through an electronic data base. Other sources of information include contingency plans, local residents, regulatory personnel (e.g. lead agency for spills, police, fish, and wildlife and forestry), area operators, utility companies, municipal offices, and unique area experts like trappers and recreational users. Identifying the stakeholders will help responders to identify spill issues and formulate a response plan. Not all this information will be available during the first few critical hours of the incident; however, it will be necessary to obtain it for an effective response. Identifying the stakeholders affected by the spill will help define the critical issues related to the incident and to prioritize those issues based on the spill response priorities; protection of life, property and the environment.

At this stage of the analysis it is advantageous to characterize the spill as stable or unstable. Stabilized means that all fires have been extinguished, all ignition sources have been controlled and all spills have been contained. Unstable means that conditions at the site are changing and control of the incident is pending.

### *Step 5 – Documentation and Information Management*

Documentation of the incident is extremely important and should be initiated early in the response and maintained throughout the event. Documentation requirements will depend on the nature of the incident and should include the following:

**First Report:** Date and time of release, location of the point of release, composition of the release, quantity of spilled substance, release cause, circumstances leading up to event, and initial response activities.

**Spill Response Organizational Structure:** Outline of the organizational structure with contact information.

**Site Description:** Spill sketch, photos, and map.

**Event Records:** Chronological record of events.

**Safety:** Findings of initial hazard assessment, safety controls, safety meetings, worker requirements, safety orientation, incident reporting, equipment, and resources.

**Environmental Issues:** Sensitivities, sampling information, waste management plan, etc.

**Negotiations and Agreements:** Internal company representatives, regulatory, and third-party contractual agreements. It is also important to maintain detailed records of site visitors, their contact information, reason for visit and specific details related to their involvement.

**Incident Action Plan:** An overview of the issues and plan to deal with those issues.

**Regulatory Spill Reporting:** Regulatory spill reporting requirements, located in this ERP, are dictated by the type of spill, the spill volume, and location of the spill. Non-compliance related to spill reporting usually leads to enforcement action and substantial fines.

**Type of Spill:** In most jurisdictions an upstream petroleum-based spill is reported to the lead Regulatory Authority. Refined product spills and chemical spills are reported to the environmental agency. There is normally a memorandum of understanding between the Regulatory Authority and Environmental Agency related to ensuring that they advise each other of appropriate incidents. If the spill is caused by a transportation incident and the spilled product is regulated under the Transportation of Dangerous Goods Act, it is a requirement to report the incident to police as well.

**Spill Volume:** Provincial/State legislation identifies the minimum volume of spilled material that must be reported. In transportation-based spills where the product is TDG regulated, the minimum spill volumes are outlined in the Transportation of Dangerous Goods Act and Regulations.

**Location of Spill:** If the spill is not reportable because the volume is less than the reportable volume, but the spill causes an adverse effect (negatively impacts people, property, and/or environment) it is considered a reportable spill.

### *Step 6 – Developing the Incident Action Plan*

Once the spill responders have control of the site and have completed the assessment, they should develop and document an incident action plan. The plan will identify spill issues and outline tactical objectives for dealing with the issues. The following is an example of some of the issues that could be included in an incident action plan:

- Emergency conditions.
- Hazards, risks and assessment information.
- Issues identification.
- Safety controls.

- Response objectives, tactics and alternative options.
- Resources.
- Organizational structure.
- Names of individuals and agencies participating in discussions.
- Waste management.
- Sampling and analysis.

The incident action plan is subject to change. The response team evaluates the incident on a continuous basis and new spill issues are introduced as the incident progresses. It is important that responders review the plan on a frequent basis, make changes if appropriate and ensure that stakeholders are aware of those changes.

#### *Step 7 – Implementation of Response Objectives*

Once the incident action plan has been developed, the response team will implement response objectives. The incident will be handled offensively, defensively or by non-intervention.

- Offensive tactics require responders to control and/or mitigate the incident within the higher risk areas of the event. Safety controls must be in place to undertake offensive tactics.
- Defensive tactics allow responders to control/mitigate the emergency remote from the higher risk (i.e. installing barriers to prevent product from migrating into sensitive areas, deploying boom at downstream control points, etc.).
- Non-intervention refers to responders taking limited action at the emergency site, normally additional resources arrive.

### **7.17.3 Company Spill Discovery and Response Actions**

The Company has the primary responsibility for providing the initial response to spills and releases originating from one of their wells, facilities, or pipelines. To accomplish this, the Company has implemented the Incident Command System (ICS), developed response plans, and completed training to respond to a spill or release event. The Incident Commander plays a central coordinating role in any emergency situation.

The Incident Commander will direct notifications and initial response actions in accordance with the company Emergency Response Plan, training, and capabilities.

#### **Discharge Discovery and Source Control**

Upon discovery of a leak or spill the following actions should be taken:

- Immediately report the discharge to the Company Supervisor, providing the following information:
  - Exact location
  - Material involved
  - Quantity involved
  - Topographic and environmental conditions
  - Circumstances that may hinder response
  - Injuries, if any
- Turn off all sources of ignition.
- Locate the source of the discharge.
- Turn off all equipment related to the incident that could add to the impact of the release.
- If safe to do so, isolate the affected equipment by closing off the closest valves upstream and downstream from the discharge source.

#### **Assessment and Notifications**

Notifications to the appropriate Regulatory Authority must occur after the discovery of reportable discharges. The reporting clock starts when the first company or contract employee discovers the discharge.

- Investigate the discharge to assess the actual or potential threat to human health or the environment. Also consider:
  - Location of the discharge relative to receiving water bodies (drainages, creeks, or streams)
  - Quantity of spilled material
  - Ambient conditions (temperature, rain)
  - Other contributing factors such as fire or explosion hazards
  - Sensitive receptors downstream (wetlands, ponds, or reservoirs)
- Request outside assistance from local emergency responders, as needed.
- Evaluate the need to evacuate the facility and evacuate employees, as needed.
- Assess whether community evacuation is needed. Notify the local authority, fire/police for assistance, as needed.
- Contact Company Supervisor to determine if Regulatory Authority notifications are required.
- Communicate with property owners regarding the discharge and actions taken to mitigate the damage.
- If needed, bring in outside contractors and order recovery equipment such as vacuum trucks and backhoes to stop the flow. Mobilize equipment and resources to the spill site as soon as the need is identified.
- If spilled fluids reach (or threaten to reach) any nearby drainages or surface waters, you may need to notify the local authority, Regulatory Authority fire/police

to limit access to the water by local residents until the product has been contained and recovered. Additionally, notify downstream water users of the spill and of actions that will be taken to protect these downstream receptors.

### *Control and Recovery*

The Incident Commander directs the initial control of the release and other contractor personnel. The actions taken will depend on whether the product has reached water or is confined to land. All effort will be made to prevent the release from reaching water.

If the product has not yet reached water:

- Deploy sandbags and absorbent socks down gradient from the product, or erect temporary barriers such as trenches or mounds to prevent the product from reaching water.
- Implement land-based response actions (countermeasure) such as digging temporary containment pits, ponds, or curbs to prevent the flow of product into any water.
- Deploy absorbent sock and absorbent material along the water line to prevent product from entering waters.
- Contact clean-up contractor(s).
- Deploy floating booms immediately downstream from the release point.
- Control product flow on the ground by placing absorbent socks and other absorbent material or physical barriers (e.g., kitty litter, sandbags, earthen berm, trenches) across the product flow path.
- Deploy additional floating booms across the whole width of the affected waters at the next access point downstream from the release point. Plan ahead and access the stream or waters from safe locations.
- Deploy protective booming measures for downstream receptors that may be impacted by the spill.

### *Spill Clean-up/Mitigation/Reclamation*

Once the pipeline break or leak has been located and isolated and the area has been secured, the following procedure should be followed.

- Determine if there are any other pipelines or utilities within 30 metres of the break or leak site. If so, the licensee of these lines must be contacted before any ground disturbance occurs.
- Uncover the affected section(s) of pipeline by the safest method. Hand excavation or hydrovac should be used whenever the break is within 5 metres of the pipeline in question or another pipeline until the break or leak is located.
- Expose the pipeline break or leak, ensuring that the proper trenching, back sloping and shoring techniques are used and that a safe route of access and egress is maintained at all times.
- Obtain a sufficient number of samples of effluent to quantitatively determine its physical and chemical properties.
- Drain effluent into a bell hole and remove the impacted soil and waste to an approved disposal site.
- Photographs are to be taken throughout the operation for documentation.
- Refer to the Environmental Regulatory Authority regarding land reclamation standards and requirements.

### *Decontamination Guidelines*

These guidelines are for personnel directly exposed (or suspected of exposure) to oil or chemicals or their vapours, products of combustion, etc. The intention is to provide a general overview of those decontamination situations most likely to be faced by Company responders.

Decontamination areas:

- Will be set up as needed during response operations.
- These areas are to be used for decontamination at the work site.
- They are not to be used as a substitute for personal hygiene prior to arrival.
- Are designed to protect the health of response personnel and to prevent the spread of contamination into 'clean' areas.
- In the field, it will not be possible to remove all contaminated clothing before taking a break from work. It is essential, however, to clean hands and face to avoid inadvertently ingesting oil or spreading contamination to otherwise protected parts of the body.
- In the field, provisions will be made for:
  - Soap, water, paper towels, waterless hand cleaner, and/or other materials for washing hands and feet.
  - Refuse containers.
  - Eyewash station.
  - Safety equipment and clothing as needed.

Full decontamination will be required at the end of the daily shift. Typically, this involves reporting to an area designed for removing contaminated clothing. This must be done carefully to avoid allowing the contaminated clothing to come into contact with the skin or clean clothing. Cleaning stations are used to scrub the body thoroughly in order to remove all traces of chemical or other contaminants. Once fully decontaminated, clean clothing will be put on and contaminated clothing will be cleaned appropriately.

### *Communications and Control*

A Command Post will be set up near the incident site in the event of a discharge. The Command Post will be equipped with a variety of fixed and mobile communication equipment (telephone, cell phones, computers, etc.) to ensure continuous communication with Company management, responders, authorities and other interested parties. Additional equipment will be obtained from the response contractor in the event that more communications equipment is necessary.

The Incident Commander is responsible for communicating the status of the response operations and for sharing relevant information with involved parties, including Company Management; local, provincial and federal authorities.

### *Disposal of Recovered Product and Contaminated Response Material*

The Incident Commander ensures that all contaminated waste materials are disposed of in accordance with all applicable solid and hazardous waste regulations. Contact the Company Supervisor to get guidance on approved disposal locations. In some cases, on-site treatment (bioremediation) may be approved, minimizing costs.

- Place any recovered product that can be recycled into an on-site tank to be separated and recycled.
- Dispose of recovered product not suitable for on-site recycling with the rest of the waste collected at an approved and permitted location.
- Collect all debris in properly labeled waste containers (impervious bags, drums, or buckets or a roll off bin with a liner).
- Collect samples to characterize the waste for shipping and obtain approvals from licensed disposal facilities. Prepare shipping manifests and shipping documents as needed.
- Dispose of contaminated material in accordance with all applicable solid and hazardous waste regulations using a licensed waste hauler and disposal facility.

### *Termination*

The Incident Commander ensures that clean-up has been completed and that the contaminated area has been treated or mitigated according to the applicable regulations and provincial/federal clean-up requirements. In some cases, the spill area soil must be sampled before backfilling can take place. The Incident Commander collaborates with the local, provincial or federal authorities regarding the assessment of damages, as needed.

- Ensure that all repairs to the equipment or pipelines have been completed.
- Review circumstances that led to the spill or release and take all necessary precautions to prevent a recurrence. Apply lessons learned to all operations.
- Evaluate the effectiveness of the response activities and make adjustments as necessary to response procedures and personnel training.
- Carry out personnel and contractor debriefings as necessary to emphasize prevention measures or to communicate changes in operations or response procedures.
- Restock spill response supplies.
- Submit any required follow-up reports to the authorities.

### *Training Exercises and Updating Procedures*

The Company maintains an ongoing training program to ensure that personnel responding to discharges are properly trained and that all necessary equipment is available to them.

Following a response to a discharge, the Incident Commander and Company Management will evaluate the actions taken and identify procedural areas where improvements are needed. The Incident Commander will conduct a briefing with field personnel, contractors, and local emergency responders as needed to discuss lessons learned.

### 7.17.4 Spill Management Techniques

#### Spills on Land – Containment

##### General Containment Procedures

1. If the spill is not flowing or spreading, no containment is required.
2. Use the information gained from the assessment to plan the location of the initial containment measures and determine what type of measures will be required (e.g., booms, sorbents, etc.).
3. Organize and install the containment measures in order of priority to prevent the spill from getting larger and to protect sensitive areas. This will reduce the amount of clean-up work and result in lower clean-up costs and damage settlements. Oil Spill Co-op Contingency manuals should be referred to for the most appropriate containment techniques.
4. Local topography, locations of nearby streams, water bodies, and sewer outfalls, etc., should be taken into account when planning the location of containment berms and dikes. Appropriate Oil Spill Co-op Contingency manuals should be consulted for more information on this subject.
5. Containment berms and dikes should be deployed on land in a manner that will prevent any spilled material from entering a water source. Contingency back-up plans should be developed in case of a breach or failure of a containment structure.
6. If necessary, topsoil should be stripped from areas that will be affected by a fluid spill prior to the spill reaching that area.
7. If necessary, the area around the spill should be fenced off to prevent wildlife and livestock from entering the spill area.
8. If the material is producing flammable or noxious vapours, apply an appropriate foam suppressant to reduce and control the fire/vapour hazard to the surrounding area.
9. In the event of fluid spills breaching existing containment structures, contingency plans should be immediately implemented to prevent any materials from entering streams or water bodies.

##### Containment Techniques

###### Sorbing Boom and Blanket

Booms and sorbent blankets may readily contain small spills, especially those that have accumulated on the surface and not infiltrated the soil. Judge the amount of boom needed and assess migration potential based on weather conditions and the topography of the spill area.

###### Earth Berm

1. Where equipment is available for hand or machine digging, earth berms and containment dikes can be used to contain spills.
2. Suitable soil material (i.e., clay, silt) should be used in the construction of containment dikes and berms. Topsoil material should be stripped and preserved for reclamation procedures.
3. Where soils or surface materials are too permeable to provide adequate containment of spilled fluids, berms/dikes can be fortified with plastic sheeting or sorbent blankets to make the berm less permeable.

---

### **Subsurface Trenching**

1. Trenches may be contoured to direct or funnel spilled fluids towards a bellhole or other collection/containment area. If required, trenches and berms may also be constructed upstream of the spill to direct water or run off away from the spill.
2. Where significant subsurface flow of contaminants is anticipated, subsurface trenching will be required to intercept and contain any subsurface flow and direct it towards a bellhole or other low permeability containment area.
3. The specific pattern of trenching depends on the topography and flow regime in the subsurface materials. Trenches are most effective if they can be dug to the depth of the impermeable cemented hard pan or bedrock.
4. The bellhole containment area must be lined or located in impermeable material.

### **Liquid Spills on Open Ground**

1. Spills on open ground are common to the oil and gas industry. Pipeline ruptures during the course of day-to-day operations and overflows of production fluids during well development/ completion activity account for a large portion of these material spills. Once on the ground, the spread of fluids is influenced by local topography and permeability of the soil. These two (2) factors together can make containment and clean-up operations difficult. Spills in areas of high relief can spread considerable distances in a short period of time causing greater aerial impact.
2. Fluid spills in areas with soils having high permeability should be cleaned up quickly in order to reduce the amount of infiltration into soil layers.
3. Spills should be cleaned up from the perimeter towards the centre. Travel through the affected area by equipment or personnel should be avoided at all times.
4. Universal or specific use absorbents can be used to collect spilled material from the containment area. Spill Co-ops can be contacted for information regarding the appropriate uses of available absorbents.
5. Contaminated soil should be excavated and removed to an area where runoff or leaching of the contaminants into the soil can be prevented.

### **Liquid Spills on Paved Areas**

1. In areas of high relief, fluids spilled on pavement may travel rapidly over considerable distances. The viscosity of the fluid, the local relief, and lack of obstructions on the smooth surface will all affect the rate at which the spill will spread. If not contained, spilled materials may enter sewer outfalls and be transported into the local sewage system or into nearby water sources, which would complicate containment and recovery of the spill. This could potentially result in contamination of water sources and wildlife habitat. In such cases it is imperative that spilled materials are contained immediately and diverted away from any sewer outfalls that are within reach of the spill.
2. Spill Co-op procedure manuals can be consulted for the most effective method of containment and clean-up when dealing with particular fluid spills.
3. Location of downstream sewer outfalls, drainage ditches, streams, or water bodies should be determined so that they can be plugged or bermed to prevent spilled material from entering.
4. Foam suppressants should be applied on the spill if dangerous vapours are present.
5. Once contained, clean-up should start immediately. Spilled materials should be moved to collection areas utilizing shovels, scoops, squeegees, brooms, etc., and then removed by vacuum trucks.

6. Appropriate absorbent materials can be utilized to accumulate spilled material that cannot be moved to collection areas. Oil Spill Co-ops should be consulted to determine the most appropriate absorbent material.
7. Used absorbent materials should be stored in barrels or another appropriate container and disposed of appropriately.

### **Solid Materials Spills on Land**

1. Solid material spills on the land can lead to extensive environmental impacts. Material spills of this nature spread through wind and surface runoff. If not properly contained and secured, this material can travel considerable distances or become incorporated in local water bodies, adversely affecting the water quality and associated habitat. Runoff from the spill area can also contaminate these water sources if not properly collected.
2. Appropriate PPE should be donned before attempting to contain and recover spilled materials. Depending on the material, this may require the use of respiratory protection, goggles or facemask, rubber gloves, boots, and/or disposable or other coveralls.
3. No clean-up actions are to take place until the spilled material is identified and the correct safe handling procedures are put in place.
4. Environmental Regulatory Authority, local spill co-ops, and/or the manufacturer can be contacted to determine the appropriate containment and removal methods to use for the type of chemical spilled.
5. Extensive dry chemical spills should be covered immediately with secured plastic sheets to reduce the potential for the material to become wind-borne or leach into the soil from rainfall.
6. Dry chemicals can be removed with a shovel or by mechanical means and disposed of in an appropriate manner.

### ***Spills on Land – Recovery and Removal***

#### **Sorbents**

Sorbents can be used for small spills of oils, fuels, and lubricating oils that have not infiltrated the ground surface, or any other location where free product is floating or ponded.

#### **Shovel and Barrel**

Small crude/lubricating oil spills that have soaked into the ground can be dug out with a shovel. If the spill occurs on lease, spread the oil-soaked soil on a designated treatment area and work it into the first 5 cm of clean soil along with some manure and straw or other fibrous material. This can be worked in with a shovel and rake if the amount is small.

#### **Vacuum Truck and Pumps**

Hydrocarbons and saltwater can be recovered from containment areas or from standing water using vacuum trucks. The material is then transferred to holding tanks, sumps, or other approved facilities. Alternatively, 400 bbl tanks can be hauled to the site and set near the collection bell holes. Recovered fluids can then be pumped directly from the bellholes.

#### **Earth Moving Equipment**

Large earth moving equipment such as graders, scrapers, hoes, and front-end loaders may be utilized to contain and move oil contaminated sediments to a pre-approved storage, treatment, or disposal area. If the amount of oily sediment is small, it can be spread on a designated treatment area with some manure and straw or other fibrous material to bio-degrade the contaminated material.

## Recovery Wells

Where spilled hydrocarbon or saltwater has infiltrated subsurface permeable materials and removal of the contaminated material is not desirable, it may be necessary to drill recovery wells around the spill area to the necessary depth, so the fluid can be intercepted and pumped to the surface.

### *Spills on Water – Containment, Recovery, and Removal*

In situations where a substance that may be deleterious to the health and/or safety of humans and/or livestock or irrigated crops has been spilled into a watercourse it is necessary to notify regulators immediately and warn downstream users to take appropriate actions.

## General Containment Procedures

1. In stagnant water bodies, floating booms should be deployed in a manner that will utilize winds and currents to help reduce the spreading of the spill.
2. Shorelines should be protected with floating booms, sorbent booms, or sorbent mats before the spill is moved to shore for removal.
3. In slow flowing watercourses (less than 1 km/h), floating booms should be placed downstream to accumulate spilled material. At higher rates of flow, booms should be angled in a manner that will divert floating material to an area of low flow velocity for removal.
4. Do not place booms in areas where the flow rate is greater than 6 km/h as they will be ineffective in containing the spill. If the flow rate is too high, try to locate a more suitable containment location downstream. Refer to an Oil Spill Co-op Contingency manual for more information on this subject. Flow rates can be determined by measuring the time it takes for an object to float a known distance downstream. The use of elongated objects (such as sticks) may produce erroneous results (on the low side), as they tend to align themselves in the direction of the current, which allows water to slip past them.

## Floating Spills

1. Materials that float on water such as oil, diesel fuel, or gasoline, if left to spread, may have serious environmental implications. The rate and direction at which such a spill will spread is dependent on wind, currents, and rate of flow. Spills into stagnant water bodies are generally affected by wind currents and can spread to form complex configurations making containment more difficult. Spills into watercourses such as rivers or streams are often more difficult to handle. Materials may be transported considerable distances by the stream flow before they are contained. High rates of flow or large debris being transported by the stream (i.e., ice, logs, and branches) may damage floating booms or render boom deployment ineffective. It is essential that immediate containment and clean-up be initiated for floating spills in order to limit adverse environmental affects and to reduce clean-up costs.
2. Floating debris in the stream course should be removed or contained upstream. This will prevent floating booms that are located downstream from being damaged and reduce the potential for clogging or damage of skimming or vacuum equipment.
3. Accumulated spill material should be removed by vacuum truck, skimmers, trash pump, or suitable absorbents as quickly as possible.

---

**Floating Spills Under Ice**

1. Oil spilled under ice will collect in pockets. In stagnant water bodies, oil will concentrate near the spill area. Holes should be drilled into these pockets and the oil removed by suction equipment.
2. Oil spilled under ice that has formed over moving water is best recovered by constructing an ice slot or trench angled to the stream bank. Oil should be removed by suction equipment on a continual basis to prevent build-up and escape.
3. If ice is too thin to support men or equipment, holes can be formed by dropping large inanimate objects using a helicopter (which requires prior approval from Environmental Regulatory Authority).

**Insoluble Liquids Denser than Water**

1. Materials that are heavier than water and do not dissolve, such as oily sludges or heavy oils, present unique problems when spilled into water bodies, rivers, or streams. These materials tend to flow and accumulate in low spots due to their greater density. Because they do not dissolve, contaminants can mix with bottom sediments and damage these shallow nutrient rich zones. The spread of these types of spills is dependent on such factors as bottom relief, currents, and flow rate. Containment and clean-up of such spills can be difficult, depending on site-specific factors. Speed and effectiveness of containment and clean-up procedures are critical in reducing the negative impacts associated with these types of spills.
2. Oil Spill Co-op Contingency manuals should be referred to for the most appropriate method of containment and clean-up when dealing with a specific type of spill.
3. If the material has entered a water body or watercourse, natural low areas into which the material will flow and accumulate, should be identified.
4. Natural low areas should be pumped free of spilled material. Any contaminated bottom sediments should be transferred by vacuum lines to corresponding holding tanks. Sediments can then be removed to an appropriate disposal or reclamation facility.
5. Dredging low areas to accumulate spilled material in fast flowing watercourses should only be done when determined necessary, and upon proper authorization from Environmental Regulatory Authority.
6. Construction of a dam or dam system downstream, and diversion of upstream flow should be done only when determined necessary, and upon proper authorization from Environmental Regulatory Authority.

**Soluble Chemical Spills into a Water Course**

1. Chemicals that dissolve in water, such as “caustic” and other process chemicals, can result in serious environmental impacts when spilled into water bodies. Depending on the toxicity and concentration of the substance, local water quality could be severely affected, and downstream users placed at considerable risk. Once incorporated in the aqueous environment, tracing these contaminants can be difficult. Wind, currents, flow rate, and sometimes bottom relief influence the spread of contaminated water. It is imperative that all reasonable effort be made to prevent soluble chemicals from entering water sources, and land based clean-up operations be initiated immediately. If spilled chemicals do enter a watercourse, a quick and effective response will help to limit the environmental impact.
2. Immediate notification should be given to the appropriate Oil Spill Co-ops, Regulators, and the affected landowners to ensure public safety and an expeditious clean-up operation.
3. Oil Spill Co-op Contingency manuals should be consulted for the most effective method of containment and clean-up method for particular spills.
4. Clean-up of the spilled material should be initiated immediately in order to minimize the area affected and the degree of environmental impact.

5. If chemicals have entered the watercourse, a dam should be constructed downstream from the spill site. If possible, water upstream of the spill should be diverted upon proper authorization from Environmental Regulatory Authority.
6. If damming and diversion are not feasible, then an accepted method for in-situ treatment of the contaminated water should be considered (i.e., activated carbon absorption, precipitation, neutralization, etc.).

### *Procedures for Obtaining Initial Soil Samples After a Spill*

#### **Sample Labelling and Storage**

1. Store samples below 4°C and send them to the laboratory within 48 hours of sampling.
2. Clearly label all samples with the:
  - company name
  - well name/location
  - dates
  - sample location
  - unique sample identifier number, and
  - the name of the person who obtained the sample.
3. Store samples for transport in a secure travel container (i.e., a cooler).
4. In summer months pack the cooler with some frozen ice packs or ice to keep the samples below 4°C.
5. Wrap samples kept in glass jars individually in “bubble wrap” prior to packing in the cooler.

#### **Laboratory Details**

1. A chain-of-custody (CoC) or laboratory supplied Analysis Request Form should be completed and sent with the samples.
2. Ensure that all of the samples being sent to the lab are documented on the form, and that the proper analyses are requested for each sample.
3. Ensure that the required turnaround time for results is indicated. Normally these forms are in triplicate.
4. Retain one (1) copy for filing and send the other two (2) copies along with the samples.
5. The laboratory should be instructed to sign the CoC form when the samples are received and send one (1) of the copies back to confirm that they received the samples.
6. Keep both copies of the CoC form on file.
7. The laboratory will supply the sample containers, labels, CoC/Analysis Request forms, and the shipping container.

## 7.18 Electrical Incident Response

If an electrical incident occurs the NorthRiver Midstream Emergency Management Program requirements will be followed.

- “Calling the Alert” is the first requirement, call 911!
- The following emergency response procedure is recommended:
  1. Evacuate away from the area where the electrical incident occurred, assess the situation, and ensure there are no continuing hazards to yourself or others.
  2. Sound the alarm, alert other personnel.
  3. Call for help, call 911 and then notify the Supervisor.
  4. Assess the hazards don’t rush in to initiate rescue. Only complete an electrical incident rescue if you are authorized and competent to complete the rescue safely.
  5. Secure the area, treat all electrical equipment as energized. If you are authorized to do so turn off the electrical power supply (e.g., for high voltage power distribution equipment  $\geq 1001V$  you may not be authorized and/or competent to operate the isolation device), isolate and lock out the electrical source following established electrical safe work procedures. If you cannot turn the power off, then assess if you can safely rescue using a hot stick. If a hot stick is not available, are rubber insulating gloves available?
  6. Initiate rescue, when it is confirmed safe to do so, rescue the injured worker.
  7. When the injured worker has been removed to a safe area begin first aid if properly trained. If the injured worker is unconscious or breathing is erratic monitor closely. If breathing stops apply artificial respiration immediately.
  8. Don’t leave the injured worker unattended.
  9. If the injured worker is burned do not touch the injured worker’s affected area or apply any lotions or gauzes.
  10. Confirm emergency services have been dispatched.
  11. The Supervisor or HSE will follow up, ensuring government/regulatory agencies have been notified as required.
  12. The Supervisor or HSE will complete an incident report.

Workers exposed to electrical hazards are to be trained in methods of release of victims from contact with exposed energized electrical conductors or circuit parts. This should include emergency isolation procedures. Electrical Workers shall also receive regular training in methods of first aid, CPR and use of an AED (if they are available).

Only those workers authorized to do so should undertake electrical incident emergency response rescue. If a worker is unsure of what to do, they shall wait until the authorized worker arrives at the scene.

**Never attempt to rescue a victim of an electrical incident without de-energizing the electrical system first or suitably protecting the person that would attempt to rescue the victim!**

### 7.18.1 Methods of Contact Release for Electric Shock

When a worker is exposed to an electrical shock hazard the first responder to the electrical incident shall follow the NRM emergency response plans. When assessing if the first responder can rescue, they must protect themselves from being shocked by following approved methods of contact release:

1. As a priority if the first responder is trained and authorized, they shall turn off the power to the electrical equipment. In many cases the isolation device may not be accessible quickly and the following two methods of contact release can be utilized. Using an insulating hot stick (e.g., shotgun, fixed length, telescopic or rescue) remove the worker that has been shocked to a safe location. Apply first aid and CPR.
2. Don rubber insulating gloves and using a modified grab pull the worker that has been shocked to a safe location. Apply first aid and CPR.

If the first responder cannot adequately protect themselves, they shall make safe the incident scene until someone arrives at the incident scene that can implement appropriate contact release.

### **7.18.2 Over Head Power Lines & Buried Cables**

When an overhead power line or buried cable incident has occurred no emergency responder will take action to rescue until the Electrical Utility has advised that the power has been turned off.

The rescuer must stay back at least 10 metres and advise anyone remaining in a vehicle that has contacted an energized overhead power line or buried cable to remain calm and remain in their vehicle. If the vehicle catches on fire from contact with an overhead power line the rescuer can provide instructions to anyone in the vehicle to get out the vehicle without contacting the vehicle and the ground at the same time. After the person exits the vehicle, they should be instructed to shuffle away from the vehicle keeping their feet as close together as possible until they are at least 10 metres away from the vehicle.

### **7.19 General Fire Response**

Extinguish fires and protect property impacted from fire without putting responders at risk. Control or eliminate product release and extinguish ignition sources to prevent a fire or explosion.

- Shut-in source (if safe to do so).
- Ensure personal safety.
- Call emergency services as required - 911 - Police, Fire, or Ambulance.
- Conduct a risk assessment.
- Determine the level of emergency.
- If practical, implement a fire attack strategy to extinguish fire or cool equipment/facilities from the fire.
- Order resources such as water tanker, local fire department equipment and/or fire response contractor to assist in the response.
- Implement off site monitoring for LEL, hazardous gas and/or smoke particulates.
- If the public is at risk from smoke or hazardous gas, implement a public communication and protection plan.
- Make the appropriate notifications.
- If safe to do so, remove ignitable products from the fire scene.
- Consider off-site fire hazard conditions (dry vegetation, etc.) and implement a response plan to prevent the spread of the fire.
- Maintain ICS 214 – Activity Log.
- Restrict access to site.
- Preserve the site so that a follow-up investigation can be conducted.
- Participate in debriefing and share learning.

### 7.19.1 Volunteer Fire Personnel

Company personnel can only expect the volunteer fire department to assist with public safety issues (road closures, grass fires, fire containment).

The Company can assist volunteer fire departments by providing a list of fire detection equipment on-site: high level shutdowns, call out alarms, personnel response times to alarms, and basic fire suppression on lease.

Operators should be trained to shut-in any sources of fuel and conduct reasonable and prudent fire suppression when it is safe.

Volunteer fire departments have a duty to provide an adequate level of public safety services such as rescue, fire suppression, and first aid. Keep in mind the level of training that the volunteers have and the type and condition of their equipment. Do not expect them to attempt fire suppression in unsafe conditions with inappropriate or inadequate equipment.

If you have any question of what types of services your volunteer fire department can supply, feel free to contact them and ask.

## 7.20 Facility Fires

### 7.20.1 Facility Fires Safety

- Ensure effective evacuation and identification of trapped and/or missing workers.
- Establish response zones and PPE requirements.

The conducting of rescue operations, product isolation or fire suppression operations during facility fire events are restricted to:

- Activities that are consistent with the experience and reasonable capability of the utilized personnel.
- Activities within the level of training and PPE utilized by the personnel involved.
- Activities that are deemed consistent and appropriate for the scale of the fire event and the conditions present.

All operations must be evaluated relative to their risk potential vs. the benefit to be gained:

- The gain that may be achieved.
- Versus the potential exposure to risk that may or will be present.

Pressurized fuel fires that contain heavier than air components (typically all liquids) pose a significant risk to personnel in the event that the fire is extinguished.

Lighter than air fuels (typically natural gas) pose a significant risk if extinguished inside a closed space e.g. compressor building.

In all cases, personnel shall not be committed to operations or locations that may expose them to any of the following hazardous conditions (this includes the direct positioning, the proximity positioning or the positioning of personnel in locations that may create an exposure to incident escalation, fire growth or event escalation):

- Direct fire contact.
- Heat exposure.
- Smoke and products of combustion.
- Areas of diminished oxygen content.
- Confining or restrictive spaces.
- Locations in proximity to buildings or structures that have been weakened by fire exposure, heat exposure or significant water application.

### 7.20.2 Action Plan for Facility Fires

- Conduct an assessment to identify all the hazards, conditions, and facets of the event.
- Call for additional internal and external resources as required.
- Develop the Incident Action Plan.
- Initiate remote isolation where facility/local isolation is not possible.
- Close Site Retention Basin outlet valve where applicable.
- Do not direct fire suppression operations where run-off may cause environmental damage.
- Initiate Unified Command with emergency responders; ensure safety guidance is reviewed and adhered to before commencing response operations.
- Execute Incident Action plan.

#### **Conduct an Extensive Assessment**

Gather event information to identify all the hazards, conditions and facets of the event, including but not limited to:

- Location of the fire and the areas involved in fire.
- Location and accountability of all personnel – rescue requirement.
- Type of fuel involved.
- Source of the fuel.
- Wind direction.
- Critical escalation potentials – BLEVE potential, chemical fire, catastrophic failure, high value assets.
- Fire growth exposures.

#### **Call for additional resources as required**

Inventory personnel, fire suppressant resources (fire extinguishers, water supplies) and fire suppression appliances.

- Identify the resources required and not present on scene.
- Request the resources required.

#### **Establish Response Zones**

Establish Response Zones and the PPE requirements per zone.

- No Entry Zone - perimeter.
- Emergency Planning Zone - perimeter and PPE requirement.

#### **Develop the Incident Action Plan**

Develop the Incident Action Plan consistent with appropriate event management priorities:

- Rescue or protection of life.
- Protection of critical escalation potentials.
- Protection of uninvolved structures, machinery or assets.
- Confinement of fire to currently involved locations.
- Extinguishment of fire.

The Incident Action Plan once developed shall identify:

- Incident objectives.
- Strategies.
- Safety.
- Weather.
- Resource allocation.
- Critical support requirements.

**Brief Personnel**

Brief site personnel to identify the parameters of the incident and to set initial expectations with regard to safety and assignments. Identify:

- Assessment information.
- Response Zones and PPE requirements.
- Incident Action Plan.
- Provide personnel assignments.

**Ensure Critical Command Issues are established**

Ensure any fire event activities conducted must be done so with the following critical emergency event command issues fully established and in place prior to initiating any proximity operations:

- An organized ICS deployment structure.
- An effective communication system.
- An established personnel accountability system.
- A risk versus benefit-based Incident Action Plan.
- Identified strategies, tactics and operational applications to support the Incident Action Plan.
- The presence and full availability of all required resources.
- A comprehensive air management system to control SCBA operations.
- Resource allocation providing a 2-man team appropriately equipped and supported to protect, maintain and ensure the safe egress route of every 2-man proximity team.

**Execute the Incident Action Plan**

- Conduct, direct, monitor and adjust the application of the Incident Action Plan.
- Re-evaluate the appropriateness of the Incident Action Plan and its strategies, tactics and operational applications.
- Ensure adherence to appropriate event management priorities.
- Re-evaluate the resource requirements of the event.
- Ensure the completion and adherence to the critical command issues.

## 7.21 High Vapour Pressure (HVP) Release

### 7.21.1 HVP Product Release Monitoring

Monitoring may occur downwind or upwind depending on how the plume is tracking, with priority being directed to the nearest un-evacuated residence or areas where people may be present.

The licensee is expected to provide monitored HVP product LEL information on a regular basis throughout the emergency to the environmental agency, the Regulatory Authority, local health authority, and other local authorities and on request to the public.

Air Quality Monitoring equipment will be used to:

- Track the plume.
- Determine if ignition concentration criteria are met.
- Determine whether evacuation and/or sheltering concentration criteria have been met, particularly beyond the EPZ.
- Assist in determining when the emergency status can be downgraded.
- Determine roadblock locations.
- Determine concentrations in areas being evacuated to ensure that evacuation is safe.

The type of air quality monitoring units and the number of monitors required are based on site specific information, including:

- Access and egress points.
- Population density and proximity to urban density developments.
- Local conditions.

NorthRiver will dispatch mobile air quality monitoring equipment from contract service companies located in the area to monitor and record air quality.

Ambient air quality data from the monitoring unit(s) will be communicated by cell phone or mobile radio to the On-Site Command Post.

If a sour gas release has been ignited, the permit holder should continue to monitor response zones for H<sub>2</sub>S from incomplete combustion as well as SO<sub>2</sub>.

### 7.21.2 Ignition Considerations

Company and Contract Operators should be familiar with the guidelines for igniting a high vapour pressure release. ERP procedures should be reviewed as part of a pre-job safety meeting whenever work begins on or near HVP pipelines or wells.

The following items must be considered:

- **Immediate Ignition:** If Company personnel are on-site when a release occurs, and a qualified company representative is present they may ignite the release.
- **Delayed Ignition:** If Company personnel are not on-site when a product release occurs a vapour plume may form.

The following items should be considered before ignition:

- Has the perimeter of the EPZ been established?
- Have all persons been evacuated from the area?
- Will ignition worsen the situation by endangering the environment, public, private property, equipment or facilities?
- Has the wind direction been established and is it being continually monitored?

Following an initial assessment, the Incident Commander must decide if plume ignition is a viable option. Once ignited, the dangers inherent with the vapour cloud are eliminated. The Response

Team should prepare for potential problems as a result of ignition by placing fire fighters on standby.

If trees, buildings, or any obstructions are in the product plume, these items may ignite explosively. All people should be moved to a safe distance.

Controlled ignition eliminates the potential of vapours finding an unsuspected ignition source. Typical issues that may affect high vapour pressure releases include:

- Time of release (day, night, weekend).
- Injuries requiring medical attention.
- Identification of the release boundaries.
- Estimate product volume and plume size.
- Wind direction and speed.
- Topography.
- Vegetation.
- Road access.


### **7.21.3 Guideline for Igniting HVP Plume**

The following steps are a guideline to igniting a high vapour pressure plume:

1. Conduct a complete assessment that includes the identification of the plume perimeter.
2. Take steps to prevent injury including evacuation (if necessary) and the protection of the response team.
3. Approach wearing flame resistant clothing, eye protection, hard hat and a flammable gas detector.
4. Approach the plume from up-wind and slightly cross wind (as there is a greater area of the plume to hit with a flare).

#### **Refer to figure below**

- Stop 200 metres (minimum) from the suspected perimeter of the vapour plume.
- Remember that the flammable perimeter may extend beyond the visible portion of the plume.
- Remember that the heat affected zone extends beyond the flammable perimeter.
- Test for flammable vapour in the atmosphere using a flammable gas detector.
- Use the manufacturer's procedures for loading the flare shell and always point the pistol or launching device at the ground during loading (and until fired).
- Ensure that you begin outside the defined hazardous area.
- Attempt to hit the perimeter of the vapour cloud where the air to fuel mixture is correct for ignition (near outer edge and ground level).
- If no ignition takes place it can be assumed that the flare did not pass through the flammable vapour range of the plume.
- Make the appropriate trajectory adjustments and shoot again. Proceed in this manner until ignition is accomplished.
- Upon ignition, proceed with preventative steps to control unwanted fire.
- Do not extinguish the burning vapour plume.



### 7.22 Pressurized Fuel Fire

The Company strategy is to isolate the fuel, remotely if practical, while protecting exposures (compressor buildings, forests, etc.) and controlling any damage to the environment.

Where local/direct isolation is to be undertaken, the appropriate safety requirements are to be met e.g. responders trained in pressurized fuel firefighting tactics.

- Pressure fires must not be extinguished unless immediate isolation is assured (typically with a dry chemical extinguisher), as the resulting gas release will endanger personnel.
- Pressurized fuel fires with liquids may involve a ground fire, potentially with burning liquids raining down. Suppressing these fires with water streams could result in run-off that causes environmental damage.
- Where the fuel is sour, some portion of the SO<sub>2</sub> emitted from the fire can be knocked down by the use of water sprays. The benefit must be weighed against the potential environmental damage of entrained SO<sub>2</sub> in the run-off i.e. run-off may require collection and neutralization.
- Typically, pressure fires can be quenched with water streams without fear of extinguishment. As depressurization occurs, caution needs to be exercised that the fire is not extinguished, which would lead to flammable vapours being released into the incident area.

### 7.23 Propane or LPG Tank Fire

The Company strategy is to evacuate as far as possible, as soon as possible; up to the distances recommended below. Many factors affect the failure time of a propane tank and as such are outside the expertise of non-professional responders. Site personnel are to assume a catastrophic tank failure is imminent (e.g. > 5 minutes) regardless of the tank size.

Evacuation distances are based on predicted fire ball and fragmentation areas as expressed by the radius of the fire ball and based on size of the propane tank.

- Recommended evacuation for a propane tanker truck is 1.6 km (1 mile) in all directions.
- Recommended evacuation for a small propane tanker truck is 1,000 m (2/3 mile) in all directions.

- Recommended evacuation for a 500-lb tank is 350 m or 1,200 feet in all directions.
- Recommended evacuation for a 100-lb Tank is 200 m or 650 feet in all directions.
- Recommended Evacuation for a 20-lb Tank is 150 m or 500 feet in all directions.

### 7.23.1 Boiling Liquid Expanding Vapour Explosion (BLEVE)

A BLEVE occurs when a sealed container of liquefied gas (e.g. propane tank) is accidentally exposed to and enveloped by fire. The internal pressure of the containment vessel rapidly rises. At the same time, the container wall temperature rises, and the wall strength deteriorates. Even though a pressure relief valve may be operating, the stress applied by the increased pressure exceeds the strength of the containment wall.

The container eventually ruptures, and extremely heated liquid is released, expands and vaporizes in seconds resulting in catastrophic damage, as well as the spread of ignited vapours. The ruptured vessel or tank could propel dangerous shrapnel significant distances.

It is important that vessels or tanks are kept cool and the external fires extinguished quickly with water sprays or natural fluoroprotein-based foams.

Propane is naturally in the gaseous phase with a boiling point of  $-42^{\circ}\text{C}$  ( $-44^{\circ}\text{F}$ ). One gallon of liquid propane will expand to 270 gallons of propane gas.

- Isolate spill or leak area immediately.
- Stay upwind, and out of low areas.
- Eliminate all ignition sources.
- All equipment used when handling the product must be grounded.
- Do not walk through spilled material.
- Keep unauthorized personnel away.
- If required, wear positive pressure self-contained breathing apparatus.
- Do not extinguish a leaking gas fire unless leak can be stopped.

### 7.23.2 How big is the fireball from a Propane or LPG BLEVE?

If the propane or LPG release is ignited immediately then a fireball will result. The size of the fireball depends on the mass of the tank contents at the time the tank fails. The shape of the fireball depends on how the tank fails and on the lading temperature. LPGs include the following flammable gases: Butane UN1011, Butylene UN1012, Isobutylene UN1055, Propylene UN1077, Isobutane UN1969 and Propane UN1978.

If we consider a spherical fireball, then an approximate equation for the fireball maximum radius is:

$$R_{\text{fireball}} = 3m^{1/3}$$

where,

$R_{\text{fireball}}$  = radius of fireball in metres

$m$  = mass of propane in kg

However, keep in mind that fireballs are not always spherical. In some cases, when the tank fails a large ground fire can result that has a radius larger than that predicted above. Don't assume if you are just beyond the predicted fireball radius that you will be outside of the fire envelope.

**Fireball sizes and durations for a range of tank sizes**

<p><b>WARNING</b> The data given are approximate and should only be used with extreme caution. These times can vary from situation to situation. LPG tanks have been known to BLEVE within minutes. Therefore, never risk life based on these times.</p>															
<p align="center"><b>BLEVE (USE WITH CAUTION)</b></p>															
Capacity		Diameter		Length		Propane Mass		Minimum time to failure for severe	Approx. time to empty for engulfing fire	Fireball radius	Emergency response distance	Minimum evacuation distance	Preferred evacuation distance	Cooling water flowrate	
Litres (Gallons)	Meters (Feet)	Meters (Feet)	Meters (Feet)	Kilograms (Pounds)	Minutes	Minutes	Meters (Feet)	Meters (Feet)	Meters (Feet)	Meters (Feet)	Meters (Feet)	Meters (Feet)	Meters (Feet)	Litres/min	US gal/min
100 (26.4)	0.3 (1)	1.5 (4.9)	40 (88)	4	8	10 (33)	90 (295)	154 (505)	307 (1007)	97	26				
400 (106)	0.61 (2)	1.5 (4.9)	160 (353)	4	12	16 (53)	90 (295)	244 (801)	488 (1601)	195	51				
2000 (528)	0.96 (3.2)	3 (9.8)	800 (1764)	5	18	28 (92)	111 (364)	417 (1368)	834 (2736)	435	115				
4000 (1057)	1 (3.3)	4.9 (16.1)	1600 (3527)	5	20	35 (115)	140 (459)	525 (1722)	1050 (3445)	615	163				
8000 (2113)	1.25 (4.1)	6.5 (21.3)	3200 (7055)	6	22	44 (144)	176 (577)	661 (2169)	1323 (4341)	870	230				
22000 (5812)	2.1 (6.9)	6.7 (22)	8800 (19400)	7	28	62 (203)	247 (810)	926 (3038)	1852 (6076)	1443	381				
42000 (11095)	2.1 (6.9)	11.8 (38.7)	16800 (37037)	7	32	77 (253)	306 (1004)	1149 (3770)	2200 (7218)	1994	527				
82000 (21662)	2.75 (9)	13.7 (45)	32800 (72310)	8	40	96 (315)	383 (1257)	1435 (4708)	2200 (7218)	2786	736				
140000 (36984)	3.3 (10.8)	17.2 (56.4)	56000 (123457)	9	45	114 (374)	457 (1499)	1715 (5627)	2200 (7218)	3640	962				

Emergency Response Guidebook

U.S. Department of Transportation, Pipeline and Hazardous Materials Safety Administration, Transport Canada, Secretariat of Transport and Communications, 2020

## Safe Standoff Distance

Liquefied Petroleum Gas (LPG – Butane or Propane)	Threat Description	LPG Mass/Volume <sup>1</sup>		Fireball Diameter <sup>2</sup>		Safe Distance <sup>3</sup>	
	Small LPG Tank	20 lbs/ 5 US gal	9 kg/19 L	40 ft	12 m	160 ft	48 m
	Large LPG Tank	100 lbs/ 25 US gal	45 kg/95 L	69 ft	21 m	276 ft	84 m
	Commercial/ Residential LPG Tank	2,000 lbs/ 500 US gal	907 kg/1 893 L	184 ft	56 m	736 ft	224 m
	Small LPG Truck	8,000 lbs/ 2,000 US gal	3 630 kg/7 570 L	292 ft	89 m	1,168 ft	356 m
	Semi tanker LPG	40,000 lbs/ 10,000 US gal	18 144 kg/37 850 L	499 ft	152 m	1,996 ft	608 m

<sup>1</sup> Based on the maximum amount of material that could reasonably fit into a container or

<sup>2</sup> Assuming efficient mixing of the flammable gas with ambient air.

<sup>3</sup> Determined by U.S. firefighting practices wherein safe distances are approximately 4 times the flame height. Note that an LPG tank filled with high explosives would require a significantly greater standoff distance than if it were filled with LPG.

Adapted from: Emergency Response Guidebook  
 U.S. Department of Transportation, Pipeline and Hazardous Materials Safety Administration, Transport Canada,  
 Secretariat of Transport and Communications, 2020

### 7.23.3 Fire Fighting a BLEVE

Fire fighters should do the following:

- Fight the fire from the maximum distance possible. If possible, use unmanned equipment such as a fixed fire monitor (deluge gun) or a ground fire monitor. These pieces of equipment are used to direct up to 7500 litres per minute onto a vessel or facility.
- Cool the container by flooding it with large amounts of water. Continue to cool after the fire is out.
- Do not direct water at the source of leak or at the pressure relief device (icing may occur).
- Leave the area immediately if you hear venting from the safety device or see discoloration of the tank.

## 7.24 Transportation Incident

### 7.24.1 Transportation Incident Safety

- Intervene to initiate the development of a safe and static incident scene.
- Identify the current and immediate hazards within the incident scene.
- Identify any hazards outside of the incident scene created by the accident.
- In the event of incidents involving or damaging electric service poles or transformer vaults:
  - Remain back an absolute minimum distance of 9 metres (30 feet) in all directions.
  - Restrict access to the area, permitting no entrance regardless of the need.
- In the event of uncontrolled fuel releases:
  - Restrict access and evacuate personnel from areas where an ignition and/or fire exposure is possible.

### 7.24.2 Action Plan for Transportation Incident

- Call 911.
- Establish roadway notification of the emergency incident.
- Survey the accident site from a safe distance and attempt to identify hazards.
- Isolate any present controllable hazards within the incident scene.
- Secure the incident scene and vehicles depending upon severity of incident (e.g. fatality).
- Assess and treat the injured, within level of training.
- Notify TDG if accident involves Dangerous Goods.

#### **Identify the Accident Site to Roadway Users**

- Utilize vehicles and or barriers to identify the roadway hazard and create an exclusion zone to prevent further accident occurrence:
  - Position a vehicle far enough back from the incident site, in both directions, such that on coming roadway users have the opportunity to identify the hazard and slow down to a safe stop.
  - Engage hazard lights of positioned vehicles.
  - Place additional vehicles in closer proximity to protect the incident scene from additional vehicle contact.
- Position traffic cones or road markers, as are available, to identify the accident site.
- Utilize accident bystanders who are uninvolved and uninjured to take positions safely off the roadway in high visibility vests close to the perimeter vehicles to wave down oncoming traffic alerting them to an incident scene.

#### **Perform an Outside Accident Site Survey**

- Survey the accident site from a minimum 9 metres (30 feet) safe distance, identifying all hazards outside of the accident site including:
  - Damaged utility poles.
  - Ground level power transformer vaults.
  - Any additional vehicles involved and not initially identified.
  - Location of injured; involved and uninvolved persons.
  - Discharged vehicle or transported fluids or materials.
  - Identify the discharge of gasoline or diesel fuel.
  - Identify any waterways or sources of fluids that could enter sewers etc.
  - Suspended loads or vehicles precariously positioned.

#### **Perform an Inside Accident Site Survey**

- Survey the incident scene within the 9 metres (30 feet) perimeter identifying all hazards inside the incident scene while maintaining a safe distance from any identified hazards including:
  - Damaged utility poles.
  - Ground level power transformer vaults.
  - Any additional vehicles.
  - Location of the injured.
  - Discharged vehicle or transported fluids or materials.
  - Suspended loads or vehicles precariously positioned.

Any tampering and/or altering of a vehicle's original position and/or controls (e.g. putting in park or out of gear, moving debris, letting air out of tires, etc.) should be documented and provided to investigators in order that investigation findings are not compromised (preferably with before and after photographs).

**Stabilize the Accident Site**

- Identify and restrict access to areas of uncontrollable hazard.
- Attempt to access each vehicle individually, assessing to ensure vehicle(s):
  - Ignition system is disengaged.
  - Automatic transmissions are in the “park” position.
  - Manual transmissions are in neutral gear, once the ignition is disengaged.
  - Parking brakes are engaged.
- Where access to the vehicle is not possible to secure the vehicle in a disengaged position:
  - Place larger debris or available materials under the wheels to provide a makeshift wheel block.
  - If possible, mark the location of vehicle component debris prior to moving, as this will assist any required investigations.
- If materials are not present to provide wheel blocking, pull the valve stems of each tire to secure the vehicle and document for investigators.
- Control any hazardous condition as is possible:
- Dilute or suppress fuel leaks.
- Identify exclusion zones due to uncontrollable hazards.

**Triage and Treat the Injured Personnel**

- Provide medical treatment only within level of training.
- Identify the location and injuries sustained by each individual involved in the accident.
- Remove persons slightly injured, uninjured or uninvolved from the immediate accident site to a safe controlled holding location away from any hazards of the accident site and on-coming roadway traffic.
- Protect in place any injured persons found within the vehicles.
- Gather uninjured personnel from the scene to assist with medical treatment as is available.
- Assess the safety of field medical treatment in the position found:
  - Where the injured person’s safety is threatened, they may be moved to prevent further significant injury.
- Identify and prioritize the injury treatment based on criticality of need.
- Ensure qualified personnel provide medical treatment within prioritized medical aid protocols.
- Treat for shock.
- Closely monitor the injured until relieved by arriving emergency responders.

**Meet and Brief Emergency Responders**

- Position personnel to meet and direct emergency responders to the accident site.
- Provide a scene safety and hazard briefing.
- Identify the number of injured.
- Identify the location of the injured and from which vehicle they belong.
- Identify the initial position found and condition of each of the injured.
- Identify the injuries sustained by each victim.
- Identify the medical treatment provided.
- Provide personal information on each victim as is available.
- Monitor the safety of the scene.
- Assist emergency responders within ability and level of training.
- Gather information regarding the medical treatment provider, the transport provider and the destination of medical treatment center.

### 7.25 Product Transportation Incident

The first priority of a product transportation incident is to protect the driver and the public from risk as well as containing and preventing the product from impacting the environment.

If a transportation incident involves propane, see BLEVE requirements.

The party in charge or control of the product (carrier) is responsible to remedy the dangerous occurrence. However, the ultimate responsibility remains with the Company (shipper). Products that may be shipped include produced water or higher risk Liquefied Petroleum Gas (LPG).

Response actions include:

- On public roadways, the Company will not assume the on-site command but will act on behalf of local police to respond to the incident.
- Notify/activate police and report incident.
- If applicable, Implement ERAP by contacting Emergency Response Assistance Canada, see Section 9 Federal Government Support Agencies.
- Notify Transportation of Dangerous Goods Spill Department and provide the following information:
  - Location of incident and directions to site.
  - Name and contact number.
  - On-site response actions implemented.
  - Type of vehicle involved.
  - Type of container(s) involved and volumes.
  - Type of Dangerous Goods or environmentally sensitive products involved and volumes.
  - Copy of Safety Data Sheet (SDS).
- Secure the incident scene from on-coming traffic.
- Provide medical aid to the driver and passengers involved in the incident.
- If possible, interview the driver and review the manifest for products, volumes and carrier company name.
- Review SDS with the Emergency Response Guidebook for product hazards, PPE requirements, response action and public protection measures.
- Assess the container integrity and secure the leak (if safe to do so).
- Respond to public safety by reviewing the public protection plan.
- Contain and clean up spilled product.
- Keep a log of the time and sequence of events.
- Record information on a Company incident report form.
- Stay at site until relieved by additional Company personnel (if required).
- Restrict access to the site immediately and preserve site for follow-up investigations.
- Clean up and repair as directed by the Incident Commander.

## 7.26 Hazardous Materials Incident

### 7.26.1 Hazardous Material Safety

- Ensure the safety of site personnel and the public.
- Assess the potential exposure to human life.
- Assess the harm created by exposure to human life.
- Restrict the access to areas of potential exposure.
- Ensure the hazards associated with any product release are fully communicated.
- Activate emergency response agencies.
- Establish a safe incident scene.
- Decontaminate exposed personnel.

### 7.26.2 Action Plan for Hazardous Material Incident

- Identify the released material.
- Assess the hazard associated with the release.
- Identify any environmental impacts.

#### **Initiating Incident Response**

- Notify local emergency response agencies.
- Notify Company management.
- Establish a safe incident scene perimeter.
- Secure and restrict access to the area.
- Contain persons requiring decontamination.
- Evacuate persons from the area.
- Designate a holding area for evacuees.
- Identify safe access routes and communicate clearly and promptly to the responding agencies.
- Identify appropriate staging locations.
- Account for all personnel:
  - Number of persons involved.
  - Injured persons.
  - Injured employees.
  - Injured contractors.
  - Injured public.

#### **Decontaminate Exposed Personnel**

- Identify, contain and hold exposed personnel requiring decontamination in a safe location.
- Provide decontamination by removing clothing and thoroughly rinsing with large volumes of water.
- Control the runoff of the decontamination water.
- Remove person's clothing and shelter in a safe isolated location.
- Medically treat exposed personnel as is possible and only as trained.

#### **Identify the Released Material**

- Identify the material carrier.
- Identify vehicle number.
- Identify the trailer number(s).
- Identify the placard number.
- Acquire the shipping papers reference number.
- Identify the SDS reference number.

- Reference the CANUTEC Emergency Response Guide.
- Reference the AAR Guide, if applicable.

**Assess the Hazards Associated with the Release**

- Inhalation.
- Flammability.
- Toxicity.
- Water reactivity.
- Contact exposure hazard.
- Organic reactivity.

**Evaluate the Release**

- Identify the release type: static or dynamic.
- Maximum potential-volume of release.
- Current volume and rate of release.
- Outfall direction of the release.
- Identify the outfall exposure potentials.
  - Public exposures.
  - Natural waterways.
  - High impact environmental outfalls.
  - Low impact environmental outfalls.
  - Natural containment characteristics.

**Identify Environmental Impacts**

- Identify the current weather and potential impacts:
  - Temperature.
  - Chance of precipitation.
  - Wind conditions: strength and direction.
  - General grade of topography.
- Brief emergency responders on their arrival.
- Identify the medical treatment provider.
- Identify the receiving medical treatment center.

**Meet and Brief Arriving Emergency Responders**

- Position personnel to meet and direct emergency responders to the incident site.
- Provide a scene safety and hazard briefing.
- Identify the event timeline.
- Identify the released material(s) involved.
- Identify the hazards associated with the released material(s).
- Identify the personnel accountability.
- Identify the injuries present.
- Identify the chemical exposures present.
- Identify the decontamination procedures undertaken.
- Identify the environmental exposure and impacts.
- Identify the containment actions undertaken.
- Identify the current operational status of the facility.

### 7.27 Injury/Fatality

All personnel must be prepared to provide timely and effective response to preserve the health and safety of personnel injured due to an emergency event. Always consider the consequences and risks prior to taking response actions to assist a victim and providing medical assistance. Ensure that the rescuer does not become a victim.

If an incident involving equipment results in the death of a worker, the person who is in charge of the equipment must ensure the site of incident is not disturbed, unless:

- Protecting the health and safety of other personnel.
- Aiding an injured person involved in an incident.
- Taking essential action to make the scene safe or to prevent a further occurrence of the incident.

The On-Site Group Supervisor has the obligation to preserve the site intact until:

- An OHS inspector or police officer arrives at the site of incident.
- Or an OHS inspector or police officer directs otherwise at the time of notification.

#### 7.27.1 *Serious Injury/Fatality Safety*

- Assess the incident site for hazards, consider the following hazards before proceeding to the victim:
  - Hazardous gases (H<sub>2</sub>S, carbon monoxide, etc.).
  - Electrical.
  - Uncontrolled pressure.
  - Unsecured mechanical.
  - Liquid.
  - Fire and explosion.
  - Unsecured suspended loads.
  - Other unsafe conditions.

If at any time the scene is deemed unsafe to enter:

- Do not enter or approach the victim.
- Responders are to immediately return to a confirmed safe area.
- Conduct any mitigating actions that are possible from a safe area.
- Wait for assistance if unsafe conditions remain.
- Identify the mechanism of injury and establish control mechanisms (water spray, electrical de-energizing, etc.).
- Identify the victims that will require decontamination prior to medical treatment.

#### 7.27.2 *Action Plan for a Serious Injury/Fatality*

##### **Identify the Emergency Event Occurrence**

- Notify facility personnel of an emergency event occurrence.
- Sound a facility wide alert.
- Identify the location of the emergency event.
- Provide initial personnel actions to ensure their safety.

**Direct Facility Personnel**

- Communicate the presence of uncontrolled hazards to facility personnel.
- Provide direction to facility personnel for ensuring their safety.
- Specify and assign personnel to safe mustering positions.
- Identify the safe access routes from, or around, areas of hazard, to the safe mustering positions.
- Account for all facility personnel.

**Initiate External Emergency Response**

- Call 911.
- Request medical aid and transport.
- Identify incident location.
- Provide a call back number.
- Provide basic injury information.
- Provide known event timeline.
- Identify hazards present.

**Brief Personnel Tasked to Assist in Hazard Stabilization**

- Current incident site conditions.
- Uncontrolled hazards.
- Hazard control priorities.
- Provide individual assignments.
- Identify personnel safety considerations during stabilization operations.
- Specify communication and coordination protocols for stabilization operations.
- Review critical considerations of individual tasks.
- Specify emergency evacuation plan.

**Stabilize Hazards and the Incident Site**

- Remove or control incident scene hazards.
- De-energize/safety equipment and power supplies.
- Isolate uncontrolled material releases.
- Remove sources of ignition.
- Lower elevated or suspended loads.
- Identify any areas of, or remaining scene hazards.
- Monitor, direct and coordinate stabilization operations.
- Monitor safety conditions in areas of stabilization operations.
- Monitor condition of and impact on the injured.
- Maintain effective communication with all intervening personnel.
- In the event that significant hazardous conditions remain uncontrolled, consider the activation and assignment of the Site Safety Officer.

**Approach and Assess the Injured**

- Approach the injured and check for signs of life.
- Confirm the total number of injured.
- Identify injuries present.
- Triage the injured: identify and prioritize the injury treatment based on criticality of need.
- Assess the safety of field treatment in the position found.
- Assess the ability or effectiveness of field medical treatment in the position found.
- Confirm the accountability of facility personnel versus known numbers on site:
  - Safe mustering position.
  - Tasked for stabilization.
  - Medical treatment.
  - Injured.

**Assess the Need for Chemical Decontamination**

- Identify the need to decontaminate injured prior to initiating field medical treatment.
- Identify the chemical exposure.
- Reference applicable SDS.
- Contact the chemical manufacturer to obtain additional decontamination/neutralization information.
- Contact Company Corporate Health to advise.
- Contact the Canadian Transport Emergency Centre (CANUTEC) for assistance.

**Provide Field Medical Treatment**

- Provide chemical decontamination/neutralization prior to initiating field medical treatment.
- Stabilize injured in position found if possible.
- In the event that the injured must be moved:
  - Mark the position found.
  - Create a sketch.
- Provide medical treatment only within level of training.
- Ensure qualified personnel provide field medical treatment within prioritized medical aid protocols.
- Closely monitor injured until relieved by arriving emergency responders.
- Maintain appropriate confidentiality of incident, medical and injured personal information.

**Provide Company Management with Incident Notification**

- Provide event timeline.
- Provide total number of injured.
- Provide names of injured.
- Provide specific injuries.
- Provide ages of injured.
- Provide employers of injured.
- Provide job description of injured.
- Provide contact information of injured.
- Provide current medical status.
- Identify field medical treatment provider.
- Identify medical transport provider.
- Identify receiving hospital – trauma center.
- Provide next of kin contact information.

---

**Meet and Brief Emergency Responders**

- Position personnel to meet and direct emergency responders to the incident site.
- Provide a scene safety and hazard briefing.
- Identify the mechanism(s) of injuries.
- Provide an event timeline.
- Identify the number of injured.
- Identify the initial position and condition of each victim.
- Identify the injuries sustained by each victim.
- Identify the medical treatment provided.
- In the event of a victim chemical exposure:
  - Identify any decontamination provided.
  - Provide an SDS.
  - Provide personal information for each victim.
- Assist emergency responders within ability and level of training.
- Monitor the safety of the incident site.
- Gather information regarding the medical treatment provider, the transport provider and the destination medical center, hospital or trauma center.

**Special Considerations for Fatality Events**

- The deceased must not be moved unless:
  - Doubt of death exists, or
  - Authorized/requested to do so by the medical examiner or designate.
- If the victim's injuries are obviously fatal no additional risk shall be taken to recover the body.
- The recovery of suspected fatalities does not take priority over the rescue of the living and incident control activities.
- Scene preservation is critical – lawful movement of a fatality is only permitted to rescue a person in danger or to establish area safety.
- Once the emergency event has been controlled, the area of a suspected fatality is to be cleared of all personnel and cordoned off.
- Institute a tracking log to account for all persons with access to the cordoned off area.
- Non-authorized pictures are prohibited.
- Police and OHS will attend to conduct investigations.

**Provide Field Management of the Incident**

- Isolate and maintain the incident site undisturbed until custody is handed over to the investigating agency.
- Re-evaluate the overall safety of the facility.
- Assess, monitor, and manage the individual condition of the uninjured facility employees.
- Interview witnesses to the incident, providing a written statement, immediately if possible, or delayed if the witness is physically or emotionally unable.
- Receive approval from Company management prior to re-establishing site operations.

### 7.27.3 Next of Kin Notification

If any personnel are seriously injured, missing or killed, it is the responsibility of the Incident Commander to ensure that NorthRiver provides prompt notification to a senior Company representative so that the immediate family can be notified as quickly as possible.

Next of Kin Notifications should be made in the following instances:

- A serious injury.
- A fatality.
- Instances where personnel may be involved in an emergency and are unharmed, but are not able to contact family members to advise of their status.

Death should never be declared by NorthRiver no matter how obvious. Death notifications are not to occur until a medical doctor or medical examiner with the local authorities has pronounced the casualty legally dead.

If the incident involves the death or serious injury of a member of the public, local police or RCMP will be contacted by the Incident Commander (or designate) and asked to identify and notify the next of kin.

**Under no circumstances are the names of casualties or missing persons to be released to the public or media unless next of kin are notified and their consent is obtained.**

#### **Contractor Next of Kin Notification**

If an employee of a contractor employed by NorthRiver is injured, the Incident Commander and a senior Company representative will ensure that the contractor's head office is notified. The Contract Company is responsible for their own employees' notification of Next of Kin. In the case where a contractor is a small operation, or with no office, NorthRiver will request that the RCMP or local police identify and notify the next of kin.

#### **Employee Next of Kin Notification**

If an employee or contract employee employed by NorthRiver is injured, a senior Company representative or the most senior company field representative known by the family will make Next of Kin notifications in conjunction with a Victims Services representative from the local police or RCMP detachment.

## 7.28 Air Ambulance

### 7.28.1 Command and Control

Air Ambulances are dispatched based on flight conditions, aircraft availability/capability and criticality of the injured. Once you believe that an air ambulance is needed, call the appropriate number identified in the Telephone Directory in this binder and provide:

- Description of the patient's condition.
- Severity of injury.
- Type of injury.
- Level of consciousness.
- Exposure to hazardous materials.

If possible, establish contact with helicopter crew on a secure, dedicated radio frequency and remain in contact until touchdown. Identify the pre-designated Landing Zone if available.

All Landing Zone personnel must wear full PPE including, helmet, glasses, ear protection and a high-visibility vest.

### 7.28.2 Pre-Landing Checklist:

The flight crew will contact ground units via a prearranged radio frequency, ambulance radio frequency, or phone line for the following information.

TERRAIN	HAZARDS	LZ Markings
Level or sloping	Street signs	Four turbo flares
Type of surface	Vehicles	Four road flares
Dust or loose snow	Towers	Four reflective flares
Rocks, bushes, stumps, etc.	Poles	Four highway cones (days only)
	Wires	(Extra strobes/flares/cones on upwind side)

### 7.28.3 Landing Zone

When choosing a landing zone, look for the following:

- Flat or relatively level surface.
- Approximately 35 metres (120 feet) downwind from the scene to protect the incident from any downwash and exhaust.
- Ideally 30 metres (100 feet) square in size.

Sweep the site for all foreign unsecured and loose debris and wet the area down to reduce dust or lose debris from dislodging.

Communicate hazards (typically through the Air Ambulance dispatch) using the mnemonic **HOTSAW**:

- Hazards.
- Obstructions.
- Terrain.
- Surface.
- Animals.
- Wind/weather.

The landing zone should be marked on all four corners by either bright LED lights, or traffic cones.

### 7.28.4 Ground Operations

- Designate a Landing Zone Operator (LZO).
- When helicopter approaches the LZO will extend both arms straight above their head, giving the 'all-clear' signal.
- If there are any sudden changes or if any hazards arise the LZO simply waves off the landing, communicates the hazards to the crew and then the helicopter crew will assume a holding pattern until it is clear to land.
- The LZO remains in place, in a kneeling position, to act as a horizontal reference point for the pilot.
- For helicopter departure, the LZO again assumes a kneeling position at 12 o'clock giving the 'all-clear' signal for takeoff.


### 7.28.5 Loading and Unloading

- Do not approach the helicopter.
- The co-pilot will guide all crews nearing the helicopter for patient loading.
- For loading patients, crews must approach the helicopter in the 10 - 2 o'clock positions avoiding the tail rotor of the aircraft.

### 7.28.6 Hazards and Special Situations

- Landing zone operations and practices are the same for day and night operations.
- For night landings, all emergency personnel in the vicinity of the landing zone must don high visibility vests throughout operations.
- Nearby vehicles can focus lights on hazards in the immediate area but must not direct the lights at the helicopter as they could potentially obscure vision for the crew.
- If the incident is in a remote area turn nearby vehicles lights on to illuminate the landing zone, preferably vehicles should be located at the four corners of the landing zone.
- If the landing zone is covered in snow or partially obscured take up position in the centre of the landing zone and the pilot will land directly beside the LZO using them as a reference point.
- For road landings, all single lane highways or roads, traffic must be blocked in both directions throughout both the aircrafts' landing and take-off procedures work with the local police or highway authorities with jurisdiction.

### 7.28.7 Approach Routes



## 7.29 Missing Worker

If a member(s) of staff does not attend work during a scheduled shift and contact cannot be made, the On-Site Group Supervisor should assess the situation and decide whether to activate the Emergency Response Team.

Where it is determined that a worker is potentially missing the Emergency Response Team is to be activated to assist in determining their whereabouts and in mobilizing company personnel.

### 7.29.1 Response Plan for Missing Worker

- Attempt to establish contact with the missing person(s) by phone.
  - Leave a voicemail message with a provided call back number.
- Establish a history of the missing person(s) last known movements, by contacting colleagues, friends, family, contacts, and work associates.
- Identify the missing person(s) personal vehicle and attempt to locate vehicle on site or in proximity to his/her last known movements.
- Make enquiries with local/county/regional/state hospitals.
- Make enquiries with local/county/regional/state police.
- Continue to try to establish contact with the missing person using:
  - Mobile telephone number(s).
  - Home telephone number.
  - Text messages.
  - Email messages.
- If the missing person is a contractor:
  - The contracting company shall be contacted to determine if they know of the person's whereabouts or movements.
  - Continue to maintain regular contact with contracting company.

## 7.30 Severe Weather Incidents

Wildfires, thunderstorms, tornadoes, hail, blizzards, high winds, and heavy rain can develop quickly and hit hard posing a threat to life and property. Municipal governments are responsible for informing the public and providing detailed information about the nature of the emergency.

### 7.30.1 Severe Weather Safety

Identify the immediate hazards associated with the impact of a severe weather incident to the facility or any facility egress routes. If at any time the facility is threatened by a severe weather incident, prioritize the preparations in accordance with:

- Safety of personnel.
- Environmental protection.
- Protection of facility assets.

Identify the safety risk associated with facility personnel weathering the severe weather within the protection of the facility vs. the risks of evacuation.

Effectively use of the lead time prior to the arrival of the severe weather to achieve either:

- Early evacuation to prevent exposure to unsafe conditions.
- Shelter in Place preparations including adequate food and water supplies.

Minimize personnel exposure to hazardous conditions by rescheduling services, deliveries and non-essential activities.

Account for secondary effects of severe weather e.g. icy roads, toppled trees, flooding etc. in risk assessments.

## Response Plan for Severe Weather

- Prepare a virtual or mobile Command Post to sustain operations in the event of power loss or building damage including:
  - Pre-printed maps.
  - ICS wall charts.
  - Communication devices (satellite and cell phones, chargers etc.).
  - Portable generators and heaters.
- Sustain Command Post operations by hardening the building against storm damage.
- Identify the current status of any potential or impending severe weather.
- Identify the safety of the facility location with regard to severe weather impact.
- Assess the appropriateness of continuing current facility operations.
- Maintain personnel accountability throughout any facility evacuation process.
- Identify the facility's ability to provide protection for personnel during the severe weather.
- Brief facility personnel to provide incident information and current status.
- Identify incident contingency plan(s) for the timely and safe shutdown of facility operations and the protection of facility assets.

### 7.30.2 Wildfire

A wildfire is an uncontrolled fire in an area of combustible vegetation that occurs in the countryside or a wilderness area. A wildfire differs from other fires by its extensive size, the speed at which it can spread out from its original source, its potential to change direction unexpectedly, and its ability to jump gaps such as roads, rivers and fire breaks. Wildfires are characterized in terms of the cause of ignition, their physical properties such as speed of propagation, the combustible material present, and the effect of weather on the fire.

#### Action Plan for Wildfire Response

- Make contact with supervision to obtain current fire statuses and fire spread predictions:
  - Location.
  - Spread direction.
  - Rate of growth.
  - Evacuation areas, evacuation routes, and proximity of facility areas under mandatory evacuation orders.
  - Provide and obtain contact numbers for periodic information and status updates.
- Identify actions and time required to safely shutdown the facility operations:
  - The safe evacuation of the personnel remains paramount.
  - Protect company assets by shutting down early in a managed and organized fashion.
  - Consult Company management for guidance.
- Brief all personnel as to the current status of the wildfire and its:
  - Location.
  - Direction and rate of fire growth/spread.
  - Potential shutdown procedures.
  - Contingent evacuation procedures.
- Identify and specify the safe egress route including any new safe mustering location for all evacuating personnel.
- Maintain a common communication link with all evacuating personnel groups.
- Maintain a tracking and accountability system during the evacuation to:

- Identify the current location of each evacuating individual.
- Identify and confirm the safety of each evacuating individual.
- Contact the supervisor and provide the current status of the facility and evacuation status of the personnel.

### 7.30.3 Tornadoes

Tornadoes form suddenly, are often preceded by warm humid weather, and are always produced by thunderstorms, although not every thunderstorm produces a tornado. Choose an appropriate shelter.

#### **Tornado warning signs:**

- Severe thunderstorms with frequent thunder and lightning.
- An extremely dark sky sometimes highlighted by green or yellow clouds.
- A rumbling sound, such as a freight train might make or a whistling sound such as a jet aircraft might make.
- A funnel cloud at the rear base of a thunder cloud often behind a curtain of heavy rain or hail.

#### **What to do in case of a tornado:**

- Take cover immediately, if you are in a building seek shelter under a heavy table or desk, stay away from windows and outside walls and doors.
- Do not get into your car. Seek shelter in a building with a strong foundation. If no shelter is available, then lie down in a ditch away from automobiles or mobile homes.
- In all cases, get as close to the ground as possible, protect your head, and watch out for flying debris.

### 7.30.4 Lightning

Lightning is a powerful sudden flow of electricity (an electrostatic discharge) accompanied by thunder that occurs during an electric storm. To estimate how far away the lightning is count the seconds between the flash of lightning and the thunderclap. If you count fewer than five seconds, take shelter immediately, you do not want to be the tallest object in the area.

#### **If caught outdoors:**

- Avoid putting yourself above the surrounding landscape. Seek shelter in low-lying areas such as valleys, ditches, and depressions but be aware of flooding.
- Stay away from water. Get to land as quickly as possible if you are on the water. Lightning can strike the water and travel a substantial distance from its point of contact.
- Stay away from objects that conduct electricity, such as tractors and metal fences.
- Avoid being the highest point in an open area or holding an object that can make you the tallest object and a target for lightning.
- You are safe inside a car during lightning but be aware of downed power lines which may be touching your car. You are safe inside the car, but you may receive a shock if you step outside.
- In a forest, seek shelter in a low-lying area under a thick growth of small trees or bushes.
- Keep alert for flash floods, sometimes caused by heavy rainfall, if seeking shelter in a ditch or low-lying area.

### 7.30.5 Floods

A flood is an overflow of water that submerges land which is usually dry. Flooding may occur as an overflow of water from water bodies, such as a river or lake, in which the water overtops or breaks levees, resulting in some of that water escaping its usual boundaries, or it may occur due to an accumulation of rainwater on saturated ground.

#### What to do in case of flooding:

- For information listen to the radio, watch television, check Government Agency websites or follow Social Media.
- Be aware that flash flooding can occur. If there is any possibility of a flash flood, move immediately to higher ground. Do not wait for instructions to move.
- Be aware of stream, drainage channels, canyons and other areas known to flood suddenly. Flash floods can occur in these areas with or without typical warnings such as rain clouds or heavy rain.
- Do not walk through moving water. Six inches of moving water can make you fall. If you have to walk in water, walk where the water is not moving. Use a stick to check the firmness of the ground in front of you.
- Do not drive into flooded areas. If floodwaters rise around your car, abandon the car and move to higher ground when water is not moving or not more than a few inches deep. You and the vehicle can be swept away quickly. If your vehicle is trapped in rapidly moving water, stay in the vehicle. If the water is rising inside the vehicle, seek refuge on the roof.
- Do not park your vehicle along streams, rivers or creeks, particularly during threatening conditions.
- Sandbag and/or build a dike if possible.

### 7.30.6 Seismicity

Earthquakes are caused by subsurface breaking and/or shifting of rock, which will release small to extremely large forces of energy through the Earth's lithosphere creating seismic waves. These seismic waves can cause severe damage to drilling rigs, well-sites, pipelines, facility buildings etc. Gas, electricity and phone services are also in danger of being affected. Landslides, avalanches, and flash floods can also be triggered. Earthquakes can occur at any time of the year. After an earthquake there is the possible danger of an "After-shock" which can occur in the hours, days weeks or even months after the initial wave. Some earthquakes could actually be foreshocks and a larger earthquake could occur.

#### *During an earthquake*

Wherever you are when an earthquake starts, take cover immediately. Move to a nearby safe place if need be. Stay there until the shaking stops.

#### **If you are indoors: "DROP, COVER, HOLD ON"**

- Stay inside.
- **Drop** under heavy furniture such as a table, desk or any solid furniture.
- **Cover** your head and torso to prevent being hit by falling objects.
- **Hold** onto the object that you are under so that you remain covered.
- If you can't get under something strong, or if you are in a hallway, flatten yourself or crouch against an interior wall.
- Stay away from windows and shelves with heavy objects.

#### **If you are outdoors**

- Stay outside.
- Go to an open area away from buildings.

**If you are in a vehicle**

- Pull over to a safe place where you are not blocking the road. Keep roads clear for rescue and emergency vehicles.
- Avoid bridges, overpasses, underpasses, buildings or anything that could collapse.
- Stop the car and stay inside.
- Listen to your car radio for instructions from emergency officials.
- Do not attempt to get out of your car if downed power lines are across it. Wait to be rescued.
- Place a HELP sign in your window if you need assistance.

**AVOID the following in an earthquake**

- Doorways. Doors may slam shut and cause injuries.
- Windows, bookcases, tall furniture and light fixtures. You could be hurt by shattered glass or heavy objects.
- Downed power lines - stay at least 10 metres away to avoid injury.

*After an earthquake***Stay calm. Help others if you are able.**

- Be prepared for aftershocks.
- Listen to the radio or television for information from authorities. Follow their instructions. Place telephone receivers back in their cradles; only make calls if requiring emergency services.
- Put on sturdy shoes and protective clothing to help prevent injury from debris, especially broken glass.
- Check your building for structural damage and other hazards. If you suspect the building is unsafe, do not re-enter.
- If you have to leave the building, take your emergency kit and other essential items with you. Post a message in clear view, indicating where you can be found. Do not waste food or water as supplies may be interrupted.
- Do not light matches or turn on light switches until you are sure there are no gas leaks or flammable liquids spilled. Use a flashlight to check utilities and do not shut them off unless damaged. Leaking gas will smell.
- If tap water is still available immediately after the earthquake, fill a bathtub and other containers in case the supply gets cut off. If there is no running water, remember that you may have water available in a hot water tank (make sure water is not hot before touching it) and toilet reservoir (not the bowl).
- Carefully clean up any spilled hazardous materials. Wear proper hand and eye protection.
- Check on your co-workers. Organize rescue measures if people are trapped or call for emergency assistance if you cannot safely help them.
- Place a HELP sign in a window if you need assistance.
- Beware of secondary effects. Although ground shaking is the major source of earthquake damage, secondary effects can also be very destructive. These include landslides, saturated sandy soils becoming soft and unstable, and flooding of low-lying areas.

Department of Public Safety and Emergency Preparedness Canada  
<https://www.getprepared.gc.ca/cnt/hzd/rthqks-drng-en.aspx>

## 7.31 Wildlife

### 7.31.1 Wildlife Incidents and Mortalities

Wildlife observations should be tracked on a daily basis (nuisance or not) to determine which wildlife are in the area and whether activities are attracting wildlife. Mitigations may need to be incorporated to reduce the potential risk to workers and wildlife.

Wildlife mortalities should be reported to your supervisor and appropriate Company Representative immediately.

The following information should be recorded and reported:

- Nature of the incident (i.e., road collision).
- Type of species and number of individuals.
- Location of incident/collision.
- Time of incident/collision.
- Details of incident/collision (e.g., if animal was clipped or hit directly).

### 7.31.2 Wildlife Awareness

There are a number of different species of wildlife that can present hazards to workers.

Wildlife awareness is not limited only to working in remote areas but should be oriented to the habitat of the work area and included into local hazard assessments. Workers are required to follow the practices developed to manage local wildlife hazards.

### 7.31.3 Working in wildlife habitat

- Make enough noise to prevent surprising wildlife.
- Watch for tracks and signs.
- Young animals are usually well-hidden. However, if you do stumble upon babies, do not approach or attempt to pick them up. Leave the area immediately, as a female will defend her young.

#### **If you meet wildlife:**

- Never approach wildlife. Although animals will normally avoid a confrontation, animals are unpredictable. Animals feeding may be dangerous.
- Always give animals an avenue of escape.
- Stay calm. Talk in a confident voice.
- Do not run. Try to back away slowly.
- Do not turn your back on wildlife.
- Do all you can to enlarge your image. Don't crouch down or try to hide. Pickup sticks or branches and wave them about.

### 7.31.4 Bears

All employees should be informed of the following:

- types of bears in the area
- recent bear activity
- general policies and procedures in place to mitigate potential conflict with bears
- actions to be taken if a bear is sighted including reporting procedures

### *Monitoring Work Sites*

Employees working away from the main site may occasionally find themselves working in an area of high bear hazard. Normally work should be halted and workers removed until the bear hazard is no longer present. However, if work can not be shut down, a qualified bear monitor should be assigned to alert workers when bears are present and move people out of harms way. Only in extreme cases would bear monitors displace the bears in order for work to continue.

### *Monitoring Camps*

Problem encounters with bears are more likely in a camp situation than a chance encounter in the field or at work sites. When bears are active in the area, monitors may be called upon to provide bear detection services and to alert personnel of the presence of a bear on site. If necessary, the bear monitor will attempt to deter the bear. Bear monitors may also advise on preventative measures within a camp, including altering camp locations or configurations as appropriate.

### *What to do if you see a Bear*

If It does not approach:

- If spotted in the distance, do not approach the bear. Make a wide detour or leave the area immediately.
- If you are at close range, do not approach the bear. Remain calm, keep it in view. Avoid direct eye contact. Move away without running.

If the bear approaches:

- If the bear is standing up, it is usually trying to identify you. Talk softly so it knows what you are. If it is snapping its jaws, lowering its head, flattening its ears, growling or making 'woofing' signs, it is displaying aggression.
- Do not run unless you are very close to a secure place. Move away, keeping it in view. Avoid direct eye contact. Dropping your pack or an object may distract it to give you more time. If it is a grizzly, consider climbing a tree.

### *What to do if a Bear Attacks*

Your response depends on the species and whether the bear is being defensive or offensive. Bears sometimes bluff their way out of a confrontation by charging then turning away at the last moment. Generally, the response is to do nothing to threaten or further arouse the bear. While fighting back usually increases the intensity of an attack, it may cause the bear to leave.

Every encounter is unique, and the following are offered as guidelines to deal with unpredictable animals and potentially complex situations.

#### **Grizzly Attacks from Surprise (defensive)**

- Do nothing to threaten or further arouse the bear.
- Play dead. Assume the 'cannonball position' with hands clasped behind neck and face buried in knees.
- Do not move until the bear leaves the area. Such attacks seldom last beyond a few minutes.

#### **Black Bear Attacks from Surprise (defensive)**

- Playing dead is not appropriate. Try to retreat from the attack.

#### **Grizzly or Black Bear Attacks Offensively (including stalking you or when you are sleeping)**

- Do not play dead.

- Try to escape to a secure place (car or building) or climb a tree unless it is a black bear.
- If you have no other option, try to intimidate the bear with deterrents or weapons such as tree branches or rocks.

### *Equipment/Deterrent*

#### **Bear Spray**

- Must be used at very close range and should be used downwind only to avoid getting on yourself.
- It is indiscriminate and can cause extreme irritation to both the bear and the user.
- Will only work if fired at a bear, IT IS NOT A REPELLENT.
- If discharged, wash all your clothing, packs and any exposed skin with soap to help avoid attracting more bears with the smell.
- Works on cougars.

#### **Bear Bangers.**

- Should be fired up into the air between you and the bear.
- Do not fire the bear bangers at or behind the bear.

### *7.31.5 Elk*

Elk can be aggressive and attack without warning. During the fall mating season (August – September) male are particularly belligerent. During the spring calving season (May – June) female elk aggressively defend their young. DO NOT approach elk in any season as they are DANGEROUS.

### *7.31.6 Moose*

A moose encounter has the potential to be just as dangerous as a bear encounter. Therefore, similar measures must be taken to avoid these large ungulates. Moose are especially aggressive in the spring (calving season) and the fall (rutting season). Moose are most active in the early hours of the morning. However, one can expect to meet a moose any time of the day, especially in marshy woodland and around lakes. The best method of avoiding unwanted encounters with wildlife is to make a lot of noise. Hence, while practicing good bear-avoidance measures, moose will also be alerted of your presence. As harmless as a moose encounter may seem, it is important to have a high level of respect for the damage and injury these animals can incur if they feel threatened. Hence, if a moose is encountered, a minimum of 100 m must be put between yourself and the animal. If the moose remains stationary, you should cautiously move away from the animal, monitoring its behaviour in the process. Signals such as whether its ears are forward or back, or a lowering of the head are good indicators of aggressiveness (forward and erect is the animal being alert, back and down over the head is aggressive). React according to the signals being sent by the animal. Also, the direction you use in moving away should not interfere with any natural escape routes the moose may want to take. Similarly, it is very important not to position yourself between two moose (cow and calf or two rutting males).

If a moose feels threatened, it may charge at the person that has invaded its space. Moose are not predatory animals. Some examples of aggressive behaviour that may be exhibited are flattening of the ears and approaching humans. Unlike in a bear encounter, walking quickly, or if safe to do so, running away from an angry moose will not lead to a sustained attack; it will likely prevent it. Should the moose charge regardless, the best method of defense is to move behind a big tree, light standard or other large stationary object. Continue to try to get away from the animal while always keeping large solid objects between yourself and the moose. It is imperative that no false sense of security is attained once a large solid object is between a person and an angry

moose, as moose are very capable of kicking accurately with their forelegs around a tree trunk. Although it is best to try to get away from the animal, this is sometimes difficult, particularly if the area is challenging to move through.

### 7.32 Site Security

Site security describes security measures that are designed to deny unauthorized access to facilities, equipment and resources, and to protect personnel and property from damage or harm (such as espionage, theft, or terrorist attacks). Site security involves the use of multiple layers of interdependent systems which includes Closed-Circuit Television surveillance, security guards, protective barriers, locks, access control protocols, and many other techniques.

#### 7.32.1 Safety

The safety of facility personnel is paramount during periods of elevated security risk. Facility personnel have the right to ensure the safety of their fellow employees, prevent damage to facility property and prevent harm to trespassers but do not have the authority or permission to confine persons trying to leave the property.

#### 7.32.2 Response Plan for Site Security

- Call 911.
- Assess the threat risk versus the ability to safely continue the facility operations.
- Conduct a team meeting to include all facility personnel apprising them of the threat potential, an assessment of its legitimacy and include precautionary and egress measures.
- Advise facility support companies and contractors of the threat potential and the precautionary measures.
- Remain and operate in pairs during periods of elevated security risk, each team should be provided with a reliable means of communication.
- The facility gates should be closed and remain closed.
- When risk assessment deems it appropriate, anyone entering or exiting must be identified and the date and time documented by security.
- During periods of elevated security risk and continued operation, facility management shall coordinate the travel plans of personnel to and from the facility.
- In the event that the threat is assessed to be credible and provides potential for injury to facility personnel, consider operational shutdown and the initiation of either a controlled proactive evacuation or shelter in place.
- Consider the initiation of two-person security patrols throughout the facility.
- Confer with Company management with regard to acquiring security support.
- Do not attempt to challenge unauthorized persons who appear to be armed or significantly distraught.
- Ensure that none of the security measures restricts safe and immediate egress from the facility in the event of an emergency evacuation.
- Consider the postponement of all non-essential facility activities until an appropriate reduction in the security risk has occurred.

In the event of civil disobedience or ideological protest, facility personnel are directed as follows:

- Do not attempt to engage the protestors in anyway.
- Do not enter into discussions or verbal conversation.

- The On-Site Group Supervisor is to identify and communicate alternate egress routes from the facility in the event of emergency.
- Facility personnel should be sheltered away from the protestors as is possible to limit exposure.

### 7.33 Bomb Threat

A bomb threat is generally defined as a threat, usually verbal or written, to detonate an explosive or incendiary device to cause property damage, death, or injuries, whether or not such a device actually exists.

#### 7.33.1 Evaluating the Threat

The assessment of the threat is primarily made on the basis of the nature, tone, and specifics of the call or letter.

The following conditions increase the threat credibility:

- Details of type, size and location of device.
- Detonation timing provided.
- Ideological rhetoric, citing of political or social cause.
- Identified with known terrorist organization.
- Threat towards a company individual, specific position or job function or process.

The following conditions decrease the threat credibility:

- Vague threat to “bomb the whole facility”.
- Immature speech, voice or mannerisms.
- Background of laughter, trivial conversation, etc.
- Tendency to continue conversation, harangue, over-stress on obvious point.
- A non-specific threat (from a seemingly intoxicated individual, giggler, child or incoherent person).

#### 7.33.2 Action Plan for Bomb Threat

- Employee will notify On-Site Group Supervisor.
- On-Site Group Supervisor will notify Incident Commander.
- Incident Commander will notify police.
- Incident Commander will review the information, assess the situation and make critical event management decisions including the activation of the Emergency Response Team, as appropriate.
- Incident Commander will evacuate non-essential personnel from the concerned area.
- Emergency Response Team will collect information and evaluate the threat and decide whether to shut in the facility.
- Emergency Response Team, in the event of an explosion, will support the activities of the On-Site Group Supervisor.

#### 7.33.3 Critical Event Decisions

- Police notification is mandated due to the criminal aspect of a bomb threat.
- Identify if a full or partial evacuation (or none at all) is warranted.
- Identify if a search is warranted and can be done safely.
- Identify when it is safe to reoccupy the site.

#### **7.33.4 Bomb Search Considerations**

If a credible threat is received, use the available time to evacuate the immediate area.

If assisting the authorities in the search effort, it is imperative that personnel do not move, jar, or handle any suspicious object, or anything attached to the object.

#### **7.33.5 Bomb Search Procedures**

Emergency Response Team may work with the Police as a resource as the Police are not familiar with the facility.

The following points relate to teams and search methods:

- Work with a designated police officer.
- Once a room has been searched and nothing has been found, close and mark the door with a piece of tape in the shape of an X. This will indicate to other teams that the room has been search and it will eliminate repetition.
- Let the police assume responsibility.

#### **7.33.6 Discovery of Suspect Device**

- DO NOT TOUCH OR MOVE THE OBJECT!
- Evacuate all people from the bomb location.
- Notify the Incident Commander.
- Designate an assembly area far enough away from possible flying debris or other effects of a possible detonation.
- Instruct people on actions to be taken in view of the location of the bomb.
- Do everything possible to minimize any damage from an explosion:
  - Deploy firefighting equipment and personnel to a safe area.
  - Shutdown construction activities, lower suspended loads.

#### **7.33.7 No Suspected Devices Found**

After a thorough search of the site and no bomb is found, the police, Emergency Response Team and Incident Commander will decide if operational activities are to resume. A minimum of one hour should have elapsed from any stated detonation time prior to resuming normal operations. Review all details and actions with police prior to resuming normal operations.

#### **7.33.8 Explosion Occurrence**

- Have rescue personnel administer first aid and remove any injured personnel.
- Secure scene with the assistance of the police.
- Preserve any and all evidence; even the smallest pieces could be used for investigation and court proceedings.
- Only when authorised to do so, have maintenance personnel begin salvage and damage control operations.

## 8.0 POST EMERGENCY

### 8.1 Overview

The decision to stand-down the emergency, allow stakeholders to return to the incident area and resume normal operations is made by the Incident Commander and EOC Director in conjunction with the Regulatory Authority.

The EOC Director and Incident Commander ensure that the EOC Command Team and Site Command Team carry out post-incident activities as required, including the following tasks:

- Emergency stand-down notification.
- Public assistance and support.
- Clean-up and repair.
- Ongoing media communication.
- Post-incident documentation.
- Post-incident Investigation.
- Critical Incident Stress Debriefing.
- Post-incident Report.

### 8.2 Responsibility

The Incident Commander and EOC Director manage the following post-incident activities:

- Deactivate the emergency response operations.
- Establish post-incident goals.
- Delegate the responsibility for the completion of post-incident tasks.
- Ensure that all contacts are notified about the emergency stand-down.
- Ensure all post-incident activities are documented.
- Arrange for critical incident stress debriefing sessions as necessary.
- Conduct a debriefing meeting for all response team members.

### 8.3 Critical Incident Stress Debriefing (CISD)

Any individual directly involved in a critical incident and/or experiencing strong feelings relating to the event should be debriefed to encourage communication about their feelings and reactions without being judged or blamed.

Individuals include:

- Operating Personnel directly involved.
- Co-workers.
- Management.
- Contractors.
- Family Members.
- Community Members.

The Incident Commander and EOC Director ensure the following actions are completed:

- When practical after a serious incident, mobilize professionals who are trained in CISD.
- Explain to the participants that the debriefing is confidential. CISD meetings do not judge or lay blame. Recording devices at these meetings is prohibited.
- Do not schedule more than 20 people to do a debriefing session. Advise the CISD professional about the size of the session and provide information about the attendees before the session starts.
- Debriefing should occur 24-72 hours post-incident.

Objectives of the debriefing are to:

- Minimize the severity and duration of the trauma.
- Normalize feelings and reactions.
- Acknowledge each individual's personal experience.
- Provide support.
- Provide information on crisis reactions and stress management.

### 8.3.1 Key Reactions to Stress

PHYSICAL	COGNITIVE (PERCEIVED)
Headaches	Poor Concentration
Dizziness	Slow Thinking
Disorientation	Memory Lapses
Fatigue	Loss of Objectivity
Digestive Problems	Flashbacks
Frozen Fright	Abnormal Pondering
Loss of Control over Body Functions	Difficulty Processing Information
Numbness	Distorted Thinking
Increased Heart Rate	
Heightened Sensory Perception	
Sleep Disruptions	

### 8.4 Public Assistance and Support

The Incident Commander oversees the following actions:

- Verifies that the incident area is safe to re-enter in consultation with applicable Regulatory Authorities, if required.
- This may involve ensuring all equipment and debris are removed from public roadways. Any remaining hazardous areas must be cordoned off.
- Ensures that all sheltered or evacuated residents are contacted and informed that the incident is over.
- Secures the evacuated area until the evacuees have returned to their homes and businesses.
- Confers with the EOC Director about sending a company representative to visit all members of the public who were affected.
- Ensures that the residents are provided with post-incident contacts and telephone numbers.
- Confers with the EOC Director to schedule a follow-up meeting(s) with the residents to clearly explain the incident and address their concerns.
- Ensures resident expense and damage claims are addressed.

### 8.5 Investigation

Site and evidence preservation is extremely important after an unplanned event. Senior Company Management must be contacted, and a decision will be made whether to send personnel or a third-party contractor to the site to conduct an investigation.

If an incident involving equipment at a site results in a death, the site must be secured. The Incident Commander must ensure that the location is not disturbed (unless protecting the health or safety of other workers or aiding an injured person) until the police have investigated the accident and an OHS inspector directs otherwise.

Third party investigations by police, insurance companies, and others may be required. It is important to co-operate with all third-party investigators; therefore, the following guidelines will apply:

- Do not allow third party investigators on-site, unless authorized by the Incident Commander; this is to ensure everyone's safety. Obtain the name, title, address, and telephone number of all inspectors.
- If access is granted to the site, ensure that third party investigators are escorted while on company property and, for their safety, denied access to any hazardous areas. Inspectors must not be left unattended.
- Ensure inspectors receive only the information they request and limit tours to the specific area the investigator has asked to investigate.
- Always tell the truth. Do not speculate.
- Wait until legal counsel is present before answering questions if the inspector suggests that the statements may be used as evidence or indicates that you have the right to counsel.
- Copy all documents given to third parties, including investigators.

An internal investigation can be a valuable learning experience. The findings can be applied to other operations and improve the emergency response system. An investigation can also result in improved incident prevention methods and operating practices.

## 8.6 Clean Up and Repair

The Incident Commander oversees the following actions:

- Ensures that site clean-up is managed in a timely manner. The remediation phase of the site clean-up may be filled by an environmental specialist.
- Ensures that all hazardous waste is disposed appropriately according to applicable regulations.
- Ensures the priority is given to clearing debris and restoring the site to normal operating conditions after the government and company investigations are complete.
- Ensures that all equipment is demobilized, cleaned and inspected for contamination.
- Ensures all roadblocks, staging area and detour equipment is demobilized.
- Ensures that all clean-up and repair actions follow safety and environment policies and safe-work procedures.

## 8.7 Post-Incident Notifications

The objective in post-incident notifications is to ensure that the best possible communication with stakeholders are made; to sustain Company core value commitments and capture any outstanding or legacy issues.

All affected parties are to be advised of the post-incident status of the incident:

- Company employees and contractors.
- Joint Venture Owners.
- Mutual Aid partners.
- Evacuees.
- Members of the Public who were involved.
- Government Agencies.
- Non-Governmental Organizations (NGOs).

Typically, this should be done through personal calls (supported by media releases) by the Information Officer.

All communications are to be approved by the EOC Director and Legal.

### 8.8 Incident Documentation/Company Records

The Incident Commander and the EOC Director instruct their teams to complete the following duties:

- Collect and compile all forms and documentation for the incident, including all electronic records.
- Securely store all incident documentation. The protection of records is extremely important to ensure the evidence is complete and unchanged.
- Obtain all photographs and videos of the incident site and response. All photographs of the incident site which have been taken are considered Company material and are to be properly documented.
- Ensure that pages and checklists from all emergency response manuals are replaced.
- Prepare letters thanking support agencies, groups and individuals who provided assistance. Mention names of key individuals in correspondence.
- Company records must be reviewed by legal counsel before they are released.

### 8.9 Post-Incident Debriefing and Incident Assessment

The Incident Commander should follow the checklist below to ensure the following items and/or personnel are available at the debriefing session:

- A comfortable classroom/conference area large enough to conduct a post-incident debriefing.
- Refreshments.
- Map of Response Area.
- Copy of Incident Logs and all other Response Forms.
- Any Video Tape and/or Photos of the incident that may be helpful during the debriefing.
- If videotape is used, secure a video player and monitor.
- Flip chart or white board.
  - Masking tape to hang flip chart pages.
  - Drawing markers (various colors).
- Copy of Company's ERP.
- Note-taking materials for attendees (pads, writing instruments).
- Copies of any planning cycle plan(s).
- Copies of Daily Site-Specific Safety and Health Plans.

#### 8.9.1 Session Guidelines

The debriefing should be facilitated by the Incident Commander. The following provides some session guides:

- Awareness on room safety e.g. emergency alarms, evacuation procedures for those participants not familiar with the facility.
- Objective and agenda of meeting.
- Need for openness and honesty.
- Emphasize that the debriefing is to provide learning and response improvement opportunities - not fault finding.

- Conduct session in a non-confrontational manner.
- Allow everyone involved in the response to have an opportunity for input.
- Have a Scribe available to document comments and action items.
- Do not solve the issues but record as action items to be reviewed and addressed later.
- Participants should not try to justify their actions but can provide clarification if requested by the facilitator(s).
- Introduce the participants and the organizations they represent e.g. location and role.
- Conclude the meeting by communicating future action plans e.g. "where do we go from here?"

### 8.9.2 *Site Response Team Debriefing Questions*

- Did pre-emergency planning efforts occur relating to this particular incident?
- Did pre-emergency training take place relating to this particular type of incident?
- Was the Incident Command System (ICS) promptly activated?
- Was ICS terminology implemented early on during the incident and utilized throughout the incident?
- Was the location of the Command Post established early on?
- Was a safe Staging Area established early on during the incident?
- Did responders receive thorough initial briefings before assignment?
- Was a Check-In/Check-Out area established early on (preferably at Staging)?
- Were all employees accounted for early on during the incident?
- Did responders preplan which escape or egress routes to utilize during emergency operations?
- Was there necessary command and control of resources to prevent freelancing?
- Were all hazardous substances and conditions identified before responders took direct action?
- Were the planning zones established by responders before action was taken?
- Did the On-Site Group Supervisor take action to ensure that all responders utilized the proper PPE?
- Were adequate resources ordered early on?
- Were planning cycle time guidelines utilized?
- Was employee evacuation undertaken?
- Were all required permits obtained prior to hazardous operations?
- Was site security and control provided?
- Were Incident goals and objectives established?
- Did emergency medical treatment occur in a timely fashion?
- Was PPE utilized in a safe and effective manner?
- Were direct mitigation efforts taken?
- Was action taken early enough to provide resources to perform monitoring?
- Was action taken early enough to provide resources to adequately complete source control efforts?
- Was a Site-Specific Health and Safety Plan completed?

### 8.9.3 EOC Team Debriefing Questions

- Did someone establish a EOC early on and implement the Incident Command System (ICS)?
- Were public notifications made in a timely manner?
- Were governmental notifications made in a timely manner?
- Was action taken early on to make required telephone notifications other than public and government?
- Was ICS terminology implemented early enough during the incident?
- Was action taken early enough to provide resources for Public Affairs and Community Relations Assistance?
- Was action taken to provide a 12-Hour Plan?

### Response Actions Debriefing Questions

#### Detection

- Was the incident detected promptly?
- How was it detected?
- By whom?
- Could it have been detected earlier? How?
- Are there any instruments or procedures which might aid in detection?

#### Notification

- Was Management notified promptly?
- Was Management response appropriate?
- Was Head Office notified promptly?  
If so, why, how and who? If not, why not?

#### Evaluation

- Was the magnitude of the problem assessed correctly at the start?
- What means were used for this assessment?
- Are there any guides or aids to assist evaluation?
- What sources of information were available on public/structures in the area that could be at risk?
- What sources of information were available on winds and on water currents?
- Was information adequate?
- Was the information useful (and used) for trajectory forecasts?
- Were the forecasts realistic?
- Do we have adequate information on product properties?
- Do we need additional information on changes of product properties with respect to time (e.g. as a result of weathering) and other processes?

#### Mobilization

- What steps were taken to mobilize incident countermeasures?
- What resources were used?
- Was mobilization prompt?
- Could it have happened faster, or should it have been?
- What about mobilization of manpower resources - timely?
- Were the local response co-operatives or contractors used appropriately?
- How could this be improved?
- Was it appropriate to mobilize Head Office resources and was this effected promptly?

- What other corporate resources were available and were they identified and used adequately?

**Response - Strategy**

- Is the Company ERP an adequate response plan?
- Is it flexible enough to cope with unexpected events?
- Does the plan include clear understanding of local environmental sensitivities?
- What was the initial strategy for response to the incident?
- Is the strategy defined in the response plan?
- How did the strategy evolve during the incident and how were the changes implemented?
- What caused the changes?
- Are there any improvements needed? More training?

**Response – Resources Used**

- What resources were mobilized?
- How were they mobilized?
- How did utilization change with time? Why?
- Were the following resources used effectively:
  - Contractors?
  - Government agencies?
  - Company resources?
  - Co-operatives?
  - Mutual Aid?
  - Volunteers?
  - Consultants?
  - Others?
- What changes would have been useful?
- Is there adequate knowledge of resource availability?

**Response – Effectiveness**

- Was containment effective and prompt?
- How could it have been improved?
- Are additional resources required for containment?
- Was recovery effective and prompt?
- How could it have been improved?
- Are additional resources required for recovery?

**Command Structure**

- Who was initially in charge of the response?
- What sort of organization was initially set up?
- How did this change with time? Why?
- What changes would have been useful?
- Was there adequate surveillance?
- Were communications adequate?
- What improvements are needed? (Hardware, procedures, etc.)
- Was support from financial services adequate? Prompt?
- Should there be any changes?
- Is more planning needed?

**Measurement**

- Was there adequate measurement or estimation on the magnitude of the incident or volume of material released?
- Was there adequate measurement or estimation of the volume of product recovered?
- Should better measurement procedures be developed for either phase of operations?
- What would be appropriate and acceptable?

**Government Relations**

- What are the roles and effects of the various government agencies involved?
- Was there a single point of contact for the government agencies?
- Should there have been better communication with the agencies?
- Were the agencies adequately informed at all stages?
- Were too many agencies involved?
- Are any procedural changes needed to manage government relations?
- Was there agreement with the agencies on criteria for clean-up?
- How was this agreement developed?

**Public Relations**

- How were relations with the media handled?
- What problems were encountered?
- Are improvements needed?
- Was public outcry serious? How could it have been reduced?
- What communication systems were engaged by public and media (e.g. social media?)

**8.10 Post-Incident Reports**

The severity of an incident determines the report requirements.

Post-incident reports that are restricted to facts are limited to indisputable information such as the location of the incident, when the incident occurred, who responded, the number of injuries or casualties, and other information of this nature.

The report should include the following:

- A general description of the incident.
- Description of the response, containment, and recovery efforts.
- Area and site rehabilitation program.
- Recommendations for preventive measures in the future.
- Copy of personnel statements.
- Photographs illustrating the incident.
- Cost analysis for lost production, facility repairs, land reclamation, and community compensation.

A post-incident report contains analyses and evaluation of the incident. The report provides advice on how to prevent a recurrence and makes emergency preparedness recommendations. In addition, it may identify the immediate and basic causes.

Issues related to liability and responsibility may arise from the analysis of the report.

Reports that define responsibility, liability or corrective actions may have to be presented during legal proceedings. In such cases, however, the report may be protected from the disclosure by the legal doctrine of privilege. Any report that relates to the causation or liability of the company for an incident should be privileged and not given to a plaintiff in legal proceedings. A report that is not reviewed by a Company lawyer and that has been requested by a third-party legal counsel; should be addressed to Company legal counsel.

In addition to company reports, independent report(s) may be prepared by government agencies.

### 8.11 Cause and Liability Report

Cause and Liability Reports are privileged and confidential. They are prepared at the request of legal counsel in contemplation of litigation.

Cause and liability reports should be clearly separated from the reports that document factual matters and set out the remedial actions.

Privileged reports may include the following information:

- A description of the sequence of events that led up to the incident, during the incident and following the incident.
- Details related to the potential severity and the potential for frequency of recurrence. This suggests the importance of investigation and priority for action.
- An analysis including a logical determination of the cause of the incident.
- Evaluation of the emergency response:
  - On-site remedial procedures.
  - Safety standards that were applied during the response.
  - Internal notification and communication systems.
  - Effectiveness of media, government liaison or community relations efforts.
  - Public safety actions.
  - Actions taken to temporarily reduce the risk.
- An assessment of any potential legal or environmental issues that may be raised because of the incident or because of the company's responses.
- A plan to reduce the risk of a similar incident, including recommendations for the following actions:
  - Future actions.
  - Design changes and operating procedure changes.
  - Improvements to the emergency preparedness program.

### 8.12 Incident Investigations

Incidents in the work environment must be thoroughly investigated and reported to ensure every effort is made to identify and correct underlying causes. In every emergency involving a fatality, serious injury and loss or significant damage to Company property, corporate officials will either provide assistance with or take the lead in an incident investigation.

**Particular care must be exercised to ensure that all evidence is preserved in its original state.**

Where loss or damage to Company property or loss of revenue has occurred, evidence will not be disturbed until permission has been received from the Insurance Company adjuster and/or any government agencies involved.

Work within the incident area is only permitted in order to make an incident scene safe or to preserve equipment against loss.

Examples: Lowering a suspended load or draining water from equipment to prevent freezing damage.

All such work must be done in a manner that preserves the incident scene as much as possible.

Where an injury or fatality has occurred, the incident scene may be disturbed to preserve life and/or prevent catastrophic loss but must be proportional to the disruption of evidence.

Example: Isolation of equipment to prevent a spill to water shed.

Every attempt should be made to obtain permission for re-entry to an incident scene from the Jurisdiction Having Authority.

#### ***8.12.1 Serious Injury/Fatality Investigations***

Following an incident where a fatality or a serious injury has occurred, government agency representatives will likely decide to carry out an investigation into either the extent or cause of the injury/fatality.

After presenting their credentials, these representatives are to be afforded full co-operation in the performance of their duties. Work at the scene of the injury/fatality may not be resumed until permission has been obtained from the various agencies involved.

#### ***8.12.2 Insurance Investigations***

Insurance companies may wish to conduct investigations of their own into an incident. Once they have shown their credentials, they must be accompanied by a senior Company employee.

Access to an incident scene is predicated on the scene being safe and the persons entering the scene following Company Health and Safety requirements (e.g. PPE, etc.).

## **9.0 JURISDICTIONAL REQUIREMENTS**

Federal and provincial/state specific emergency response regulations and guidelines are identified in the following sections.

9.1 Spill & Release Reporting Requirements

## Spill & Release Reporting Requirements

**All spills must be reported to your Environment Specialist**

Reportable Quantities						
		Alberta <i>(see Note 1)</i> <i>Any release that may cause and adverse effect must be reported</i>		Federal	British Columbia <i>(see Note 2)</i> <i>All releases must be reported, regardless of a minimum reportable quantity, if the release of a "polluting substance" is causing "pollution".</i>	
Product	Onsite	Offsite	Transportation <i>(see Note 3)</i>		Onsite	Offsite
<b>Spills</b>						
Crude oil, condensate, emulsions, diluent, etc.	2 m <sup>3</sup> , or any quantity not confined to site.	All spills. Any spill from a pipeline.	Any quantity that endangers public safety		100 L	100 L, or any spill from a pipeline.
Produced water	2 m <sup>3</sup> , or any quantity not confined to site	All spills. Any spill from a pipeline.	Any quantity that endangers public safety		2 m <sup>3</sup>	2 m <sup>3</sup> or any spill from a pipeline.
Diesel fuel, gasoline and other refined flammable liquids (Class 3)	200 L	200 L	Any quantity that endangers public safety		100 L	100 L
Used Glycol (Due to BTEX)	25 L (or see Note 1)	25 L (or see Note 1)	Not Regulated		25 L (or see Note 2)	25 L (or see Note 2)
Methanol (New or used)	200 L	200 L	Any quantity that endangers public safety		100 L	100 L
Lube oil (New or used)	200 L (or see Note 1)	200 L (or see Note 1)	Not Regulated		100 L	100 L
Oilfield wastes (See Note 4)	2 m <sup>3</sup> , or any quantity not confined to site	All spills.	Any quantity that endangers public safety		Note 4	Note 4
Molten sulphur or flammable solids (Class 4)	25 kg	25 kg	Any quantity that endangers public safety		25 kg	25 kg
Pesticides (See Note 4)	Reportable quantity dependent on product classification.		Any quantity that endangers public safety		Reportable quantity dependent on product classification.	
Toxic substances (Class 6.1)	5 kg or 5 L	5 kg or 5 L	Any quantity that endangers public safety		5 kg or 5 L	5 kg or 5 L
Corrosives (Class 8)	5 kg or 5 L	5 kg or 5 L	Any quantity that endangers public safety		5 kg or 5 L	5 kg or 5 L
Other refined products (See Note 4)	Reportable quantity dependent on product classification.		Any quantity that endangers public safety		Reportable quantity dependent on product classification.	
<b>Air releases</b>						
Natural gas	Any release from a pipeline and any other release >30,000 m <sup>3</sup> (See Note 5).	Any quantity that could pose a danger to public safety or 50 kg (non-pipeline)	10 kg, if there is a breakage in a pipeline or fitting operated above 100 psi that results in a sudden and uncontrolled release of natural gas.		Any quantity that could pose a danger to public safety or 50 kg (non-pipeline).	
<b>Report to:</b>						
Upstream produced fluids and natural gas	<p style="text-align: center;"><b>Alberta Energy Resources (AER) field office</b></p> <p>Bonnyville: 780-826-5352      Midnapore: 403-297-8303                      Drayton Valley: 780-542-5182      Red Deer: 403-340-5454                      Grande Prairie: 780-538-5138      St. Albert: 780-460-3800                      High Level: 780-926-5399      Wainwright: 780-842-7570                      Medicine Hat: 403-527-3385</p> <p>Oral report immediately to above. A written report may be requested. Report any pipeline release to AER and notify landowner.</p>			<p style="text-align: center;"><b>Emergency Management BC 1-800-663-3456</b></p> <p>Oral report immediately to above. Written report only required if requested by the BCER in accordance with BCER Emergency Response Plan Requirements, Section 4.8.</p> <p>for BCER regulated/permitted assets, an update to ministry and end of spill report (entered into KERMIT within 24 hours) is only required for the following:</p> <ul style="list-style-type: none"> <li>• It is a Level 1, 2, or 3 emergencies (i.e., anything above the minor notification requirement)</li> <li>• It is a pipeline asset</li> <li>• It is requested by the BCER</li> </ul>		
Other substances or TDG releases	<p style="text-align: center;"><b>Alberta Environment (AENV)</b></p> <p style="text-align: center;">1-800-222-6514; Fax: 780-427-3178</p> <p><b>TDG releases to be reported to local police and 1-800-272-9600.</b></p> <p>Oral report immediately to above. Written report to AENV within 7 days. Written report within 30 days to Transport Canada for TDG releases. TDG releases also require reporting to: the consignor of the dangerous goods; the owner, lessee or charterer of the road vehicle; and, for an accidental release from a cylinder that has suffered a catastrophic failure, CANUTEC at 613-996-6666.</p>			<p style="text-align: center;"><b>B.C. Ministry of Environment, local police &amp; TDG releases</b></p> <p style="text-align: center;">via the EMBC 1-800-663-3456</p> <p>Oral report immediately to above. Written report may be required by the MOE. Written report within 30 days to Transport Canada for TDG releases. TDG releases also require reporting to: the consignor of the dangerous goods; the owner, lessee or charterer of the road vehicle; and, for an accidental release from a cylinder that has suffered a catastrophic failure, CANUTEC at 613-996-6666.</p>		
Federally regulated releases	<ul style="list-style-type: none"> <li>• Report to Environment Canada 1-780-499-2432 for any release of a deleterious substance directly or indirectly (including through groundwater) into water frequented by fish.</li> <li>• Canadian Energy Regulator (CER)-regulated pipelines require reporting to the CER 403-299-2773 for all construction and operation releases. Operation incidents must also be reported to the Transportation Safety Board of Canada (TSBC) 819-997-7887.</li> <li>• Radioactive releases must be immediately reported to any CNSC (Canadian Nuclear Safety Commission) office and a full report must be filed within 21 days. CNSC Western Regional Office 403-292-5181.</li> </ul>					
<b>Notes:</b>						
1	<p><b>In Alberta:</b> A release includes to spill, discharge, dispose of, spray, inject, inoculate, abandon, deposit, leak, seep, pour, emit, empty, throw, dump, place, and exhaust. To be reportable, the release must be into the environment. For example, a spill that is fully contained within a building, including odours, is not considered a release into the environment. However, if there is any possibility of odours venting from the building into the environment, AENV should be notified.</p> <p>All releases must be reported, regardless of a minimum reportable quantity, if the release has caused, is causing or may cause an adverse effect. An "adverse effect" is defined as "impairment of or damage to the environment, human health or safety, or property". All releases must be reported, regardless of a minimum quantity, if the release is into a watercourse, groundwater, or surface water. <b>If there is any doubt, report the release.</b></p>					
2	<p><b>In B.C.:</b> All releases must be reported, regardless of a minimum reportable quantity, if the release of a "polluting substance" is causing "pollution". A "polluting substance" is any substance, whether gaseous, liquid or solid, that is capable of causing pollution if it were to escapable to air, or be spilled or escape onto land or into a waterbody. "Pollution" is the presence in the environment of substances or contaminants that substantially alter or impair the usefulness of the environment. <b>If there is any doubt, report the release.</b></p>					
3	<p><b>Transportation</b> refers to the TDG and means all handling, offering for transport and transporting of dangerous goods by any means of transport. Handling means loading, unloading, packing, or unpacking dangerous goods in a means of containment for the purposes of, during, or following transportation, and includes storage during transportation. <b>Transportation does not include pipelines.</b></p>					
4	<p>Contact your Environment Specialist. Classification (Waste/TDG) is variable. Refer to the product's SDS or the WPS to determine TDG classification; of note: amines and inhibitors can have a variety of classifications (e.g., corrosive, flammable, etc.).</p>					
5	<p>Additional AER immediate reporting requirements include: any fire that occurs at a well or facility, or at a storage tank or pit, where the loss exceeds 30,000 m<sup>3</sup> of natural gas or where damage to the wellhead occurs; any break or leak in a vessel or gathering line from which the loss exceeds 30,000 m<sup>3</sup> of natural gas; any unexplained loss, including theft of oil at a well or facility, where the loss exceeds 2 m<sup>3</sup> of oil, condensate or crude bitumen; any casing leak or failure; any leak or break in a pipeline; any leak in a pipeline during pressure testing.</p>					

*Uncontrolled when printed. The controlled copy is on the NRM EHS e-site. Rev. April 3, 2023*

## 9.2 ALBERTA

### 9.2.1 Assessment Matrix for Classifying Incidents

NorthRiver's ERP will be implemented as deemed necessary in response to either an alert or an emergency (Level 1, 2, 3).

Table 1. Consequence of Incident		
Rank	Category	Example of consequence in category
1	Minor	<ul style="list-style-type: none"> <li>No worker injuries.</li> <li>Nil or low media interest.</li> <li>Liquid release contained on lease.</li> <li>Gas release impact on lease only.</li> </ul>
2	Moderate	<ul style="list-style-type: none"> <li>First aid treatment required for on-lease worker(s).</li> <li>Local and possible regional media interest.</li> <li>Liquid release not contained on lease.</li> <li>Gas release impact has potential to extend beyond lease.</li> </ul>
3	Major	<ul style="list-style-type: none"> <li>Worker(s) require hospitalization.</li> <li>Regional and national media interest.</li> <li>Liquid release extends beyond lease – not contained.</li> <li>Gas release impact extends beyond lease – public health/safety could be jeopardized.</li> </ul>
4	Catastrophic	<ul style="list-style-type: none"> <li>Fatality.</li> <li>National and international media interest.</li> <li>Liquid release off lease not contained – potential for or is impacting water or sensitive terrain.</li> <li>Gas release impact extends beyond lease – public health/safety jeopardized.</li> </ul>

Table 2. Likelihood of incident escalating*		
Rank	Descriptor	Description
1	Unlikely	The incident is contained or controlled, and it is unlikely that the incident will escalate. There is no chance of additional hazards. Ongoing monitoring required.
2	Moderate	Control of the incident may have deteriorated but imminent control of the hazard by the licensee is probable. It is unlikely that the incident will further escalate.
3	Likely	Imminent and/or intermittent control of the incident is possible. The licensee has the capability of using internal and/or external resources to manage and bring the hazard under control in the near term.
4	Almost Certain or currently occurring	The incident is uncontrolled and there is little chance that the licensee will be able to bring the hazard under control in the near term. The Licensee will require assistance from outside parties to remedy the situation.

\* What is the likelihood that the incident will escalate, resulting in an increased exposure to public health, safety or the environment?




Table 3 Incident Classification	
Risk Level	Assessment results
Very Low 2-3	Alert
Low 4-5	Level – 1 Emergency
Medium 6	Level – 2 Emergency
High 7-8	Level – 3 Emergency

**Incident Response**

Incident Classification				
Responses	Alert	Level 1 Emergency	Level 2 Emergency	Level 3 Emergency
<b>Communications</b>				
<b>Internal</b>	Discretionary, depending on licensee policy.	Notification of off-site management.	Notification of off-site management.	Notification of off-site management.
<b>External Public</b>	Courtesy, at licensee discretion.	Mandatory for individuals who have requested notification within the EPZ.	Planned and instructive in accordance with the specific ERP.	Planned and instructive in accordance with the specific ERP.
<b>Media</b>	Reactive as required.	Reactive as required.	Proactive media management to local or regional interest.	Proactive media management to national interest.
<b>Government</b>	Reactive, as required. Notify the AER 24-Hour Response Line if public or media is contacted.	Notify the AER 24-Hour Response Line. Call local authority and AHS if public or media is contacted.	Notify the AER 24-Hour Response Line, local authority and AHS.	Notify the AER 24-Hour Response Line, local authority, and AHS.
<b>Actions</b>				
<b>Internal</b>	On site as required by licensee.	On site as required by licensee. Initial response undertaken in accordance with the specific or corporate level ERP.	Predetermined public safety actions are under way. Corporate management team alerted and may be appropriately engaged to support on-site responders.	Full implementation of incident management system.
<b>External</b>	On site as required by licensee.	On site as required by licensee.	Potential for multi-agency (operator, municipal, provincial or federal) response.	Immediate multi-agency (operator, municipal, provincial or federal) response.
<b>Resources</b>				
<b>Internal</b>	Immediate local. and No additional personnel required.	Establish what resources would be required.	Limited supplemental resources or personnel required.	Significant incremental resources required.
<b>External</b>	None.	Begin to establish resources that may be required.	Possible assistance from government agencies and external support services required.	Assistance from government agencies and external support services required.

### *Levels of Emergency Definitions*

#### **ALERT**

An incident that can be handled on site by the licensee through normal operating procedures and is deemed to be a very low risk to members of the public.

#### **LEVEL 1 EMERGENCY**

There is no danger outside the licensee's property, there is no threat to the public, and there is minimal environmental impact. The situation can be handled entirely by licensee personnel. There will be immediate control of the hazard. There is little or no media interest.

#### **LEVEL 2 EMERGENCY**

There is no immediate danger outside the licensee's property or the right-of-way, but there is potential for the emergency to extend beyond the licensee's property. Outside agencies must be notified. Imminent control of the hazard is probable but there is a moderate threat to the public and/or the environment. There may be local and regional media interest in the event.

#### **LEVEL 3 EMERGENCY**

The safety of the public is in jeopardy from a major uncontrolled hazard. There are likely significant and ongoing environmental impacts. Immediate multi-agency municipal and provincial government involvement is required.

### *Downgrading the Emergency Levels and Stand-Down*

Any discussions regarding downgrading of the incident Emergency Level classification must be preceded by a thorough review of the following considerations:

- Has the release been stopped?
- Is the hazard mitigated?
- Have all public safety threats been eliminated?
- Are there any remaining risks that could escalate if the Emergency Level was downgraded?
- Has an appropriate environmental monitoring plan been initiated (surface water, groundwater, soils, wildlife, vegetation, air quality monitoring)?
- Has environmental data been collected, analyzed and is it available to be submitted to the Regulatory Authority?
- Has an environmental mitigation plan been developed based on the data collected and has it been evaluated relative to potential residual impacts?

If there is agreement on the above points between the Incident Commander, EOC Director and the Regulatory Authority then a coordinated discussion with the Regulatory Authority can be held to obtain approval to downgrade the emergency to the appropriate level.

Once site restoration is deemed appropriate and incident facts justify the relaxation from a state of readiness or alert, the Company must make the decision to stand-down the emergency in consultation with the Regulatory Authority.

The Company must keep all notified stakeholders and evacuated persons informed of the status of an emergency.

9.2.2 Notification Requirements for Key Government Agencies and Local Resources


INCIDENT TYPE	AGENCY OR RESOURCE	Initial Responders			Lead Agencies				Other Government Contacts						Support Services	
		Ambulance Services	Local Fire Department or Industrial Fire Service	Police/RCMP <sup>2</sup>	AER	AEP	Local Authorities (i.e. urban centres, MDs, and first nations reserves)	AHS - Alberta Health Services <sup>3</sup>	Alberta Occupational Health and Safety	Workers' Compensation Board	AEMA - Alberta Emergency Management Agency	ABSA - Alberta Boilers Association	Alberta Agriculture and Forestry <sup>4</sup>	Alberta Safety Services - Electrical Branch	Alberta Transportation EDGE <sup>5</sup>	Oil Spill Cooperative (WCSS)
					Energy/Environmental Emergency and Operations Complaint Line											
Sour Gas Release				✓	✓	✓	✓	✓		✓		✓		✓		
Sweet Combustible Gas Release				✓	✓	✓	✓	✓		✓		✓		✓		
Spill - Unrefined Products*				✓	✓	✓	✓	✓		✓		✓		✓	✓	
Spill - Refined Products*				✓	✓	✓	✓	✓		✓		✓		✓	✓	
Trucking/Motor Vehicle Incident		✓	✓	✓	✓	✓		✓						✓		
Serious Injury or Fatality (including sour gas exposure)		✓		✓	✓		✓	✓	✓							
Fire/Explosion			✓	✓	✓	✓	✓	✓		✓		✓		✓		
Boiling Liquid Vapour Explosion - BLEVE			✓ <sup>1</sup>	✓	✓	✓	✓	✓		✓		✓		✓		
Collapse or upset of a crane, derrick or hoist Collapse or failure of any component of a building or structure								✓								
Pressure Vessel or Piping Incident					✓			✓			✓			✓		
Electrical Incident			✓		✓			✓					✓	✓		
Security Incident				✓	✓			✓					✓	✓		

- ✓ Mandatory contact
- ✓ Contact consideration based on emergency event details.
- \* Refer to the Alberta Petroleum Industry Release Reporting Requirements chart included in the ERP.
- <sup>1</sup> Contact Local Fire Department or Industrial Fire Service in a BLEVE scenario to be a backup to ERAC.
- <sup>2</sup> Contact RCMP if the emergency affects a highway designated by 1, 2, or 3 digits (e.g. Hwy 2, Hwy 47, Hwy 837).
- <sup>3</sup> Contact Alberta Health Services (AHS) if the incident has the potential to impact public health (i.e. sour gas release impacting stakeholders.)
- <sup>4</sup> Contact Alberta Agriculture and Forestry for any event that could affect forested areas.
- <sup>5</sup> Alberta Transportation EDGE is the first call for all transportation related spills/incidents.

INCIDENT TYPE	AGENCY OR RESOURCE	Initial Responders	Lead Agencies	Other Government Contacts				Support Services	
		RCMP	CER <sup>1</sup>	Transportation Safety Board (TSB)	Environment and Climate Change Canada <sup>2</sup>	Indian Oil and Gas Canada <sup>3</sup>	DFO <sup>4</sup>	CANUTEC <sup>5</sup>	ERAC - Emergency Response Assistance Canada <sup>6</sup>
Sour Gas Release		✓	✓	✓	✓	✓			✓
Sweet Combustible Gas Release		✓	✓	✓	✓	✓			✓
Spill - Unrefined Products*			✓	✓	✓	✓	✓	✓	
Spill - Refined Products*			✓	✓	✓	✓	✓	✓	
Trucking/Motor Vehicle Incident		✓		✓	✓	✓	✓	✓	
Marine, pipeline, rail and air modes				✓			✓		
Serious Injury or Fatality (including sour gas exposure)		✓	✓	✓		✓			
Fire/Explosion		✓	✓	✓	✓	✓			✓
Boiling Liquid Vapour Explosion - BLEVE			✓				✓	✓	
Pressure Vessel or Piping Incident			✓		✓		✓	✓	
Electrical Incident			✓		✓				
Security Incident		✓	✓	✓					

- ✓ Mandatory contact
- ✓ Contact consideration based on emergency event details.
- <sup>1</sup> Contact the Canada Energy Regulator (via the Transportation Safety Board of Canada) for emergencies involving CER regulated sites and inter-provincial pipelines.
- <sup>2</sup> Contact Environment and Climate Change Canada for incidents involving spills on First Nation's lands, in National Parks, into river or lake systems containing fish or onto railway rights-of-way.
- <sup>3</sup> Contact Indian Oil and Gas Canada for incidents affecting First Nation reserves and Metis settlements.
- <sup>4</sup> Contact the DFO to report any spill that occurs in or around fresh, marine, or fish bearing waters.
- <sup>5</sup> Contact the Canadian Transport Emergency Centre (CANUTEC) if information is required about handling procedures for toxic material releases.
- <sup>6</sup> Contact ERAC for emergencies related to specific ERAP products for vessels containing over 450 liters or greater by road, rail and stationary tank.

Initial Notification Process



The assigned Liaison Officer based on the notification requirements for key government agencies will advise the assigned AER Duty Officer of the emergency services, government agencies and support services they are in the process of contacting.

### 9.2.3 Spill Reporting

NorthRiver must report all spills or releases that are or may cause an adverse effect as defined in the Responsible Energy Act and the Alberta Environmental Protection and Enhancement Act (EPEA) regarding the Energy Industry. The AER must be notified through the 24-Hour Response Line. This system is designed to streamline and standardize the reporting of spills and to ensure a coordinated, integrated response from different government agencies. The AER 24-Hour Response Line notifies both Alberta Environment and Parks (AEP) and Environment and Climate Change Canada.

#### Notification Requirements

For both refined and unrefined products, upon becoming aware of a reportable release, NorthRiver **must orally** notify the AER at the first available opportunity.

Upon completing the oral notification, the AER sends the licensee the Field Inspection System Number (FIS) along with the Initial Incident Report which is to be completed **within seven days** of receiving the document from the AER.

**Note:** NorthRiver must notify the landowner of any release that occurs off lease, or that occurs on an easement or right-of-way (Landowners can be private or any of the following: on Crown land (AEP), on reserves (First Nations), in provincial parks (tourism, parks and recreation). Landowner cooperation is essential in being able to quickly respond to a release.

For the purposes of reporting, NorthRiver shall use the following guidelines and considerations to assess whether the release may cause, is causing or has caused an adverse effect.

- Any third-party impact (off lease) e.g. crop damage, vegetation damage and livestock impact.
- Spilled substance likely to contaminate surface or ground water.
- Groundwater and/or surface water is contaminated.
- Release or spill has potential for offsite odour complaints.
- Toxic or flammable release to air going offsite.
- Chemical and physical characteristics of the substance released.
- Receiving or potential to receive media attention.
- Location of the release.

The onus is on the party who causes the release and has control of the situation to assess the adverse effect.

**Adverse effect** is defined in the EPEA as “impairment of or damage to the environment, human health or safety, or property”.

**Unrefined products** include conventional crude oil, LPG, diluents, condensate, synthetic crude, sour gas, produced water, and other produced fluids), pipeline breaks and incidents involving oilfield wastes.

**Refined Product** includes diesel, gasoline, sulphur, and solvents.

For further Alberta spill release reporting guidelines please refer to the following:

**Alberta Water Act,**  
revised December 15, 2022

<http://www.qp.alberta.ca/documents/Acts/w03.pdf>

**Alberta Provincial Release Reporting Regulation,**  
Revised June 30, 2021

[http://www.qp.alberta.ca/documents/Regs/1993\\_117.pdf](http://www.qp.alberta.ca/documents/Regs/1993_117.pdf)

**Oil Sands Conservation Rules,**  
Revised October 24, 2022

[http://www.qp.alberta.ca/documents/Regs/1988\\_076.pdf](http://www.qp.alberta.ca/documents/Regs/1988_076.pdf)

**AER's Release Reporting Brochure,**  
August 2022

<https://static.aer.ca/prd/documents/directives/AERReleaseReportingBrochure.pdf>

#### **9.2.4 TDG Reporting – Alberta Environmental and Dangerous Goods Emergencies (EDGE)**

Alberta EDGE is a 24-hour centre that supplies technical information to industry, the public and enforcement officials about the Transportation of Dangerous Goods (TDG) Regulations and all associated standards. They are also the emergency response centre for reporting releases or anticipated releases of dangerous goods during any aspect of transport as outlined in the Regulations.

In addition, Alberta Transportation has agreements with Environment and Parks (AEP) and Alberta Energy Regulator (AER), serving as a contact point for contraventions, spills, and complaints.

Whether a release or emission originated from the oil, gas, chemical, or manufacturing industry, Albertans can feel assured that the correct departments are informed of the situation immediately and actions are taken to minimize any impact on the public, the environment or public infrastructure.

Alberta Transportation is the only jurisdiction in Canada that has dually appointed Provincial and Federal Dangerous Goods Inspectors that inspect dangerous goods facilities, monitor highway tank facilities and respond to incidents involving dangerous goods.

The Safety and Compliance Services Branch is responsible for the compliance and enforcement of the Provincial Dangerous Goods Transportation and Handling Act and Dangerous Goods Transportation and Handling Regulation as well as the Federal Transportation of Dangerous Goods Regulation which has been adopted by Alberta. Both regulations set safety standards and shipping requirements for thousands of dangerous goods, in addition to providing a means of communicating the nature and level of danger associated with various chemicals and other products.

Part 8 of the TDG Regulations details the situations and requirements for reporting of specific events involving dangerous goods. These are briefly discussed in this document. Specific sections of the Regulations have been referenced.

Any person who has the charge, management or control of the Dangerous Goods must report a release or anticipated release of dangerous goods that are being offered for transport, handled or transported by road vehicle, railway vehicle or ship as soon as possible, after a release or anticipated release. The verbal report has to be made to any local authority that is responsible for responding to emergencies at the location of the release or anticipated release. The report must be made if the dangerous goods are, or could be, in excess of the quantity set out in the following table AND if the release endangers or could endanger public safety.

**TDG Reporting Requirements**

Types of Report	Who must make the report?	When is the report required?	Who should receive the report?	Method of Reporting	Is a 30-day follow-up report required?
Emergency Report	Person who has the charge, management or control of the dangerous goods (DG).	<ul style="list-style-type: none"> <li>As soon as possible;</li> <li>In the case of a release or an anticipated release of DG that are or could be in excess of the quantity set out in Section 8.2 of the TDG Regulations and if it endangers or could endanger public safety.</li> </ul>	<ul style="list-style-type: none"> <li>Local authority responsible for emergency response.</li> <li>911 (or local police; relevant provincial authorities).</li> <li>Alberta Transportation</li> <li>Canadian Coast Guard.</li> </ul>	Telephone (Verbal)	No
Release or Anticipated Release Report	Person who made the Emergency Report.	<ul style="list-style-type: none"> <li>The report is required in these situations:</li> <li>the death of a person;</li> <li>a person sustaining injuries requiring immediate medical treatment by a health care provider;</li> <li>an evacuation of people or their shelter-in-place;</li> <li>the closure of a facility, road, main railway line or main waterway;</li> <li>a means of containment has been damaged;</li> <li>the centre sill or stub sill of a tank car is broken or there is a crack in the metal &lt; 15 cm (6 inches).</li> </ul>	<ul style="list-style-type: none"> <li>CANUTEC;</li> <li>the consignor (shipper);</li> </ul> <p>And, if applicable,</p> <ul style="list-style-type: none"> <li>The Canadian Nuclear Safety Commission (CNSC); or</li> <li>A Vessel Traffic Services Centre, or the Canadian Coast Guard.</li> </ul>	Telephone Followed by Written Report	Yes
Loss or Theft Report	Any person who had the charge, management or control of the dangerous goods before the loss of theft.	<ul style="list-style-type: none"> <li>As soon as possible.</li> <li>In case of loss or theft if the quantity of DG is greater than the quantities indicated in Subsection 8.16(2) of the TDG Regulations.</li> </ul>	<ul style="list-style-type: none"> <li>CANUTEC;</li> </ul> <p>And, if applicable,</p> <ul style="list-style-type: none"> <li>Natural Resources Canada, or</li> <li>CNSC.</li> </ul>	Telephone (Verbal)	No
Unlawful Interference Report	Person who has the charge, management or control of the dangerous goods (DG).	<ul style="list-style-type: none"> <li>As soon as possible after it is discovered that dangerous goods have been unlawfully interfered with.</li> </ul>	<ul style="list-style-type: none"> <li>CANUTEC;</li> </ul> <p>And, if applicable,</p> <ul style="list-style-type: none"> <li>Natural Resources Canada; or</li> <li>CNSC.</li> </ul>	Telephone (Verbal)	No

For a detailed description of the information required in the report, refer to the Emergency Release or Anticipated Release Report Requirements (Alberta Government, February 2020).

[Emergency, Release or Anticipated Release Report Requirements \(alberta.ca\)](https://www.alberta.ca/emergency-release-or-anticipated-release-report-requirements.aspx)

### 9.2.5 Flaring Reporting

AER is the primary contact for flaring from approved facilities. Flared volumes at an AER approved facility need to be reported to the AER 24-Hour Response Line when exceeding an approved limit which results in smoke or odours, or that extends over a long duration (24-hours).

#### Temporary Flaring, Venting, and Incineration Notification Requirements 1

Type of operation (applies to sweet and sour streams)	Duration of event (hrs in 24-hr period)		Gas volume <sup>2</sup> (10 <sup>3</sup> m <sup>3</sup> in a 24-hr period)	Notification <sup>3,4</sup>
Temporary (i.e., for well clean-up, testing, or maintenance)	< 4	and	< 30	No notification <sup>5</sup>
Temporary (i.e., for well clean-up, testing, or maintenance) if gas contains ≤ 10 mol/kmol H <sub>2</sub> S	> 4	or	> 30	Residents, schools, 1.5 km radius; AER field centre
Temporary (i.e., for well clean-up, testing, or maintenance) if gas contains >10 mol/kmol H <sub>2</sub> S	> 4	or	> 30	Residents, schools, 3 km radius; AER field centre
Temporary (i.e., for well clean-up, testing, or maintenance) through permanent battery or plant flare or incinerator	< 4		--	No public notification; <sup>5</sup> Notify the AER if flaring >30 10 <sup>3</sup> m <sup>3</sup>
Temporary (i.e., for well clean-up, testing, or maintenance) through permanent battery or plant flare or incinerator	> 4		--	Residents, schools, 0.5 km radius; AER field centre

<sup>1</sup> See section 1.6 of Directive 060 for information on the AER DDS system and how to notify the appropriate AER field centre via the DDS system.

<sup>2</sup> Notification requirements include duration and volume from flowback operations. These gases may be hydrocarbon or gases used in fracturing fluids (carbon dioxide or nitrogen) in any mixture. For reporting purposes, hydrocarbon volumes must be distinguished from fracture gas volumes (see section 3.9 of Directive 060).

<sup>3</sup> 24 to 72 hours in advance of planned flaring, venting, or incineration operations, the licensee, operator, or approval holder must notify the appropriate AER field centre via the DDS system, all rural residents outside towns, villages, and urban centres and within the specified radius, and the chief administrative officer or equivalent of a town, village, or urban centre within the specified radius. Note that for incorporated centres and hamlets, it is sufficient to contact only the appropriate administrator. Advance notification of more than 72 hours (but not longer than 90 days) must also offer the option for renotification 24 to 72 hours before the start of operations. After 90 days, renotification is mandatory.

<sup>4</sup> The AER recommends additional "good neighbour" notification for short-duration events for residents and schools that have identified themselves to the licensee, operator, or approval holder as being sensitive to or interested in emissions from the facility within the same notification radius as specified for events of more than four hours.

<sup>5</sup> The AER recommends additional "good neighbour" notification for longer duration events (of more than four hours) for residents and schools that have identified themselves to the licensee, operator, or approval holder as being sensitive to or interested in emissions from the facility.

### 9.2.6 Emergency Planning and Response Zones

Various factors will determine the extent of the EPZ:

- The nature of the product released.
- The volume released.
- The product flow rate.
- Weather or meteorological conditions.
- Topography.

For sour gas/emulsion properties the calculated EPZ is the distance to the time weight average of 100-ppm H<sub>2</sub>S over a 60-minute period which is equivalent to 235 ppm for 3 minutes. This pre-calculated zone serves as the initial defined spatial area of response efforts until the sour gas hazard can be assessed using gas monitoring equipment to determine actual conditions.

To determine the size of the response zones, response personnel should approach the perimeter of the response zone cautiously so as not to exceed personal exposure limits and begin monitoring with handheld equipment at the nearest residence. Note that the H<sub>2</sub>S personal exposure limit in Alberta is 10 ppm (8-hour exposure limit) and 15 ppm (ceiling exposure limit).

From this location, the response personnel should continue to approach any additional downwind residences that may be closer to the release until the outer boundary of the response zone is determined.


Whereas the EPZ is used for planning purposes and it reflects an area where significant exposure could result without prompt action, actual conditions during an incident need to be assessed to ensure an appropriate initial response. The response zones are where resources are focused during an incident to protect public safety. A licensee should also be aware that a different type and size of response zone could be established by the police if a bomb has been confirmed at the pipeline, well, or facility.

#### *Response Zones*

The Emergency Planning Zone (EPZ) is a geographical area surrounding a licensed well, pipeline and/or facility containing hazardous product that requires specific emergency response planning by the licensee. During any operations involving H<sub>2</sub>S or HVP product, the licensee must ensure that on-site personnel are aware of the size of the EPZ. In the case of a sour gas or toxic hazardous gas release the initial hazard area is the predefined EPZ determined using the ERCBH<sub>2</sub>S model shown on the area maps. The size and shape of the hazard area or EPZ may change with the nature of the incident and any related data from the incident, such as air or environmental monitoring results.

The Initial Isolation Zone (IIZ) defines an area in close proximity to a continuous hazardous release where indoor sheltering may provide temporary protection due to proximity of the release. If safe to do so, the licensee must attempt to evacuate the residents from the IIZ.

The Protective Action Zone (PAZ) is an area downwind of a hazardous release where outdoor concentration levels may result in life threatening or serious and possibly irreversible health effects to the public. Immediately following a release of the H<sub>2</sub>S or HVP product, the approximate size and direction of the PAZ can be determined using actual conditions at the time. The PAZ is a triangular area that starts at the IIZ and runs outwards to the edge of the EPZ. The PAZ is estimated to initiate priority response actions within the EPZ.



Initial Isolation and Protective Action Zones for illustration purposes only

### 9.2.7 Methods of Public Protection

If the health and safety of the public cannot be assured, then the Company must determine the best approach for protecting the public. Depending on the severity of the emergency, the Company will implement one of three approaches to public protection: sheltering, evacuation, or ignition.

The purpose of public protection measures is to proactively address public health and safety concerns and to take appropriate response actions to protect the public from harm. This may include removing or reducing the hazards and asking public stakeholders to shelter and/or evacuate as required.

It is the Company's responsibility to initiate public protection measures in the EPZ for any incident involving a release of sour gas product if there is potential for the release to impact members of the public. This could also include SO<sub>2</sub> if the sour gas release was ignited.

The type of public protection measure employed depends on the severity of the incident and/or on the monitored results in the unevacuated areas. The licensee is responsible for ensuring that appropriate emergency response procedures are in place and can be implemented, including for areas of potential impact beyond the EPZ.


#### Affected Parties within a Predetermined EPZ

- Permanent and part-time residents, including those residing on dead-end roads, beyond a predetermined EPZ, where occupants are required to egress through the EPZ.
- Business owners and/or operators and industrial operators, including oil and gas operators with manned facilities inside a predetermined EPZ.
- Private and public recreational property owners and/or operators (e.g. campgrounds, trapper cabin, private cabins, etc.) in and adjacent to a predetermined EPZ.

- Public facilities and publicly used development, such as schools and community centres in or adjacent to a predetermined EPZ.
- Non-resident landowners or farmers renting land who do not dwell on the property but whose lands are within a predetermined EPZ. These persons must be considered in the development of the ERP and be advised their property lies within the EPZ.
- First Nation reserves, registered trappers, guides, outfitters, and registered grazing lease rights holders or any other rights holders if the EPZ impacts the safety or livelihood of these stakeholders.
- Oil and gas operators with unmanned assets (e.g. wells, pipelines, facilities, etc.) in a predetermined EPZ whose activities may be impacted in the event of an emergency.

**Public Protection Decision Tree**

Use the following Public Protection Decision Tree for all planning and response zones:



### *Sheltering*

Sheltering may be the safest and most viable public protection measure in avoiding exposure to toxic or combustible gases in the following situation:

- Incident is of relatively short duration.
- Source of a release is uncertain.
- Residents are waiting for evacuation and transportation assistance.
- Not enough time is available to safely evacuate residents.
- Evacuation poses a higher risk to evacuees.

Residents will be asked to remain inside and ensure that all windows and doors are closed and that all air intakes (furnace, stove, bathroom, and dryer vents) are plugged to limit exposure to outside air until the situation is rectified or they are further notified.

**Note:** For general Shelter in Place Instructions, refer the Response Action Plans Section in this document.

### *Evacuation*

Safe evacuation is the primary public protection measure for long term H<sub>2</sub>S, SO<sub>2</sub>, or other toxic releases. Evacuation begins in the IIZ and radiates outward into the PAZ downwind of the release.

Evacuation must begin at the declaration of a Level 2 Emergency. The licensee must continuously assess and act on the need to expand the evacuation area based on the monitored levels of H<sub>2</sub>S, SO<sub>2</sub>, and other toxic releases.

Public within the IIZ must be evacuated or sheltered first. Once the IIZ has been secured, responders will address the public within the PAZ, downwind of the incident site. Once the PAZ has been secured, responders will address the public in the rest of the EPZ as necessary.

Evacuation of occupants inside the defined IIZ, PAZ and EPZ shall be prioritized as above and in the following manner:

1. Individuals located immediately downwind or adjacent to the incident site.
2. Individuals who have indicated they have special needs or require assistance.
3. Individuals who cannot be contacted by telephone.

Should area users be affected by an emergency involving Company operations, the response personnel will notify stakeholders by telephone or by personal contact with Rovers. A notice of evacuation is also placed on any unattended vehicles in the evacuation area and on doors of residences who are not home and cannot be contacted by phone.

**Note:** Individuals who have been identified as having special needs should be treated with priority and may choose to evacuate an area at an earlier time than other residents. These individuals may be highly responsive or sensitive to H<sub>2</sub>S or other toxic gases.

## Evacuation Requirements

H <sub>2</sub> S concentrations in unevacuated areas	Requirements
1 to 10 ppm (3-minute average)	Individuals who requested notification so that they can voluntarily evacuate before any exposure to H <sub>2</sub> S must be notified.
Above 10 ppm (3-minute average) *	Local conditions must be assessed, and all persons must be advised to evacuate and/or shelter.
*If monitored levels over the 3-minute interval are declining (e.g., three readings show a decline from 15 ppm to 10 ppm to 8 ppm over 3 minutes), evacuation may not be necessary even though the average over the 3-minute interval would be 11 ppm. The company should use proper judgement in determining if evacuation is required.	
SO <sub>2</sub> concentrations in unevacuated areas	Requirements
5 ppm (15-minute average) 1 ppm (3-hour average) 0.3 ppm (24-hour average)	Immediate evacuation of the area must take place.

If evacuation is initiated, the Company will establish a Reception Centre at a designated location. The Public Protection Group Supervisor will dispatch a representative to open the Reception Centre and record the arrival of evacuated stakeholders.

To ensure public safety, Company personnel will coordinate their public safety actions with the Local Authority.

### Evacuation outside of the EPZ

The evacuation of the public outside of the EPZ may be required if the incident cannot be controlled and/or H<sub>2</sub>S, SO<sub>2</sub>, or other toxic releases concentrations reach the maximum allowable limits adjacent to the EPZ boundary. In the unlikely event that public protection measures are required beyond the EPZ, they will be conducted in accordance with the licensee's arrangement with the local authority.

Alberta Municipal Affairs and Alberta Emergency Management Agency, local Disaster Services and the Alberta Regional Health Authority, in conjunction with the industrial operator, shall coordinate the evacuation outside the EPZ in accordance with the Energy Resources Industry Emergency Support Plan. The Company shall provide the necessary personnel and equipment deemed necessary to assist. The AER shall be available for assistance if required.

### Ignition

Ignition is the final means of protecting the public when evacuation is impractical, and the safety of the public/Company personnel is threatened. The decision to ignite a release will be made in conjunction with the Incident Commander and an AER Representative, if time permits.

If an immediate threat to human life exists and there is not sufficient time, the Incident Commander is authorized to ignite the release. This decision to ignite will be fully supported by Management.

Company personnel are expected to take immediate steps to prepare for ignition at the earliest signs of a release or a well control problem to ensure there will be no delay.

The company must:

- Ensure that appropriate ignition equipment is available during all operations.

- Assign the decision-making authority to ignite the release to a licensee representative on-site.
- Ignite a sour gas flow to atmosphere in accordance with the Assessment and Ignition Criteria Flowchart.
- If an uncontrolled release is ignited to protect the public, continuous monitoring for SO<sub>2</sub> or H<sub>2</sub>S in the surrounding area would determine if public evacuation becomes necessary.


The ignition team must be certified in sour well ignition and properly equipped to ignite the well within the planned time limits for which the EPZ was designed. Certification in ignition training may be obtained from Enform or from other training facilities that have a comparable program.


AER senior staff may make the decision to ignite a release if the licensee does not agree to ignite the release or is not prepared to take the necessary steps.

Ignition doesn't negate the need for continuing with evacuation as there may be residual pockets of H<sub>2</sub>S or SO<sub>2</sub> in the area.

It is important that mobile air quality monitoring be dispatched as quickly as possible to the emergency site because specialized monitoring equipment can more accurately record readings in the emergency area.

### Assessment and Ignition Criteria Flowchart





### 9.2.8 Fire Hazard Order and NOTAM

In an emergency situation requiring isolation of the response zones, contact the AER to discuss the issuance of a Fire Hazard Order.

It may be necessary to obtain a Fire Hazard Order or to declare a Local State of Emergency to restrict access to a designated area. A local state of emergency may be declared by the local authority should the incident escalate beyond the defined EPZ.

It also may be necessary for NAV Canada to issue a Notice to Airmen (NOTAM) to advise pilots of restrictions in the airspace above the EPZ or to close the airspace for a certain radius from the release (a no-fly zone). NOTAMs or closure of airspace may be requested by the AER at a Level 2 or 3 emergency.

### *9.2.9 Government Roles and Responsibilities*

#### *Provincial Operations Centre (POC)*

The Provincial Operations Centre (POC) serves as a communication and response coordination centre that is staffed 24-hours a day, 7 days a week. The POC is a central point for the collection, evaluation and dissemination of information concerning a single incident or multiple incidents in the province of Alberta. The POC is responsible for coordinating the initial response and maintaining support for a response to a natural or human-induced disaster.

The Alberta Provincial Emergency Operations Centre (POC) set up under the Government's Response Readiness Plan will provide notification by radio, television, or other practical means. The Company shall have a representative at the POC to assist as liaison. The broadcast media (radio, television) will be used to notify residents outside the EPZ in the event of an immediate evacuation of the area.

### Alberta Energy Regulator

The AER ensures the safe, efficient, orderly, and environmentally responsible development of hydrocarbon resources over their entire life cycle. This includes allocating and conserving water resources, managing public lands, and protecting the environment while providing economic benefits for all Albertans.

The AER will provide full-lifecycle regulatory oversight of energy resource development in Alberta - from application and construction to abandonment and reclamation, and everything in between.

The AER is the lead government agency that initiates and oversees government response. The AER can provide assistance to alert other applicable government and emergency response agencies.

<b>ALBERTA ENERGY REGULATORY</b>	
<input type="checkbox"/>	Acts as lead provincial government organization in petroleum industry emergency responses.
<input type="checkbox"/>	Review and approve licensee ERPs.
<input type="checkbox"/>	Participate in selected licensee ERP exercises.
<input type="checkbox"/>	Review and recommend changes to ERPs.
<input type="checkbox"/>	Participate in validation and testing of ERPs.
<input type="checkbox"/>	Maintain a 24-hour emergency contact number where resources can be accessed for a response related to Emergency Response Plans.
<input type="checkbox"/>	Receive information pertaining to petroleum industry incidents.
<input type="checkbox"/>	Determine the emergency level of an incident through consultation with the licensee.
<input type="checkbox"/>	Dispatch AER representative to the site of the incident, as required.
<input type="checkbox"/>	Confirm that local resources have been notified as appropriate.
<input type="checkbox"/>	Identify and request initial provincial resources to support the incident, to be coordinated at the regional level if necessary, through the REOC.
<input type="checkbox"/>	Notify EDGE to carry out notification in accordance with this plan.
<input type="checkbox"/>	Confirm, plan and/or implement public safety actions taken to ensure the safety of the public and the environment, including issuing fire hazard orders or requesting NOTAMs.
<input type="checkbox"/>	Provide Situation Reports to AEMA if requested.
<input type="checkbox"/>	Send AER representative to the On-Site Command Post.
<input type="checkbox"/>	Establish an EOC at the local AER Field Centre until the licensee or local authority establishes a MEOC.
<input type="checkbox"/>	Dispatch an AER Regulatory Liaison to the MEOC or POC and issue timely media releases in conjunction with the licensee and PAB.
<input type="checkbox"/>	Request, through AEMA, the deployment of the other provincial Government staff be sent to the MEOC or the local Field Centre EOC.
<input type="checkbox"/>	Request a local authority liaison officer to be present at the MEOC if necessary.
<input type="checkbox"/>	Carry out investigations.
<input type="checkbox"/>	Provide timely situation reports, through AEMA, to other Government departments activated by this plan.
<input type="checkbox"/>	Notify all participants when the event has concluded and there is no longer any hazard to the public.
<input type="checkbox"/>	Complete reporting protocols.
<input type="checkbox"/>	As part of the lessons-learned process, recommend any mitigating actions that may reduce the event from re-occurring.
<input type="checkbox"/>	Establish processes to receive and address community concerns.
<input type="checkbox"/>	In consultation with AEMA, review and recommend updates for the ERP.

**ALBERTA ENERGY REGULATORY**

### Alberta Environment and Parks

<b>ALBERTA ENVIRONMENT AND PARKS</b>	
<input type="checkbox"/> Maintain a 24-hour emergency contact number where resources can be accessed for a response related to Emergency Response Plans.	<b>ALBERTA ENVIRONMENT AND PARKS</b>
<input type="checkbox"/> Provide oversight role in ensuring air quality monitoring needs and activities associated with public safety around the event site are adequately addressed by the licensee.	
<input type="checkbox"/> Ensure the air quality monitoring log is being maintained.	
<input type="checkbox"/> Participate in the evaluation of the incident and the potential area at risk from product releases.	
<input type="checkbox"/> Provide assistance in monitoring discharges and ensuring appropriate mitigation and response actions are taken to reduce the impact of liquid releases for land-based spills and to ensure watercourses are protected.	
<input type="checkbox"/> Assist in notifying Fish and Wildlife personnel of the hazard.	
<input type="checkbox"/> Monitor environmental recovery, when required.	
<input type="checkbox"/> Compile and maintain environment related records and log.	
<input type="checkbox"/> Request and review environmental impact assessment if necessary.	
<input type="checkbox"/> Carry out investigation, when required, having regard for the existing investigative protocols and procedures.	
<input type="checkbox"/> Investigate non-compliance with the EPEA and the Water Act. The investigation may be coordinated with, or independent of any other investigation in relation to the incident.	

### Alberta Agriculture and Forestry

<b>ALBERTA AGRICULTURE AND FORESTRY</b>	
<input type="checkbox"/> Maintain a 24-hour emergency contact number where resources can be accessed for a response related to Emergency Response Plans.	<b>ALBERTA AGRICULTURE AND FORESTRY</b>
<input type="checkbox"/> Assist the industrial operator and/or the local authority in establishing and maintaining roadblocks. If requested.	
<input type="checkbox"/> Assist in notifying Forestry personnel of the hazard.	
<input type="checkbox"/> Assist in locating transients for evacuation in cooperation with licensee and local authority.	
<input type="checkbox"/> Inform transients within the hazard area of the incident and safety measures to take including evacuation details as applicable.	
<input type="checkbox"/> Fight any fires started as the result of the product release within the Forest Protection Area.	
<input type="checkbox"/> Compile and maintain event records and log.	
<input type="checkbox"/> Complete reports concerning the incident.	

### Occupational Health and Safety

The Occupational Health and Safety Branch operates within the Ministry of Jobs, Skills, Training, and Labour. OHS promotes health and safety through partnerships, resources, education and enforcement of the Occupational Health and Safety Act.

The Occupational Health and Safety Act sets standards for the protection of workers throughout the Province. Employers are required to ensure the health and safety of workers on the site.

OHS is responsible for the compliance policy and procedures implemented as a result of employee injuries/or death. Compliance policies and procedures are updated periodically.

<b>OCCUPATIONAL HEALTH AND SAFETY</b>	
<input type="checkbox"/> Maintain a 24-hour emergency contact number where resources can be accessed for a response related to Emergency Response Plans.	<b>OHS</b>
<input type="checkbox"/> Maintain the capacity to send an OHS officer to the POC on a 24-hour a day, 7 day a week basis.	
<input type="checkbox"/> Monitor the health and safety aspect of applicable occupations within the hazard area to ensure that the necessary precautions are taken to protect worker safety.	
<input type="checkbox"/> Compile and maintain health and safety related records and log.	
<input type="checkbox"/> Monitor lease holder/contractor's plan to determine if site is safe for recovery workers.	
<input type="checkbox"/> Investigate non-compliance with the Occupational Health and Safety Act. The investigation may be coordinated with, or independent of, any other investigation in relation to the incident.	

### Local Authority

#### Municipal Emergency Plans

Municipal Emergency Plans vary depending on the circumstances of each community. Generally, they deal with the following:

- Authority of the Plan.
- Implementation.
- Direction and Control.
- Organization and Functions.
- Tasks.
- Communications.
- Transportation.
- Health Units.
- Hazard Analysis.
- Medical Service.
- Police.
- Fire Service.
- Public Works.
- Social Services.
- Evacuation and Reception.
- 

<b>LOCAL AUTHORITY</b>	
<input type="checkbox"/>	Maintain a 24-hour emergency contact number where resources can be accessed for a response related to Emergency Response Plans.
<input type="checkbox"/>	Conduct a hazard assessment of petroleum facilities and operations.
<input type="checkbox"/>	Work with the operator to effectively prepare for a petroleum industry incident. Provide input to the industrial operator's Emergency Response Plan to ensure it is compatible with the municipal emergency plan (MEP).
<input type="checkbox"/>	Include preparedness and response information concerning facilities and operations in the MEP.
<input type="checkbox"/>	Train personnel to carry out function as assigned by the MEP or procedures.
<input type="checkbox"/>	Assess emergency incident and evaluate operator response with the AER.
<input type="checkbox"/>	Activate the emergency public warning system to alert people to life threatening hazards, as required.
<input type="checkbox"/>	Initiate public protection option, as required if resources are available.
<input type="checkbox"/>	Maintain communication with industrial operator during emergency.
<input type="checkbox"/>	Activate the MEP, in accordance with local authority policy.
<input type="checkbox"/>	Manage the local authority's emergency response.
<input type="checkbox"/>	Dispatch a representative to the incident command post, if resources are available.
<input type="checkbox"/>	Activate the MEOC, as required by the municipality.
<input type="checkbox"/>	Coordinate with the industrial operator, the establishment and the administration of reception centres for evacuees, as required.
<input type="checkbox"/>	Assist with the establishment of roadblocks and maintain them if resources are available.
<input type="checkbox"/>	Assist with fire protection (secondary fires only).
<input type="checkbox"/>	If necessary, declare a local state of emergency, as determined by the local authority.
<input type="checkbox"/>	Coordinate a public information service, including the use of the news media to inform and instruct the public of the emergency and of any protective actions to be taken.
<input type="checkbox"/>	Provide timely news releases.
<input type="checkbox"/>	Inform Municipal Affairs, Emergency Management Alberta and the public when the emergency is over in accordance with the Energy Resources Industry Emergency Support Plan.
<input type="checkbox"/>	Conduct a damage assessment to the extent of government infrastructure (roads/bridges).
<input type="checkbox"/>	Compile a municipal log.
<input type="checkbox"/>	Properly shutdown MEOC as appropriate.
<input type="checkbox"/>	Conduct municipal incident debriefing.
<input type="checkbox"/>	Participate in multi-agency debriefings if resources are available.
<input type="checkbox"/>	Review and update the municipal emergency plan.
<input type="checkbox"/>	Communicate any changes to the plan to all plan holders.
<input type="checkbox"/>	Track costs associated with the response.

**LOCAL AUTHORITY**

**Emergency Services: Police, EMS, and Fire Fighting**

<b>EMERGENCY SERVICES</b>	
<input type="checkbox"/>	Understand the hazards associated with the petroleum facilities and operations within the area.
<input type="checkbox"/>	Work with the operator to effectively prepare for a petroleum industry incident.
<input type="checkbox"/>	Understand the response role when there is a private and public-sector response.
<input type="checkbox"/>	Train personnel to carry out their functions when there is an incident.
<input type="checkbox"/>	Establish contact with the industrial operator.
<input type="checkbox"/>	Prior to dispatching staff to scene, determine the hazards associated with the incident.
<input type="checkbox"/>	Determine where roadblocks are established.
<input type="checkbox"/>	Where applicable, maintain roadblocks as necessary.
<input type="checkbox"/>	Determine the direction of approach to the incident.
<input type="checkbox"/>	Determine if there are any injuries.
<input type="checkbox"/>	Find out what response and public protection actions have been taken by the operator.
<input type="checkbox"/>	Initiate public protection option, when necessary.
<input type="checkbox"/>	Identify what resources are required and where they should be staged.
<input type="checkbox"/>	Determine the location of the On-Site Command Post.
<input type="checkbox"/>	Respond and assess emergency incident.
<input type="checkbox"/>	Communicate to REOC and provide situation reports as required.
<input type="checkbox"/>	Dispatch a representative to the REOC, when it is established to coordinate the response.
<input type="checkbox"/>	Assist with fire protection, where applicable.
<input type="checkbox"/>	Provide emergency medical assistance, as required.
<input type="checkbox"/>	Compile response logs.
<input type="checkbox"/>	Participate in municipal incident debriefing.
<input type="checkbox"/>	Participate in multi-agency debriefings.

**EMERGENCY SERVICES**

### Alberta Emergency Management Agency

The Alberta Emergency Management Agency is a division of the Ministry of Municipal Affairs and Housing. AEMA leads the coordination, collaboration and co-operation of all organizations involved in the prevention, preparedness, and response to disasters and emergencies.

AEMA has its headquarters in Edmonton and incorporates several domains of practise which encompass; emergency response, disaster recovery programs, business continuity, government ERPs, grants and funding, and municipal wildfire assistance programs.

The AEMA management structure is divided into two divisions: Provincial Operations, and Public Safety initiatives. Each separate division has five separate branches who report to an executive director. A Director oversees all activities of the Agency.

AEMA maintains a 24-hour a day, 7 day a week Agency Response and Readiness Centre (AARC) that monitors and maintains contact with various regional and local authorities. This centre is the central point of contact for the collection, evaluation, and dissemination concerning a single incident or for multiple incidents. The centre is responsible for co-ordinating an initial response at which time it will change roles into an active management centre known as the Provincial Operations Centre (POC). The POC is responsible for establishing and maintaining contacts with federal assistance and agencies.

<b>ALBERTA EMERGENCY MANAGEMENT AGENCY</b>	
<input type="checkbox"/>	Act as the provincial coordinating agency in petroleum industry emergency responses as per the Emergency Management Act.
<input type="checkbox"/>	Make the plan available to stakeholders.
<input type="checkbox"/>	Train provincial personnel to carry out functions as assigned by their emergency plan or procedures.
<input type="checkbox"/>	Communicate changes to the plan with plan holders.
<input type="checkbox"/>	Maintain 24-hour a day, 7 day a week duty manager system.
<input type="checkbox"/>	Assist in the planning and coordination of exercises with the AER.
<input type="checkbox"/>	Confirm AER has been notified.
<input type="checkbox"/>	Conduct the Initial Response Report (IRR) notification.
<input type="checkbox"/>	Obtain a situation report from the AER, AEP, local authority, etc.
<input type="checkbox"/>	Confirm the level of emergency.
<input type="checkbox"/>	Activate the Provincial Operations Centre (POC) as required.
<input type="checkbox"/>	Notify the appropriate provincial officials as per standard operating procedures.
<input type="checkbox"/>	Release consolidated SITREPs in accordance with the Energy Resources Industry Emergency Support Plan.
<input type="checkbox"/>	Coordinate the Government of Alberta response including requests for provincial/federal resources.
<input type="checkbox"/>	Provide ongoing situation reports or briefing notes to appropriate provincial officials.
<input type="checkbox"/>	Notify partners and stakeholders when the event is over.
<input type="checkbox"/>	Conduct the post-incident assessment.
<input type="checkbox"/>	Communicate any changes to the plan to all plan holders.
<input type="checkbox"/>	Complete documentation or reporting in relation to the activation of the Energy Resources Industry Emergency Support Plan and the incident.

**ALBERTA EMERGENCY MANAGEMENT AGENCY**

*Alberta Health Services***ENVIRONMENTAL PUBLIC HEALTH ROLES AND RESPONSIBILITIES**

Alberta Health Services (AHS) - Environmental Public Health (EPH) roles and responsibilities in public health emergency preparedness and response to the oil and gas industry are outlined below. The provision of services during an emergency depends upon our assessment of legislative responsibilities, impact to services, and business continuity.

**EPH will endeavor to:**

- Participate with the Licensee in the development of their Emergency Response Plans as it relates to the Environmental Public Health Program's role and responsibility.
- Provide the AHS Zone Single-Point-of-Contact (SPOC) emergency phone number to enable the Licensee to notify and alert the Zone of an emergency. From the initial notification or alert, AHS emergency response will fan out to and coordinate with other AHS programs and facilities as necessary. The 911 EMS services remain independent of the Zone SPOC notification/alert process.
- Participate with stakeholders in preparedness training and exercises associated with a Licensee's simulated activation of an Emergency Response Plan in which EPH has a role and responsibility.
- Participate in public information sessions during the Licensee's Emergency Response Plan development process when appropriate and as resources allow.
- Provide guidance to stakeholders and local municipal authorities in identifying sites suitable for establishing and operating an evacuation centre and/or reception centre, including operational requirements.
- Provide guidance to stakeholders on substances that may affect public health in consultation with the Zone Medical Officer of Health (MOH), including Alberta Health Acute Exposure Health Effects for Hydrogen Sulphide and Sulphur Dioxide information.
- Conduct assessments, inspections and give regulatory direction, when appropriate, to ensure the requirements of provincial legislation and EPH program areas of responsibilities for public health protection and disease prevention are maintained.
- Notify the Zone Medical Officer of Health of any incident affecting or potentially affecting other AHS programs or facilities. The Zone MOH will notify and coordinate emergency response in other program areas and facilities as necessary.
- Establish EPH emergency management operations, when appropriate, to support regional response efforts and liaise with the Government Emergency Operations Centre, Municipal Emergency Operations Centre and/or Industry Emergency Operations Centre, if needed.
- Assist the Zone Medical Officer of Health, local municipal authority, and Public Information/Communication officers in the development, issuance, and rescinding of public health, public evacuation and shelter-in-place advisories.
- Provide guidance to stakeholders on matters relating to evacuation of the public and/or public facilities, and the re-occupancy of those evacuated areas or facilities.
- Record and respond to health complaints or concerns from the public during and following an incident.
- Participate in stakeholder debriefings as necessary.

<http://www.albertahealthservices.ca/assets/wf/eph/wf-eh-oil-gas-epr-roles.pdf>

Updated: February 2016

**First Nations and Inuit Health**

<b>FIRST NATIONS AND INUIT HEALTH</b>	
<b>Before the Event.</b>	
<input type="checkbox"/>	Maintain 24-hour emergency contact numbers where resources can be accessed to carry out a response related to the Energy Resources Industry Emergency Support Plan.
<input type="checkbox"/>	Participate in provincial and industrial operators' preparatory training and exercises where feasible.
<input type="checkbox"/>	Liaise with other federal departments where needed.
<b>During the Event</b>	
<input type="checkbox"/>	Provide environmental public health advice to health care or special care facilities on First Nation reserves related to adverse environmental conditions resulting from a petroleum incident.
<input type="checkbox"/>	Investigate environmental public health related complaints from on-reserve Indigenous communities.
<input type="checkbox"/>	Provide guidance on public health advisories, public evacuation and sheltering for first nation communities.
In addition to the primary roles above, the following assistance will be provided during an event:	
<input type="checkbox"/>	Provide representation at the off-site REOC or when established, if requested and if available
<input type="checkbox"/>	Assist with messaging to provide accurate information to the public concerning the incident
<input type="checkbox"/>	Provide guidance and assistance at Evacuation Centre(s) to help ensure that public health standards are being met.
<input type="checkbox"/>	Provide health related information about toxic chemicals and by-products when the products or their make-up are known and reported.
<input type="checkbox"/>	Provide guidance on rescinding and declaration of public evacuation and on allowing re-occupancy – consultative capacity only.
<input type="checkbox"/>	Provide advice to the REOC on existing or potential health effects associated with the incident where possible
<input type="checkbox"/>	When possible work with all other responders to establish a single Regional Emergency Operations Centre (REOC).
<b>After the Event</b>	
<input type="checkbox"/>	Compile and maintain environmental public health related documents on inspected facilities.
<input type="checkbox"/>	Participate in PIA (Post Incident Assessments).
<input type="checkbox"/>	Provide guidance on assessing and mitigating public health risks following an upstream petroleum incident.
<b>FIRST NATIONS AND INUIT HEALTH</b>	

**Alberta Transportation**

<b>ALBERTA TRANSPORTATION</b>	
<input type="checkbox"/>	Maintain a 24-hour emergency contact number where resources can be accessed for a response related to Emergency Response Plans.
<input type="checkbox"/>	Respond to Dangerous Goods transportation emergencies in Alberta.
<input type="checkbox"/>	Manage transportation route closures.
<input type="checkbox"/>	Provide assistance with the closure of provincial highways in the establishment of suitable detour routes.
<input type="checkbox"/>	Provide advice and assistance with the procurement of roadblock equipment.
<input type="checkbox"/>	Ensure that all requests and reports are completed.
<input type="checkbox"/>	Work with the appropriate local authority to facilitate the restoration of roadways.
<b>ALBERTA TRANSPORTATION</b>	

**Public Affairs Bureau**

<b>PUBLIC AFFAIRS BUREAU</b>	
<input type="checkbox"/>	Maintain a team of trained Public Affairs personnel.
<input type="checkbox"/>	Confirm distribution of AER messaging. Provide support as required.
<input type="checkbox"/>	Activate Crisis Communication Plan and Crisis Communications Response.
<input type="checkbox"/>	Advise AEMA if media boardroom will be required for media events.
<input type="checkbox"/>	Coordinate key messaging with the AER.
<b>PAB</b>	

### Alberta Justice and Solicitor General

<b>ALBERTA JUSTICE AND SOLICITOR GENERAL</b>	
<input type="checkbox"/> Maintain the list of critical infrastructure in the Province of Alberta.	<b>SOLICITOR GENERAL</b>
<input type="checkbox"/> Maintain and regularly test the emergency notification system.	
<input type="checkbox"/> Maintain awareness of threats, vulnerabilities, and risks related to human induced intentional hazards.	
<input type="checkbox"/> Notify Government department of concerns arising from the effects of the incident on critical infrastructure.	
<input type="checkbox"/> Advise other Government departments of modifications to procedures if the incident was intentionally caused.	
<input type="checkbox"/> Provide technical expertise to all stakeholders in the event of an intentional incident and advise appropriate Government officials of potential future targets.	
<input type="checkbox"/> Ensure that effects on critical infrastructure have been resolved.	
<input type="checkbox"/> Recommend changes to critical infrastructure plans to mitigate future events.	

### 9.2.10 Alberta Pressure Equipment Incidents

<b>ALBERTA BOILERS SAFETY ASSOCIATION</b>	
<input type="checkbox"/> Review, accept and register pressure equipment designs and construction procedures that relate to pressure equipment.	<b>ABSA</b>
<input type="checkbox"/> Issue certification of inspection permits for pressure equipment before the equipment is placed into service.	
<input type="checkbox"/> Ensure that regular inspection of in-service pressure equipment is conducted.	
<input type="checkbox"/> Keep records for pressure equipment that has been registered for use, or manufactured, in Alberta.	
<input type="checkbox"/> Examine, certify and register Pressure Welders and Welding Examiners, Power Engineers, and Pressure Equipment Inspectors.	
<input type="checkbox"/> Authorize and monitor, through quality management system, organizations that have been permitted to conduct some of the activities subject to the regulations.	
<input type="checkbox"/> Conduct safety education and training.	
<input type="checkbox"/> Receive notification of an incident.	
<input type="checkbox"/> Investigate accidents or unsafe conditions that involve pressure equipment.	

Accidents that must be reported include:

- All accidents involving pressure equipment (boiler, pressure vessel, pressure piping system, fitting, or thermal liquid heating system) that result in damage to property or injury to, or death of, a person.
- Accidents not caused by pressure equipment but having some impact on pressure equipment.

Incidents above must be immediately reported to the following:

- The Company's Pressure Equipment Chief Inspector.
- Alberta Boilers Safety Association (ABSA) Office or ABSA Safety Codes Officer. After hours, call the Edmonton Switchboard. The message will provide after-hours phone numbers for contact.

For non-critical incidents, notify the Company's Chief Inspector and ABSA by the next business day. As soon as possible, send a full written report via mail (See ABSA Accident Reporting Form AB-97).

Form 97:

<https://www.absa.ca/unsafe-condition-accident-fire-reporting/ab-97-accident-report-form/>

### 9.2.11 Reporting Electrical Incidents

Section 15 of the Administrative Items Regulation requires that electrical incidents, as well as fires which are suspected to be of an electrical origin, be reported as soon as practicable to the technical Administrator for the electrical discipline: either directly or via a safety codes officer. The regulation also requires that nothing be tampered with at the scene of an incident until a safety codes officer has granted permission and determined whether further investigation is required.

Incidents should be reported to a safety codes officer representing the inspection authority having jurisdiction (i.e. accredited municipality, accredited corporation or Alberta Municipal Affairs for non-accredited areas of the province).

In addition to reporting an electrical incident, Section 48 of the Safety Codes Act also requires that when an incident is investigated, the corresponding investigation report must be submitted to the technical Administrator for the electrical discipline.

### 9.2.12 List of Abbreviations

Acronym	Name
<b>AAF</b>	Alberta Agriculture and Forestry
<b>ABSA</b>	Alberta Boilers Safety Association
<b>AEMA</b>	Alberta Emergency Management Agency
<b>AEP</b>	Alberta Environment and Parks
<b>AER</b>	Alberta Energy Regulator
<b>AHS</b>	Alberta Health Services
<b>AT</b>	Alberta Transportation
<b>CMO</b>	Consequence Management Officer
<b>EPEA</b>	Environmental Protection and Enhancement Act
<b>Local Authority</b>	County, Municipal District, Special Areas
<b>MEP</b>	Municipal Emergency Plan
<b>MOH</b>	Medical Officer of Health
<b>PAB</b>	Public Affairs Bureau
<b>POC</b>	Provincial Operations Centre
<b>Regulatory Authority</b>	Alberta Energy Regulator
<b>SOLGEN</b>	Alberta Justice and Solicitor General.

### 9.3 BRITISH COLUMBIA

#### 9.3.1 Incident Classification Matrix

The Incident Classification Matrix is designed for use as a tool for determining the severity of an incident. Instructions: Start at the top and continue down until you check off any one box in both consequence and probability to determine the incident classification. This matrix is required as an attachment upon submission of an incident through the Online Minor Incident Reporting System.

**Table 1: Consequence Ranking**

RANK	CONSEQUENCE (any one of the following)
4	<input type="checkbox"/> Major on-site equipment or infrastructure loss <input type="checkbox"/> Major act of violence, sabotage, or terrorism which impacts permit holder assets <input type="checkbox"/> Reportable liquid spill beyond site, uncontained and affecting environment <input type="checkbox"/> Gas release beyond site affecting public safety
3	<input type="checkbox"/> Threats of violence, sabotage, or terrorism <input type="checkbox"/> Reportable liquid spill or gas release beyond site, potentially affecting public safety, environment, or property <input type="checkbox"/> HAZMAT worker exposure exceeding allowable <input type="checkbox"/> Major on-site equipment failure
2	<input type="checkbox"/> Major on-site equipment damage <input type="checkbox"/> A security breach that has potential to impact people, property or the environment <input type="checkbox"/> Reportable liquid spill or gas release potentially or beyond site, not affecting public safety, environment, or property
1	<input type="checkbox"/> Moderate on-site equipment damage <input type="checkbox"/> A security breach that impacts oil and gas assets <input type="checkbox"/> Reportable liquid spill or gas release on location <input type="checkbox"/> **Occurrence of magnitude 4.0 or greater induced earthquake within 3 km of oil and gas operations or any earthquake which is felt on surface within a 3 km radius of oil and gas operations
0	<input type="checkbox"/> No consequential impacts

\*\* For this consequence criteria, a probability score of 2 or higher must be used.

**Table 2: Probability Ranking**

RANK	PROBABILITY (any one of the following)
4	<input type="checkbox"/> Uncontrolled, with control unlikely in near term
3	<input type="checkbox"/> Escalation possible; under or imminent control
2	<input type="checkbox"/> Escalation unlikely; controlled or likely imminent control
1	<input type="checkbox"/> Escalation highly unlikely; controlled or imminent control
0	<input type="checkbox"/> Will not escalate; no hazard; no monitoring required

**Table 3: Incident Risk Score and Classification**

Consequence \_\_\_\_ + Probability \_\_\_\_ = Risk Score \_\_\_\_ (this must be completed)

Risk Score	Assessment Result
Minor (1-2)	<b>Notification Only</b> ; permit holder must notify the Commission online within 24-hours using the Form A: Minor Incident Notification Form. In addition to Form A, spills must also be reported to EMBC.
Moderate (3-4)	<b>Level-1 Emergency</b> ; immediate notification (call EMBC)
Major (5-6)	<b>Level-2 Emergency</b> ; immediate notification (call EMBC)
Serious (7-8)	<b>Level-3 Emergency</b> ; immediate notification (call EMBC)

 BRITISH COLUMBIA ENERGY REGULATOR <b>BCER Incident Classification Matrix</b>			Probability				
			4	3	2	1	0
			<input type="checkbox"/> Uncontrolled, with control unlikely in near term	<input type="checkbox"/> Escalation possible; under or imminent control	<input type="checkbox"/> Escalation unlikely; controlled or likely imminent control	<input type="checkbox"/> Escalation highly unlikely; controlled or imminent control	<input type="checkbox"/> Will not escalate; no hazard; no monitoring required
<b>Consequence</b>	4	<input type="checkbox"/> Major on-site equipment or infrastructure loss <input type="checkbox"/> Major act of violence, sabotage, or terrorism which impacts permit holder assets <input type="checkbox"/> Reportable liquid spill beyond site, uncontained and affecting environment <input type="checkbox"/> Gas release beyond site affecting public safety	Level 3	Level 3	Level 2	Level 2	Level 1
	3	<input type="checkbox"/> Threats of violence, sabotage, or terrorism <input type="checkbox"/> Reportable liquid spill or gas release beyond site, potentially affecting public safety, environment, or property <input type="checkbox"/> HAZMAT worker exposure exceeding allowable <input type="checkbox"/> Major on-site equipment failure	Level 3	Level 2	Level 2	Level 1	Level 1
	2	<input type="checkbox"/> Major on-site equipment damage <input type="checkbox"/> A security breach that has potential to impact people, property or the environment <input type="checkbox"/> Reportable liquid spill or gas release potentially or beyond site, not affecting public safety, environment, or property	Level 2	Level 2	Level 1	Level 1	Minor Notification Form
	1	<input type="checkbox"/> Moderate on-site equipment damage <input type="checkbox"/> A security breach that impacts oil and gas assets <input type="checkbox"/> Reportable liquid spill or gas release on location <input type="checkbox"/> ** Occurrence of magnitude 4.0 or greater induced earthquake within 3 km of oil and gas operations or any earthquake which is felt on surface within a 3 km radius of oil and gas operations	Level 2	Level 1	Level 1	Minor Notification Form	Minor Notification Form
	0	<input type="checkbox"/> No consequential impacts	Level 1	Level 1	Minor Notification Form	Minor Notification Form	No Notification Required

\*\* For this consequence criteria, a probability score of 2 or higher must be used.

*Classification: Consequence Level*

**Natural Gas Release and Consequence Levels**

When the gas release exceeds 2,000 m<sup>3</sup> or when the duration of the release is uncertain, and the volume is unknown, a Consequence Level of 2 or more must be selected based on the migration of gas beyond lease.

When a sour gas product is released, any measurement of 10 ppm or greater measured at 1 meter from the source of the leak requires reporting as an incident. Protective actions to prevent public access must be taken. This requirement applies to leaks from any source, including surface casing vents.

**For Kicks and Induced Seismicity**

The BCER requires that permit holders classify a magnitude 4.0 or greater induced earthquake within 3 km of oil and gas operations; or any earthquake which is felt on surface within a 3 km radius of oil and gas operations as a Level 2 or higher probability.

Seismic activity has the potential to result in future damage to equipment. The reporting of seismic activity assists permit-holders and the Commission to monitor equipment and reduce the possibility of such incidents.

Well Kicks	Induced Seismicity
Consequence Level 2: Kick size in excess of 3 cubic meters or shut-in casing pressure in excess of 1000 kpa.	Consequence Level 2: Occurrence of magnitude 4.0 or greater induced earthquake (felt at surface) Probability must be recorded as 2 or higher
Consequence Level 3: Kick size in excess of 65% of current kick tolerance or shut-in casing pressure in excess of 65% current MACP.	Consequence Level 3: Occurrence of magnitude 4.5 or greater induced earthquake (felt at surface) Probability must be recorded as 2 or higher. Multiple felt events must also be recorded at this level.
Consequence Level 4: Kick size in excess of 85% of current kick tolerance or shut-in casing pressure in excess of 85% current MACP.	

**Security Incidents and Consequence Levels**

Consequences for security-based incidents will typically be determined by the outcome and impact on operations – a piece of equipment is vandalized or stolen which affects the ability to continue some day to day or scheduled activity. There may be occasions when a permit holder is advised of a credible threat and takes additional precautions that have some impact on operations, such as shutting in a well or facility, or significantly enhancing security precautions that affect normal activities. In these cases, a Consequence Level of 1 or greater should be selected.

**Consequence Levels Explained**

**Consequence 0** – “No consequential impacts” – At this level, there are no reportable spills, no equipment damages, and no reason to interrupt normal operations.

**Consequence 1** – At this level, there has been some minor effect on operations; a spill had to be cleaned, equipment fixed with a minor repair, etc. For a sour product spill, H<sub>2</sub>S must be under 100 ppm at the source point of the spill with no detectable levels off lease. Total incurred costs are typically under \$50,000.

**Consequence 2** – At this level impacts have become more pronounced; there may be some loss of production capability (temporary stoppages, reduced output, etc.) or the incident may have, or

has the potential to extend off lease / beyond ROW. Any sour product of 100 ppm or greater must have a consequence level of 2 or more indicated due to the threat to workers, public or environment.

**Consequence 3** – At this level impacts have had a noticeable effect on operational capabilities, affected public or environment, or have raised significant concerns for operational safety - such as malicious equipment tampering, or a pattern of failure in an equipment type or process.

**Consequence 4** – At this level, operations would typically be suspended or impossible to continue, at least in the short term. Critical equipment would be damaged / destroyed.

*Classification: Probability Level*

**Probability 0** – “Will not escalate; no hazard; no monitoring required” – This level is typical of a fixed quantity spill that is completely contained by a berm or impoundment, or able to be immediately remediated. A probability of zero can not be assigned if the source of the spill has not been controlled, accurately identified, or the extent of the spill fully defined. Spills to water are highly unlikely to ever have a probability of zero given the likelihood of spill migration and impacts.

**Probability 1** – “Escalation highly unlikely; controlled or imminent control” - Small equipment failures that are easily isolated would be rated at this level. Turning off power or closing valves to / from the equipment bring the incident under control, with very little possibility of further damage or release of product.

**Probability 2** – “Escalation unlikely; controlled or likely imminent control” - This level is typical of incidents where the cause of the incident is easily determined, and control measures are able to be enacted promptly and successfully.

**Probability 3** – “Escalation possible; under or imminent control” - Pit gains of 10 m<sup>3</sup> or greater during a drilling operation, or a fire on site that was of limited scope – such as a fire in a holding tank or generator shack would normally be ranked as a Probability 3. Additional considerations in this example would be the potential for expansion such as to other nearby equipment or forested areas, or possible need for an evacuation of a public area or residents. Repeating, related or similar security incidents, such as ongoing vandalism targeting a particular site or type of operation would use this probability level.

**Probability 4** – “Uncontrolled, with control unlikely in near term” - An equipment failure that has caused uncontrolled release of product beyond the ability of the operator to control – such as a facility explosion, a pipeline rupture with uncontained product moving into the environment, or a fire that is spreading / growing without possible containment with the resources at hand would all be classified as Probability 4.

*BCER Incident Reporting Guidelines*

**Minor Incident**

- Those with a total score of two or less on the Classification Matrix, permit holders are responsible for directly entering information into the Commission’s on-line reporting tool Kermit within 24-hours of the incident.
- If the minor incident involves a leak or a spill, EMBC must also be called for the Ministry of Environment & Climate Change Strategy to be notified.
- The incident must be reported by electronic submission by the permit holder incident representative. A copy of the Form A: Minor Incident Notification Form and the Incident Classification Matrix can be found on the Emergency Response and Safety section of the Commission’s website to help the permit holder gather

the information required before entering it online. The matrix and any photos or any other relevant documentation can be attached to the online submission.

### Level 1, 2, or 3 Emergency

If the incident receives a score of Level 1, 2, or 3, it must be reported immediately (within 1 hour) to the BCER by calling EMBC's incident reporting line.


For incidents that involve the release of a reportable volume / product – as defined under the Spill Reporting Regulation – a Dangerous Goods Incident Report (DGIR) must be obtained from EMBC.

Note that incidents involving a form of transportation (truck or rail) also have reporting requirements under federal Transportation of Dangerous Goods (TDG) regulations, and some products have significantly smaller reportable thresholds.

When a sour gas product is released, any measurement of 10 ppm or greater measured at 1 meter from the source of the leak requires reporting as an incident. Protective actions to prevent public access must be taken. This requirement applies to leaks from any source, including surface casing vent assemblies.

A release of any product into moving water is considered to be an off-lease/right of way spill.

Incidents scoring 3 or higher are classified as emergencies and are reported through EMBC. The Commission's duty emergency officer will be notified by EMBC and will directly contact the permit holder (or representative) who has assumed the on-scene incident commander role. A DGIR is also obtained if there is release of product.



### Permit Holder Post-Incident Report

Form D: Permit Holder Post-Incident Report Form must be submitted by the permit holder to the BCER within 60 days for:

1. Any Level 1, 2 or 3 emergency incident: complete Part A-P.
2. Any pipeline incident (including minor notification): complete Part A-U.
3. Upon request by the BCER.

This report and accompanying documentation can be found on the BCER's website under Emergency Response and Planning and must be emailed electronically to [EMP@bc-er.ca](mailto:EMP@bc-er.ca).

### Other Reportable Incidents

The BCER's Incident Risk Classification Matrix is designed to assist permit holders in determining which incidents must be reported. However, some incidents, which do occur, may not meet the criteria outlined in the Incident Risk Classification Matrix but still require notification to the BCER as a minor notification.

These include the following:

- Spills or release of hazardous substances which are not provincially regulated, such as radioactive substances.
- Major damage to oil and gas roads or road structures.
- Drilling kicks when any one of the following occur:
  - Pit gain of 3 m<sup>3</sup> or greater.
  - Casing pressure 85% of MA.
  - 50% out of hole when kicked.
  - Well taking fluid (LC).
  - Associated spill.
  - General situation deterioration, e.g. leaks, equipment failure, unable to circulate, etc.
- Pipeline incidents, such as spills during construction phase, exposed pipe caused by flooding, pipeline over pressure, failure (without release) of any pressure control or ESD device during operations.
- Security related issues which are relatively minor; such information may be required for tracking and monitoring purposes only.

### *Downgrading the Emergency Levels and Stand-Down*

Any discussions regarding downgrading of the incident Emergency Level classification must be preceded by a thorough review of the following considerations:


- Has the release been stopped?
- Is the hazard mitigated?
- Have all public safety threats been eliminated?
- Are there any remaining risks that could escalate if the Emergency Level was downgraded?
- Has an appropriate environmental monitoring plan been initiated (surface water, groundwater, soils, wildlife, vegetation, air quality monitoring)?
- Has environmental data been collected, analyzed and is it available to be submitted to the Regulatory Authority?
- Has an environmental mitigation plan been developed based on the data collected and has it been evaluated relative to potential residual impacts?

If there is agreement on the above points between the Incident Commander, EOC Director and the Regulatory Authority then a coordinated discussion with the Regulatory Authority can be held to obtain approval to downgrade the emergency to the appropriate level.

Once site restoration is deemed appropriate and incident facts justify the relaxation from a state of readiness or alert, the Company must make the decision to stand-down the emergency in consultation with the Regulatory Authority.

The Company must keep all notified stakeholders and evacuated persons informed of the status of an emergency.

BCER Emergency and Incident Response Flowchart




9.3.2 Notification Requirements for Key Government Agencies and Local Resources

INCIDENT TYPE	AGENCY OR RESOURCE	Initial Responders			Lead Agencies				Other Government Contacts				Support Services	
		Ambulance Services	Local Fire Department or Industrial Fire Service	Police	EMBC	BCER	Ministry of Environment & Climate Change Strategy	Local Authorities	Local Health Authority <sup>1</sup>	WorkSafe BC	Technical Safety BC	Ministry of Forests, Lands, Natural Resource Operations & Rural Development <sup>2</sup>	Ministry of Transportation and Infrastructure <sup>3</sup>	Electrical Provider
Sour Gas Release				✓	✓	✓	✓	✓			✓	✓		
Sweet Combustible Gas Release				✓	✓	✓	✓	✓			✓	✓		
Spill - Unrefined Products*					✓	✓	✓	✓			✓	✓		✓
Spill - Refined Products*					✓	✓	✓	✓			✓	✓		✓
Trucking/Motor Vehicle Incident				✓	✓	✓	✓	✓				✓		
Serious Injury or Fatality (including sour gas exposure)		✓	✓	✓	✓				✓					
Fire/Explosion			✓ <sup>4</sup>	✓	✓	✓	✓	✓	✓	✓	✓	✓		
Boiling Liquid Vapour Explosion - BLEVE				✓	✓	✓	✓	✓	✓		✓	✓		
Pressure Vessel or Piping Incident					✓	✓						✓		
Electrical Incident					✓						✓	✓	✓	
Security Incident				✓	✓	✓						✓		

✓ Mandatory contact \* Refer to the British Columbia Petroleum Industry Release Reporting Requirements chart included in the ERP.  
<sup>1</sup> Contact the Local Health Authority if the incident has the potential to impact public health.  
<sup>2</sup> Contact BC Ministry of Forests, Lands, Natural Resource Operations & Rural Development for any event that could affect forested areas.  
<sup>3</sup> Contact BC Ministry of Transportation and Infrastructure or the RCMP if the emergency affects a highway designated by 1, 2, or 3 digits (e.g. Hwy 2, Hwy 47, Hwy 837).  
<sup>4</sup> Contact local Fire Department or Industrial Fire Service in a BLEVE scenario to be a backup to ERAC.

INCIDENT TYPE	AGENCY OR RESOURCE	Initial Responders	Lead Agencies	Other Government Contacts				Support Services	
		RCMP	CER <sup>1</sup>	Transportation Safety Board (TSB)	Environment and Climate Change Canada <sup>2</sup>	Indian Oil and Gas Canada <sup>4</sup>	DFO	CANUTEC <sup>3</sup>	ERAC - Emergency Response Assistance Canada <sup>5</sup>
Sour Gas Release		✓	✓		✓	✓	✓		✓
Sweet Combustible Gas Release		✓	✓		✓	✓	✓		✓
Spill - Unrefined Products*			✓		✓	✓	✓	✓	
Spill - Refined Products*			✓		✓	✓	✓	✓	
Trucking/Motor Vehicle Incident		✓			✓		✓	✓	
Marine, pipeline, rail and air modes				✓					
Serious Injury or Fatality (including sour gas exposure)		✓	✓			✓			
Fire/Explosion		✓	✓		✓	✓			✓
Boiling Liquid Vapour Explosion - BLEVE			✓				✓	✓	
Pressure Vessel or Piping Incident			✓		✓			✓	
Electrical Incident			✓		✓				
Security Incident		✓	✓						

✓ Mandatory contact  
<sup>1</sup> Contact the Canada Energy Regulator (via the Transportation Safety Board of Canada) for emergencies involving CER regulated sites and inter-provincial pipelines.  
<sup>2</sup> Contact Environment and Climate Change Canada for incidents involving spills on first nation's lands, in National Parks, into river or lake systems containing fish or onto railway rights-of-way.  
<sup>3</sup> Contact the Canadian Transport Emergency Centre (CANUTEC) if information is required about handling procedures for toxic material releases.  
<sup>4</sup> Contact Indian Oil and Gas Canada for incidents effecting First Nation reserves and Metis settlements.  
<sup>5</sup> Contact ERAC for emergencies related to specific ERAP products for vessels containing over 450 liters or greater by road, rail and stationary tank.



\*AD HOC COMMITTEE THAT MAY BE FORMED IN THE EVENT OF A SEVERE EMERGENCY OR CATASTROPHIC EVENT.

### 9.3.3 Spill Reporting

For land-based spills during daytime operations, responses must be initiated within six (6) hours from the time spill is discovered.

For spills occurring on weekends or during the night, responses must be initiated within twelve (12) hours from time of discovery.

As per the Environmental Management Act, all spills (including type, size and location) must be reported immediately to the Emergency Management British Columbia (EMBC).

#### *Notification Requirements*

The person who had possession, charge or control of a substance immediately before it is spilt shall immediately report to EMBC or when not practical to the local police or RCMP. He/she shall take all reasonable and practical action and have due regard for the safety of the public to stop, contain and minimize the effects of the spill.

A report under this section must include, to the extent practicable, the following information:

- a) the contact information for
  - i) the individual making the report,
  - ii) the responsible person in relation to the spill, and
  - iii) the owner of the substance spilled;
- b) the date and time of the spill;
- c) the location of the spill site;
- d) a description of the spill site and the surrounding area;
- e) a description of the source of the spill;
- f) the type and quantity of the substance spilled;
- g) a description of the circumstances, cause and adverse effects of the spill;
- h) details of action taken or proposed to comply with section 91.2 (2) [responsible persons - spill response 1 of the Act];
- i) the names of the government, federal government, local government and first nation government agencies at the spill site;
- j) the names of other persons or government, federal government, local government or first nation government agencies advised about the spill.

Please refer to the BC Environmental Management Act; [Spill Reporting Regulation](http://www.bclaws.ca/civix/document/id/oic/oic_cur/m329_2017)  
[http://www.bclaws.ca/civix/document/id/oic/oic\\_cur/m329\\_2017](http://www.bclaws.ca/civix/document/id/oic/oic_cur/m329_2017)

#### *BCER Spill Reporting Criteria*

Where the permit holder holds or maintains rights, the permit holder must report to the British Columbia Energy Regulator, all spills of materials are identified in Section 9.1 Spill & Release Reporting Requirements.

### 9.3.4 Flaring

Permit holders must notify the Commission and all residents and administrators of incorporated centres located within the notification radius that flaring, incinerating or venting will occur.

The Commission does not require permit holders to obtain the consent of the residents within the notification radius. **Flaring and Venting Reduction Guideline**, British Columbia Energy Regulator <https://www.bc-er.ca/node/5916/download>

#### Notification Requirements

H <sub>2</sub> S Content	Flaring Event Duration or Volume	Notification Radius
Any	<4 hr and < 10 e <sup>3</sup> m <sup>3</sup>	None
<1%	>4 hrs or > 10 e <sup>3</sup> m <sup>3</sup>	1.0 km
1%≤H <sub>2</sub> S<5%		1.5 km
≥5%		3.0 km

#### Notification of Residents and Administrators of Incorporated Areas

- 1) Notification must be given a minimum of 24-hours prior to commencement of planned flaring events and within 24-hours of unplanned flaring events.
- 2) Permit holders should consult with residents and administrators of incorporated centres to develop and implement a notification process that is mutually acceptable.
- 3) If a mutually acceptable notification process has not been implemented, notification must be in writing and include the following minimum information:
  - a) Company name, contact persons and telephone numbers;
  - b) Location of the flaring;
  - c) Duration of the event;
  - d) Expected volume and rate;
  - e) Information on the type of well (oil or gas) and information on H<sub>2</sub>S content; and,
  - f) Commission contact number.
- 4) The Commission recommends that permit holders consider placing signage on public roads in the vicinity of temporary flaring operations indicating the operation type and contact number for inquiries.

#### Notification of the Commission

Notification must be given a minimum of 24-hours prior to commencement of planned flaring events and within 24-hours of unplanned flaring events.

For flaring at wells, including underbalanced drilling, well clean-up, testing and maintenance operations, permit holders must notify the Commission through the online drilling reporting system.

For flaring at Pipelines and Facilities, permit holders must notify the Commission Pipelines and Facilities Department by email.

### 9.3.5 Emergency Planning and Response Zones

Under Emergency Management Regulation in British Columbia EPZs are required for all sour gas facilities and HPZs are required for all other significant hazards.

The principle hazards associated with a hydrocarbon release are:

- Exposure to the toxicity of H<sub>2</sub>S following an unignited sour gas release.
- Exposure to the toxicity of SO<sub>2</sub> following an ignited sour gas release.
- Exposure to flame for people located within a flammable region of a dispersing gas plume following delayed ignition of a release.

- Heat radiation from a fire following ignition of a release.

To determine the size of the response zones, response personnel should approach the perimeter of the response zone cautiously so as not to exceed the ceiling exposure limits and begin monitoring with handheld equipment at the nearest residence. Note that the ceiling H<sub>2</sub>S exposure limit in British Columbia is 10 ppm.

From this location, the response personnel should continue to approach any additional downwind residences that may be closer to the release until the outer boundary of the response zone is determined.

Various factors will determine the extent of the EPZ/HPZ:

- The nature of the product released.
- The volume released.
- The product flow rate.
- Weather or meteorological conditions.
- Topography.

Whereas the EPZ/HPZ is used for planning purposes and it reflects an area where significant exposure could result without prompt action, actual conditions during an incident need to be assessed to ensure an appropriate initial response. The response zones are where resources are focused during an incident to protect public safety. A licensee should also be aware that a different type and size of response zone could be established by the police if a bomb has been confirmed at the pipeline, well, or facility.

#### *Emergency Planning Zone (EPZ)*

British Columbia Energy Regulator defines an EPZ as a geographical area surrounding a well, pipeline, or facility containing hazardous product (H<sub>2</sub>S or SO<sub>2</sub>) that requires specific emergency response planning by the licensee. The Emergency Planning Zone may also be referred to as Hazard Planning Zone or HPZ.

Existing wells and pipelines are assessed annually to ensure the H<sub>2</sub>S release volume calculations are based on actual operating and licensed conditions.

#### *Hazard Planning Zone (HPZ)*


Hazard planning distances are used to identify a geographical area (a hazard planning zone) within which persons, property or the environment may be affected by an emergency. The combined geographic areas of hazard (emergency) planning zones are used by the applicant or permit holder to identify an EPZ where immediate response actions are required in the event of an emergency. The HPZ is based upon the greatest hazard present, or expected to be normally present, for which the Emergency Response Plan has been developed. Section 7 of the Emergency Management Regulations defines a hazard planning distance as a horizontal distance measured from the site of an oil and gas activity that is the subject of the plan.

**Hazard Response Zone (HRZ)**

The Hazard Response Zone (HRZ) is the area affected by an incident/emergency.

**Emergency Awareness Zone (EAZ)**

The Emergency Awareness Zone (EAZ) is an area twice the radius of the Emergency Planning Zone.



**9.3.6 Methods of Public Protection**

If the health and safety of the public cannot be assured, then the Company must determine the best approach for protecting the public. Depending on the severity of the emergency, the Company will implement one of three approaches to public protection: sheltering, evacuation, or ignition.

The purpose of public protection measures is to proactively address public health and safety concerns and to take appropriate response actions to protect the public from harm. This may include removing or reducing the hazards and asking public stakeholders to shelter and/or evacuate as required.

It is the Company’s responsibility to initiate public protection measures in the EPZ for any incident involving a release of sour gas product if there is potential for the release to impact members of the public. This could also include SO<sub>2</sub> if the sour gas release was ignited.

The type of public protection measure employed depends on the severity of the incident and/or on the monitored results in the unevacuated areas. The licensee is responsible for ensuring that appropriate emergency response procedures are in place and can be implemented, including for areas of potential impact beyond the EPZ.

***Affected Parties within a Predetermined EPZ***

- Permanent and part-time residents, including those residing on dead-end roads, beyond a predetermined EPZ, where occupants are required to egress through the EPZ.
- Business owners and/or operators and industrial operators, including oil and gas operators with manned facilities inside a predetermined EPZ.
- Private and public recreational property owners and/or operators (e.g. campgrounds, trapper cabin, private cabins, etc.) in and adjacent to a predetermined EPZ.
- Public facilities and publicly used development, such as schools and community centres in or adjacent to a predetermined EPZ.
- Non-resident landowners or farmers renting land who do not dwell on the property but whose lands are within a predetermined EPZ. These persons must be considered in the development of the ERP and be advised their property lies within the EPZ.
- First Nation reserves, registered trappers, guides, outfitters, and registered grazing lease rights holders or any other rights holders if the EPZ impacts the safety or livelihood of these stakeholders.
- Oil and gas operators with unmanned assets (e.g. wells, pipelines, facilities, etc.) in a predetermined EPZ whose activities may be impacted in the event of an emergency.

**Procedures for contacting affected parties within the HRZ or HPZ**


**Well Operations:** Ensure the Wellsite Supervisor or delegate notifies residents, landowners / land-renters and rights holders inside the HRZ:

- At the beginning of drilling and initial completion operations.
- 24-hours before entering the sour zone.
- At the conclusion of drilling and initial completion operations.
- At the beginning and conclusion of other operations, including workovers, flaring, fracking, etc.

**Production Operations:** Ensure the Field Foreman or his delegate notifies all applicable stakeholders prior to the commencement and conclusion of any high-risk operations.

Refer to the Supplemental ERP - Field Specific Response Actions - for site-specific procedures regarding contacting and communicating with affected parties within the HPZ.

### Public Safety Decision Process



### *Sheltering*

Sheltering may be the safest and most viable public protection measure in avoiding exposure to toxic or combustible gases in the following situation:

- Incident is of relatively short duration.
- Source of a release is uncertain.
- Residents are waiting for evacuation and transportation assistance.
- Not enough time is available to safely evacuate residents.
- Evacuation poses a higher risk to evacuees.

Residents will be asked to remain inside and ensure that all windows and doors are closed and that all air intakes (furnace, stove, bathroom, and dryer vents) are plugged to limit exposure to outside air until the situation is rectified or they are further notified.

**Note:** For general Shelter in Place Instructions, refer the Response Action Plans Section in this document.

### *Evacuation*

Safe evacuation is the primary public protection measure for long term H<sub>2</sub>S, SO<sub>2</sub>, or other toxic releases.

Evacuation of occupants inside the defined EPZ shall be prioritized in the following manner:

1. Individuals located immediately downwind or adjacent to the incident site.
2. Individuals who have indicated they have special needs or require assistance.
3. Individuals who cannot be contacted by telephone.

### **Voluntary Evacuation**

For a Level 1 Emergency, residents within the EPZ will be notified and given the Voluntary Evacuation Message.

The decision to proceed with this initial notification will be made by the Incident Commander after careful consideration to ensure residents are not unnecessarily stressed.

Should area users be affected by an emergency involving Company operations, the response personnel will notify stakeholders by telephone or by personal contact with Rovers. A notice of evacuation is also placed on any unattended vehicles in the evacuation area and on doors of residences who are not home and cannot be contacted by phone.

**Note:** Individuals who have been identified as having special needs should be treated with priority and may choose to evacuate an area at an earlier time than other residents. These individuals may be highly responsive or sensitive to H<sub>2</sub>S or other toxic gases.

### **Urgent Evacuation/Shelter**

For a Level 2 Emergency or Level 3 Emergency, residents inside the EPZ will be notified and given the **Shelter in Place** or **Urgent Evacuation Message**. The Company must provide for air monitoring at the nearest downwind unevacuated residence.

### **Evacuation Outside of the EPZ**

The evacuation of the public outside of the EPZ may be required if the incident cannot be controlled and/or H<sub>2</sub>S, SO<sub>2</sub>, or other toxic releases concentrations reach the maximum allowable limits adjacent to the EPZ boundary. In the unlikely event that public protection measures are required beyond the EPZ, they will be conducted in accordance with the licensee's arrangement with the local authority.

The Company shall provide the necessary personnel and equipment deemed necessary to assist. The BCER shall be available for assistance if required.

### Mandatory public safety response criteria

H <sub>2</sub> S concentrations in non-evacuated areas	Requirement
Above 10 ppm (3-minute average) *, or above 1 ppm (1-hour average) in an urban centre	Carry out immediate shelter-in-place and/or evacuate all persons in the area and ignite the release if the criteria are met.
* If monitored levels in successive three-minute intervals are declining and shelter-in-place is occurring, evacuation may not be necessary. Operators should consult with the regulatory authority (if applicable) and use proper judgment in determining if evacuation is required.	
SO <sub>2</sub> concentrations in non-evacuated areas	Requirement
Above 5 ppm (15-minute average), above 1 ppm (3-hour average), or above 0.3 ppm (24-hour average)	Carry out immediate shelter-in-place and/or evacuate all persons in the area.
Ignition assessment criteria and flowchart	

The evacuation area will be expanded in areas where monitored H<sub>2</sub>S and/or SO<sub>2</sub> concentrations exceed the evacuation levels and/or resident health effects are apparent. If an uncontrolled release is ignited to protect the public, continuous monitoring for SO<sub>2</sub> or H<sub>2</sub>S of the surrounding area would determine if public evacuation becomes necessary.

Company personnel cannot force a resident to evacuate their residence. Forced evacuation is possible only if the local authority declares a local State of Emergency under the Provincial ERP.

### *Ignition*

If an immediate threat to human life exists and there is not sufficient time, the Incident Commander is authorized to ignite the release. This decision to ignite will be fully supported by Management.

It is important that mobile air quality monitoring be dispatched as quickly as possible to the emergency site because specialized monitoring equipment can more accurately record readings in the emergency area. The mobile air quality unit must be equipped to continuously measure and record wind speed and direction and to monitor H<sub>2</sub>S and SO<sub>2</sub> to parts per billion (PPB). Permit holder personnel will monitor and record the air until a mobile air monitoring unit arrives or until the incident is over. At a minimum, these readings must include LEL and H<sub>2</sub>S.

When time permits, the decision to ignite will be made jointly with the Incident Commander, EOC Director, and the BCER Representative.


The following factors should be considered before the decision to ignite proceeds:


- Safety and health risks to emergency personnel;
- Proximity of release to public areas;
- Availability of air monitoring equipment and personnel;
- Availability of ignition equipment, and training of staff in its use;
- Detectable concentration of H<sub>2</sub>S and/or flammable gases near the source of the release and within the Emergency Planning Zone;
- Weather conditions;
- Duration of the release and potential volume;
- Impacts to wildlife; and
- Impacts to other values at risk including property, timber, or infrastructure.

All sour wells must have an ignition system such as a flare gun on site during all drilling, completion, well testing, or workover operations in the sour zone.

Company personnel are required to ensure that all special sour wells have a dual ignition system on site during all drilling operations in the critical zone(s) and during all completions, well testing, or work-over operations when the wellhead is off. The primary ignition system should be installed such that remote activation can be achieved from a safe location through a triggering device. The secondary system may be a manual system, such as a flare gun.

### Ignition Assessment Criteria and Flowchart





Adapted from AER Directive 071, Emergency Preparedness and Response Requirements

### 9.3.7 Drinking Water Emergency Contingency Plan

As per BC Public Health NorthRiver is required to have a contingency plan to deal with drinking water quality at our remote facilities that have potable drinking water systems.

- A) Drinking water advisories
- B) Contamination of source
- C) Loss of source
- D) Flood conditions
- E) System failures

#### ACTIONS:

- The Area Operations Team Leader will:
  - Shut down pumps and close valve to users
  - Notify all users and post a drinking water advisory notice
  - Contact the Drinking Water Program Coordinator
  - Arrange alternate source of water for plant and personnel. (i.e. bottled water, bulk hauler)
  - Order sample kits for post treatment and/or cleaning retesting

### EMERGENCY CISTERN DISINFECTION

It will be necessary to disinfect the cistern if bacteria tests show that it has become contaminated. If a routine water test shows a positive result for bacteria, follow the cleaning and disinfection procedure as detailed below:

#### **PROCEDURE**

- 1) Drain water from tank.
- 2) Scrub or pressure-wash the interior walls to remove sediment and grime.
- 3) Rinse the inside surfaces of tank with clean potable water and drain wash water.
- 4) Fill tank with clean potable water.
- 5) Add the required amount of unscented household bleach (Sodium hypochlorite) to the water in the storage tank (see table below). Mix well.
- 6) To disinfect the plumbing lines and fixtures, open all taps in the distribution system until a chlorine smell is apparent at each outlet. Close taps.
- 7) Let chlorine solution sit in the water system for **at least 12 hours**. Do not consume this highly concentrated solution.
- 8) Drain the water tank (not into a septic system or fish bearing stream).
- 9) Refill with fresh potable water.
- 10) Open valve to distribution lines. Run water from the taps until there is no smell of chlorine.
- 11) Submit a new laboratory sample once cleaning and disinfection has taken place, and once new potable water has been replaced in the cistern. This will verify that contamination has been eliminated.

Dosage of Household Bleach (~ 5% chlorine) required for the Cleaning and Disinfecting of Water Holding Tanks				
Tank Size		Amount of Household Bleach to obtain 50 ppm Chlorine		
Litres	Imp. Gallons	Metric	Imp. Ounces	Cups
225	50	225 mL	8	1
450	100	450 mL	18	2
900	200	900 mL	32	4
1150	250	1.2 L	40	5
2300	500	2.3 L	80	10
4500	1000	4.5 L	160	20
6800	1500	6.8 L	240	30
9100	2000	9.1 L	320	40
11400	2500	11.4 L	400	50

### DISINFECTING A WELL

In a well-supplied drinking water system, it will be necessary to disinfect the well if bacteria tests show that it has become contaminated. The method outlined below describes the procedure to disinfect a well. If you have any questions about this procedure contact a Public Health Inspector for direction.

#### PRODECURE

- 1) Pour unscented household bleach (5% chlorine) directly into the well. Make sure that the chlorine gets all the way to the bottom of the well. (Please note: this instruction applies to all types of wells, be they drilled, driven or dug. In every case, pour the chlorine solution right down into the well, either through the drill pipe, or well head, or simply by adding the bleach to the water in an open or dug well, preferably through a hose inserted to the bottom of the well.) Check the amount of chlorine to add in the chart that follows.
- 2) Start the pump and open all taps one at a time, starting with the tap furthest from the well.
- 3) Close the taps one-by-one and stop the pump when you begin to smell chlorine at the taps.
- 4) Open the valve or plug at the top of the pressure tank just before stopping the pump to allow the solution to contact the entire inside surface of the tank. Then close the valve or plug.
- 5) Leave the chlorinated water in the system for at least 12 hours. This is a very strong chlorine solution (about what you should use for cleaning floors) – **DO NOT DRINK THE WATER**
- 6) Pump out the water until the chlorine odour disappears. **\*Do not drain this water into a stream, ditch, or storm drain which connects with any fish bearing streams.**
- 7) Monitor frequently and treat again as necessary.
- 8) Control the factors that limit the effect of chlorine, e.g., cloudiness, and high levels of iron, manganese and hydrogen sulphide.
- 9) Submit a new laboratory sample once disinfection has taken place and chlorine has been flushed from the system. This will verify that contamination has been eliminated.

Amount of 5% Chlorine Bleach Solution Required <u>PER</u> 3m (10ft)* of Water to Disinfect Well Water System (200 ppm)		
Well Pipe Diameter		Bleach*
Inches	Centimeters	
4	10	5 tbsp, 100 ml
6	15	13 tbsp, 200 ml
8	20	1.5 cups, 360 ml
10	25	2.5 cups, 560 ml
12	30	3.5 cups, 808 ml
24	60	14.6 cups, 3.3 L
36	90	7.5 L
48	120	13.3 L

Note: 1 cup = 227 mL = 16 tbsp (tablespoons) = 48 tsp (teaspoons); 1 quart = 4 cups = 946 mL

### **BOIL WATER ADVISORY RESAMPLING**

In the event that a Public Health Inspector issues a Boil Water Advisory, two consecutive satisfactory water samples shall be taken at least 24 hours apart once all stages of the investigation, repair and remediation have been completed to the satisfaction of the Public Health Inspector.

- F) A Public Health Inspector may direct an alternate time span between samples based upon the bacteria detected.
- G) The Public Health Inspector shall provide written notice when the boil water notice may be lifted.

### **9.3.8 Closure Orders**

#### **Notice to Airmen (NOTAM)**

In an emergency situation requiring isolation of the response zones, contact the BCER to discuss the issuance of a Closure Order.

It may be necessary to obtain a closure order (if issued by the BCER) or to declare a local state of emergency to restrict access to a designated area. A local state of emergency may be declared by the local authority should the incident escalate beyond the defined EPZ.

It also may be necessary for NAV Canada to issue a Notice to Airmen (NOTAM) to advise pilots of restrictions in the airspace above the EPZ or to close the airspace for a certain radius from the release (a no-fly zone). NOTAMs or closure of airspace may be required by the BCER at a level 2 or 3 emergency.

#### **Oil and Gas Road Closures**

In Emergency situations, permit holders must phone the BCER's 24-hour Incident Reporting line to notify the BCER of needed emergency oil and gas road closures. Under Section 20 of the OGRR a permit holder may temporarily close or restrict access if the action is necessary to address an existing or imminent threat to the environment or human life.

Under such circumstances, the Permit Holder must promptly notify the Commission. The notices of closure and resumption must be submitted to the Commission by email to

BCER.ExternalNotifications@bcer.ca using the Road Notification Form:  
<http://www.bcer.ca/node/11088/download>

Closure Order	Agency
Petroleum Development Road	BCER
Forestry Roads	Ministry of Forestry
Numbered Highway	Ministry of Transportation

### 9.3.9 Government Roles and Responsibilities

#### Provincial Regional Emergency Operations Centre (PREOC)

The Provincial Regional Emergency Operations Centre manages activities at the Provincial Regional Coordination Level and coordinates the joint efforts of government and non-government agencies.

If the situation escalated beyond BCER control, EMBC may establish a Provincial Regional Emergency Operations Centre (PREOC) near the emergency site to coordinate provincial response. The PREOC also keeps elected provincial officials informed through personal contacts and briefing notes.

#### British Columbia Energy Regulator (BCER)

The BCER is a Crown Corporation of the province of British Columbia whose mandate is to regulate oil and gas activities and pipelines in the province. It is the petroleum authority that will participate in the emergency response to all situations involving or threatening oilfield wells, production facilities, or pipelines in British Columbia.

In an emergency, the BCER would be notified by EMBC, however, as EMBC works on a priority basis, the Company should take action and contact the BCER personally.

BRITISH COLUMBIA ENERGY REGULATOR	
<input type="checkbox"/>	Oversee the operator's response to an incident.
<input type="checkbox"/>	Establish communication with the operator.
<input type="checkbox"/>	Confirm incident level with operator.
<input type="checkbox"/>	Confirm downgrade of incident level.
<input type="checkbox"/>	Issue road closure order upon request from the operator.
<input type="checkbox"/>	Request NOTAM order from NAV Canada upon request from the operator.
<input type="checkbox"/>	Send an BCER representative to the Operator's On-Site Command Post and/or Evacuation Centre.
<input type="checkbox"/>	Establish a government EOC at the BCER office.
<input type="checkbox"/>	Confirm ignition decision with operator if time permits.
<input type="checkbox"/>	Confirm media releases to be sent out by operator.

**BRITISH COLUMBIA  
 ENERGY  
 REGULATOR**

#### Emergency Management BC (EMBC)

Emergency Management BC (EMBC) was formed to be the lead coordinating agency in the provincial government for all emergency management activities. EMBC provides executive coordination, strategic planning, and multi-agency facilitation and strives to develop effective working relationships in an increasingly complex emergency management environment.

EMBC works with local governments, First Nations, federal departments, industry,

non-government organizations and volunteers to support the emergency management phases of mitigation/ prevention, preparedness, response and recovery. Additionally, EMBC engages provincial, national and international partners to enhance collective emergency preparedness.

The EMBC acts as a 24-hour incident reporting line and initiates government notification fan-out by notifying the BCER, Ministry of Environment & Climate Change Strategy and Environment and Climate Change Canada.

### *Regional District*

The local authority will usually participate in any emergency that impacts or threatens land or residents outside the confines of company property.

In B.C., if regional districts have not been granted the powers of a municipality under the Emergency Program Act, then EMBC is responsible for coordinating response activities.

<b>REGIONAL DISTRICT</b>		<b>REGIONAL DISTRICT</b>
<input type="checkbox"/>	Implement the rural municipality/regional district disaster or emergency plan.	
<input type="checkbox"/>	Provide local knowledge about conditions, resources, and the community.	
<input type="checkbox"/>	Assist with the establishment and administration of a Reception Centre if required.	
<input type="checkbox"/>	Ensure local emergency services are available to assist the emergency response team.	
<input type="checkbox"/>	Dispatch representative(s) to the BCER's Emergency Operations Centre (EOC), if established.	
<input type="checkbox"/>	Provide support to ensure notification of endangered area residents.	
<input type="checkbox"/>	Provide support to coordinate and deliver emergency social services to evacuated residents.	
<input type="checkbox"/>	If necessary, declare a State of Local Emergency and issue an evacuation Alert, Order and Rescind.	
<input type="checkbox"/>	Assist in a public information service (joint BCER, Industry, local government).	
<input type="checkbox"/>	Provide building re-entry procedures.	

### *Emergency Services: Police, EMS, and Fire Fighting*

<b>EMERGENCY SERVICES</b>		<b>EMERGENCY SERVICES</b>
<input type="checkbox"/>	Understand the hazards associated with the petroleum facilities and operations within the area.	
<input type="checkbox"/>	Work with the operator to effectively prepare for a petroleum industry incident.	
<input type="checkbox"/>	Understand the response role when there is a private and public sector response.	
<input type="checkbox"/>	Train personnel to carry out their functions when there is an incident.	
<input type="checkbox"/>	Establish contact with the industrial operator.	
<input type="checkbox"/>	Prior to dispatching staff to scene, determine the hazards associated with the incident.	
<input type="checkbox"/>	Determine where roadblocks are established.	
<input type="checkbox"/>	Where applicable, maintain roadblocks as necessary.	
<input type="checkbox"/>	Determine the direction of approach to the incident.	
<input type="checkbox"/>	Determine if there are any injuries.	
<input type="checkbox"/>	Find out what response and public protection actions have been taken by the operator.	
<input type="checkbox"/>	Initiate public protection option, when necessary.	
<input type="checkbox"/>	Identify what resources are required and where they should be staged.	
<input type="checkbox"/>	Determine the location of the On-Site Command Post.	
<input type="checkbox"/>	Respond and assess emergency incident.	
<input type="checkbox"/>	Communicate to REOC and provide situation reports as required.	
<input type="checkbox"/>	Dispatch a representative to the REOC, when it is established to coordinate the response.	
<input type="checkbox"/>	Assist with fire protection, where applicable.	
<input type="checkbox"/>	Provide emergency medical assistance, as required.	
<input type="checkbox"/>	Compile response logs.	
<input type="checkbox"/>	Participate in municipal incident debriefing.	
<input type="checkbox"/>	Participate in multi-agency debriefings.	

### Ministry of Transportation and Infrastructure

The British Columbia Ministry of Transportation and Infrastructure is the British Columbia government ministry responsible for transport infrastructure and law.

The ministry is responsible for the planning of transportation networks, providing transportation services and infrastructure, developing and implementing transportation policies, and administering many transportation-related acts and regulations.

The Ministry of Transportation and Infrastructure would assist with closures of any provincial road or highway.

<b>MINISTRY OF TRANSPORTATION AND INFRASTRUCTURE</b>		<b>TRANSPORTATION &amp; INFRASTRUCTURE</b>
<input type="checkbox"/>	Maintain a 24-hour emergency contact number where resources can be accessed for a response related to Emergency Response Plans.	
<input type="checkbox"/>	Respond to Dangerous Goods transportation emergencies in British Columbia.	
<input type="checkbox"/>	Provide advice and assistance in procurement of roadblock equipment.	
<input type="checkbox"/>	Provide authorization/assistance for establishing road closures and emergency roadblocks.	
<input type="checkbox"/>	Manage transportation route closures.	
<input type="checkbox"/>	Provide assistance with the closure of provincial highways in the establishment of suitable detour routes.	
<input type="checkbox"/>	Work with the appropriate local authority to facilitate the restoration of roadways.	
<input type="checkbox"/>	Ensure that all requests and reports are completed.	

### WorkSafeBC

WorkSafe BC requires that all serious incidents and accidents be immediately reported and investigated. WorkSafe BC also carries out workplace inspections and investigations of work-related injuries and fatalities.

#### Regulatory excerpt

Section 172 of the Workers Compensation Act states:

- 172 (1) An employer must immediately notify the Board of the occurrence of any accident that:
- a) Resulted in serious injury to or the death of a worker,
  - b) Involved a major structural failure or collapse of a building, bridge, tower, crane, hoist, temporary construction support system or excavation,
  - c) Involved the major release of a hazardous substance,
  - c.1) Involved a fire or explosion that had a potential for causing serious injury to a worker, or
  - d) Was an incident required by regulation to be reported.

#### POLICY

Section 172(1)(c) requires the employer to notify the Board of any accident that involved the major release of a hazardous substance.

A major release does not only mean a considerable quantity, or the peculiar nature of the release, such as a gas or volatile liquid, but, more importantly, the seriousness of the risk to the health of workers. Factors that determine the seriousness of the risk include the degree of preparedness of the employer to respond to the release, the necessity of working in close proximity to the release, the atmospheric conditions at the time of the release and the nature of the substance.

As a general guideline, a report would be expected when:

- The incident resulted in an injury that required immediate medical attention beyond the level of service provided by a first aid attendant, or injuries to several workers that require first aid.
- The incident resulted in a situation of continuing danger to workers, such as when the release of a chemical cannot be readily or quickly cleaned up.

<http://www.worksafebc.com/forms/assets/PDF/7.pdf>

**Local Health Authority**

<b>LOCAL HEALTH AUTHORITY</b>	
<input type="checkbox"/>	Act as a consultant to the Emergency Operations Centre.
<input type="checkbox"/>	Monitor health effects of the incident to ensure appropriate data is collected and investigated.
<input type="checkbox"/>	Provide health advice on health and safety levels for the more vulnerable residents, including those in health care or special care facilities.
<input type="checkbox"/>	Provide advice to the government on the existing or potential health effects of the incident.
<input type="checkbox"/>	Establish health and safety levels for the escaping contaminants.
<input type="checkbox"/>	Establish and operate trauma teams for emergency health services.
<input type="checkbox"/>	Monitor adverse effects/contamination of water systems.
<input type="checkbox"/>	Enforce and regulate Public Health Regulations.
<input type="checkbox"/>	Recommend further investigation or research after the event, if warranted.

**LOCAL HEALTH AUTHORITY**

**Ministry of Environment & Climate Change Strategy**

The Ministry of Environment & Climate Change Strategy is responsible for ensuring sustainable development of the province's land, water, and resources while protecting environmental values.

In the event of an emergency, a ministry representative will provide regulatory oversight and monitor the situation to ensure that the responsible party is taking the appropriate actions.

The MOE may provide a representative to the Incident Command Centre and the BCER Emergency Operations Centre and/or the Provincial Regional Emergency Operations Centre (PREOC) on a 24-hour basis. In a larger scale incident, based on risk, additional ministry resources such as Incident Management Teams may be deployed to establish Unified Command and monitor, augment, or take over the response if the responsible party fails to take appropriate action as deemed necessary by the ministry representative or Provincial Incident Commander.

<b>MINISTRY OF ENVIRONMENT &amp; CLIMATE CHANGE STRATEGY</b>	
<input type="checkbox"/>	Assist the responsible party to ensure that other required agencies and affected stakeholders are contacted.
<input type="checkbox"/>	Monitor all discharges to the land, atmosphere and all water bodies.
<input type="checkbox"/>	Provide assistance with hazardous waste management.
<input type="checkbox"/>	Conduct sampling for monitoring and enforcement purposes.

**MOE**

**B.C. Ministry of Forests, Lands, Natural Resource Operations & Rural Development**

If a forest fire is associated with the incident, and a provincial emergency is declared, B.C. Ministry of Forests, Lands, Natural Resource Operations & Rural Development personnel will assist. The Ministry will provide assessment of potential damage and offer advice for remedial control in areas relating to renewable resources.

### BC Government Communications & Public Engagement (GCPE)

<b>BC GOVERNMENT COMMUNICATIONS &amp; PUBLIC ENGAGEMENT</b>	
<input type="checkbox"/> Maintain a team of trained Public Affairs personnel.	<b>GCPE</b>
<input type="checkbox"/> Confirm distribution of BCER messaging. Provide support as required.	
<input type="checkbox"/> Activate Crisis Communication Plan and Crisis Communications Response.	
<input type="checkbox"/> Advise EMBC if media boardroom will be required for media events.	
<input type="checkbox"/> Coordinate key messaging with the BCER.	

#### 9.3.10 Technical Safety BC - Pressure Equipment

Technical Safety BC is an independent, self-funded organization mandated to oversee the safe installation and operation of technical systems and equipment.

#### How to Report Incidents and Hazards to Technical Safety BC.

For emergency assistance call 911 or your local police or fire department directly.

Incidents and hazards are to be reported to Technical Safety BC through our website at:

<https://portal.technicalafetybc.ca/report-incident/incident-reporting-form>

Alternatively, you can call 1-866-566-7233 and follow the prompts to report an incident or hazard.

Note: voicemail and email messages made to Technical Safety BC employees concerning incidents and hazards are not considered to have been reported to Technical Safety BC as required by regulation.

#### Definitions

**Incident:** A failure of a regulated product, work or operation that causes:

- Damage to property, personal injury or death.
- Damage to safety features.

Note:

- Property damage or injury focuses on the impact that the failed equipment may have had outside the boundaries of the product, work or operation.
- Damage to safety features relates to failures where the damage:
  - is limited to the failed product, work or operation and,
  - does not render the product or activity inoperative and,
  - impairs the safety feature's effectiveness.

**Safety feature:** An aspect of a product's design, installation, maintenance or operation that is intended to prevent people or property from being exposed to a hazard.

**Hazard:** A source of potential harm to persons or potential damage to property.

**Duty holder:** A person or company who is responsible for compliance because they either own regulated products or perform regulated work.

#### Reporting of Incidents to Technical Safety BC

The following duty holders are required to report all incidents to Technical Safety BC:

- Person in charge of a regulated product or regulated work.
- Owner of the regulated product.
- Permit holder.
- Person authorized to perform or performing regulated work.
- Person authorized to operate or operating a regulated product.
- An officer or employee of a utility.
- Owner of a plant (as defined in the regulations).

Only one incident report per incident is required.

#### *Duty to Preserve Incident Site for Investigation*

A person must not remove, disturb or interfere with anything in, on or about the place where the incident occurred except as necessary to rescue a person, prevent injury or to protect property unless directed by a safety officer or safety manager.

#### *Reporting of Hazards to Technical Safety BC*

Hazards are required to be prevented or immediately corrected by duty holders that are responsible for the regulated product, work or operation. Hazards must be immediately reported to Technical Safety BC when:

- It is not known that the hazard is being corrected by the duty holder, or
- The same or similar hazards have been repeatedly observed and are associated with the same duty holder.

#### *When to Report Incidents and Hazards to Technical Safety BC*

##### **Incidents:**

Unless otherwise indicated, all incidents are to be reported within the following timeframes:

- Incidents resulting in a moderate, major or fatal injury – immediately.
- Incidents resulting in moderate, major or severe damage – immediately.
- All other incidents – within 24-hours (or as soon as practicable).

*Moderate injuries* are those that, while serious, are considered unlikely to have a significant effect to long-term quality of life. Examples include single limb fractures, concussions, and/or disorientation.

*Moderate damage* is damage that results with controlled exposure to energy (i.e. electrical, thermal, mechanical) or the limited/controlled release of substances intended to be contained.

##### **Hazards:**

All hazards as described in the 'reporting of hazards' section above are to be reported to Technical Safety BC immediately.

#### *What to Expect After Reporting an Incident or Hazard to Technical Safety BC*

Technical Safety BC tracks and investigates incidents and hazards that are reported to inform awareness and prevention initiatives. Consequently, Technical Safety BC does not investigate all reported incidents and may not follow-up with a notification unless there is an intention to investigate.

Summaries of all reported incidents and completed investigations can be accessed via Technical Safety BC at <https://www.technicalafetybc.ca/hazard-data-and-incident-data>. Technical Safety BC protects the identity of persons who report or may be involved with incidents or hazards.

Unless otherwise indicated, duty holders are required to preserve the equipment, products and items involved in an incident. Technical Safety BC will contact duty holders within 24-hours of the next regular business day following the report of an incident if more information is required or an investigation is planned to occur.

For more information, refer to Technical Safety BC's website.

<https://www.technicalafetybc.ca/alerts/incident-and-hazard-reporting-boilers-pressure-vessels-piping-and-fittings>

### 9.3.11 List of Abbreviations/Definitions

Acronym	Name
<b>EAZ</b>	Emergency Awareness Zone: The area twice the radius of the EPZ.
<b>Local Authority</b>	Regional District
<b>EMBC</b>	Emergency Management British Columbia
<b>MOE</b>	Ministry of Environment & Climate Change Strategy
<b>BCER</b>	British Columbia Energy Regulator
<b>PAB</b>	Public Affairs Bureau
<b>PREOC</b>	Provincial Regional Emergency Operations Centre:
<b>Regulatory Authority</b>	British Columbia Energy Regulator
<b>Rights Holders</b>	Refers to anyone holding a permit under section 15 or a licence under section 39 of the Land Act, under which the person is granted non-intensive occupation or use of the land; a forestry licence to cut, master licence to cut, road use permit, timber sales licence, tree farm licence or woodlot licence under the Forest Act; a grazing permit or grazing license under the Range Act; a guide outfitter's certificate or a registered trapline under the Wildlife Act; a mineral claim under the Mineral Tenure Act; or, a water licence or approval under the Water Act.

## 9.4 CANADIAN FEDERAL GOVERNMENT

### 9.4.1 Royal Canadian Mounted Police (RCMP)

The RCMP is both a federal and a national police force of Canada. The RCMP provides policing services to all of Canada at a federal level, and also on a contract basis to the three territories, eight of Canada's provinces (the RCMP does not provide provincial or municipal policing in either Ontario or Quebec), more than 190 municipalities, 184 Indigenous communities, and three international airports.

<b>RCMP</b>	
<input type="checkbox"/> May assist in the initial area isolation, security traffic and crowd control.	<b>RCMP</b>
<input type="checkbox"/> In conjunction with transportation, local authorities and Company personnel, may provide assistance with closure of roadways.	
<input type="checkbox"/> If available, assist company personnel with resident evacuation.	
<input type="checkbox"/> Clarify responsibilities when fatalities are involved. Police must be notified in the case of a fatality.	
<input type="checkbox"/> Assist the coroner in the event of a fatality in which there is no criminal wrong-doing.	
<input type="checkbox"/> Notify next-of-kin in the event of a fatality of a member of the public.	

### 9.4.2 Environment and Climate Change Canada

Environment and Climate Change Canada is responsible for coordinating environmental policies and programs as well as preserving and enhancing the natural environment and renewable resources. The powers, duties and functions of the Minister of the Environment extend to and include matters relating to: preserve and enhance the quality of the natural environment, including water, air, soil, flora and fauna; conserve Canada's renewable resources; conserve and protect Canada's water resources; forecast daily weather conditions and warnings, and provide detailed meteorological information to all of Canada; enforce rules relating to boundary waters; and coordinate environmental policies and programs for the federal government.

Under the Canadian Environmental Protection Act (CEPA 1999), Environment and Climate Change Canada is the lead federal department to ensure the clean-up of hazardous waste and oil spills for which the government is responsible, and to provide technical assistance to other jurisdictions and the private sector as required.

<b>ENVIRONMENT AND CLIMATE CHANGE CANADA</b>	
<input type="checkbox"/> Identify actions required under the Fisheries Act and the Canadian Environmental Protection Act (CEPA).	<b>ENVIRONMENT AND CLIMATE CHANGE</b>
<input type="checkbox"/> Work together with provincial environmental protection agencies.	
<input type="checkbox"/> Provide advice on environmental implications as a result of operational decisions.	
<input type="checkbox"/> Work together with provincial environmental protection agencies.	
<input type="checkbox"/> Assign inspectors where appropriate.	
<input type="checkbox"/> Assist with plume monitoring.	
<input type="checkbox"/> Provide advice on the characteristics of substances and how they might affect human health and environment; weather forecasting and spill modeling to identify where these substances are likely to move in the environment.	
<input type="checkbox"/> Provide sampling and laboratory analytical support.	
<input type="checkbox"/> Advise about clean up technology and techniques.	
<input type="checkbox"/> May develop damage assessment and restoration tools and techniques.	

### *Canadian Environmental Protection Act (CEPA)*

Under the Canadian Environmental Protection Act (CEPA), the Government of Canada is required to take preventive and remedial measures to protect, enhance and restore the environment.

An environmental emergency is defined as an incident that:

1. may have an immediate or long-term harmful effect on the environment or its biological diversity,
2. may constitute a danger to the environment on which human life depends or
3. may constitute a danger in Canada to human life or health.

Any person in Canada who owns or manages a listed substance in a quantity at or over the prescribed minimum quantity is required to provide Environment and Climate Change Canada with information on the quantity of the substance, along with the facility location and an emergency plan. Any existing emergency plan may be used to satisfy the requirements of the regulations.


Environment and Climate Change Canada requires any responsible person who has charge, management or control of substances within a facility in excess of threshold limits listed in Schedule 1 of the Environmental Emergency Regulations to:

- File a declaration with the minister.
- Prepare an environmental emergency (E2) plan.
- Implementation by yearly maintenance and testing of the plan.

### Exemptions

- Amounts temporarily stored for 72 hours or less in a container not normally located at the site.
- Quantities in a container with capacity of 30 kg or less.
- Quantities of substance when it is a component of another substance in Schedule 1.
- Quantities of a substance when it is a component of natural gas.
- A substance that is used to fuel a heating appliance or to generate power at the facility where it is located and is present in a quantity that is less than the quantity set out in column 4 or Part 1 of Schedule 1.
- Quantities of a substance in fuel tank supplying engine of conveyance.
- Quantities of a substance regulated under Transportation of Dangerous Goods Act or the Canada Shipping Act.
- A substance that is in a pipeline located entirely within a province and that is on a property where there are no fixed onshore installations other than pipelines, compressor stations or pump stations.

### Environmental Emergencies Regulations – Quick Reference



### *Overview of Environmental Emergency Regulations Schedules*

The CEPA schedules can be found via the Environment and Climate Change Canada website link found here:

<http://gazette.gc.ca/rp-pr/p2/2019/2019-03-06/html/sor-dors51-eng.html>

The schedules submitted by the company should be reviewed during the annual ERP update to ensure all contact and technical information is correct.

Schedule 1 – List of toxic substances

Schedule 2 – Company name and substances located at a facility

Schedule 3 – E2 Plan preparation

Schedule 4 – E2 Plan brought into effect

Schedule 5 – Full Scale Exercise of E2 plan

Schedule 6 – Notice of change in circumstances (quantity or capacity)

Schedule 7 – Notice of cessation of operations or transfer of ownership

Schedule 8 – Written report of environmental emergency

### *Environmental Emergency (E2) Plan*

The objectives of the Environmental Emergency Regulations (2019) under the Canadian Environmental Protection Act, 1999 are to reduce the frequency and consequences of uncontrolled, unplanned or accidental releases of hazardous substances into the environment. The objective is obtained through proper environmental emergency planning so that companies are able to prevent, prepare for, respond to and recover from an environmental emergency.

#### **Essential Features of an Environmental Emergency (E2) Plan**

The E2 Plan must address the types of emergencies that might reasonably occur, including both on-site and off-site consequences, and the associated prevention, preparedness, response and recovery issues.

Persons involved with an E2 Plan along with their respective roles and responsibilities will have to be identified in the plan.

Environmental emergency plans may address:

- Prevention
- Preparedness
- Response
- Recovery

#### **Prevention Plan**

Preventing environmental emergencies means taking action to reduce or eliminate the environmental risks. The Company recognizes that prevention is by far the most important area for focus.

To qualify as an approved petroleum operator the Company is required to meet strict government standards. These legislated standards govern the construction, maintenance and operations of petroleum assets throughout Canada and help ensure the safe operation of petroleum industry infrastructure, limiting the impact on the public and the environment.

The Company has in place the following key elements of a maintenance program and safety management system:

- The operations are designed and constructed to specific industry standards.
- The Company has preventative maintenance checks and programs that include using: An Owners Inspection Program that meets Boilers Safety Association regulations. This includes a maintenance tracking system to schedule preventative maintenance work.
- The Company is committed to maintaining effective operating procedures and facility documentation.
- Operator competency is reviewed to determine the type and amount of training each employee requires upon hiring.
- Process and procedures are in place to ensure that changes in design, service or staff are effectively managed to minimize impacts on operations.
- Incident investigation and analysis is conducted to minimize reoccurrence of accidents and incidents are tracked through the Company workplace tracking system.
- The Company is committed to conducting regular reviews to assess compliance to standards.

### **Preparedness Plan**

Being prepared for an emergency is critical to mounting a quick and effective response that will help minimize impacts on the health of people and the environment.

The Company's Environmental Emergency Plan will work in partnership with government, other industry members and communities to:

- Identify potential risks and sensitive resource environments.
- Develop contingency plans that outline how to deal with emergencies.
- Train personnel to apply this plan.
- Review and exercise this plan to strengthen their effectiveness and ensure continuous improvement.

The Company has conducted a risk assessment and identified the most reasonable worst-case scenarios to be:

- An uncontrolled release.
- A fire/explosion.

The potential consequences of an emergency may include:

- Negative environmental impact caused by a hazardous substance.
- Serious injury or fatality.

The purpose of an ERP is to establish an action plan structure so that the Company can quickly and effectively respond to an emergency. This ERP outlines the criteria for assessing an emergency situation. The document also lists procedures for mobilizing response personnel (including government agencies) and provides procedures for establishing communication and coordination amongst the vested parties.

Refer to the facilities on-site information/plot plans showing:

- Tanks and vessels.
- Process equipment.
- Worker muster points.
- Safety equipment.
- Fire prevention/protection/suppression/equipment.
- Surface run-off control points and off-lease control points.

- Spill kits.

Facilities also have well marked signs for containers, hazardous substances, operating procedures and site-specific emergency information.

## Response Plan

Key sections in this ERP that define the emergency response protocol include:

- Assessment Matrix for Classifying Incidents
- Roles and Responsibilities
- Command Centres
- Crisis Communication Plan
- Response Action Plans

The roles and procedures to carry out response activities are described in the Roles and Responsibilities section of this manual. The Telephone Directory contains government agency and support service contact information who could be involved in the response to an environmental emergency. The stakeholder information in the Field Specific Section identifies members of the public or industry that could be affected by an environmental emergency. Each site-specific section also contains an area summary. The area summary includes pertinent area information that may be relevant during an environmental emergency such as topography, spill receptors, and land use.

When it comes to environmental emergencies, no single organization can do it all. Effective emergency response requires teamwork among industry, governments, communities and local organizations.

Environment and Climate Change Canada's Emergency officers have HAZMAT (Hazardous Materials) expertise, backed by scientific support, which enables response in the event of spills involving hazardous materials. The role of Environment and Climate Change Canada's environmental emergency response team is to provide advice and support on:

- Hazardous material properties, behaviour, fate and environmental effects.
- Spill-behaviour and spill-movement modeling using the latest-generation models and techniques.
- Training in personnel protection at pollution emergencies.
- Advice and direct support on state-of-the-art, on-site monitoring of human and environmental hazard levels at pollution emergencies.
- Sample collection at spill sites.
- The contract administration of airborne services for the remote sensing of spills.
- The evaluation of spill countermeasures, particularly those relating to containment and recovery, treatment and disposal techniques.
- Priority assessment for shoreline protection and clean-up using its Shoreline Clean-up and Assessment Technique (SCAT).

## Recovery Plan

It is important to clean-up and recover from environmental damage after an emergency. Environmental damage is the impact pollution causes to the bio-physical environment. It can affect survival, growth, reproduction, behaviour, community composition, ecological process functions, physical and chemical habitat quality and structure. There can also be impacts on socio-economic services.

The two key parts of recovery are environmental damage assessment and restoration. The Company's end goal is to restore the environment after a spill.

The Company will shut-in the impacted facility, assess and respond to the environmental impacts in compliance with regulation. The Company will conduct an assessment of the incident with the appropriate government agencies to decide if the site is safe for operations to continue. The Company will ensure the site is safe for normal work resumption. Workers affected by the incident will be informed of work resumption dates and times. Work resumption, investigation and critical incident stress debriefing procedures are outlined in the Post Emergency section of this manual.

Once the immediate emergency has ended and the initial clean-up has been done, there may be lingering environmental impacts. Recovery activities are designed to examine these possible impacts through damage assessment. During this phase, the Company will determine the nature and extent of the environmental pollution and develop strategies to restore injured natural resources, ecological service flows and socio-economic service flows.

### ***ERP Exercises and Training***

CEPA E2 regulations require that an E2 plan be updated and tested at least once each calendar year by a simulation exercise in respect of one substance from each of the hazard categories referred to in column 5 of Parts 1 and 2 of Schedule 1, using an environmental emergency identified under paragraph 4(2)(d) as the emergency being simulated. Environment and Climate Change Canada recognizes that a full-scale simulation exercise may not be achievable every year. Therefore, facilities may conduct a full-scale simulation exercise at least once within a five-year period must respect the yearly testing requirement by testing different components of their E2 plan at least once each calendar year.

The exercise design process for E2 training must be composed of the following four main steps:

- 1) Planning the annual ERP exercise;
- 2) Conducting the exercise;
- 3) Evaluating and reporting on the outcomes; and
- 4) Correcting and updating the E2 plan.

Testing must reflect a credible type of environmental emergency that can be reasonably be expected to occur for the place in question and that would likely cause harm to the environment or constitute a danger to human life or health. Testing or exercising enables critical aspects of the plan to be examined in a structural way, simulating conditions to reveal major mistakes and / or omissions so that they can be subsequently corrected before real emergencies occur. Once every five years a Major exercise must be held on the regulated site and should test their facilities' E2 plan. Documentation of all exercises must be kept for a period of seven years.

**Simulation Exercise** means an exercise simulating the response to an environmental emergency involving the release of a substance.

**Full-Scale Simulation Exercise** means an action-based simulating exercise requiring the deployment of personnel, resources and equipment.

### **Record of Simulation Exercise**


After each Simulation Exercise is conducted in relation to the environmental emergency plan, a responsible person must prepare a record that contains the date, a summary and the results of the simulation exercise and any modifications to be made to the plan as a result of the simulation exercise.

### **Notice – Simulation Exercises Conducted**

A responsible person must, within five years after the day on which the environmental emergency plan is brought into effect, submit a notice to the Minister containing the information referred to in

Schedule 5 concerning the simulation exercises conducted in relation to an environmental emergency plan.

**Training Cycle**



### *CEPA Compliance and Enforcement*

Environment and Climate Change Canada may request copies of environmental emergency plans. In addition to facility visits by enforcement officers, violations of CEPA Sections 199 and 200 may result in warnings, directions, compliance orders, and prosecution.

### *Environmental Emergencies Program*

The Environmental Emergencies Program protects Canadians and their environment from the effects of environmental emergencies through the provision of science-based expert advice and regulations. The Environmental Emergencies Program provides expert advice during the environmental assessment process of large development projects to improve mitigation measures that prevent accidents from occurring and improve emergency response plans so that effective and timely actions can be taken when accidents occur.

**Note:** The Federal government and Provinces have reciprocal harmonization agreements to share information as required to protect human life, health and environmental protection.

### **Who to Contact:**

<b>Province</b>	<b>Agency</b>
Alberta	Alberta Ministry of Environment and Parks
British Columbia	Emergency Management British Columbia – Ministry of Justice
Saskatchewan	Saskatchewan Ministry of Environment
Manitoba	Manitoba Agriculture and Resource Development – Petroleum Branch

**9.4.3 Department of Fisheries and Oceans (DFO)**

The department within the government of Canada that is responsible for developing and implementing policies and programs in support of Canada's economic, ecological and scientific interests in oceans and inland waters. Its mandate includes responsibility for the conservation and sustainable use of Canada's fisheries resources while continuing to provide safe, effective and environmentally sound marine services that are responsive to the needs of Canadians in a global economy.

Any amount of hydrocarbons entering a waterway frequented by fish or occupied by waterfowl is deemed to be in contravention of the Federal Fisheries Act and must be reported to the Department of Fisheries and Oceans.

<b>DEPARTMENT OF FISHERIES AND OCEANS</b>	
<input type="checkbox"/> Design and develop related regulations, policies, strategies and tools.	<b>DFO</b>
<input type="checkbox"/> Review, assess and monitor activities associated with fish habitat to ensure their compliance with the Fisheries Act and Species at Risk Act.	
<input type="checkbox"/> Conduct environmental assessments under the Canadian Environmental Assessment Act.	
<input type="checkbox"/> Design, develop, and implement communication and education strategies.	
<input type="checkbox"/> Work together with provincial environment protection agencies.	
<input type="checkbox"/> Receive notification from Environment and Climate Change Canada.	
<input type="checkbox"/> May send personnel to the site if there has been or could potentially be an impact to fish or fish habitat.	
<input type="checkbox"/> Work closely with Environment and Climate Change Canada, The Canadian Coast Guard and other provincial environmental agencies.	

**9.4.4 Public Safety Canada**

Public Safety Canada formerly known as Public Safety and Emergency Preparedness Canada, legally incorporated as the federal Department of Public Safety and Emergency Preparedness, is the department of the government of Canada with responsibility for protecting Canadians and helping to maintain a peaceful and safe society.

Public Safety Canada houses the Government Operations Centre at the hub of the national emergency management system. The Government Operations Centre is an advanced centre for monitoring and coordinating the federal response to an emergency.

In the event of a large-scale natural disaster where response and recovery costs exceed what individual provinces and territories could reasonably be expected to bear on their own, Public Safety Canada provides financial assistance to the provincial and territorial governments through the Disaster Financial Assistance Arrangements (DFAA). Assistance is paid to the province or territory – not directly to individuals or communities. The provincial or territorial governments design, develop, and deliver disaster financial assistance, determining the amounts and types of assistance that will be provided to those who have experienced losses.

<b>PUBLIC SAFETY CANADA</b>	
<input type="checkbox"/> Ensure first responders and emergency management personnel are well-prepared through education, support, and exercises.	<b>PUBLIC SAFETY</b>
<input type="checkbox"/> Work with provincial response agencies.	
<input type="checkbox"/> Monitor and coordinate the Federal response to an emergency.	
<input type="checkbox"/> Provide financial assistance to the provincial and territorial governments through the Disaster Financial Assistance Arrangements (DFAA).	

### 9.4.5 Transport Canada – Transportation of Dangerous Goods

The department within the government of Canada which is responsible for developing regulations, policies and services of transportation in Canada. It is part of the Transportation, Infrastructure and Communities (TIC) portfolio. The federal Transportation of Dangerous Goods (TDG) Regulations regulate the transportation of dangerous goods for the road, rail, air and marine transport modes.

The purpose of the TDG legislation is to reduce the risk to emergency response personnel, the public and the environment. One secondary objective is to collect data on accidents which involve dangerous goods either directly or indirectly. This data will allow the measurement of the influence of this legislation on safety.

The Surface Transport Dangerous Goods Directorate of Transport Canada may assume federal Lead Agency status for land-based spills involving rail cars or tank trucks. It also administers and enforces the requirements of the Transportation of Dangerous Goods (TDG) Act following a transportation emergency incident.

The Marine Safety Branch also administers and enforces the pollution provisions and regulations of the Canada Shipping Act (CSA) and has the legal authority to board vessels, draw samples, and collect evidence. This work is performed by an authorized Pollution Prevention Officer.

Transport Canada also staffs and manages the Canadian Transport Emergency Centre (CANUTEC) which provides 24-hour advice on chemical spill response, TDG requirements, and also serves as a 24-hour emergency reporting centre for hazardous materials incidents anywhere in Canada. The Directorate's overall mandate is to promote public safety in the transportation of dangerous goods by all modes.

Federal regulations require that CANUTEC be contacted in the event of an incident or accident involving dangerous goods and infectious substances.

CANUTEC staff does not go to the site of an incident, however, should on-site assistance be required, CANUTEC can assist in the implementation or industry Emergency Response Assistance Plans.

<b>TRANSPORT CANADA</b>	
<input type="checkbox"/>	Regulate the handling, offering for transport and the transport of dangerous goods by all modes in order to ensure public safety.
<input type="checkbox"/>	Maintain a 24-hour emergency telephone service.
<input type="checkbox"/>	Assist emergency response personnel in handling dangerous good emergencies.
<input type="checkbox"/>	Provide advice on chemical, physical and toxicological properties and incompatibilities of the dangerous goods.
<input type="checkbox"/>	Provide advice on health, hazards, and first aid.
<input type="checkbox"/>	Provide advice on fire, explosion, spill, or leak hazards.
<input type="checkbox"/>	Provide advice on remedial actions for the protection of life, property, and the environment.
<input type="checkbox"/>	Provide advice on evacuation distances.
<input type="checkbox"/>	Provide advice on personal protective clothing and decontamination.
<input type="checkbox"/>	Provide communication links with the appropriate industry, government, or medical specialists.

**TRANSPORT CANADA**

### *CANUTEC – Public Safety Measures*

CANUTEC is the Canadian Transport Emergency Centre operated by the Transportation of Dangerous Goods (TDG) Directorate of Transport Canada. The Directorate's overall mandate is to promote public safety in the transportation of dangerous goods by all modes. CANUTEC was established in 1979 and is one of the major safety programs Transport Canada delivers to promote the safe movement of people and goods throughout Canada.

The 2020 Emergency Response Guidebook (ERG2020) was developed, in an international effort between Argentina, Canada, Mexico and the United States for use by fire fighters, police, and other emergency services personnel who may be the first to arrive at the scene of a transportation incident involving dangerous goods. It is primarily a guide to aid first responders in quickly identifying the specific or generic hazards of the material(s) involved in the incident and protecting themselves and the general public during the initial response phase of the incident. For the purposes of the ERG2020, the "initial response phase" is that period following arrival at the scene of an incident during which the presence and/or identification of dangerous goods is confirmed, protective actions and area securement are initiated, and assistance of qualified personnel is requested. It is not intended to provide information on the physical or chemical properties of dangerous goods.

The ERG2020 is designed to assist responders in making initial decisions upon arriving at the scene of a dangerous goods incident. It should not be considered as a substitute for emergency response training, knowledge or sound judgment. ERG2020 does not address all possible circumstances that may be associated with a dangerous goods incident. It is primarily designed for use at a dangerous goods incident occurring on a highway or railroad. Be mindful that there may be limited value in its application at fixed facility locations.

In the event of an emergency involving dangerous goods, call CANUTEC at 1-888-CAN-UTEC (226-8832), 613-996-6666 or \*666 on a cellular phone. CANUTEC's emergency response advisors provide immediate advice over the phone about the actions to take and to avoid during a dangerous goods emergency. They can also send technical information to local authorities responsible for responding to emergencies by email or fax during an incident.

ID No.	Guide No.	Name of Material	Public Safety (Immediate precautionary measures)	Evacuation						
				Large Spill			Fire			
1971	115	<ul style="list-style-type: none"> <li>Methane</li> <li>Methane, compressed</li> <li>Natural gas, compressed</li> </ul>	100 m (330 ft)	Consider initial downwind evacuation for at least 800 metres (1/2 mile)						
1075	115	<ul style="list-style-type: none"> <li>Butane</li> <li>Liquefied Petroleum Gas (LPG)</li> <li>Propane</li> <li>Propane mixture</li> </ul>	100 m (330 ft)	Consider initial downwind evacuation for at least 800 metres (1/2 mile)						
1071	119	<ul style="list-style-type: none"> <li>Oil gas</li> <li>Oil gas, compressed</li> </ul>	100 m (330 ft)	Increase, in the downwind direction, as necessary, the isolation distance shown under "PUBLIC SAFETY".						
1267	128	<ul style="list-style-type: none"> <li>Petroleum crude oil</li> </ul>	50 m (150 ft)	Consider initial downwind evacuation for at least 300 metres (1000 ft).						
1114	130	<ul style="list-style-type: none"> <li>Benzene</li> </ul>	50 m (150 ft)	Consider initial downwind evacuation for at least 300 metres (1000 ft).						
ID No.	Guide No.	Name of Material	Public Safety (Immediate precautionary measures)	Initial Isolation and Protective Action Distances						Fire
				Small Spills			Large Spills			
				First Isolate in all directions	Then protect persons downwind during		First Isolate in all directions	Then protect persons downwind during		
Day	Night	Day	Night							
1053	117	<ul style="list-style-type: none"> <li>Hydrogen Sulphide</li> </ul>	100 m (330 ft)	30 m	0.1 km	0.4 km	400 m	2.1 km	5.4 km	If tank, rail car or tank truck is involved in a fire, ISOLATE for 1600 meters (1 mile) in all directions; also, consider initial evacuation for 1600 meters (1 mile) in all directions.
3494	131	<ul style="list-style-type: none"> <li>Petroleum sour crude oil, flammable, toxic</li> </ul>	50 m (150 ft)	30 m	0.1 km	0.2 km	60 m	0.5 km	0.7 km	If tank, rail car or tank truck is involved in a fire, isolate for 800 metres (1/2 mile) in all directions; also, consider initial evacuation for 800 metres (1/2 mile) in all directions.
1017	124	<ul style="list-style-type: none"> <li>Chlorine</li> </ul>	100 m (330 ft)	60 m	0.3 km	1.1 km	See table below			If tank, rail car or tank truck is involved in a fire, isolate for 800 metres (1/2 mile) in all directions.

Toxic Inhalation Hazardous Materials	Transport Container	First ISOLATE in all Directions	Initial Isolation and Protective Action Distances					
			Day			Night		
			Low wind < 6 mph = < 10 km/h	Moderate wind 6-12 mph = 10 - 20 km/h	High wind > 12 mph = > 20 km/h	Low wind < 6 mph = < 10 km/h	Moderate wind 6-12 mph = 10 - 20 km/h	High wind > 12 mph = > 20 km/h
Chlorine (UN 1017) Sulphur Dioxide (UN 1079)	Rail Tank Car	1000 m (3000 ft)	9.9 km (6.2 mi)	6.4 km (4.0 mi)	5.1 km (3.2 mi)	11+ km (7+ mi)	9.0 km (5.6 mi)	6.7 km (4.2 mi)
	Highway tank truck or trailer	600 m (2000 ft)	5.8 km (3.6 mi)	3.4 km (2.1 mi)	2.9 km (1.8 mi)	6.7 km (4.3 mi)	5.0 km (3.1 mi)	4.1 km (2.5 mi)
	Multiple ton cylinders	300 m (1000 ft)	2.1 km (1.3 mi)	1.3 km (0.8 mi)	1.0 km (0.6 mi)	4.0 km (2.5 mi)	2.4 km (1.5 mi)	1.3 km (0.8 mi)
	Multiple small cylinders or single ton cylinder	150 m (500 ft)	1.5 km (0.9 mi)	0.8 km (0.5 mi)	0.5 km (0.3 mi)	2.9 km (1.8 mi)	1.3 km (0.8 mi)	0.6 km (0.4 mi)

Emergency Response Guidebook  
U.S. Department of Transportation, Pipeline and Hazardous Materials Safety Administration, Transport Canada, Secretariat of Transport and Communications, 2020

### **Reporting Requirements**

The Transportation of Dangerous Goods Act, 1992 (TDG Act) requires reporting dangerous goods incidents which meet or exceed established reporting criteria listed in the Transportation of Dangerous Goods Regulations (TDG Regulations).

#### **Who should report:**

The report must be made by the person who has the charge, management or control of a means of containment (e.g. a driver, a company representative, a shipmaster, a train operator etc.) at the time of the incident if the release or anticipated release (e.g. spills, accidents), loss or theft of dangerous goods that is or could be in excess of a quantity or concentration specified by regulation from the means of containment if it endangers, or could endanger, public safety.

#### **When to report:**

Part 8 of the TDG Regulations (Reporting Requirements) requires a number of different report types. When certain conditions are met, persons subject to the TDG Regulations must submit one of the report types below.

##### Reports for the Transport of Dangerous Goods by Road, Rail and Marine


- Emergency Report – Road, Rail or Marine (Section 8.2 of the TDG Regulations)
- Release or Anticipated Release Report – Road, Rail or Marine (Section 8.4 of the TDG Regulations)
- 30-Day Follow-Up Report (Section 8.6 of the TDG Regulations)

##### Reports for the Transport of Dangerous Goods by Air


- Dangerous Goods Accident or Incident Report — Air (Section 8.9 of the TDG Regulations)
- 30-Day Follow-up Report (Section 8.11 of the TDG Regulations)
- Undeclared or Mis-declared Dangerous Goods Report (Section 8.14 of the TDG Regulations)

##### Reports Relating to Security – All Modes of Transport

- Loss or Theft Report (Section 8.16 of the TDG Regulations)
- Unlawful Interference Report (Section 8.18 of the TDG Regulations)

**Emergency Report – Road, Rail or Marine Transport**

## Release or Anticipated Release Report - Road, Rail or Marine



### *Transportation of Dangerous Goods ERAP*

The TDG Act requires any person importing or offering for transport certain higher risk dangerous goods (for example chlorine, propane, crude oil) in quantities specified by the TDG Regulations to have an approved Emergency Response Assistance Plan (ERAP) and ERAP number.

The ERAP number is found on the shipping document. If you call the ERAP telephone number, you will be connected with someone who can implement the plan. They will: provide technical and/or emergency response advice promptly.

An ERAP describes what to do in the event of a release or anticipated release of certain higher-risk dangerous goods while they are in transport. The plan is intended to assist local emergency responders by providing them with technical experts and specially trained and equipped emergency response personnel at the scene of an incident.

ERAPs may be used along with emergency response plans from other organizations (for example, carriers and local or provincial authorities). An incident management system, usually the Incident Command System (ICS), ensures coordination between the ERAP and other emergency response plans.

### 9.4.6 Transportation Safety Board

The Transportation Safety Board of Canada (TSB) has a mandate to advance transportation safety in the marine, pipeline, rail and air modes of transportation.

The CER and the TSB have adopted a single window reporting approach for inter-provincial or cross border pipelines. The new Online Event Reporting System (OERS) automates the single-window pipeline occurrence notification process that was established by the TSB and the CER.

#### Roles and Responsibilities

<b>TRANSPORTATION SAFETY BOARD</b>	
<input type="checkbox"/>	Conduct independent investigations, including public inquiries when necessary, into selected transportation occurrences in order to make findings as to their causes and contributing factors.
<input type="checkbox"/>	Identify safety deficiencies, as evidenced by transportation occurrences.
<input type="checkbox"/>	Make recommendations designed to eliminate or reduce any such safety deficiencies.
<input type="checkbox"/>	Report publicly on their investigations and on the findings in relation thereto.

TSB

#### TSB Pipeline Occurrence Reporting

##### Requirement to Report

A "pipeline occurrence" must be reported if it results directly from the operation of the pipeline, where

1. a person is killed or sustains a serious injury;
2. the safe operation of the pipeline is affected by
  1. damage sustained when another object came into contact with it, or
  2. a fire or explosion or an ignition that is not associated with normal pipeline operations;
3. an event or an operational malfunction results in
  1. an unintended or uncontrolled release of gas,
  2. an unintended or uncontrolled release of HVP hydrocarbons,
  3. an unintended or uncontained release of LVP hydrocarbons in excess of 1.5 m<sup>3</sup>, or
  4. an unintended or uncontrolled release of a commodity other than gas, HVP hydrocarbons or LVP hydrocarbons;
4. there is a release of a commodity from the line pipe body;
5. the pipeline is operated beyond design limits or any operating restrictions imposed by the Canada Energy Regulator;
6. the pipeline restricts the safety operation of any mode of transportation;
7. an unauthorized third-party activity within the safety zone poses a threat to the safe operation of the pipeline;
8. a geotechnical, hydraulic or environmental activity poses a threat to the safe operation of the pipeline;
9. the operation of a portion of the pipeline is interrupted as a result of a situation or condition that poses a threat to any person, property or the environment; or
10. an unintended fire or explosion has occurred that poses a threat to any person, property or the environment.

Source: [Transportation Safety Board Regulations Section 4\(1\)](#)

**Input the information you have as soon as possible after the occurrence**

As soon as possible after the occurrence, enter the information you have about it into the Online Event Reporting System (OERS). When the information is submitted, the OERS will automatically notify the TSB and the CER.

Information must be entered in the OERS even if you have reported the occurrence by telephone.

Enter factual information only. Information that is considered a witness statement and/or personal information must not be entered in the OERS.

**Submit additional information as soon as available**

Provide the remainder of the information required by the TSB through the OERS as soon as it becomes available and no later than 30 days after the occurrence.

If you have any questions or concerns about using the Online Event Reporting System for reporting occurrences to the TSB, call the TSB.

**Online Event Reporting System (OERS)**

<https://apps.cer-rec.gc.ca/ERS/Home/Index/>

### 9.4.7 Health Canada

Health Canada is the department of the Government of Canada with responsibility for national public health.

<b>HEALTH CANADA</b>	
<input type="checkbox"/> Communicates information about health and wellness and disease prevention to protect Canadians from avoidable risks.	<b>HEALTH CANADA</b>
<input type="checkbox"/> During a health emergency or disaster, Health Canada and the Public Health Agency of Canada are responsible for supporting emergency health and social services in the provinces and territories.	
<input type="checkbox"/> Work collaboratively with the provinces and territories to test ways in which the Canadian health care system can be improved and ensure its sustainability for the future.	

### 9.4.8 Public Health Agency of Canada

Public Health Agency of Canada is an agency of the Government of Canada that is responsible for public health, emergency preparedness, and response and infectious and chronic disease control and prevention.

In an emergency situation, the Office of Emergency Response Services (OERS) is responsible for supporting emergency health and social services in the provinces, territories, or abroad. It manages the National Emergency Stockpile System (NESS), which includes medical, pharmaceutical and related emergency supplies.

<b>PUBLIC HEALTH AGENCY OF CANADA</b>	
<input type="checkbox"/> Facilitate national approaches to public health policy and planning.	<b>PUBLIC HEALTH</b>
<input type="checkbox"/> If a public health emergency grows beyond one province and/or territory activate response actions.	
<input type="checkbox"/> Deploy health emergency response teams (HERT) as part of the federal response to emergencies that have health repercussions.	
<input type="checkbox"/> Work with Health Canada to test ways in which the Canadian health care system can be improved and ensure its sustainability for the future.	

### 9.4.9 Indigenous Services Canada (ISC)

The department of the Government of Canada with responsibility for policies relating to Indigenous peoples in Canada, that comprise the First Nations, Inuit, and Metis.

<b>INDIGENOUS SERVICES CANADA</b>	
<input type="checkbox"/> Ensure that the First Nation communities have emergency management services comparable to those of Canadian in similar situations.	<b>ISC</b>
<input type="checkbox"/> Work to establish an all-hazard approach for responding to emergencies that impact First Nation communities.	
<input type="checkbox"/> Mitigation of the effects of emergencies on First Nations reserves for which the department has legal responsibility, including arrangements for community evacuation, temporary shelter, and provision of territorial support.	
<input type="checkbox"/> Coordination of federal assistance and response to emergencies in response to requests from territorial government authorities.	
<input type="checkbox"/> Provide funding to cover costs related to emergency assistance in First Nations communities.	
<input type="checkbox"/> Mitigate the effects of an emergency on First Nationals people in the area.	
<input type="checkbox"/> Work with the Chief and Council to assess the situation, determine the most effective way to report damage.	
<input type="checkbox"/> Work with the Chief and Council to assess the situation, determine the most effective way to repair damage and ensure delivery of programs and services to the community.	

#### ***9.4.10 Indian Oil and Gas Canada***

Indian Oil and Gas Canada's (IOGC) mandate is to further First Nation initiatives to manage and control their oil and gas resources (i.e. governance).

According to the Indian Oil and Gas Regulations, every operator must adhere to all provincial laws applicable to non-Indian lands. This includes the environment, exploration, development, treatment, conservation or equitable production of oil and gas and that are not in conflict with the (Indian Oil and Gas) Act or Regulations.

**Note:** First Nations reserves and Métis settlements within the EPZ are considered to be local authorities and are required to be notified and consulted as a local authority.

#### ***Indian Oil and Gas Spill Reporting Regulations***

Indian Oil and Gas Canada, the First Nation and the provincial authority must be notified immediately in the event of any health or environment-threatening emergency or off-lease spills on First Nation reserve lands. On-lease spills greater than 1 m<sup>3</sup> must be reported to Indian Oil and Gas Canada (IOGC) immediately.

#### **9.4.11 ERAC – A Not-For Profit Organization**

Emergency Response Assistance Canada (ERAC) is a not-for-profit corporation created by industry for industry and is a subsidiary of the Canadian Propane Association (CPA). As a co-operative emergency preparedness and response organization, ERAC is instrumental in assisting hundreds of industry and transportation organizations requiring Emergency Response Assistance Plans (ERAPs).

ERAC's Emergency Response Assistance Plan (ERAP) provides emergency response support to road, rail and stationary tank incidents for vessels.

#### **ERAC Response TDG (ERAP) and CEPA (E2)**

ERAC's emergency responders are available 24/7 through their Emergency Call Centre (ECC) telephone number.

When the ECC number has been called, the Emergency Call Centre Operator (ECCO) connects with a Home Base Coordinator (HBC) to provide details on the incident. The HBC assesses the situation based on the information provided and then determines the closest Remedial Measures Advisor (RMA) or Technical Advisor (TA) to be sent to the scene of the emergency. A response team may be dispatched if necessary. If your company is involved in an emergency, the HBC will contact you for permission to implement the plan.

#### **Home Base Coordinator**

The Home Base Co-ordinator (HBC) performs the vital function of keeping the ECCO, RMA's, TA's response teams once they assess the situation based on the information that is provided by the ECCO. Their role then throughout is provide constant communication to your company designate(s). This starts from the moment ERAC gets the call and continues until the emergency has been handled successfully. If your company is involved in an emergency, the HBC will contact you for permission to activate the plan.

#### **Remedial Measures Advisors and Technical Advisors – First on the scene**

Once the RMA or Technical Advisor is determined which is based on geographic location to the incident the arrival time is an estimated 6 hours or less from the original callout to being on-site. Once at scene this role provides technical and product subject matter expertise by providing advice and assistance in handling the incident. In some instances, they may also conduct minor repairs.

#### **Response Teams – Hand on expertise**

These teams will be activated if necessary and dispatched through the HBC. Once activated they'll bring all necessary equipment and expertise to perform remedial measures. ERAC emergency responders are experts in initial containment, confinement, transferring, flaring products and purging LPG and flammable liquids containers.

### ERAP Response

Who completes the following tasks, the Plan Participant and / or the ERAC?

Question	Answer
1. Secure accident site upon arrival?	ERAC
2. Call ERAC to advise of Incident by phone and take direction from Home Base Co-ordinator?	Plan Participant
3. Conduct site assessment to identify hazards?	ERAC
4. Implement emergency response procedures as outlined in the ERAP?	ERAC
5. Conduct formal accident assessment (including inspect damaged transport vehicle, etc.)?	ERAC
6. Notify appropriate regulatory authorities? Answer: Person(s) in care and control e.g. Trucker.	Plan Participant
7. Contact local residents?	Plan Participant
8. Transfer dangerous goods from damaged containment?	ERAC
9. Responsible for obtaining and providing the recovery means of containment (e.g. Truck tank(s) or Rail car(s))?	Plan Participant
10. Person (s) responsible for any communications e.g. Media, public, corporate?	Plan Participant
11. Provides transportation to incidents which cannot be accessed by land. (e.g. barge offshore)?	Plan Participant

### ERAP Tiered response levels

Two response tiers are based on the level of response needed to address the release or anticipated release of dangerous goods.

A person who implements an ERAP to tier 1 must:

- provide technical or emergency response advice as soon as possible after a request for advice; and
- remotely monitor the response to the release or anticipated release.

A person who implements an ERAP to tier 2 must:

- provide technical or emergency response advice as soon as possible after a request for advice;
- monitor the response to the release or anticipated release; and
- send ERAP emergency response resources to the location of the release or anticipated release.

### ERAP implementation report

Each time an ERAP is implemented to tier 1 or tier 2, an ERAP implementation report must be made by the person listed in the ERAP to the Canadian Transport Emergency Centre (CANUTEC) at 1-888-CANUTEC (1-888-226-8832) or 613-996-6666 as soon as possible.

### ERAP Response Parameters

As Canada's emergency preparedness and response organization, ERAC assists Plan Participant members who transport specified products by road or rail, or those who store these products in tanks with capacities of 450 litres or greater. See link for details on ERAP specified products <https://erac.org/en/services/emergency-response-assistance-plans/>

## 9.5 CANADA ENERGY REGULATOR

The Canada Energy Regulator (CER) is an independent federal agency established to regulate international and interprovincial aspects of the oil, gas and electric utility industries.

CER-regulated companies have the primary responsibility for ensuring safety and environmental protection because they are the owners, designers, builders and operators of the facilities. The CER recognizes this responsibility in the ongoing development of goal-oriented regulation that places the onus on companies to ensure their facilities are safe and secure and are operated in an environmentally responsible manner. The CER plays a significant role by ensuring that the companies maintain or improve their safety and environmental performance. The CER ensures that companies:

- Identify and manage the potential hazards associated with their facilities and operations.
- Conduct a risk analysis of those hazards.
- Eliminate, reduce and manage the risks in order to protect the public and regulated company personnel, the safety and security of the facilities and operations, and the protection of property and the environment.

All companies under the CER's jurisdiction are responsible for developing and maintaining an Emergency Response and Preparedness Program generically referred to as "Emergency Management Program" for all aspects of their operations. In the event an emergency occurs, the regulated company is responsible for responding to the emergency and coordinating emergency response activities.

- That result in death or serious injury.
- Involve a significant release of hydrocarbons.
- Could result in potential or real impact due to loss of service.
- Attract significant media attention.
- On the advice of Natural Resources Canada (NRCan) or other federal Agencies.

All inter-provincial and cross border pipelines are regulated by the CER and require an Emergency Response Plan. To fully comply with the CER Onshore Pipeline Regulations (OPR) and meet CER expectations for an effective emergency preparedness program, NorthRiver is required to have an emergency procedures section for the field operations and conduct emergency response training and exercises.

### 9.5.1 Contact Information

All incidents, accidents and occurrences as defined by the Onshore Pipeline Regulations (OPR), the Canada Labour Code, and the Transportation Safety Board (TSB) Regulations should be reported.

<b>CALL</b>
For emergencies involving inter-provincial or cross border pipelines, the CER is the Regulatory Authority. In the event of a CER regulated pipeline emergency, call the TSB's 24-hour hotline (collect calls accepted). The TSB will contact the CER to notify them of the incident.
<b>1-819-997-7887</b>

<b>ONLINE REPORTING</b>
Report all events on the CER's Online Event Reporting System.
This system is intended for use by regulated companies to provide notification to the Canada Energy Regulator (CER) and Transportation Safety Board (TSB) of various events that are defined in regulation including incidents, unauthorized activities, and operations and maintenance activities.
<b><a href="https://apps.cer-rec.gc.ca/ers/home/index">https://apps.cer-rec.gc.ca/ers/home/index</a></b>

### 9.5.2 Roles and Responsibilities

<b>CANADA ENERGY REGULATOR</b>	<b>CANADA ENERGY REGULATOR</b>
<input type="checkbox"/> Monitors, observes and assesses the overall effectiveness of the company's emergency response in terms of: <ul style="list-style-type: none"> <li>• Emergency Management</li> <li>• Safety</li> <li>• Security</li> <li>• Environment</li> <li>• Integrity of operations and facilities, and</li> <li>• Energy Supply.</li> </ul>	
<input type="checkbox"/> Investigates the event, either in cooperation with the Transportation Safety Board of Canada, under the Canada Labour Code, or as per the Canada Energy Regulator Act or Canada Oil & Gas Operations Act (whichever is applicable).	
<input type="checkbox"/> Inspects the pipeline or facility.	
<input type="checkbox"/> Examines the integrity of the pipeline or facility.	
<input type="checkbox"/> Requires appropriate repair methods are being used.	
<input type="checkbox"/> Requires appropriate environmental remediation of contaminated areas is conducted.	
<input type="checkbox"/> Coordinate stakeholders and Indigenous community feedback regarding environmental clean-up and remediation.	
<input type="checkbox"/> Confirms that a company is following its Emergency Procedures Manual(s), commitments, plans, procedures, and CER regulations and identifies non-compliances.	
<input type="checkbox"/> Initiates enforcements action as required.	
<input type="checkbox"/> Approves the restart of the pipelines.	

### 9.5.3 CER Definitions of Incident and Emergency

#### Incident

Incidents and releases reportable to the CER under sections 1 and 52 of the OPR are:

- The death of or serious injury to a person.
- A significant adverse effect on the environment.
- Unintended fire or explosion.
- Unintended or uncontained release of low-vapour pressure (LVP) hydrocarbons in excess of 1.5 m<sup>3</sup>.
- Unintended or uncontained release of gas or high-vapour pressure (HVP) hydrocarbons.
- Operation of a pipeline beyond its design limits as determined under CSA Z662, CSA Z276 or any operating limits imposed by the CER.

Although incidents are defined in the OPR, it is also necessary for companies to have a clear understanding of what constitutes incidents and emergencies at their facilities, as well as methods or procedures for determining the magnitude and levels of an emergency as circumstances change.

#### Emergency

Can/CSA – Z731 and CSA Z246 defines an emergency as “a present or imminent event that requires prompt co-ordination of actions or special regulation of persons or property to protect the health, safety or welfare of people or to limit damage to property and the environment”.

Companies must consider all probable emergencies and have applicable procedures in place to deal with potential effects and treats to people, property and the environment, as determined through a formal hazard assessment.

Level 1	Level 2	Level 3
<ul style="list-style-type: none"> <li>• No effects outside company property</li> <li>• Control of Hazardous substance completed or pending</li> <li>• No immediate threat to the public or company personnel</li> <li>• Minimal environmental effects</li> <li>• Incident/Spill handled by company personnel</li> <li>• Low potential to escalate</li> </ul>	<ul style="list-style-type: none"> <li>• No immediate threat outside company property but potential exists to extend beyond property boundaries</li> <li>• Outside services and government agencies likely to be directly involved</li> <li>• Imminent control of hazardous substance probable</li> <li>• Some injury or threat to the public and company personnel</li> <li>• Moderate environmental effects</li> </ul>	<ul style="list-style-type: none"> <li>• Serious injury to the public and company personnel and ongoing threat to the public</li> <li>• Uncontrolled release of hazardous substance continuing</li> <li>• Significant and ongoing environmental effects</li> <li>• Immediate and significant government agency involvement</li> <li>• Assistance from outside parties required</li> <li>• Effects extend beyond company property</li> </ul>

#### 9.5.4 CER Event Reporting

The task of completing the notifications will be completed by the Company's EOC Liaison Officer. The Transportation Safety Board of Canada (TSB) has the option to choose to be the lead investigator for determining the cause and contributing factors leading to an incident/ emergency. For the CER's Event Reporting Guidelines, please refer to the following:

*Canada Energy Regulator Event Reporting Guidelines Revised October 2020*

<https://www.cer-rec.gc.ca/bts/ctrq/gnnb/rprtnggdlns/index-eng.html>

#### **Canada Energy Regulator Online Event Reporting System (OERS)**

<https://apps.cer-rec.gc.ca/ers>

#### *Precautionary Approach*

It is the CER's expectation that each company take a precautionary approach to the reporting of events. This means that even if there is some doubt as to whether an event should be reported, the company is to report the event. In other words, companies should adopt a "when in doubt, report" approach. This approach to event reporting is consistent with CER-regulated companies' responsibility for anticipating, preventing, mitigating and managing incidents of any size or duration.

The CER's Online Event Reporting System (OERS) now contains a field where the company must indicate that it is reporting an incident on a precautionary basis. In these cases, the CER will determine whether the incident is reportable based on information provided by the company. In cases where an event was reported using the precautionary approach and subsequent information indicates that it was not reportable, the CER records will reflect this and the event will not be included on the company's compliance record and will not be posted on the CER Interactive Incident Map.

#### *Immediately Reportable Events*

Where regulations require an event to be reported "immediately", companies must also consider whether the event meets any of the following definitions:

- An Incident that Harms People or the Environment:
  - a death;
  - a serious injury (as defined in the OPR or TSB regulations);
  - an unintended or uncontrolled LVP hydrocarbon release in excess of 1.5 m<sup>3</sup> that leaves company property or occurs on or off the right of way;
  - an unintended or uncontrolled sweet natural gas or HVP release >30,000 m<sup>3</sup>;
  - any unintended or uncontrolled release of sour natural gas or hydrogen sulfide; and/or
  - a significant adverse effect on the environment.
- A Rupture:
  - an instantaneous release that immediately impacts the operation of a pipeline segment such that the pressure of the segment cannot be maintained.
- A Toxic Plume:
  - a band of service fluid or other contaminant (e.g. hydrogen sulfide or smoke) resulting from an incident that causes people, including employees, to take protective measures (e.g. muster, shelter-in-place or evacuation).

Where an event meets any of the above definitions, companies are required to notify the TSB Reporting Hotline at **1-819 997-7887**. Subsequently, the company is required to input the details required by both the TSB and the CER into the OERS. The phone notification and the input of information into OERS are required to occur **as soon as possible and no later than three hours** of the incident being discovered. The goal of the initial phone notification is to allow the relevant agencies to mobilize a response to an incident, if required. Note that OERS will automatically determine whether the event meets the definition of an “Incident that Harms People or the Environment”, however the company will be responsible for specifically indicating whether the incident meets the definitions of “Rupture” and “Toxic Plume”.

For all other events that do not meet any of the definitions in this section, companies are not required to phone the TSB Reporting Hotline but must report the event as soon as possible and no later than twenty-four hours after the event was discovered.

### **Multiple Incident Types**

It is possible that a single occurrence may result in multiple incident types. If multiple incident types occur as a result of a single occurrence, companies are expected to report those incident types under a single incident report.

Examples of situations where this might be the case include but are not limited to:

- a pipeline rupture (occurrence) where there is a release of gas (incident type) and an explosion (incident type);
- an industrial accident (occurrence) that causes a death (incident type), a serious injury (incident type) and a fire (incident type);
- an operational malfunction (occurrence) that causes an overpressure (incident type) and a release of product (incident type); or
- an operational malfunction (occurrence) that causes several concurrent or immediately consecutive overpressures (incident types).

In cases where an incident has occurred, and a second incident occurs during the response to the initial incident (e.g. a fire occurs during the clean-up of a spill), the second incident is considered distinct and should be reported separately.

### **9.5.5 Notifications and Preliminary Incident Reports**

For initial notifications for all incidents and Preliminary Incident Reports, companies must provide, via the OERS, the following information:

- company contact information;
- date and time of occurrence and/or discovery;
- how the incident was discovered (e.g., routine patrol, landowner/public reported);
- type of incident being reported (e.g. death, release of substance, fire/explosion);
- type of substance released and initial release volume estimate, if applicable;
- qualitative details of incident type (e.g., broken bone if serious injury, exposure of a pipeline in a water body if operation beyond design limits, etc.);
- nearest populated center;
- GPS coordinates of the event in decimal degrees;
- facility name/pipeline name;
- narrative that includes a description of the events leading up to the occurrence or discovery and any immediate actions taken to protect the safety of the public, the company’s employees, and/or the environment (e.g., evacuation, containment of product);
- initial narrative information on the component that failed, if applicable; and
- affected lands (e.g., restricted to company owned land, right-of-way, private land, crown land).

### 9.5.6 Detailed Incident Reports

For Detailed Incident Reports, companies must provide, via the OERS, the following information:

- any relevant updates to the information contained in the notification and/or preliminary incident reports;
- detailed information on the pipeline/facility component that failed (e.g., equipment type, such as gate valve, and the component that failed, such as the valve packing), if applicable;
- operating conditions of the pipeline/facility at the time of incident discovery (e.g. operating pressure, product type, depth of cover, etc.), if applicable;
- maintenance history of failed component (e.g., date of last inspection/maintenance, type of inspection such as visual or non-destructive examination, etc.), if applicable;
- corrective actions completed by the company to prevent reoccurrence of the incident at local level;
- preventative actions completed by the company to prevent the similar incidents across its systems (if applicable, see appendix 1 for additional guidance);
- root cause analysis that includes at least one immediate cause (e.g., equipment/component failure), as well as at least one basic (root) cause (e.g., normal wear and tear); and
- supporting information (e.g., metallurgical reports), if applicable.

### 9.5.7 Incident Costs

The CER now expects companies to report on costs, as described below, for any incident that meets the following definition under any of the CER's regulations:

- i. An unintended or uncontrolled release of low-vapour pressure (LVP) hydrocarbons in excess of 1.5 m<sup>3</sup> that extends beyond a company's property;
- ii. Significant adverse effect on the environment;
- iii. A rupture;
- iv. A toxic plume; and/or
- v. A loss of containment of any fluid from a well.

Companies will be expected to report categorized costs related to the incident as follows:

- Category 1 – Actual costs (to be reported separately) related to:
  - The emergency response, including containment of the incident;
  - The clean-up and remediation of the incident; and
  - The repair or replacement of regulated facilities.
- Category 2 – Actual or estimated value of losses or damages not included in Category 1.

Companies are expected to provide the above costs annually (calendar) beginning the year the incident was reported and ending either when there are no further costs related to the incident or 5 years after the incident was reported (inclusive of the year that it was reported), whichever occurs first.

Reporting of costs will be integrated into the OERS at a later date and at that time OERS will automatically determine when companies are required to report costs. However, until the system changes are made, the CER will contact companies on an as-needed basis and will provide instructions and a standard form to report costs.

### 9.5.8 *Published Manuals*

All companies operating an oil or a gas pipeline under the jurisdiction of the CER must:

1. Unless the CER otherwise directs, publish the entirety of their emergency procedures manuals on their company's public internet site; provided however, manuals are not required to be published for pipelines described in the exemption clause below. Companies may protect from publication the following information:
  - a. an identifiable individual, including their name, phone number, email address, mailing address and medical condition;
  - b. the vulnerability of particular structures, including methods employed to protect those structures;
  - c. that could prejudice their competitive position or reasonably be expected to result in a material loss or gain to a person affected by publication; and
  - d. about a person, such as a daycare, school or hospital, that was requested by that person to be withheld from publication;
2. Describe information that is protected from publication; and
3. File a written confirmation from the company's accountable officer that the company's emergency procedures manuals have been published and provide a link to the published manuals to the CER and to any interested person that has expressed an interest to the company in the published manuals.

### **Exemption Clause**

Pipelines described in this section are exempt from publication.

High vapour pressure pipelines that are:

1. 168 millimeters or less in outside nominal diameter;
2. 10 kilometres or less in length; and
3. Outside of class 2 or greater locations, as determined by CSA Z662.

Liquid pipelines that are:

1. 168 millimeters or less in outside nominal diameter;
2. 10 kilometres or less in length; and
3. Located more than 500 metres from a navigable water, public drinking water source or a designated environmentally sensitive area.

**10.0 OPERATIONS**

## 10.1 Tupper Main Registered Supplement

**Printing Department: Remove this page, replace with Red tab.**

NorthRiver Midstream Inc.



**Non-Confidential**

# Tupper Main Emergency Response Plan

April, 2023



NorthRiver Midstream  
24-Hour Emergency Number  
**1-844-667-8477**

BCER Emergency Number  
1-800-663-3456

AER Emergency Number  
1-800-222-6514



**REGISTERED SUPPLEMENT  
EMERGENCY RESPONSE PLAN**

**TUPPER MAIN  
EMERGENCY RESPONSE PLAN**

**Prepared by:**

**BLACK GOLD** Emergency  
Planners Inc.

**April, 2023**

The purpose of a Registered Supplement ERP is to supplement the Core ERP with field-specific information that enhances the ability of response personnel by providing them with key area emergency response information.

**Tupper Main Registered Supplement ERP  
Receipt Form**

Upon receipt of this Field\_Name Registered Supplement, this Receipt Form must be completed and returned to the Supervisor, Emergency Management & Security in the Corporate Office. The Supplement holder is responsible for ensuring that the document is kept current by inserting the latest revisions as they are issued.

**Recipient Name (please print):** \_\_\_\_\_

**Position:** \_\_\_\_\_

**Date:** \_\_\_\_\_

**Signed:** \_\_\_\_\_

**Registered Supplement ERP Number (from Distribution List):** \_\_\_\_\_

**Return signed copy to:** NorthRiver Midstream Inc.  
1400, 888 - 3rd St. SW  
Calgary, AB T2P 5C5

Phone: 587-747-6500

Attention:



**MANAGEMENT OF CHANGE REQUEST FORM****NorthRiver Midstream Inc.**

[Redacted]

Section Number: \_\_\_\_\_

Page Number: \_\_\_\_\_

Copies of revised pages attached:  yes  no

Description of Amendment:

---

---

---

---

---

---

---

---

---

---

Requested By: \_\_\_\_\_

Address: \_\_\_\_\_

---

---

Request Acknowledgement: \_\_\_\_\_

Request Numbered and Logged: \_\_\_\_\_

Correspondence Required: \_\_\_\_\_

Approved By: \_\_\_\_\_

Approval Date: \_\_\_\_\_

Revision Date: \_\_\_\_\_

Issue Date: \_\_\_\_\_

**MANAGEMENT OF CHANGE LOG**

<b>Annual Review Date: April, 2023</b> <b>Annual Update Due: April, 2024</b>							
Date Completed (DD/MM/YYYY)	Revision #	Section(s) Updated	Description	Revision <sup>1</sup>	Annual Update <sup>2</sup>	Date Inserted into ERP: DD/MM/YYYY	Signature
30/04/2023	New	All	New Registered Supplement	<input type="checkbox"/>	<input checked="" type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		
				<input type="checkbox"/>	<input type="checkbox"/>		

<sup>1</sup> **Revision:** An interim revision to the ERP when significant changes occur to Company personnel or infrastructure (drilling, facilities, pipelines). A revision does not replace the requirement for an annual update.

<sup>2</sup> **Annual Update:** A comprehensive update to all sections of the ERP. The entire document is reviewed and updated to ensure current distribution list, emergency telephone list, roles and responsibilities, mutual aid agreements, response agencies information, government support information, asset tables, safety equipment, and maps. In a Registered Site Specific ERP, the stakeholder database is also verified, a hazard assessment is conducted, and area user contact information is updated.

*Registered Supplement Table of Contents*

10.1	Tupper Main Registered Supplement.....	1
10.1.1	Tupper Main Telephone Directory.....	2
10.1.2	Tupper Main Area Summary.....	7
10.1.3	Risk Assessment.....	9
10.1.4	Hazard Summary.....	13
10.1.5	Field Specific Response Actions.....	16
10.1.6	Command Centres.....	18
10.1.7	Equipment.....	19
10.1.8	Air Monitoring.....	22
10.1.9	Spill Support Services.....	23
10.1.10	Mutual Aid.....	27
10.1.11	Authority Roles Coordination.....	28
10.1.12	Public Summary.....	38
10.1.13	Stakeholder Data.....	45
10.1.14	Asset Data: Wells, Pipelines & Facilities.....	46
10.1.15	Maps.....	47
10.1.16	CEPA E2 Supplemental Plan.....	1

*Registered Supplement Distribution List*

This supplement is being distributed as part of a Core ERP. For Distribution Information see the Core Distribution List.

### 10.1.1 Tupper Main Telephone Directory

**NorthRiver 24-Hour Emergency Number**  
**1-844-667-8477**

**NorthRiver Main Number**  
**587-747-6500**

Field Office			
Telephone Number		[REDACTED]	
Address		Tupper Main Gas Plant a-21-B/93-P-09	
Name	Position	Office	Cell
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

### Government Agencies

Resource	Contact	Office	Cell/24 Hour
Emergency Management BC – EMBC	Emergency Coordination Centre <i>1st call in a Level 1 or greater emergency. The EMBC will forward on the emergency notification onto the BC OGC On-Call Duty Officer.</i>	--	1-800-663-3456
	North East Region	1-250-612-4172	1-800-663-3456
British Columbia Energy Regulator	Non-Emergency Office Line	1-250-794-5200	<i>Emergency notification received through EMBC.</i>
Peace River Regional District (Zone B-C-D-E)	Allen Tonn, Protective Services Coordinator	Direct: 1-250-784-3222 Reception: 1-250-784-3200	1-800-670-7773
RCMP - Dawson Creek Detachment	NCO In Charge	1-250-784-3700	911
Health Emergency Management BC, North (HEMBC)	Dawson Creek Health Unit	--	1-855-554-3622

Resource	Contact	Office	Cell/24 Hour
Ministry of Environment & Climate Change Strategy - Peace Region	Environmental Emergency Response Officer (Peace Region)	1-250-262-9285	1-800-663-3456
Ministry of Forests - Peace Natural Resource District	Peace Forest District – Dawson Creek	1-250-784-1200	--
WorkSafe BC	Occupational Safety Officer - Fort St. John	1-250-785-1283	--
	24 Hour Number	--	1-888-621-7233 (SAFE)
Ministry of Transportation and Infrastructure - Peace District (Dawson Creek Area)	Operations Manager	1-250-784-2363	--
Argo Road Maintenance (South Peace) Inc.	South Peace - Service Area 21	1-800-663-7623	1-800-663-7623
Drug and Poison Information Centre	Province-wide	1-604-682-5050	1-800-567-8911
Report a Wildfire	Province-wide	1-250-565-6716 (PG Fire Centre)	1-800-663-5555 *5555 Cell Phone
Technical Safety BC	Province-wide	1-866-566-7233	--
BC Hydro	Province-wide	1-888-POWERON (1-888-769-3766) *49376 Cell Phone	--
Environmental Emergency Reporting Line	Province-wide	--	1-800-663-3456
Public Services and Procurement Canada - BC Alaska Highway Maintenance	Province-wide	1-250-774-6956	--
Government of Canada - DFO (Department of Fisheries and Ocean)	Province-wide	--	1-800-889-8852
Environment and Climate Change Canada	Canada-wide	1-800-668-6767	--
CN Railway Co. - Police Service	Canada-wide	--	1-800-465-9239
CP Railway - Police Service	Canada-wide	--	1-800-716-9132
CANUTEC TDG - Emergency Reporting Line	Canada-wide	--	1-888-226-8832 *666 Cell Phone
Transportation Safety Board (CER Regulated Emergencies)	Canada-wide	--	1-819-997-7887
NAV Canada - Notice to Airmen	Canada-wide	--	1-866-992-7433

### Emergency Services

Contact	Location	Telephone
<b>Emergency Response Assistance Plan (ERAP)</b>		
Emergency Response Assistance Canada ERAP # ERP 2-0010-083	Canada-wide	1-800-265-0212
<b>Ambulance - Municipal</b>		
BC Ambulance Service	BC-wide	1-800-461-9911 (where 911 not available)
<b>Ambulance - Oilfield</b>		
HSE Integrated	AB / BC wide	1-888-346-8260
Safety Boss	AB / BC wide	1-800-882-4967
911 Industrial Response	Grande Prairie	1-866-694-9111
<b>Air Ambulance</b>		
Alberta Central Air (ACA) - Medivac Flight Services	Grande Prairie	1-780-814-5888
<b>STARS 115</b> Landing Site Number Tupper Main Gas Plant a-21-B/93-P-09	BC-wide	1-888-888-4567 or 1-403-299-0932
BCAS Provincial Air Ambulance Coordination Centre	BC-wide	1-250-785-2079 or 911
<b>Hospitals</b>		
Dawson Creek & District Hospital	Dawson Creek	1-250-782-8501
Beaverlodge Municipal Hospital	Beaverlodge	1-780-354-2136
Taylor Medical Clinic	Taylor	1-250-789-6772
<b>Fire Fighters - Municipal</b>		
Tomslake Fire Department*	Tomslake, BC	1-250-784-3890
County of Grande Prairie Fire Department*	Grande Prairie, AB	1-780-532-9727
Pouce Coupe Fire Hall	Pouce Coupe	1-250-786-5794
Wildfire Management Branch Report Wildfires line	Fort St. John	1-800-663-5555 *5555 from a cell phone
<b>Fire Fighters - Oilfield</b>		
HSE Integrated	AB / BC wide	1-888-346-8260
Trojan Safety Services Ltd.	Fort St. John	1-250-785-9557
Safety Boss	AB / BC wide	1-800-882-4967

On the BC side, portions of the EPZ fall under Tomslake coverage. The rest of the BC field does NOT have fire coverage from any local fire department. These fires must be handled by NorthRiver Midstream, mutual aid partners, or contract oilfield fire fighting services. Local fire departments will only respond to motor vehicle accidents and medical emergencies unless specifically dispatched by EMBC or the Local Authority. On the AB side, the EPZ falls under Grande Prairie Fire Department coverage.

**Industry Support Services**

Contact	Location	Telephone
<b>Air Quality Monitoring Equipment</b>		
HSE Integrated	Grande Prairie	1-780-532-2088
Trojan Safety Services Ltd.	Fort St. John	1-250-785-9557
United Safety	Fort St. John	1-800-432-1809
<b>Backhoes</b>		
H.F. Nodes Construction	Pouce Coupe	1-250-786-5474
Reg Norman Trucking Ltd.	Dawson Creek	1-250-782-2778
OCL Group Inc.	Dawson Creek	1-778-949-5023
<b>Communication Equipment (Radio/Telephones)</b>		
North Peace Communications Ltd.	Dawson Creek	1-250-782-6664
Epscan Communications	Dawson Creek	1-250-782-9656
Whitetail Energy Services Inc.	Dawson Creek	1-844-782-9524
<b>Construction Company</b>		
H.F. Nodes Construction	Pouce Coupe	1-250-786-5474
Klassen Bros Construction	Pouce Coupe	1-780-957-3760
OCL Group Inc.	Dawson Creek	1-778-949-5023
<b>Cranes / Picker Services</b>		
SI's Oilfield Hauling Ltd.	Dawson Creek	1-250-784-5533
Northwell Oilfield Hauling (09) Inc.	Dawson Creek	1-250-795-5000
Hurst Anchors & Rentals Ltd.	Dawson Creek	1-250-784-1887
<b>Grief Counsellor</b>		
Peace Counselling	Dawson Creek	1-778-864-0560
Life Compass Counselling Services	Dawson Creek	1-250-719-7844
Burden Bearers Counselling Center	Grande Prairie	1-780-539-5225
<b>Helicopters</b>		
Ridge Rotors	Tumbler Ridge	1-877-242-4211
Mustang Helicopters Inc.	Grande Prairie	1-780-882-9182
Gemini Heli Ltd	Grande Prairie	1-780-539-4354
<b>Hotels / Potential Reception Centres</b>		
Pomeroy Inn & Suites	Dawson Creek	1-866-782-3577
Northwinds Lodge	Dawson Creek	1-250-782-9181
Holiday Inn & Suites	Dawson Creek	1-250-782-7700
<b>Radio Stations</b>		
890 AM CJDC - Bell Media Inc.	Dawson Creek	1-250-782-3341
104.1 Peace FM	Dawson Creek	1-250-784-2002
CHRX-FM-1 95.1 FM - Bell Media	Dawson Creek	1-250-785-6634

Contact	Location	Telephone
<b>Safety Equipment / Personnel</b>		
Total Oilfield Rentals Ltd.	Dawson Creek	1-250-719-0505
HSE Integrated	Grande Prairie	1-780-532-2088
Herc Equipment Rental	Grande Prairie	1-780-538-9499
<b>Spill Response / Environmental Services</b>		
Vertex Resource Group Ltd.	Dawson Creek	1-250-719-0353
Parkland Geotechnical Ltd.	Grande Prairie	1-780-539-5102
Badger Daylighting	Grande Prairie	1-780-538-2777
<b>Supply Stores</b>		
P.C. Oilfield Construction Supplies Ltd.	Dawson Creek	1-250-782-5134
Gregg Distributors Ltd.	Spirit River	1-780-864-3333
Mas-Pro	Clairmont	1-780-832-9899
<b>Tank Rentals</b>		
SI's Oilfield Hauling Ltd.	Dawson Creek	1-250-784-5533
B & C Trucking Inc.	Dawson Creek	1-250-219-6055
Whitetail Energy Services Inc.	Dawson Creek	1-844-782-9524
<b>Tank Trucks</b>		
Swamp Donkey Inc.	Dawson Creek	1-250-219-8370
CEDA West Services	Dawson Creek	1-250-784-5151
Wilmar Oilfield Pressure Services Ltd.	Beaverlodge	1-780-518-6964
<b>Vac and Steam Trucks</b>		
Swamp Donkey Inc.	Dawson Creek	1-250-219-8370
CANVAC Oil Field Services	Dawson Creek	1-250-784-7066
Vertex Resource Group Ltd.	Dawson Creek	1-250-719-0353
<b>Well Control Equipment</b>		
Safety Boss	BC-wide	1-800-882-4967
Halliburton Boots & Coats	BC-wide	1-800-BLOWOUT (256-9688)
Hellfire Suppression Services Inc.	BC-wide	1-281-931-8884 1-877-846-4499
<b>Wellsite Accommodations</b>		
Longhorn Oilfield Services	Dawson Creek	1-855-855-7353
Vertex Resource Group Ltd.	Dawson Creek	1-250-719-0353
Total Oilfield Rentals Ltd.	Dawson Creek	1-250-719-0505

**Note:** The above listed corporate entities are subject to change without notice. Information regarding support services is accurate at time of printing.

### 10.1.2 Tupper Main Area Summary

NorthRiver's Tupper Main field is an oil/gas producing property located in northeastern British Columbia and northeastern portion of Alberta. The City of Dawson Creek is located 28km northwest of the Tupper Main Gas Plant and Grande Prairie is located approximately 60km from the field area. It is located in Township 74-75, Range 12-13 W6M, in the Peace River Regional District and the County of Grande Prairie No. 1.

NorthRiver has no wells in this field area.

Pipeline Information	
Licensed Maximum Operating Pressure	13000 kPa
Licensed H <sub>2</sub> S Concentrations	0% H <sub>2</sub> S
Emergency Planning Zones	0.0 km
Thermal Radiation Hazard Planning Zone	0.277 km
Maximum H <sub>2</sub> S Release Volumes	0 m <sup>3</sup>

The NorthRiver Tupper Main Gas Plant is the gathering point for sour production from the Tupper Main field and is located in the Peace River Regional District.

The Tupper Main Gas Plant processes the sour gas to remove H<sub>2</sub>S, hydrocarbon liquids and water. The facility has the option to run a Sulferox unit to convert acid gas to Sulphur cake. Sweet gas production is then pipelined through an interprovincial sales gas pipeline to a TCP Meter Station at 09-07-74-12 W6M.

This pipeline crosses the Alberta / British Columbia provincial border and is regulated by the CER. The Tupper Main Gas Plant is regulated by the BCER.

A plot plan is enclosed at the end of this Section.

#### *Geography and Area Use*

The Tupper Main field is heavily populated with residences and recreational users. The area primarily consists of oil and gas activities, agricultural activities and recreational activities including logging/hauling.

The area surrounding NorthRiver's Tupper Main operations include active cutblocks and range tenures, the grazing season runs from mid-May to the end of October. The Tupper Main field lies in the Boreal White and Black Spruce Bio geoclimatic Zone in the Peace River District. Topography consists of gently to strongly rolling on the till uplands, with long slopes on the lacustrine plains. Vegetation consists predominantly of trembling aspen, balsam poplar, white spruce and willows.

The Tupper Main field includes the Swan Lake Provincial Park and Campground and the Tomslake Sudeten Heritage Park. The Swan Lake Provincial Park and Campground (82 hectares) is in the east of the Tupper Main Gas Plant, accessible via Highway 2. The Campground is operational from May 10th to September 11<sup>th</sup> (annually). Recreational activities at the park include canoeing, cycling, hiking, scuba diving, swimming, water skiing and windsurfing. There is also a boat launch and dock that is open year-round. Swan Lake is also popular with local anglers. Sport fish include walleye, northern pike, yellow perch and burbot. Northern pike spawn in the spring among lakeshore weeds.

The Sudeten Heritage Park (5 hectares), operated by Tomslake and District Recreation Commission, is situated 4 km west of Swan Lake Provincial Park and Campground. Sudeten often functions as an overflow camping site for Swan Lake Provincial Park during weekends and holidays. Sudeten includes a recreational camping and picnicking area for local and regional residents.

**Highways / Area Roads / Railways**

Highway 52 (Heritage Highway) runs north / south through the Tupper Main EPZ.

There are several petroleum development roads in the area. The roads are a combination of pavement and gravel and not all are all-weather roads. Access to the area is dependent on weather.

**Creeks / Rivers / Lakes**

There are numerous waterbodies flowing through the Tupper Main & CER Pipeline field area including Tupper River, Swan Lake, Keering Lake, Albright Lake, Chain Lakes, Ray Lake, Updike Lake, Updike Creek, Little Tupper Creek, Tupper Creek, Bordet Creek and a few unnamed rivers and creeks.

In the event of an emergency near a waterbody, NorthRiver will determine if they need to call WCSS to aid in response activities.

**Tie-In Oil/Gas Companies**

Company	Location	Mutual Aid Agreement (yes/no)	Key Field Contact
TC Energy Corporation	TCPL Meter Station & Tie-In 09-07-074-12 W6M	No	Calgary, AB: 1-403-920-2000  24 Hour Emergency Number: 1-888-982-7222

**Response Procedures:** Advise of the situation; request for mutual aid support (if applicable); provide regular reports; advise when the situation has been rectified and advise when normal operations can continue. Communication link between companies will be maintained until normal operations commence.

### 10.1.3 Risk Assessment

#### Purpose

Risk assessment is a method for analyzing the probability and impact of failure on personnel, the public, the facility, the environment, and/or NorthRiver's reputation. Utilizing the Hazard, Risk and Vulnerability Assessment Matrix during the response to an emergency will help to ensure the incident is managed within NorthRiver risk tolerances.

The nature of the hazard(s) will influence the responses that are implemented by the Site Operations Section Chief and the Incident Commander. NorthRiver risk management during response to any incident is based on the following:

- Activities that present an extreme risk to workers, responders, and public must be limited to only situations where there is a potential to save endangered lives. Life Safety is the number one priority in every incident; this includes the safety of responders.
- Where there is no possibility to save lives, personnel should not attempt extreme risk operations.
- Activities to protect the environment or property are recognized as inherent risks to the safety of response personnel and actions should be taken to reduce or avoid these risks.

The Incident Commander is responsible for the overall coordination and direction of all activities and has the primary responsibility to evaluate the risk to on-site personnel with respect to the purpose and potential results of their actions in each situation. In situations where the risk to personnel is excessive, activities should be limited to defensive and protective operations.

The Site Operations Section Chief has the primary responsibility to evaluate the risk to on-site personnel with respect to the purpose and potential results of their actions in each situation. In situations where the risk to personnel is excessive, activities should be limited to defensive and protective operations.

#### Determining Risk

There are four steps in assessing the risk of an activity or process (see Hazard, Risk and Vulnerability Assessment Matrix):

1. Identify the risk or concern: Describe the risk or concern.
2. Assess the impact: The potential consequence of an incident is defined in terms of impact to people, the environment, operational assets, and the company's reputation.
3. Assess the Probability: The probability of occurrence is estimated in a range from Remote to Frequent.
4. Plot risk level and take action: Risk is categorized in terms of:
  - Critical - the activities must stop until risk controls have been implemented to reduce the risk to a lower level.
  - High - extensive risk controls must be immediately implemented.
  - Moderate - risk controls are required.
  - Low - some risk controls are justified.

---

### *Hazard Identification*

NorthRiver Emergency Response Plans are BC Oil and Gas Commission Emergency Management Regulation compliant 'all hazards' ERPs covering production operations. Although written and employing an 'all hazards' approach, the focus of these plans are upstream petroleum production operations.

Under Canadian Standards Association (CSA) Z1600-08, organizations are required to identify and monitor hazards that can have an impact on their operations or areas of responsibility. Organizations are mandated to consider the impact of natural, technological hazards and human-caused.

Hazards and risks for NorthRiver were identified and vulnerabilities were assessed by NorthRiver Emergency Response Planning section personnel using the Hazard, Risk and Vulnerability Assessment Matrix. As per the Risk Assessment process, staff evaluated information to facilitate the assignment of both probability and impact scores to the three categories of hazards. The combined scores were then plotted on the Risk Matrix so that the Risk Potential/Level could be determined, and appropriate ERP procedures developed where necessary.

**Hazard, Risk and Vulnerability Analysis**

**Step 1 – Assess the Impact**

Level	People	Environment	Assets	Reputation
<b>4 Critical</b>	<ul style="list-style-type: none"> <li>Fatality</li> <li>Long-term health impact</li> <li>Permanent disability</li> <li>Life altering injury or illness</li> <li>Evacuation of a facility and community</li> <li>Action from / activist involving weapons</li> </ul>	<ul style="list-style-type: none"> <li>Severe long-term environmental damage</li> <li>Wide-spread impacts to sensitive environments, wildlife and/or major bodies of water</li> <li>Significant off lease/site groundwater impacts</li> </ul>	<ul style="list-style-type: none"> <li>One-month facility/equipment outage</li> <li>Production, equipment, property, motor vehicle loss and or damage greater than \$10 million</li> <li>Terrorist attack/attempt</li> </ul>	<ul style="list-style-type: none"> <li>Action resulting in regulatory and/or legal prosecution or suspension of operations</li> <li>Prolonged national/international media attention</li> <li>Sustained widespread stakeholder public protest</li> </ul>
<b>3 High</b>	<ul style="list-style-type: none"> <li>Short term health impact</li> <li>Lost time injury or illness</li> <li>Evacuation of facility and immediate area</li> <li>Violent action from landowner/ activist</li> </ul>	<ul style="list-style-type: none"> <li>Severe short-term environmental damage</li> <li>Localized on lease groundwater impacts</li> <li>Significant off lease/site surface impacts</li> </ul>	<ul style="list-style-type: none"> <li>One-week facility/equipment outage</li> <li>Production, equipment, property, motor vehicle loss and or damage greater than \$1 million</li> <li>Substantial loss from theft/ vandalism</li> </ul>	<ul style="list-style-type: none"> <li>Regulatory and/or legal action resulting in fines or punitive action</li> <li>Prolonged national/regional media attention</li> <li>Prolonged local/regional stakeholder public protest</li> </ul>
<b>2 Moderate</b>	<ul style="list-style-type: none"> <li>Medical aid injury or illness</li> <li>Restricted work/modified duties</li> <li>Evacuation of job site</li> <li>Specific threat from landowner/ activist</li> </ul>	<ul style="list-style-type: none"> <li>Moderate environmental damage</li> <li>No groundwater impacts</li> <li>Localised off lease/site surface impacts</li> <li>Immediate clean-up</li> </ul>	<ul style="list-style-type: none"> <li>Short term (less than one week) facility/equipment outage</li> <li>Production, equipment, property, motor vehicle loss and or damage greater than \$100,000</li> <li>Major property crime</li> </ul>	<ul style="list-style-type: none"> <li>Regulatory and/or legal action resulting in administrative response</li> <li>Brief local/regional media attention</li> <li>Brief local public protest</li> </ul>
<b>1 Low</b>	<ul style="list-style-type: none"> <li>First aid injury or illness</li> <li>Implied threat from landowner/ activist</li> </ul>	<ul style="list-style-type: none"> <li>Minor environmental damage</li> <li>Localized on lease/site surface impacts</li> </ul>	<ul style="list-style-type: none"> <li>Negligible production loss</li> <li>Protection, equipment, property, motor vehicle loss and/or damage less than \$100,000</li> <li>Minor property crime</li> </ul>	<ul style="list-style-type: none"> <li>No regulatory action anticipated</li> <li>Brief or no media attention</li> <li>Brief or no public attention</li> </ul>

**Step 2 – Determine the Probability**

Level	Description	Likelihood
<b>4 Frequent</b>	Event is expected to occur in most circumstances.	One or more occurrences per year.
<b>3 Likely</b>	Event will probably occur at home time based on current practices.	One occurrence every 1-5 years.
<b>2 Unlikely</b>	Event should occur at some time based on current practices	One occurrence ever 5-20 years
<b>1 Remote</b>	Event could occur at some time based on current practices	One in the life of the facility

**Step 3 – Determine the Risk Level**

	4 Critical				
	3 High				
Impact	2 Moderate				
	1 Low				
	1 Remote	2 Unlikely	3 – Likely	4 Frequent	

Probability

Impact x Probability = Risk Level

**Step 4 – Risk Level**

**Critical – STOP activities. Work cannot proceed until risk is reduced to a lower level.**

**High – Extensive risk controls/mitigation measures must be implemented, and possible corporate approval is required to allow work to proceed. Efforts to reduce risk to a MEDIUM or LOW level should be undertaken.**

**Moderate- Risk controls/mitigation measures must be implemented to allow work to proceed. Efforts to reduce risk to a LOW level should be undertaken.**

**Low – Some risk controls/mitigation measures may be justified. Represents an acceptable level of risk.**

**Step 5 – Take Action**

Ensure all Risks are understood, controlled, and communicated prior to starting work.

**Hazard Risk Analysis**

The chart below identifies the high-risk hazards that are present at the Tupper Main area of Operations:

Risk Level	Hazards	Controls
<b>Critical</b>	None Identified	N/A
<b>High</b>	None Identified	N/A
<b>Moderate</b>	Fire: Industrial/Facility	Section 7.21 - Facility Fires
	Release: Chemical (e.g. produced water, cleaning agents)	Section 7.16 – Liquids Release
	Release: Gas (Sweet)	Section 7.11 Sweet Gas (Hydrocarbon) Release
	Release: Gas (Sour)	Section 7.10 Sour Gas Release
	Fire: Wildland/Grass/Forest	Section 7.20 – General Fire Response
	Flood	Sub-Section 7.31.5 - Floods
	Release: Liquid Product	Section 7.16 – Liquids Release, Section 7.17 Spill Contingency Plan
	Excessive Runoff from Facility	Section 7.17 Spill Contingency Plan
<b>Low</b>	Medical Event (Slips, Trips, First Aid, Heart Attack, etc.)	Section 7.28 – Injury/Fatality
	Transportation/Vehicle Incident: On Site	Section 7.25 – Transportation Incident
	Transportation/Vehicle Incident: Off Site Involving Company/Contractor Personnel	Section 7.25 – Transportation Incident
	Weather: Lightning Strike	Section 7.31.4 – Lightning
	Weather: Extreme Cold	Section 7.31.1 – Severe Weather Safety
	Threat or Suspicious Activity	Section 7.34 – Bomb Threat
	Disgruntled Landowner/Employee/Contractor/Vendor	Section 7.33 - Site Security
	Weather: Extreme Heat	Section 7.30.1 – Severe Weather Safety
	Wildlife Bites/Attacks	Section 7.32 – Animal Attacks
	Intruder/Squatter	Section 7.33 - Site Security
	Landslide	Section 7.31.6 – Seismicity
	Seismic Event: Earthquake	Section 7.31.6 – Seismicity
	Weather: Tornado	Section 7.31.3 - Tornadoes
	Prolonged Power Outage	Refer to Business Continuity Plan

10.1.4 Hazard Summary

Tupper Main Field Area – Hazard Summary					
Hazardous Product	General Description	Health Effects	Downwind Evacuation	Fire	HPZ Public Safety (immediate precautionary measures)
Methane	<ul style="list-style-type: none"> <li>Often referred to as "sweet gas".</li> <li>Flammable.</li> <li>Lighter than air.</li> <li>At room temperature and standard pressure, methane is a colorless, odorless gas.</li> <li>It is the simplest alkane and the main component of natural gas.</li> </ul>	<ul style="list-style-type: none"> <li>Vapors may cause dizziness or asphyxiation without warning.</li> <li>Some may be irritating if inhaled at high concentrations.</li> <li>Contact with gas or liquefied gas may cause burns, severe injury and/or frostbite.</li> <li>Fire may produce irritating and/or toxic gases.</li> </ul>	<p><b>Large Spill</b> Consider initial downwind evacuation for at least 800 metres (1/2 mile)</p>	<p>If tank, rail car or tank truck is involved in a fire, isolate for 1600 metres (1 mile) in all directions; also, consider initial evacuation for 1600 metres (1 mile) in all directions.</p>	<p>100 m (330 ft)</p>
Methane, compressed					
Natural gas, compressed					
Propane	<ul style="list-style-type: none"> <li>Extremely Flammable – will be easily ignited by heat, sparks or flames.</li> <li>Colourless</li> <li>Denser than air.</li> <li>When odourized has a sulphur type odour. Non-odourized has a slight hydrocarbon odour.</li> <li>A by-product of natural processing and petroleum refining, it is commonly used as a fuel for engines, oxy-gas torches, portable stoves, and residential central heating. Propane is one of a group of liquefied petroleum gases (LPG).</li> </ul>	<ul style="list-style-type: none"> <li>Vapours may cause dizziness or asphyxiation without warning.</li> <li>Some may be irritating if inhaled at high concentrations.</li> <li>Contact with gas or liquefied gas may cause burns, severe injury and/or frostbite.</li> <li>Fire may produce irritating and /or toxic gases.</li> </ul>	<p><b>Large Spill</b> Consider initial downwind evacuation for at least 800 metres (1/2 mile)</p>	<p>If tank, rail car or tank truck is involved in a fire, isolate for 1600 metres (1 mile) in all directions; also, consider initial evacuation for 1600 metres (1 mile) in all directions.</p>	<p>100 m (330 ft)</p>
Butane					
Liquefied Petroleum Gas (LPG)					
Petroleum Crude Oil	<ul style="list-style-type: none"> <li>Brown to black.</li> <li>Viscous liquid.</li> <li>May contain or release poisonous hydrogen sulfide gas.</li> <li>Extremely flammable liquid and vapour</li> </ul>	<ul style="list-style-type: none"> <li>Inhalation or contact with material may irritate or burn skin and eyes.</li> <li>Fire may produce irritating, corrosive and/or toxic gases.</li> <li>Vapors may cause dizziness or suffocation.</li> </ul>	<p><b>Large Spill</b> Consider initial downwind evacuation for at least 300 metres (1000 ft).</p>	<p>If tank, rail car or tank truck is involved in a fire, isolate for 800 metres (1/2 mile) in all directions; also, consider initial evacuation for 800 metres (1/2 mile) in all directions.</p>	<p>50 m (150 ft)</p>

Tupper Main Field Area – Hazard Summary					
<p>Hydrogen Sulphide (H<sub>2</sub>S)</p>	<ul style="list-style-type: none"> <li>Flammable – explosive when mixed with air.</li> <li>Forms SO<sub>2</sub> when combusted.</li> <li>Rotten egg smell at low concentrations.</li> <li>Inhibits olfactory senses at high concentrations.</li> <li>Heavier than air.</li> <li>Will tend to disperse slower in sheltered or low-lying areas.</li> <li>Extremely toxic.</li> </ul>	<ul style="list-style-type: none"> <li>Toxic; extremely hazardous.</li> <li>May be fatal if inhaled or absorbed through skin.</li> <li>Initial odour may be irritating or foul and may deaden your sense of smell.</li> <li>Contact with gas or liquefied gas may cause burns, severe injury and/or frostbite.</li> <li>Fire will produce irritating, corrosive and/or toxic gases.</li> </ul>	<p><b>Small Spill – Day</b> Consider initial downwind evacuation for at least 0.1 km. (100 m)</p> <p><b>Small Spill – Night</b> Consider initial downwind evacuation for at least 0.4 km (400 m)</p> <p><b>Large Spill – Day</b> Consider initial downwind evacuation for at least 2.1 km (2100 m)</p> <p><b>Large Spill – Night</b> Consider initial downwind evacuation for at least 5.4 km (5400 m)</p>	<p>If tank, rail car or tank truck is involved in a fire, isolate for 1600 metres (1 mile) in all directions; also, consider initial evacuation for 1600 metres (1 mile) in all directions.</p>	<p>100 m (330 ft)</p>
<p>Petroleum sour crude oil, flammable, toxic</p>	<ul style="list-style-type: none"> <li>Rotten egg smell at low concentrations.</li> <li>Inhibits olfactory senses at high concentrations.</li> <li>Brown to black.</li> <li>Viscous liquid.</li> <li>May contain or release poisonous hydrogen sulfide gas.</li> <li>Extremely flammable liquid and vapour</li> </ul>	<ul style="list-style-type: none"> <li>Toxic; extremely hazardous.</li> <li>May be fatal if inhaled or absorbed through skin.</li> <li>Initial odour may be irritating or foul and may deaden your sense of smell.</li> <li>Contact with gas or liquefied gas may cause burns, severe injury and/or frostbite.</li> <li>Fire will produce irritating, corrosive and/or toxic gases.</li> <li>Inhalation or contact with material may irritate or burn skin and eyes.</li> <li>Fire may produce irritating, corrosive and/or toxic gases.</li> <li>Vapors may cause dizziness or suffocation.</li> </ul>	<p><b>Small Spill – Day</b> Consider initial downwind evacuation for at least 0.1 km. (100 m)</p> <p><b>Small Spill – Night</b> Consider initial downwind evacuation for at least 0.2 km (200 m)</p> <p><b>Large Spill – Day</b> Consider initial downwind evacuation for at least 0.5 km (500 m)</p> <p><b>Large Spill – Night</b> Consider initial downwind evacuation for at least 0.7 km (700 m)</p>	<p>If tank, rail car or tank truck is involved in a fire, isolate for 800 metres (1/2 mile) in all directions; also, consider initial evacuation for 800 metres (1/2 mile) in all directions.</p>	<p>100 m (330 ft)</p>

*Facilities - Hazardous Products*

Tupper Main Gas Plant A-021-B/093-P-09							
		Latitude	Longitude	Easting	Northing		
UTM Zone 10 NAD83		55.518750	-120.128125	--	--		
STARS Landing Site Number				ERAP Number			
115				ERAP 2-0010-083			
Type	Capacity	Substance	United Nations (UN) ID Number	Transport Canada ER Guide Number	Downwind Evacuation	Fire	HPZ Public Safety (immediate precautionary measures)
Tank	2 tanks 5.68 M3, aprox. 3.31 tonnes	Propane	1075	115 – Gases (Flammable)	Large Spill - 800 metres (1/2 mile)	1600 metres (1 mile)	200 m (660 ft)
Tank	320 M3	Condensate	1267	128 – Flammable Liquids (Water-Immiscible)	Large Spill - 300 metres (1000 feet)	800 metres (1/2 mile)	1200 m (3940 ft)
Tank	5x 2000 bbl	Produced Water	1993	128 – Flammable Liquids (Water-Immiscible)	Large Spill - 300 metres (1000 feet)	800 metres (1/2 mile)	50 m (150 ft)

### *10.1.5 Field Specific Response Actions*

#### *Area Isolation*

The Incident Commander has overall responsibility for isolating the hazard area. Access to the incident location will be restricted by responding personnel who shall:

- Establish roadblocks at required sites to secure identified HRZ.
- Ensure responders have proper safety equipment, i.e. PPE, air monitors, etc.
- Take air quality monitoring readings periodically for your safety and reposition as necessary.
- Record any incoming and outgoing vehicles and equipment.

Highway 2 traverses the EPZ east of the facility. Highway 2 will be isolated by Caribou Road Services (South) Ltd. accompanied by the RCMP. NorthRiver will assist with providing additional manpower and equipment, as required. If required, Caribou Road Services (South) Ltd. in conjunction with the RCMP and The Ministry of Transportation will establish detour routes /traffic points

#### *Notification*

The Public Protection Group Supervisor will be responsible for notifying stakeholders and transients in the EPZ. If necessary, the Public Protection Group Supervisor may delegate notification duties to the Telephone Team Leader.

In a Level 1 Emergency, notification must be made to all stakeholders with special needs or who requested early notification. All stakeholders and locations with unknown phone numbers are deemed special needs and must be visited during a Level 1 Emergency. Impacted non-resident landowners (district lots) will be notified by pulling the applicable land title(s), as required.

In the event of a Level 2 or 3 Emergency, the NorthRiver Public Protection Group Supervisor will contact all Rights Holders and other area users in the EPZ.

See ERP map for more details.

#### *Transients*

Response personnel will be dispatched to the incident location to deliver evacuation notices during an emergency.

The Incident Commander and Public Protection Group Supervisor may also dispatch a helicopter (during daylight hours) equipped with a loud hailer to search the area for transients (industrial operators, area trappers, recreational users, etc). A Rover will drive on the road(s) within the HRZ to ensure that there are no transients.

The status of any transients spotted from the air would be communicated to the Public Protection Group Supervisor for follow-up. If the Rover encounters any parked vehicles in the EPZ, he/she will leave a Notice of Evacuation.

### *Evacuation*

NorthRiver may decide to evacuate the HPZ if the emergency appears it will be of a long duration. NorthRiver cannot force an evacuation unless the local authority has declared a state of emergency; in which case, evacuation is mandatory.

The Public Protection Group Supervisor will dispatch Rovers or activate Telephoners to evacuate stakeholders to the designated Reception Centre. Pets should be evacuated with the residents to the Reception Centre.

Closure Order	Agency
Petroleum Development Road	BCER
Forestry Roads	Ministry of Forestry
Numbered Highway	Ministry of Transportation

Restriction of Airspace	Agency
Notice to Airmen (NOTAM)	NAV Canada

### *Shelter in Place*

If there is no advanced warning to an incident, or if a release is of a short duration (several minutes to half an hour) the Public Protection Group Supervisor will initiate Shelter in Place procedures.

Stakeholders will be asked to remain inside and ensure all windows and doors are closed, and that all air intakes (furnace, stove, bathroom and dryer vents) are plugged to limit exposure to outside air.

The Public Protection Group Supervisor will notify sheltered stakeholders once the emergency has been stood down.

### *Ignition*

If an immediate threat to human life exists and there is not sufficient time, the Incident Commander is authorized to ignite the release.

It is important that mobile air quality monitoring be dispatched as quickly as possible to the emergency site because specialized monitoring equipment can more accurately record readings in the emergency area.

### 10.1.6 Command Centres

Name	Location	Duties
On-Site Command Post (OSCP)	TBD at time of incident – ground zero	<ul style="list-style-type: none"> <li>• Well control and containment</li> <li>• Fire suppression</li> <li>• Worker safety and injury management</li> <li>• Site security by preventing unauthorized personnel from entry</li> <li>• Spill clean-up</li> </ul>
Incident Command Post (ICP)	Tupper Main Gas Plant 05-01-77-17 W6M  Control Room Land Line: 1-250-786-5050  Control Room Cell: 1-250-784-8820	<ul style="list-style-type: none"> <li>• Manages public protection activity such as sheltering, evacuation, notification</li> <li>• Establishes air monitoring</li> <li>• Coordinates notification of area stakeholders</li> <li>• Liaises with government agencies (at the direction of the EOC Director)</li> <li>• Serves as a communications link between the field and the EOC</li> </ul>
Emergency Operations Centre (EOC)	NorthRiver Midstream Inc. 1400, 888 - 3rd St. SW Calgary, AB T2P 5C5	<ul style="list-style-type: none"> <li>• Supports Incident Commander and other field responders</li> <li>• Formulate strategies to manage the larger effects of the emergency such as:               <ul style="list-style-type: none"> <li>• Media</li> <li>• Government notifications and mutual aid</li> <li>• Tracking finances</li> <li>• Remaining cognizant of legal ramifications</li> </ul> </li> </ul>
Reception Centre	Super 8 Dawson Creek 1440 Alaska Avenue Dawson Creek, BC 1-250-782-8899  <b>Directions to the Reception Centre</b> <ul style="list-style-type: none"> <li>• From the Tupper Main Gas Plant a-21-B/93-P-09 site travel for 0.7km</li> <li>• Turn right onto an Unnamed Access Road for 0.8 km.</li> <li>• Turn left on an Unnamed Access Road for 1.6 km.</li> <li>• Turn left on Rd 209 for 4.9 km.</li> <li>• Turn right on Tate Creek Rd for 1.5 km.</li> <li>• Turn left, following signs for Dawson City. Stay on Highway 2 for 20.1km.</li> <li>• Turn right onto Rolla Rd and following for 1.6km.</li> <li>• Turn left onto BC-49 W and continue for 5.1km.</li> <li>• At the roundabout take the 2nd exit onto Hwy 2 / BC-97 heading to Fort Saint John / Prince George.</li> <li>• Turn right onto 15 St.</li> <li>• Destination will be on the right.</li> </ul>	<ul style="list-style-type: none"> <li>• Register and track evacuated stakeholders</li> <li>• Provide food, possible lodging</li> <li>• Address compensation claims</li> </ul>

### 10.1.7 Equipment

#### Emergency Alarms

The Tupper Main Gas Plant is manned 24 hours a day, 7 days a week. They are equipped with numerous monitoring and detection systems, including SCADA, to alert NorthRiver personnel of any conditions outside of normal operating range.

The SCADA system monitors H<sub>2</sub>S, LEL and fire alarms inside the plant, as well as H<sub>2</sub>S monitoring along the facilities fence line. All buildings located within the plants boundaries that have rotary equipment are fitted with fire detection and vibration sensors.

The gas plant is also equipped with visual alarms (beacons) located in all buildings located within the plant boundary and on the roof of the control room. The blue beacon identifies and H<sub>2</sub>S alarm, the amber / orange identifies a general or process control alarm and the red identifies a fire or LEL alarm. Arrival time for company personnel responding to a call-out is 60 minutes.

#### Communication Equipment

Cell phones and plant telephones are the primary methods of communication. All company trucks have radio equipment in that are programmed with NorthRiver's VHF frequencies as well as the applicable Resource Road or Loading Channels for any radio-controlled roads in their area.

#### On-Site Safety Equipment (Tupper Main Gas Plant a-21-E/93-P-03)

Refer to plot plan for location.

Quantity	Equipment
Strategically located throughout	Fire Extinguishers & First Aid Kits / Equipment
1	First Aid Kit (Level 3)
1 – In Plant First Aid Room	Automatic External Defibrillator
1	Air Evacuation Kit
8	SCBA
2	SABA
2	Gas Detectors (Multi-head)
3	Radios Fixed (Control Room)
2	Radios Fixed (Plant Vehicle)
2	Radios Fixed (Portable)
18	Radios Handheld
2	Pickup Trucks (Plant)
1	Emergency Transport Vehicles
Bulk supply of 25' absorbent snakes and grey and white absorbent pads	Spill Equipment

#### Personal Protective Equipment

- Flame-resistant clothing.
- Hard hats.
- Safety glasses.
- Safety boots
- Gloves
- Personal monitor (H<sub>2</sub>S, LEL, O<sub>2</sub>, CO)

### Emergency Response Equipment

Equipment	Location
Flare pistols and flares	Truck
Scot Air-Packs	Tupper Main Gas Plant
ERPs	Tupper West Gas Plant
Roadblock equipment (Roadblock kits contain rotary beacon, Stop/Slow paddle, flashlight w/ batteries, traffic triangles, reflective vests, note pad, roadblock checkpoint binder w/ forms, note paper & pens.)	5 – Tupper Main Gas Plant 5 – Tupper West Gas Plant 2- Dawson Gas Plant (Security Trailer)

\*Each company truck contains a 30lb fire extinguisher, first aid kit, a radio and seasonal fire fighting equipment.

### Ignition Equipment

Quantity	Equipment
1	Manual operated flare gun
3 dozen	marine signal flares with a 50-75 m range (to be carried in a separate container)
3	Flame resistant coveralls to be worn by the Ignition Team.
3	Hard hats with flame resistant liner
3	Sets of ear protection (earmuffs, reusable or expendable types are acceptable)
3	Handheld gas detectors for H <sub>2</sub> S and lower explosive limit (LEL) with audible alarms from 10 ppm H <sub>2</sub> S and 25 percent LEL.
3	Self-contained breathing apparatus with a minimum 30-minute air supply for the Ignition Lead and the backup ignition team.
1	Intrinsically safe radio with communication channel for the Company REOC and one for the backup ignition team.
2	Air horns, one for the Ignition Lead and one for the backup ignition team.
1	Crew vehicle to remain with the backup ignition team.
1	Retrieval Rope.

### Safety Company Equipment List

To be supplied upon dispatch.

Equipment	Rover (2)	Roadblock (4)	Air Monitoring (2)	Total
Intrinsically safe handheld two-way radios for on-site operations (frequency 1) Public Protection (frequency 2)	2	-	2	4
Vehicle battery chargers for intrinsically safe radios	2	-	2	4
Cellular telephone	2	4	2	8
Battery chargers for cellular telephones	2	4	4	8
Personal electronic monitors (H <sub>2</sub> S, LEL, O <sub>2</sub> )	2	-	-	2
Battery chargers for monitors	2	-	-	2
Handheld gas detectors (H <sub>2</sub> S, LEL, O <sub>2</sub> )	2	-	-	2
Self-Contained Breathing Apparatus (SCBA)	2	-	-	2
4x4 passenger automobile (with radio)	2	-	-	2
2x2 passenger automobile (with radio)	2	4	-	6
Roadblock kits (see contents below)	To be obtained from the Safety Company and dispatched at a Level 1 Emergency. The number of Rovers, Roadblocks and Air Monitors required to be confirmed at the time of incident.			4
A roadblock kit contains stop paddle, reflective traffic vest, amber beacon, flashlight with spare batteries, flashing barricade, personal electronic monitor (minimum tri-head), self-contained breathing apparatus, radio (public protection frequency, truck or portable), area map and hard hat.				

### 10.1.8 Air Monitoring

There are a number of companies that provide air monitoring services in case of an emergency where either mobile or stationary air quality monitoring is required. The table below identifies the number of units, location and approximate response time, based on availability and road and weather conditions at the time of the emergency.

Company	Equipment	Number	Location	Response Time
Trojan Safety Services	Stand alone air monitoring units (Solar) Stand alone air monitoring units (Standard)	4 As required	Fort St. John / Grande Prairie	+/- 1 hour + Travel time
	Air trailers Mobile air monitoring unit Stationary air monitoring unit Roadblock kits / personnel Ignition Kits	As required 3-4 As required As required As required		+/- 3 hour + Travel time
United Safety	Quasar system (Not mobile but can be set in an area for remote air monitoring) Stand alone air monitoring unit Air trailers Gas detections Breathing air equipment	10 As required As required As required As required	Fort St. John	Immediate + Travel time
HSE Integrated	Downwind mobile air monitoring (Trucks) Stand alone air monitoring unit Roadblocks kits/ personnel Mobile meteorological tower Mobile Command Post (Communications trailer)	3 15 As required 2 2	Grande Prairie	+/- 3 hours + Travel time
BC Energy Regulator* (not contract service)	Roaming air monitoring unit (RAM)	1	Fort St. John	+/- 1 hour

\*The BCER mobile air monitoring unit would be dispatched as a resource of last resort. Responders would have to clearly demonstrate that there are no available units that could reach the incident location within a reasonable amount of time.


## 10.1.9 Spill Support Services

## WCSS – Coop 5

Area	Chairman	Contact Information
WCSS Emergency 24-Hour Number		1-866-541-8888
[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]

Equipment	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]


Equipment Storage Location	Custodian	Contact Information	Equipment	Transport Requirements
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]



## WCSS – Coop 9

Area	Chairman	Contact Information
WCSS Emergency 24-Hour Number		1-866-541-8888
[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]

Equipment Storage Location	Custodian	Contact Information	Equipment	Transport Requirements
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]



### Waterway Control Points

There is 1 waterway control point. These waterway control points are all accessible by road to allow for rapid deployment of spill control equipment.

Control Point	LSD	Latitude	Longitude
TUP-02	d-54-A / 93-P-9	55.547917	-120.040625

**10.1.10**      *Mutual Aid*

NorthRiver has no mutual aid agreements in place for the Tupper Main field area.

## 10.1.11 Authority Roles Coordination

Type of Agency	Agency Name	Provided Specific Roles	Provided Generic Roles	Notes
RHA	<b>Health Emergency Management BC, North (HEMBC)</b> Owen Brokenshire, Coordinator			This agency is contacted by NorthRiver Midstream and provided with the latest stakeholder pamphlet and their role and responsibilities to ensure up to date information regarding operations in their area.
Local Authority	<b>Peace River Regional District – Dawson Creek</b> Sean Cairns, Protective Services Manager			This agency is contacted by NorthRiver Midstream and provided with the latest stakeholder pamphlet and their role and responsibilities to ensure up to date information regarding operations in their area.
RHA	<b>Alberta Health Services, North Zone 5</b> Shane Hussey, Northern Zone 5 Director, Environmental Public Health			This agency is contacted by NorthRiver Midstream and provided with the latest stakeholder pamphlet and their role and responsibilities to ensure up to date information regarding operations in their area.
Local Authority	<b>County of Grande Prairie No. 1</b> Trevor Grant - Fire Chief			This agency is contacted by NorthRiver Midstream and provided with the latest stakeholder pamphlet and their role and responsibilities to ensure up to date information regarding operations in their area.



## Emergency Response Roles & Responsibilities

### Health Emergency Management BC, North (HEMBC)

HEMBC is a program under the Provincial Health Services Authority (PHSA). HEMBC provides the expertise, education, tools, and support specifically for the BC Health Sector to effectively mitigate, prepare for, respond to, and recover from the impacts of emergency events; ensuring the continuity of health services. There is a HEMBC team in each BC health authority. HEMBC-North deals specifically with Northern Health.

#### Roles and responsibilities:

- Maintain a 24-hour emergency/on call contact number for notification and activation of the health system in Northern BC ( appendix I)
- Notify/activate the appropriate Northern Health programs (i.e. Public Health, Acute Care, etc.) based on the nature of the incident/emergency event.

### Northern Health Authority (NH)

Northern Health is the regional health authority responsible for providing health services to 300,000 people over an area of 600,000 square kilometers in the province of British Columbia. Services include:

- Acute (hospital) Care
- Public Health (Protection, Preventive and Population Health services)
- Mental Health and Addictions
- Home and Community Care

In the event of a major emergency/disaster, Northern Health will provide health care services within its capacity, and activate its emergency response management plan(s).

#### NH Roles & responsibilities - **PREPAREDNESS (PRE-EVENT):**

- Participate with industry, local authority and other partners in the development of their Emergency Response Plans as it relates to health authority roles and responsibilities:
- Participate in stakeholder training and exercises associated with activation of an Emergency Response Plan, in which Northern Health or HEMBC have a role and responsibility (as resources allow);

Author(s): Northern Health Emergency Management  
Issuing Authority: Northern Health Chief Medical Health Officer  
Date Issued (I), REVISED (R) Reviewed (r)  
(I) July 5, 2016.; (R) Oct 5, 2016.; (r) Sept, 2018.; (R) Feb, 2019.

**NH Roles & responsibilities - RESPONSE:**

- Activate internal health emergency management plans related to ongoing provision of services (listed above);
- Provide acute care and emergency services at existing Northern Health hospitals/health centres;
- Work with BC Emergency Health Services (Ambulance) and the BC Patient Transfer Network to transport patients to the appropriate levels of care;
- Apply and enforce the Public Health Act, and associated regulations;
- Provide advice/information to the stakeholders on the existing or potential public health effects of an incident (including drinking water safety, air quality, environmental contaminants, communicable disease prevention, re-occupancy of evacuated areas, etc.);
- Provide advice/information on the best methods for monitoring health effects from an incident.
- Assist in development of (joint) messaging for public information on emergency incidents;
- Provide guidance to stakeholders and local authorities on public health considerations in operating reception and evacuation centres, and group lodging facilities

**NOTE:** British Columbia Emergency Health Services (BCEHS - Ambulance) remains independent of Northern Health. If an ambulance is required please contact BCEHS via 911 (or the local contact number, if 911 is not available in your area).

Author(s): Northern Health Emergency Management  
Issuing Authority: Northern Health Chief Medical Health Officer  
Date Issued (I), REVISED (R) Reviewed (r)  
(I) July 5, 2016.; (R) Oct 5, 2016.; (r) Sept, 2018.; (R) Feb, 2019.



## Appendix I

### Contact information:


- **For Emergency events that require immediate connection with Northern Health, please call :**
  - **HEMBC on call number (24/7) 1-855-554-3622**
    - HEMBC will notify/activate the appropriate Northern Health programs (i.e. Public Health, Acute Care, etc.) based on the nature of the event/emergency.
    - **Please include this number in industry ERPs, for the use of permit holders in contacting Northern Health on an emergency basis.**
    - **Do NOT** include this number on Public Awareness Pamphlets for individual projects; the EMBC/Oil and Gas Commission's emergency number(s) is more appropriate, and the HEMBC 24/7 number is on record with those agencies.
- **For non-urgent requests or emergency exercise planning/information,** contact HEMBC North Director Mary Charters, at:
  - Office: 250-617-5288
  - [HEMBC@northernhealth.ca](mailto:HEMBC@northernhealth.ca)
- **Please note that Northern Health does not review or approve emergency response plans (ERPs)** unless there is a request made from the regulators or governing agencies (e.g. Oil and Gas Commission, National Energy Board, Ministry of Environment, Environmental Assessment Office, etc.). Northern Health also does **not require that general stakeholder consultation/notification packages** be sent to Northern Health.
- **Please make your site and project ERPs available to Northern Health in the event of an emergency to:** [HEMBC@northernhealth.ca](mailto:HEMBC@northernhealth.ca)
- For Environmental assessment inquires and general government consultation questions pertaining to health please email the NH Office of Health and Resource Development at: [resource.development@northernhealth.ca](mailto:resource.development@northernhealth.ca)

Author(s): Northern Health Emergency Management  
Issuing Authority: Northern Health Chief Medical Health Officer  
Date Issued (I), REVISED (R) Reviewed (r)  
(I) July 5, 2016.; (R) Oct 5, 2016.; (r) Sept, 2018.; (R) Feb, 2019.



**Appendix II**

**Northern Health Geography**



Author(s): Northern Health Emergency Management  
 Issuing Authority: Northern Health Chief Medical Health Officer  
 Date Issued (I), REVISED (R) Reviewed (r)  
 (I) July 5, 2016.; (R) Oct 5, 2016.; (r) Sept, 2018.; (R) Feb, 2019.

**BC Local Authority****PEACE RIVER REGIONAL DISTRICT**

1981 Alaska Avenue, Box 810, Dawson Creek, BC, V1G 4H8  
Tel: 250-784-3200, Fax: 250-784-3201. [www.prrd.bc.ca](http://www.prrd.bc.ca)

**Local Authority (Regional District)**

Peace River Regional District (PRRD) has a formal Emergency Management Plan, which outlines the measures and sources of assistance that can be obtained to support emergency response efforts, within their jurisdictional boundaries. Upon request from the BC Oil & Gas Commission (BCOGC), the Regional District may address emergency response capabilities, expectations and preparedness. If required or requested the Regional District may activate their emergency plan in order to achieve any of the following:

- Work with the BCOG's Emergency Operations Centre (EOC) if established
  - With remote support as a cooperating agency through the BCOGC Liaison Officer and/or,
  - In the BCOGC operations section as an assisting agency
- Provide support and assistance to ensure notification of endangered area residents
  - Mass Alerting
  - Notifications
- Provide support to coordinate the delivery of Emergency Support Services (ESS) to evacuated or effected residents
- If necessary, declaration of a State of Local Emergency to enact legislative powers including but not limited to:
  - Issuance of Evacuation Alerts, Orders and Rescinds (persons, livestock, and animals);
  - Acquire or use any land or personal property considered necessary to prevent, respond or alleviate the effects of an event (following BCEMS Model); and
  - Control or Prohibit Travel in the region for safety
- Assist with public information service (joint, BCOGC, Industry and local government)
- Assist with the provision of building re-entry procedures jointly with utility providers, industry, Northern Health, and Technical Safety BC.

*Revised November 13, 2020*

**diverse. vast. abundant.**

## Oil & Gas Industry Emergency Preparedness and Response

Alberta Health Services (AHS) - Environmental Public Health (EPH) roles and responsibilities in public health emergency preparedness and response to the oil and gas industry are outlined below. The provision of services during an emergency depends upon our assessment of legislative responsibilities, impact to services, and business continuity.

EPH will endeavor to:

- Participate with the Licensee in the development of their Emergency Response Plans as it relates to the Environmental Public Health Program's role and responsibility.
- Provide the AHS Zone Single-Point-of-Contact (SPOC) emergency phone number to enable the Licensee to notify and alert the Zone of an emergency. From the initial notification or alert, AHS emergency response will fan out to and coordinate with other AHS programs and facilities as necessary. The 911 EMS services remain independent of the Zone SPOC notification/alert process.
- Participate with stakeholders in preparedness training and exercises associated with a Licensee's simulated activation of an Emergency Response Plan in which EPH has a role and responsibility.
- Participate in public information sessions during the Licensee's Emergency Response Plan development process when appropriate and as resources allow.
- Provide guidance to stakeholders and local municipal authorities in identifying sites suitable for establishing and operating an evacuation centre and/or reception centre, including operational requirements.
- Provide guidance to stakeholders on substances that may affect public health in consultation with the Zone Medical Officer of Health (MOH), including Alberta Health Acute Exposure Health Effects for Hydrogen Sulphide and Sulphur Dioxide information.
- Conduct assessments, inspections and give regulatory direction, when appropriate, to ensure the requirements of provincial legislation and EPH program areas of responsibilities for public health protection and disease prevention are maintained.

Notify the Zone Medical Officer of Health of any incident affecting or potentially affecting other AHS programs or facilities. The Zone MOH will notify and coordinate emergency response in other program areas and facilities as necessary.

For more information, visit Safe Healthy Environments  
[ahs.ca/eph](https://ahs.ca/eph)

## Oil and Gas Industry Emergency Preparedness and Response | 2

- Establish EPH emergency management operations, when appropriate, to support regional response efforts and liaise with the Government Emergency Operations Centre, Municipal Emergency Operations Centre and/or Industry Emergency Operations Centre, if needed.
- Assist the Zone Medical Officer of Health, local municipal authority, and Public Information/Communication officers in the development, issuance, and rescinding of public health, public evacuation and shelter-in-place advisories.
- Provide guidance to stakeholders on matters relating to evacuation of the public and/or public facilities, and the re-occupancy of those evacuated areas or facilities.
- Record and respond to health complaints or concerns from the public during and following an incident.
- Participate in stakeholder debriefings as necessary.

### **24 Hour Emergency Notification**

**Phone: 1-844-755-1788**

**Email: [edp@ahs.ca](mailto:edp@ahs.ca)**

Use the phone number and email for all notifications across Alberta.

---

Contact us at 1-833-476-4743 or [submit a request online](#) at [ahs.ca/eph](https://ahs.ca/eph).

PUB-0055-201711

©2017 Alberta Health Services, Safe Healthy Environments



This work is licensed under a [Creative Commons Attribution-Non-commercial-Share Alike 4.0 International license](#). You are free to copy, distribute and adapt the work for non-commercial purposes, as long as you attribute the work to Alberta Health Services and abide by the other license terms. If you alter, transform, or build upon this work, you may distribute the resulting work only under the same, similar, or compatible license. The license does not apply to content for which the Alberta Health Services is not the copyright owner.

This material is intended for general information only and is provided on an "as is," "where is" basis. Although reasonable efforts were made to confirm the accuracy of the information, Alberta Health Services does not make any representation or warranty, express, implied or statutory, as to the accuracy, reliability, completeness, applicability or fitness for a particular purpose of such information.

**AB Local Authority**
**County of Grande Prairie No. 1**

Revised April 04, 2023

**Contact information:**

Name	Title	Office #	Cell #	E-mail
Trevor Grant	Fire Chief (Primary)	780-532-9727	--	<a href="mailto:tgrant@countvqp.ab.ca">tgrant@countvqp.ab.ca</a>
Bart Johnson	Deputy Fire Chief	780-532-9727	587-297-0246	<a href="mailto:bjohnson@countvqp.ab.ca">bjohnson@countvqp.ab.ca</a>
Jason Nesbitt	Deputy Fire Chief	780-532-9727	780-882-1540	<a href="mailto:jnesbitt@countvqp.ab.ca">jnesbitt@countvqp.ab.ca</a>
Joulia Whittleton	Director Emergency Management	780-532-9722	780-933-8712	<a href="mailto:jwhittleton@countvqp.ab.ca">jwhittleton@countvqp.ab.ca</a>
Darryl Martin	Deputy Director Emergency Management.	780-532-9727	--	<a href="mailto:dmartin@countvqp.ab.ca">dmartin@countvqp.ab.ca</a>

Initial contact person for ERP's for the County of Grande Prairie No. 1 is the Fire Chief.

**Responsibilities**

The *Emergency Services Act* requires the local authority of each municipality to be responsible for Emergency Response Planning and for the direction and control of their emergency response in their respective jurisdiction (*Local Authority*).

**The Local Authority:**

- Review the Site specific Emergency Response Plan
- Initiates and manages the local municipal disaster services response
- Dispatches representative(s) to the Emergency Operations Centre, when established and as required
- If required, activates their municipal emergency operations centre and coordinates municipal activities at this centre
- Upon request, may assist with setting up and administration of the Reception Centre
- Assists with the arrangements of temporary accommodations for residents who have been evacuated
- Assist with the establishing, set up and maintenance of roadblocks as resources and staff training permit
- Ensures that if available, local emergency services and resources are available to the level that they are trained
- Assists with off-site fire protection
- Activates the Emergency Public Warning System (EPWS) to alert public to life threatening hazards as required according to criteria set out by AEMA
- Supports operator in dealing with the emergency situation
- Initiate public protection methods as required
- If necessary, declares a local state of emergency to provide local authorities with special powers (mandatory evacuation, use of or entry into private property, conscription, demolition of private property structures for safety reasons, etc), and
- Establish a public information service, including use of the news media to inform and instruct the public of the emergency as required
- Assist as required with post incident damage assessment

**County of Grande Prairie No. 1**

Revised April 04, 2023

**Resources**

- The County has and may provide equipment and manpower in an offsite support role for fire protection and emergency mitigation. No County Fire personnel will work outside of their scope of practice. All County personnel will remain under immediate control and direction of a County Fire Officer or designate. The County Fire Service is manned 24 hours a day from the Clairmont and Dunes Fire Halls. All other stations in the County service area are Paid Response or Volunteer and will be dispatched through 911.
- The County has uniformed Level 1 Peace Officers. The RCMP performs all other policing, evacuation and notification duties. The Peace Officers would be mobilized at the request of the RCMP.
- The County has a large Public Works Department (divided into 3 zones), affiliated equipment and vehicles, and a staff that ranges from 140 in the winter to 240 in the summer. Manpower and equipment may be available to assist with roadblocks and county road closures depending on training and availability.

**County of Grande Prairie Notification 24 hr. Phone Number 1-780-814-0280****For all Emergencies Dial 911**

## 10.1.12 Public Summary

Building Type	# of Surface Developments		Of the Surface Developments listed, # with Special Needs	
	Full-Time	Part-Time	Full-Time with Special Needs	Part-Time with Special Needs
Residence	7	--	6	--
Business	1	--	--	--
Cabin	--	--	--	--
Campground	--	--	--	--
Church	--	--	--	--
Manned Facility	1	--	--	--
Recreation Area	--	--	--	--
School	--	--	--	--
Tower	--	--	--	--
Trapper Cabin	--	--	--	--
Vacant	--	--	--	--
Other	--	--	--	--

Tupper Main Operations Area	
Number of First Nations:	None
Number of Rights Holders:	4 BC Area Trappers 4 AB Area Trappers 1 BC Guides & Outfitters 2 AB WMU Guides & Outfitters 2 Cutblocks / Woodlots 4 BC Range Tenures 10 AB Grazing Leases 18 Non-Resident Landowners
Number of Oil & Gas operators:	40
Number of Other Area Users:	3
Other surface facilities that were noted:	None

**First Nations**

There are no First Nations near NorthRiver Midstream operations in the Tupper Main field.

*Rights Holders*

*Area Trappers (BC)*

Trapline #	Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

*Area Trappers (AB)*

Trapline #	Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

*Guides & Outfitters (BC)*

ID #	Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

*Guides & Outfitters (AB)*

WMU 357 - Beaverlodge				
Name	Location	Telephone	Planning Zone	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	

WMU 357 - Beaverlodge			
Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
WMU 358 - Saddle Hills			
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

*Cutblocks/Woodlots*

Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

*Range Tenure (BC)*

Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

\*Significant attempts were made to locate information for all licensees.







**School Contacts**

Schools and School Divisions	Contact	Location	Telephone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

### **10.1.13 Stakeholder Data**

The Company may collect information required for emergency response and preparedness activities or as mandated by applicable regulatory agencies including, without limitation, the following information: name, age, address, contact information, and medical information. Due to the privacy and protection of personal information, this data must be kept confidential and secure.

Stakeholder information is on the following pages and it may include:

#### **Callout Sheet**

Contains the names and telephone numbers for the primary contacts. The Callout Sheets are printed on yellow paper and they can be used for telephone notification.

#### **Resident List by Legal Subdivision**

Contains a list of all primary contacts and telephone numbers organized by legal subdivision. The Resident List by Map Number can be used by the Public Protection Group Supervisor and Team Leaders.

#### **Detailed Resident Sheets**

Contains all information necessary for response activities which includes stakeholder names, telephone numbers, children, special needs and additional concerns. All Detail Sheets printed on blue paper indicate residents who have “special needs” and would require early response.

#### **Resident List by School Age Children**

Contains a list of all school aged children, their residence information, school information and a list bus departure and arrival times.

### **Public Information Package**

Public Information Package on following page:

If there is a pipeline on your property that is federally regulated by the Canada Energy Regulator (CER), we have included additional information to be followed.



- Constructing driveways, roads, or parking lots.
- Installing fence posts, piles, or underground utilities;
- Planting trees, clearing trees, or stump removal;
- Striping, grading, or plowing;
- Digging, trenching, ditching, boring, drilling, or auguring;
- In addition to the ROW, pipeline regulators have established a 30m (100') area, measured on either side of the pipeline, where ground disturbance activities deeper than 30cm (12") require permission from NRM. These activities include (but are not limited to):
  - (e.g., deep tillage);
  - Agricultural activities deeper than 45cm (18")
  - Ground disturbance deeper than 30cm (12"); or
  - Using explosives;
  - Brush pile burning or campfires;
  - or berms);
  - walls, fences, gazebos, skating rinks, swimming pools, mobile homes, sheds, driveways, roads, foundations, buildings or placing structures on the ROW (e.g., houses, stock piles);
  - Placing or storing equipment on the ROW (e.g., travel trailers, boats, motor vehicles, mobile equipment, or met;
  - perform agricultural activity and certain conditions are public road does not exist, unless the road is used to Operating heavy equipment over the ROW where a
- (but are not limited to):
  - To reduce risk of pipeline damage, and in accordance with regulatory requirements, some activities are not allowed on a ROW without written permission from NRM. These include
  - rivers, fields, urban areas, etc.).
  - because they exist in many different environments (e.g., or more pipelines. ROWs vary in width and appearance
  - A Right-of-Way (ROW) is a strip of land that may contain one

## PIPELINE DAMAGE PREVENTION

## WHAT YOU SHOULD DO

- Take shelter in your residence. Close all windows and doors. Turn down the furnace or turn off the air conditioning.
- Do not use any forms of ignition such as lighters or wood stoves, etc.
- Call **911** and NRM's 24 Hour Emergency number at **1-844-667-8477** to report your observation
- Keep your phone lines clear and wait for further direction. Monitor local radio and television stations for explanation and instructions.

## WHAT WE WILL DO

- We will take immediate action to determine the source of the report and then follow up with you.
- If necessary, we will activate our ERP for the area. These comprehensive public protection plans include criteria and procedures for:
  - Assessing emergency situations
  - Mobilizing response personnel
  - Establishing communication and coordination
- We will contact stakeholders in the immediate area, starting with downwind residents and those with special needs considerations. We will provide details of the situation and instructions about which precautions to take. Precautions could include measures such as sheltering-in-place or evacuation.
- If we are unable to contact you, we will visit your residence to verify your location and inform you of the situation. We will also visit your residence if you require evacuation or transportation assistance.
- We will keep traffic outside the hazard area by establishing roadblocks around the EPZ.
- We will contact you to provide updates if the situation changes and when the hazard has cleared.

Canada Energy Regulator  
[www.cer.gc.ca/en/safety/environment/damage-prevention/](http://www.cer.gc.ca/en/safety/environment/damage-prevention/)  
 Alberta Energy Regulator  
[www.aer.ca/providing-information/by-topic/pipelines/](http://www.aer.ca/providing-information/by-topic/pipelines/)  
 BC Energy Regulator  
[www.bc-er.ca/what-we-regulate-oil-gas-pipelines/](http://www.bc-er.ca/what-we-regulate-oil-gas-pipelines/)  
 For more information, please visit these websites:

Immediately notify NRM if you contact the pipe or its coating by calling the 24 Hour Emergency Number: **1-844-667-8477**

Follow instructions of the NRM representative

Wait for the pipeline(s) to be located - there is no charge for this service

Obtain written consent from NRM by calling: **1-866-262-3654** or emailing [crossings@nrm.ca](mailto:crossings@nrm.ca)

Call or click before you dig.

Before doing any work within an NRM ROW or conducting ground disturbance within 30m (100') of an NRM pipeline, please do the following:

**Click Before You Dig**  
[clickbeforeyoudig.com](http://clickbeforeyoudig.com)  
 BC 1 Call: 1-800-474-6886  
 Alberta One Call: 1-800-242-3447

Accordingly, before doing any ground disturbance, always call or click before you dig.

Pipeline marker signs (similar to the photo on the left) are placed along the ROW at road, railway and fence crossing locations, etc. These signs provide the company name, emergency contact number and product information. Pipeline marker signs only show approximate locations of buried pipeline(s) actual location and depth vary within the ROW.

## WORKING SAFELY NEAR PIPELINES

**Shelter-In-Place** Remaining indoors for short-term protection from exposure to toxic gas releases. Steps to follow:

- Gather all residents inside and close all window and doors;
- Turn down the furnace and turn off appliances or equipment that either blow air outside (e.g., bathroom/kitchen exhaust fans) or suck in outdoor air (e.g., air conditioning systems);
- Do not use any forms of ignition (e.g., lighters, gas/wood stoves);
- Leave inside doors open and wait in an upstairs interior room;
- Keep your phone lines clear, monitor local radio/television stations, and wait for further direction; and
- Do not leave the house or start any vehicles until you have been advised that it is safe to do so.

**Evacuation** Organized, phased, and supervised withdrawal of members of the public from dangerous or potentially dangerous areas to safe areas. Steps to follow:

- Gather all residents in your household and pack medications;
- Lock all windows and doors;
- Turn down the thermostat and shut off air exchange fans;
- Drive safely on the route provided and proceed directly to a reception centre to check-in; and
- Wait for further instructions.

**Ignition** In conjunction with sheltering or evacuation, the release may be ignited at the source to reduce exposure to the hazard. The combustion of H<sub>2</sub>S results in SO<sub>2</sub> being carried high into the atmosphere allowing additional time for the public to safely evacuate.

## WARNING SIGNS

- You might see:**
  - Dead or dying vegetation
  - Water bubbling
  - Dirt blowing into the air
  - Frost build up on the ground
  - Fire coming from the ground
  - A heat wave above a storage vessel
  - Flames coming from a storage vessel
  - A white vapour cloud
- You might hear:**
  - Aggressive hissing or loud whistling sound, similar to a jet engine
- You might smell:**
  - Rotten eggs
  - A pungent odour similar to burning a match
  - Nothing - smell cannot always be trusted as a warning

NRM 24 Hour Emergency Number: **1-844-667-8477**  
 NRM Crossing Agreements: 1-866-262-3654  
 BC 1 Call: 1-800-474-6886  
 Alberta One-Call: 1-800-242-3447

## CONTACT INFORMATION

- Potential hazards related to our operations;
- The function of our Emergency Response Plan (ERP);
- Your role in pipeline damage prevention.

awareness of emergency contact information and to ensure your You have been identified as a stakeholder within the emergency planning zone (EPZ) of an NRM asset. As part of the public safety process, we are contacting you to verify

Northern Midstream Inc. (NRM) is a Canadian-owned natural gas gathering and processing company that operates assets in Northeast British Columbia and Northwest Alberta. A detailed map of NRM's operations in your area can be found inside this brochure.

## PUBLIC AWARENESS



## POTENTIAL HAZARDS

NRM is the owner of pipelines, facilities and wells that produce, transport, process, and store potentially hazardous substances. While the probability of an uncontrolled release is low, our ERP is in place to ensure your safety.

**Potentially hazardous substances may include:**

**Hydrogen Sulphide (H<sub>2</sub>S)** H<sub>2</sub>S is a naturally occurring gas found in geological formations. In small concentrations, it has a rotten egg smell and causes eye and throat irritations. In high concentrations, it can be fatal. Natural gas containing H<sub>2</sub>S is called sour gas. Depending on various conditions, a sour gas release could be heavier, lighter, or about the same weight as air.

**Sulphur Dioxide (SO<sub>2</sub>)** SO<sub>2</sub> is a by-product from the combustion of H<sub>2</sub>S and is present if the source of H<sub>2</sub>S is ignited. It is a colourless, water-soluble, suffocating gas. SO<sub>2</sub> may be fatal with continued high-level exposure. When an SO<sub>2</sub> release is ignited, the resulting gas is lighter than air.


**Natural Gas Liquids (NGL)** - NGL is a colourless, clear liquid comprised of naturally occurring elements found in natural gas. Elements can include ethane, propane, butane, pentane-plus and condensate. Liquid components are separated from natural gas during processing and kept in a liquid state for storage, shipping, or consumption.

**Condensate** - Condensate is a combination of hydrocarbons separated as a liquid from natural gas during processing. The vapours are toxic if inhaled. Condensate vapours are highly flammable, heavier than air, and may accumulate in low areas.

**Butane and Propane** - Butane and propane are naturally occurring gases. When stored under pressure in tanks, they become colourless, odourless liquids until pressure is released and the liquids vapourize. If heated above boiling point, butane and propane liquid tanks may rupture causing an explosion. Butane and propane vapours are extremely flammable and heavier than air. Inhalation could cause anesthetic effects or asphyxiation.

## PUBLIC PROTECTION MEASURES

In the unlikely event of an uncontrolled release, NRM may use any of the following public protection measures to mitigate the impact of hazardous substances on the public.



Surface Development	<b>NRM Facility (Active)</b>
<b>NRM Pipeline (Sour Gas)</b>	Processing Plant
<b>Operating Status</b>	Booster Station
Active	Compressor Station
Inactive	<b>NRM Facility (Inactive)</b>
Emergency Planning Zone (EPZ)	Processing Plant
Isolation Valve (ESD)	Booster Station
Reception Centre	Compressor Station
Hospital	Major Waterbody
Airport	Municipality / Town / District
Highway	Park / Protected Area
Minor Road	First Nation Reserve
Railway	

**24 HR EMERGENCY CONTACT: 1-844-667-8477**

**South Peace (Zone 4)  
Operating Area  
EMERGENCY RESPONSE PLANNING  
PUBLIC AWARENESS MAP**

Revision: 0  
 Revision Date: 3/16/2023  
 Created By: AJO  
 Map Scale: 1:325,000  
 (when printed on 11x17)  
 Map Projection: NAD 1983 UTM Zone 10N

**CONTACT INFORMATION**  
 NorthRiver Midstream  
 Emergency: 1-844-667-8477  
 Crossings: 1-866-262-3654 (crossings@nrm.ca)

**Agencies**  
 Emergency Management BC: 1-800-663-3456  
 BC Energy Regulator: 1-800-663-7867  
 BC 1 Call: 1-800-474-6886  
 Canada Energy Regulator: 1-800-899-1265

DISCLAIMER: The data shown on this map is collected from numerous government and industry resources and may not be complete or accurate. Reference locations are approximated and may not exactly reflect the location of the structure. This map is provided for informational purposes only. NorthRiver Midstream Inc. bears no responsibility for the accuracy and completeness of this map and assumes no liability for any losses, damages or inconveniences due to reliance on this map.

**INSET 1**

**INSET 1**

**BC / AB BORDER**

**10.1.14**      *Asset Data: Wells, Pipelines & Facilities*

Asset tables on following pages.

Pipelines

LICENSEE	REGULATORY CODE	LICENSE	LINE	SUBSTANCE CATEGORY	STATUS CODE	FROM	FROM FACILITY	UP STREAM VALVE TYPE (CV/ESD/OPEN FLOW ( ))	GPS COORDINATES (UTM NAD 83)	TO	TO FACILITY	DOWNSTREAM VALVE TYPE (CV/ESD/OPEN FLOW ( ))	GPS COORDINATES (UTM NAD 83)	MOP (KPA)	OD (mm)	WT (mm)	LICENSED H <sub>2</sub> S CONTENT (mol/kmol)	LENGTH (KM)	MOT ( C )	VOLUME OF PIPELINE (m <sup>3</sup> )	Volume of Gas @ Standard Conditions (m <sup>3</sup> )	Gas Volume Factor (GVF) (m <sup>3</sup> /m <sup>3</sup> )	COMPRESS. (Z)	SEGMENT H <sub>2</sub> S RELEASE VOLUME (m <sup>3</sup> )	CUMULATIVE H <sub>2</sub> S RELEASE VOLUME (m <sup>3</sup> )	EPZ (KM)	EAZ (KM)	SET BACK LEVEL	CANUTEC INITIAL ISOLATION ZONE (KM)	THERMAL RADIATION HPZ (KM)	ASSIGNED HPZ (KM)	
<b>CER ASSETS BC</b>																																
ENBRIDGE G AND P CANADA PIPELINES INC	AO-003-XG-M267-03-2008	80061	2-A	NG	APPROVED	A-021-BI/093-P-09	GP	--		D-051-I/093-P-08	PL	ESD	10 N 689572-6150348	13000	323.8	10.3	0	11.75	5	na	na	na	na	0	0	0.000	0.000	na	0.100	0.277	0.277	
ENBRIDGE G AND P CANADA PIPELINES INC	AO-003-XG-M267-03-2008	80061	2-B	NG	APPROVED	D-051-I/093-P-08	PL	ESD	10 N 689572-6150348	D-051-I/093-P-08	PL	--		13000	323.8	10.3	0	0.45	5	na	na	na	na	0	0	0.000	0.000	na	0.100	0.162	0.162	
<b>CER ASSETS AB</b>																																
NORTH RIVER MIDSTREAM G AND P CANADA PIPELINES INC A	AO-004-XG-M267-03-2008	80061	001	NG	APPROVED	02-06-075-13W6	PL			14-07-074-12W6	PL	ESD	11 N 320330-6142912	13000	323.8	10.3	0	16.60	5	na	na	na	na	0	0	0.000	0.000	na	0.100	0.289	0.289	

Notes: HPZ or Hazard Planning Zones are based on the Immediate Precautionary Measures CANUTEC 2020 Emergency Response Guidebook  
Assigned HPZ is the highest value from calculated EPZ and Canutec Initial Isolation Zone  
Substance Category Codes: CO - Crude Oil FG - Fuel Gas FW - Fresh Water HVP - HVP Products LV - LVP Products MG - Miscellaneous Gases ML - Miscellaneous Liquids NG - Natural Gas OE - Oil Effluent SG - Sour Natural Gas SW - Salt Water MP - Multiphase PW - Production Water  
Status Codes A - Abandoned ACT - Active N - Not Constructed D - Discontinued DEACT - Deactivated O - Operating P - To be constructed R - Removed  
Facility Codes B - Battery BE - B Ind End CP - Chemical Plant CS - Compressor Station GP - Gas Plant IP - Injection / Disposal Facil by MR - Meter / Regulator on Station MS - Meter Station PP - Petrochemical Plant PL - Pipe line  
PS - Pump Station R - Riser RF - Refinery RS - Regulator Station S - Satellite ST - Storage Tank TF - Tank Farm WE - Well H - Heade  
Valve Codes BV - Block Valve CV - Check Valve ESD - Emergency Shutdown Valve MV - Manual Valve --- No valve


Facilities

LICENCEE	LICENCE OR FACILITY CODE	FACILITY TYPE	LOCATION	STATUS	NAME	HPZ FROM PIPELINE (KM)	EPZ Based on Pipeline	Pipeline H <sub>2</sub> S (mol/kmol) content	THERMAL RADIATION HPZ (KM)	ASSOCIATED ONSITE STORAGE HPZ (KM)	ASSIGNED HPZ** (KM)
<b>OPERATING ASSETS</b>											
NORTHRIVER MIDSTREAM	BCGP0007676	GAS PROCESSING PLANT	A-021-B/093-P-09	ACTIVE	NRM GP A-021-B/093-P-09	0.277	80061-2A	0	0.277	1.600	1.600
<p>Notes * HPZ or Hazard Planning Zones are based on the Immediate Precautionary Measures (Initial Isolation Zone) - CANUTEC 2020 Emergency Response Guidebook</p> <p>** Assigned HPZ is the highest value between the calculated EPZ and Canutec Initial Isolation Zone. The CANUTEC Initial Isolation Zone is assigned if the corresponding calculated EPZ is less than the CANUTEC IIZ.</p> <p>The EPZ for a facility that handles or processes sour fluids is the largest EPZ of any pipeline entering or leaving the facility measured outward in all directions from the facility lease boundary.</p> <p>If the facility has a sour gas well, sour water disposal well, or acid gas disposal well on site, the EPZ for the well may determine the size of the EPZ for the facility.</p>											

**E2 Substances**

LICENSE	E2 ID#	ERP	Tank / Vessel ID Facility Location	Latitude / Longitude	Highest Compound	Activity in which the substance is being used	UN #	CAS Registry #	% of Tank	Threshold Quantity of Product (Tonnes)	Max Expected Quantity on Site	Largest Container System Capacity	ECCC Hazard Category	Worst Case HPZ (Km)*	Alternate Worst Case HPZ (Km)**
<b>E2 CEPA STORAGE</b>															
NORTHRIVER MIDSTREAM	E2-P9236 NAICS-211110	Tupper Main ERP	A-021-B/ 093-P-09	55 30' 51.954"/ -120 7' 50.946"	LPG BULLET (PROPANE)	Storage	1075	74-98-6	80%	4.5	2 tanks 5.68 M3, aprox. 3.31 tonnes	2 tanks 5.68 M3, aprox. 3.31 tonnes	E	1.600	1.600
<b>NO REGISTRATION REQUIRED</b>															
NORTHRIVER MIDSTREAM	na	Tupper Main ERP	A-021-B/ 093-P-09	55 30' 51.954"/ -120 7' 50.946"	PRODUCED WATER	Storage	1993	na	65%	na	5 tanks 2000 bbl each	5 tanks 2000 bbl each	na	0.050	0.050
NORTHRIVER MIDSTREAM	na	Tupper Main ERP	A-021-B/ 093-P-09	55 30' 51.954"/ -120 7' 50.946"	CONDENSATE	Storage	1267	68919-39-1	65%	340	320 M3	320 M3	na	1.200	1.200
<b>Notes:</b> * Worst Case HPZ (Km): Catastrophic rupture of vessel, vapor cloud explosion. ** Alternate Worst Case HPZ (Km): More likely to occur - basis for public consultation program. (Based on ERG Guide)															

10.1.15 Maps



### *Access Directions*

#### **Directions to the Tupper Main Gas Plant a-21-B/93-P-09 Gas Plant**

From the intersection of Highway 2 and Highway 97 in Dawson Creek, BC:

- Travel southeast on Highway 2 for 2 km.
- Stay right on Highway 2 for 27.4 km.
- Turn right on Tate Creek Rd for 1.5 km.
- Turn left on Rd 209 for 4.9 km.
- Turn right on an Unnamed Access road for 1.6 km.
- Turn right on an Unnamed Access Road for 0.8 km.
- Turn left and travel 0.7 km into the Tupper Main Gas Plant a-21-B/93-P-09 site.

From the intersection of Highway 43 and Highway 722 in Beaverlodge, AB:


- Travel northwest on Highway 43 for 48.4 km.
- Continue northwest as Highway 43 changes to Highway 2 and travel 12.2 km.
- Turn left on Tate Creek Rd for 1.5 km.
- Turn left on Rd 209 for 4.9 km.
- Turn right on an Unnamed Access road for 1.6 km
- Turn right on an Unnamed Access Road for 0.8 km.
- Turn left and travel 0.7 km into the Tupper Main Gas Plant a-21-B/93-P-09 site.

#### **Plot Plan**

Plot plan on following page:


#### **ERP Map**

Area map on following page:



**TUPPER MAIN PLANT  
SAFETY EQUIPMENT LEGEND**

	SELF CONTAINED BREATHING APPARATUS
	FIRST AID
	EYEWASH STATION
	MUSTER AREA
	STRETCHER
	SHOWER & EYEWASH STATION
	FIRE EXTINGUISHER



Twp 76  
Twp 75  
Twp 74

- NorthRiver Wells**
- Gas
  - Oil
  - Standing
  - Injection
  - Suspended Gas
  - Suspended Oil
  - Water
  - Bottom Hole
  - Well EPZ
- NorthRiver Pipelines**
- Discontinued
  - Sour Gas
  - Natural Gas / Fuel Gas
  - Oil
  - Water
  - HVP / LVP
  - Block Valves
  - Pipeline HPZ
  - Major Transmission Lines
- NorthRiver Facilities**
- Battery
  - Compressor Station
  - Gas Plant
  - Gathering Point
  - Injection Plant
  - Meter Station
  - Pump Station
  - Satellite
  - Facility EPZ
  - Storage HPZ
- Transportation**
- High Grade Roads
  - Resource Roads
  - Low Grade / Seasonal
  - Secondary Highway
  - Primary Highway
  - Radio Controlled Roads
  - Railways
  - Dead Ends
  - Locked Gates
  - Roadblocks
  - Bridge
- Residents**
- Surface Development
  - Occupied
  - Sensitive
  - Business
  - Cabin
  - Occupied Part-Time
  - Vacant
  - Campground
  - Cemetery
  - Church
  - Community Hall
  - Farm / Ranch
  - Grain Bin
  - Gravel Pit
  - School
  - Shop
  - Tower
  - Fire Tower
  - Work Camp
  - Hospitals
  - Reception Centre
  - Stars Air Ambulance
- Other Symbols**
- Urban Area
  - Hydrology
  - Intermittent Waterbody
  - Permanent Waterbody
  - Airfields
  - Municipal District
  - Health Region
  - RCMP
  - WCSS Cooperative
  - AER Boundary
  - Parks
  - First Nations
  - Trapper Boundaries
  - Grazing Reserves
  - Water Control Point
  - Critical Water
  - Control Point
  - Contours (m)
  - Egress Area
  - FMA
  - WMU
- Other Operator Wells and Pipelines represented in BROWN.**

Map Created by DM  
May 26, 2022

Revised by LN  
February 24, 2023

0 0.5 1 2  
Kilometers

Datum: NAD 83  
Projection: UTM Zone 11  
Mapscale: 1:36 000

NorthRiver Midstream Inc.

# Tupper Main

Emergency Planning Zone Map



**Notes**

- Location of residence in LSD is approximate. Well and Pipeline information is provided by IHS and must be considered approximate.
- Surface Developments
- Surface developments outside an EPZ have not been verified.

**Contact Information - British Columbia**

BC OGC - EMBIC: 1-800-663-3456  
Local Authority - Peace River Regional District: 1-800-670-7773  
RCMP Detachment - Dawson Creek RCMP: 250-784-3700

**Contact Information - Alberta**

Alberta Energy Regulator - AER: 1-800-222-6514  
Local Authority - County of Grande Prairie No 1: 780-532-9727  
RCMP Detachment - Beaverlodge RCMP: 780-354-2955  
Alberta Health Services - North Zone: 911

**10.1.16**      *CEPA E2 Supplemental Plan*

10.1.16	CEPA E2 Supplemental Plan .....	1
	Introduction .....	2
	Facility Overview .....	4
	Preparedness - CEPA E2 Plan Requirements.....	9
	Propane.....	18
	Facility Overview Plot Plan.....	19
	E2 Plan Appendix -Training Records Summary .....	20

### Introduction

The Canadian Environmental Protection Act (CEPA) 1999 requires the Government of Canada to take preventive and remedial measures to protect, enhance, and restore the environment. Under the Act and Environmental Emergency Regulations (E2), anyone storing or using a listed substance above specified thresholds, or who have a container with a capacity for that substance more than the specified quantity will have to notify Environment and Climate Change Canada (ECCC) of the place where the substance is held, along with the maximum expected quantity and the size of the largest container for that substance. If both the above criteria are exceeded, the Licensee is required to prepare and implement an Environmental Emergency Plan and notify Environment Canada accordingly.

Environment Canada recognizes that a licensee may already have in place an Emergency Response Plan (regulated by another federal or provincial agency) for the identified location; as such, the information under this E2 section is intended to supplement the preparedness, response and recovery methods established in the Core Emergency Response Plan.

Please refer to the CORE manual section 2 for further details on Policies, Purpose, Priorities, Objective, Scope, as required.

### E2 Schedule Timelines

Schedule	Title of Notice / Report	Timeline for Submission
Schedule 2	Notice Regarding Substance Located at Facility	Within 90 days of meeting or exceeding the substance quantity or container capacity threshold, and every 5 years thereafter.
		If applicable, within 60 days after the reported company information has changed or either of the maximum expected quantity or maximum capacity has increased by 10% or more
Schedule 3	Notice Regarding the Preparation of an Environmental Emergency Plan	Within 6 months of meeting or exceeding both the substance quantity and container capacity thresholds or only the quantity threshold for a substance that is not held in a container system
Schedule 4	Notice Regarding the Bringing into Effect of an Environmental Emergency Plan	Within 12 months of meeting or exceeding both the substance quantity and container capacity thresholds or only the quantity threshold for a substance that is not in a container system
Schedule 5	Notice Regarding Simulation Exercises Conducted in Relation to an Environmental Emergency Plan	Within 5 years after the day on which the E2 plan is brought into effect, and every 5 years thereafter
Schedule 6	Notice Regarding a Change in Quantity or Capacity	Within 60 days after the end of a 12-month period during which the threshold is no longer met
Schedule 7	Notice of Cessation of Operation	Within 30 days before the day on which the operations are to cease, or as soon as feasible in the case of extraordinary circumstances (e.g., a sudden plant shutdown).
	or Transfer of Operation	On or before the date of transfer

Schedule	Title of Notice / Report	Timeline for Submission
Schedule 8	Information to Be Included in the Written Report of Environmental Emergency*	As soon as reasonably possible in the case of 1. an environmental emergency involving the release of a hazardous substance that; a. has or may have an immediate or long-term harmful effect on the environment, or b. constitutes or may constitute a danger to the environment on which human life depends, or c. constitutes or may constitute a danger in Canada to human life or health. 2. The reasonable likelihood of an occurrence of an environmental emergency.

### **Training and Recording**

The E2 Regulations require that E2 Plans be exercised every year with respect to one substance from each of the applicable hazard categories identified in the E2 Regulations. A full-scale exercise must be carried out **every five years** with respect to any one substance using the alternate worse -case scenario or the worst-case scenario. The responsible person is also required to keep a record of the results of these annual and full-scale simulation exercises including: the date and summary of the exercise, the results of the exercise, and any modifications made to the plan as a result.

Role	CEPA Required Tabletop Exercise (Annually)	CEPA Required Live Exercise (Every 5th year)
Incident Commander	X	X
EOC Director	X	X
Public Protection Group Supervisor	X	X
On-Site Group Supervisor	X	X

Please see **APPENDIX – A** for summary of training.

**Facility Overview**

**Overview of Reportable Substances**

This E2 Plan is used in conjunction with the Tupper Main Registered Supplement and is required to meet Environment Canada’s regulatory requirement for the substances listed in the table below, that is stored on-site, which exceeds the threshold capacity.

The following table(s) list(s) the regulated substances owned by NorthRiver Midstream Inc., along with the quantity of the substance and facility location that have been registered with Environment Canada.

E2 ID#	ERP	Tank / Vessel ID Facility Location	Latitude / Longitude	Is the Substance in a Mixture? (yes/no)	Highest Compound	Activity in which the substance is being used.	UN #	Cas Registry #	% of Tank	Threshold Quantity of Product (t)	Max Expected Quantity on Site (t)	Largest Container System Capacity (t)	ECCC Hazard Category	Worst Case HPZ (KM)	Alternate Worst Case HPZ (KM)
<b>E2 CEPA Storage</b>															
E2-P9236 NAICS- 211110	Tupper Main ERP	Tupper Main Gas Plant A-021-B/093-P-09	55.3051954 / -120.7050946	no	LPG Bullet Propane	Storage (blending with crude oil)	1978	74-98-6	80%	4.5	2 tanks 5.68 M3, approx.. 3.31 tonnes	5.68 M3, approx. 3.31 tonnes	E	1.6	0.489
<b>Non-Registered Substances</b>															
E2-P9236 NAICS- 211110	Tupper Main ERP	Tupper Main Gas Plant A-021-B/093-P-09	55.3051954 / -120.7050946	no	Produced Water	Storage	1993	n/a	65%	n/a	5 tanks 2000 bbl each	5 tanks 2000 bbl each	n/a	0.050	0.050
				no	Condensate	Storage	1267	68919-39-1	65%	340	320 M3	320 M3	n/a	1.2	1.2

EPZs determined by 2020 Emergency Response Guidebook and/or Aloha Software 5.4.7.

See the maps at the end of this section for all locations.

**Note: Refer to your SDS for response measures.**

**Tupper Main Gas Plant A-021-B/093-P-09**
**Description of the property**

NorthRiver's Tupper Main field includes a gas plant located at A-021-B/093-P-09.

**Characteristics of the Location and Surrounding Area**

Environment and Climate Change Canada Sensitive Receptors	Inside the EPZ	Notes
Childcare and educational facility(ies)	No	
Health care facility(ies)	No	
Senior citizen's and long-term care facility(ies)	No	
Residential building(s) or Commercial building(s) (e.g. shopping malls, restaurants)	Yes	Residential buildings
Fire station(s)	No	
Industrial building(s)	Yes	Third party facilities.
Highway(s)	Yes	Highway 2 Highway 43 Highway 52
Railway station(s)	Yes	CN Rail
Bus station(s)	No	
Airport(s)	No	
Groundwater well(s) or intake(s) to drinking water systems	No	
Waterbody(ies) (e.g. creeks, rivers, lakes, and oceans)	Yes	Tupper River, Swan Lake, Keering Lake, Albright Lake, Chain Lakes, Ray Lake, Updike Lake, Updike Creek, Little Tupper Creek, Tupper Creek, Bordet Creek and a few unnamed rivers and creeks.
Park(s) or forest(s)	Yes	Swan Lake Park Sudeten Heritage Park
Fish and wildlife habitat area(s)	Yes	Swan Lake Park Sudeten Heritage Park
Other(s) (e.g. campgrounds, etc.)	Yes	Swan Lake Park Campground

Response Considerations	Notes
Cities/Towns/Villages	The City of Dawson Creek is located approximately 28 km northwest of the Tupper Main Gas Plant A-021-B/093-P-09 and has a population of +/- 12,178..
First Nations Reserves	None
Communication Considerations	Cell phones and plant telephones are the primary methods of communications.
Access Considerations	No obstacles to access the site, well maintained roads nearby. Where industrial roads exist, the pipelines can be accessed by road vehicles and off-road vehicles.
Other	None

### **Potential Consequences to the Public and Environment**

For an incident that is not impacting public safety, consider public notifications, as a courtesy.

In the event of an incident, which exposures will be a factor?

- Atmospheric
- Waterways
- Land

The item with a rank of 1 would be the most negatively impacted by an incident involving this tank / substance.

<b>Rank</b>	<b>Impacted</b>	<b>Potential Consequences</b>
1	Company Employees	<input type="checkbox"/> Fatality <input type="checkbox"/> Permanent Disability <input type="checkbox"/> Lost Time Injury <input type="checkbox"/> Illness <input type="checkbox"/> Medical Aid / First Aid (burns / exposure)
2	Other Workers in the Area	<input type="checkbox"/> Fatality <input type="checkbox"/> Permanent Disability <input type="checkbox"/> Lost Time Injury <input type="checkbox"/> Illness <input type="checkbox"/> Medical Aid / First Aid (burns / exposure)
3	General Public	<input type="checkbox"/> Illness <input type="checkbox"/> Medical Aid / First Aid (burns / exposure)
4	Environment	<input type="checkbox"/> Release into atmosphere / plume <input type="checkbox"/> Product would likely flash to vapour and dissipate <input type="checkbox"/> Release of flammable gas <input type="checkbox"/> Liquid spill on land
5	Equipment	<input type="checkbox"/> Equipment failure / damage <input type="checkbox"/> Complete loss of equipment <input type="checkbox"/> Lost revenues

**Preparation for and Response to Potential Emergency Scenarios**

Rank	Emergency Scenario	Preventative Measures		Response Actions	Recovery Actions
1	Container Degradation	<ul style="list-style-type: none"> <li>Preventative Maintenance Program</li> <li>Clean Work Areas</li> <li>Operator Present Daily</li> <li>Internal Inspections</li> <li>External Inspections</li> <li>Ultrasonic Testing</li> </ul>	<ul style="list-style-type: none"> <li>Internal Testing</li> <li>Proper Insulating</li> <li>Vessel Coating</li> <li>Cathodic Protection</li> <li>Gas Head Monitors</li> <li>NDT (Non-Destructive Testing)</li> <li>Asset Integrity Management</li> </ul>	<ul style="list-style-type: none"> <li>Repair as Needed</li> <li>Shutdown System</li> <li>Isolate and Drain Container</li> <li>Check Vessel Daily</li> <li>Clean Up Any Residual Product</li> </ul>	<ul style="list-style-type: none"> <li>Repair According to The Pressure Vessel Boiler Safety Authority</li> </ul>
2	Loading and unloading incidents	<ul style="list-style-type: none"> <li>Training / Exercises</li> <li>SWA (Stop Work Authority)</li> <li>JHA (Job Hazard Analysis)</li> <li>Clean Work Areas</li> <li>Equipment and Lines Are Clearly Identified</li> <li>Operator Present Daily</li> <li>Truck Loading / Unloading Procedures</li> </ul>	<ul style="list-style-type: none"> <li>Barriers (i.e. Concrete, Pole, Fence, Guards etc.)</li> <li>Break Away Valves</li> <li>Check Valves</li> <li>Positive Grounding Procedures</li> <li>Driver Competency Check</li> </ul>	<ul style="list-style-type: none"> <li>Initiate ERP (Emergency Response Plan) Procedures</li> <li>Repair as Needed</li> <li>Call Out System</li> <li>Close Secondary Valves</li> <li>Depressurize Vessel</li> <li>Operators to Assist Drivers</li> <li>Safety Program</li> </ul>	<ul style="list-style-type: none"> <li>Incident Investigation</li> <li>Clean Up by Environmental Department</li> </ul>
3	Fire	<ul style="list-style-type: none"> <li>Training / Exercises</li> <li>Clean Work Areas</li> <li>Equipment and Lines Clearly Identified</li> <li>Operator Present Daily</li> <li>Compliance to Class 1 (Div 1 &amp; 2 etc.)</li> <li>Skid Fire Eye Protection</li> <li>Fire Extinguishers</li> <li>Fire Detection Call Out System</li> </ul>	<ul style="list-style-type: none"> <li>Remote ESD (Emergency Shut Down)</li> <li>SCADA (Supervisory Control and Data Acquisition)</li> <li>Grounding Procedures for Vessels and Trucks</li> <li>Gas Monitors</li> <li>Fire Eye Monitors</li> <li>Spacing Requirements</li> </ul>	<ul style="list-style-type: none"> <li>Initiate ERP (Emergency Response Plan) Procedures</li> <li>Evacuate All Persons from Facility Outside of the EPZ (Emergency Planning Zone)</li> <li>ESD (Emergency Shut Down) Facility</li> <li>Isolate and De-Pressure System to Flare</li> </ul>	<ul style="list-style-type: none"> <li>Incident Investigation</li> <li>Repair According to The Pressure Vessel Boiler Safety Authority</li> </ul>
4	Pipe System Failure	<ul style="list-style-type: none"> <li>Preventative Maintenance Program</li> <li>Equipment and Lines Clearly Identified</li> <li>Operator Present Daily</li> <li>Isolation Valve</li> <li>Manual Block Valves</li> <li>HH Pressure Alarms</li> </ul>	<ul style="list-style-type: none"> <li>Automatic or Remote ESD (Emergency Shutdown Valve)</li> <li>Quality Management Program</li> <li>ABSA (Alberta Boilers Safety Association) Compliance</li> <li>Cathodic Protection</li> <li>NDT (Non-Destructive Testing)</li> <li>Asset Integrity Management</li> </ul>	<ul style="list-style-type: none"> <li>Initiate ERP (Emergency Response Plan) Procedures</li> <li>Repair as Needed</li> <li>Isolate Failed Piping</li> <li>Close Secondary Valves</li> <li>Close Auto Valves</li> <li>ESD (Emergency Shut Down) Facility If Failure Cannot Be Controlled</li> </ul>	<ul style="list-style-type: none"> <li>Repair According to The Pressure Vessel Boiler Safety Authority</li> </ul>

Rank	Emergency Scenario	Preventative Measures		Response Actions	Recovery Actions
5	Physical Container Damage (i.e. vehicle accident, etc.)	<ul style="list-style-type: none"> <li>• Training / Exercises</li> <li>• JHA (Job Hazard Analysis)</li> <li>• PSV (Pressure Safety Valve)</li> <li>• Clean Work Areas</li> <li>• Equipment and Lines Are Clearly Identified</li> <li>• Operator Present Daily</li> <li>• Restricted Areas</li> <li>• Barriers (i.e. Concrete, Pole, Fence, Guards etc.)</li> </ul>	<ul style="list-style-type: none"> <li>• Tank Farms</li> <li>• Signage</li> <li>• Check Valves</li> <li>• ESD (Emergency Shut Down) Valves</li> <li>• Use of Piles</li> <li>• Bullet Installed Away from High Traffic Areas</li> <li>• Retention Basin (Good Size, Watertight, Capacity, etc)</li> </ul>	<ul style="list-style-type: none"> <li>• Initiate ERP (Emergency Response Plan) Procedures</li> <li>• Repair as Needed</li> <li>• Isolate and Drain Container</li> <li>• Depressurize Vessel</li> <li>• Inspect (Integrity Engineering)</li> <li>• ESD (Emergency Shutdown) Valves</li> </ul>	<ul style="list-style-type: none"> <li>• Incident Investigation</li> <li>• Repair According to The Pressure Vessel Boiler Safety Authority</li> </ul>
6	Container Rupture	<ul style="list-style-type: none"> <li>• Training / Exercises</li> <li>• Preventative Maintenance Program</li> <li>• Operator Present Daily</li> <li>• Ultrasonic Testing</li> <li>• Internal Testing</li> <li>• PSV (Pressure Safety Valve)</li> <li>• PSV Serviced Regularly</li> <li>• HH Pressure Alarms</li> <li>•</li> </ul>	<ul style="list-style-type: none"> <li>• Automatic or Remote ESD (Emergency Shutdown Valve)</li> <li>• Vessel Inspections</li> <li>• ESD (Emergency Shut Down) Testing</li> <li>• Storage Units Inspected Daily</li> <li>• Discharge to Flare Header</li> <li>• NDT (Non-Destructive Testing)</li> <li>• Asset Integrity Management</li> </ul>	<ul style="list-style-type: none"> <li>• Initiate ERP (Emergency Response Plan) Procedures</li> <li>• Evacuate All Persons from Facility Outside of the EPZ (Emergency Planning Zone)</li> <li>• Call Out System High / Low Pressure</li> <li>• ESD (Emergency Shut Down) Facility</li> <li>•</li> </ul>	<ul style="list-style-type: none"> <li>• Incident Investigation</li> <li>• Repair According to The Pressure Vessel Boiler Safety Authority</li> </ul>
N/A	Product Reaction	<ul style="list-style-type: none"> <li>• Training / Exercises</li> <li>• Preventative Maintenance Program</li> <li>• SWA (Stop Work Authority)</li> <li>• JHA (Job Hazard Analysis)</li> <li>• Clean Work Areas</li> <li>• Equipment and Lines are Clearly Identified.</li> </ul>	<ul style="list-style-type: none"> <li>• Operator Present Daily</li> <li>• PPE (Personal Protective Equipment)</li> <li>• SCBA (Self-Contained Breathing Apparatus)</li> <li>• Respirator Cartridge</li> <li>• Loading Procedures</li> <li>• SDS onsite</li> </ul>	<ul style="list-style-type: none"> <li>• Initiate ERP (Emergency Response Plan) Procedures</li> <li>• Evacuate All Persons from Facility Outside of the EPZ (Emergency Planning Zone)</li> <li>• Isolate Source of Contamination</li> <li>• Proper Venting</li> <li>• First Aid</li> </ul>	<ul style="list-style-type: none"> <li>• Incident Investigation</li> <li>• Root Cause Analysis</li> </ul>

The potential emergency scenario with a rank of 1 is of greatest concern (most likely to occur / greatest consequence).

### Preparedness - CEPA E2 Plan Requirements

Requirement	Location in the ERP
Key Personnel/On-site contacts and emergency response duties	Sections 1.0 and 10.1.1 of the ERP lists personnel (roles and titles) who will make decisions and take leadership roles in the event of an environmental emergency.
Location of CEPA regulated substances	Tupper Main Gas Plant A-021-B/093-P-09
Location Characteristics	Tupper Main Gas Plant A-021-B/093-P-09
Emergency Equipment	Emergency Response Equipment See Section 10.1.7 for additional Emergency Response Equipment listings
Public Protection Methods	Methods of Public Protection section 9.1.7
Hazard prevention, preparation, response and recovery	Propane Fact Sheet
Properties and characteristics of substances	Propane Fact Sheet
Potential health effects	Propane Fact Sheet
Identification of possible emergency expected	Propane Fact Sheet
Identification of measures used to notify the public	Communication to the Public section 6.7.2. See also section 10.1.11 Notification and Communication to the Public

### Regulatory Notification and Incident Reporting

Notification of an environmental emergency must be performed by:

- any person who owned or had the charge, management, or control of the substance immediately before the environmental emergency, or
- any person who caused or contributed to the environmental emergency.

Contact Alberta Environment if the emergency involves any of the substances identified in Environment and Climate Change Canada's E2 List of regulated substances (Schedule #1).

- Note: CEPA has not identified specific reporting thresholds; however, CEPA has suggested that existing provincial reporting thresholds or TDG reporting thresholds are acceptable for use.

### Verbal Notification

Immediate verbal notification must take place by calling the applicable phone number identified in the table below (modified based on location of facility) which is associated with the province or territory where the environmental emergency occurred. Please note that verbal notification requirements under other regulations may also apply.

See sample "Verbal Release Report" for guidance on potential data required.

### Regional Contact Information

Province	24 Hour Telephone Line
Alberta	1-780-422-4205 or 1-800-222-6514
British Columbia	1-800-663-3456

Agency	Contact	Notes
ERAC	<p><b>ERAC Telephone number to activate the plan</b> <b>1-800-265-0212</b></p> <p>Company ERAP # ERAP 2-0010-083</p> 	<p>NorthRiver is a subscribed member of Emergency Response Assistance Canada.</p> <p>ERAC is a not-for-profit corporation created by industry for industry and is a subsidiary of the Canadian Propane Association. As a co-operative emergency preparedness and response organization, they are prepared for any flammable gases and liquids incident by road or rail. They also provide emergency response for flammable gases and stationary tanks. ERAC provides comprehensive emergency response and preparedness services to organizations requiring an Emergency Response Assistance Plan (ERAP) under the Transportation of Dangerous Goods Act.</p>
<p>Note: That Emergency Response Assistance Canada (ERAC)'s Emergency Response Assistance Plan (ERAP) provides emergency response support to road, rail and stationary tank incidents (&gt;450 L), if ERAC is unable to respond to the regulated substance emergency, NorthRiver must call on another Emergency and Industry Support Service, that are best able to support the specified incident. Please refer to link for response parameters and exemptions. <a href="https://erac.org/en/services/emergency-response-assistance-plans-eraps">https://erac.org/en/services/emergency-response-assistance-plans-eraps</a></p>		
CANUTEC	<p>1-888-226-8832 or 1-613-996-6666</p>	<p>Canadian Transport Emergency Centre (CANUTEC) is operated by Transport Canada where they must be contacted in the case of:</p> <ul style="list-style-type: none"> <li><input type="checkbox"/> a release or anticipated release report (road, rail, marine);</li> <li><input type="checkbox"/> a dangerous goods accident or incident report (air);</li> <li><input type="checkbox"/> an undeclared or mis-declared dangerous goods report (air)</li> <li><input type="checkbox"/> a loss or theft report (road, rail, marine, air); or</li> <li><input type="checkbox"/> an unlawful interference report (road, rail, marine, air)</li> </ul> <p>Note: CANUTEC advisors do not go to the scene of an incident, they offer technical expertise only.</p>

### Written Notification

Written notification of environmental emergencies must take place within 30 days through one of two ways:

- Schedule 8 through Single Window Information Manager (SWIM) dashboard using their login credential or
- Written report (for non-registered sites). See sample "Written Release Report".

**Access to the E2 online Reporting System**

The link to the SWIM portal is: <https://ec.ss.ec.gc.ca>.

A facility or person that is not registered in the E2 Online reporting system must submit a written report regarding an environmental emergency through the following public link <https://pollution-waste.canada.ca/spill-reporting>.

Completing this process fulfills the requirements for the provision of a written report under Section 18 of the E2 Regulations.

**Verbal Release Report**

Name of Person Who Reported the Release to the Company:		Phone #:	
Name of Person Who Discovered the Release:		Phone #:	
Name of Company Personnel Release was Reported To:		Phone #:	
How was Release Reported to the Company: <input type="checkbox"/> Verbal/In Person <input type="checkbox"/> Verbal/Phone Call <input type="checkbox"/> Other			
Location of Release (LSD, facility, etc.):			
Date of Notification to the Company:		Time of Notification to the Company:	
Date of Discovery:		Time of Discovery:	
Date or Estimated Date of Occurrence:		Time or Estimated Time of Occurrence:	
Type of Material Released:		Quantity or Estimated Quantity of Release:	
Is the health or safety of any individuals (residences, communities, etc.) in imminent danger? <input type="checkbox"/> Yes <input type="checkbox"/> No			
If "Yes" provide details.			
Are any specially designated environmental areas (wetland, preserves, etc.) in imminent danger? <input type="checkbox"/> Yes <input type="checkbox"/> No			
If "Yes" provide details.			
Was any waterway affected? <input type="checkbox"/> Yes <input type="checkbox"/> No			
If "Yes" provide details including name of waterway.			
Was release contained? <input type="checkbox"/> Yes <input type="checkbox"/> No			
If "No" provide details including dimensions of release (length, width depth).		If "Yes" provide details including containment (within firewall, booms, etc.).	
Description of release and impacts including well(s) and/or facilities involved, source of release (stuffing box rubber on well head burned up, internal corrosion on flow line, etc.).			
Direction of flow:		Weather conditions:	
Actions taken to control release.			
Date of Verbal Notification to Alberta Environment:		Time of Verbal Notification to Alberta Environment:	
Name and Title of Person at Alberta Environment that took the Report:			
Name of Person Filling Out Report:		Title:	
Signature of Person Filling Out Report:			Date:

Names of employees summoned to assist in containment and/or clean-up effort:	
1.	2.
3.	4.
Names of contractor(s) summoned to assist in containment (if any):	
Contractor:	Cost:
Contractor:	Cost:
Contractor:	Cost:
Names of contractor(s) summoned to assist in cleanup (if any):	
Contractor:	Cost:
Contractor:	Cost:
Contractor:	Cost:
Names of special cleanup equipment used (if any):	
Equipment:	Cost:
Describe additional remedial action taken and current status.	
Name of Person Filling Out Report:	Title:
Signature of Person Filling Out Report:	
Date of Report:	
How was Release Report Sent? <input type="checkbox"/> Email <input type="checkbox"/> Fax <input type="checkbox"/> Post <input type="checkbox"/> Other	
Report sent to:	
Company Representative:	Phone #:
Company Name:	Phone #:
Address:	
City, Province:	Postal Code:

The verbal report should include as much of the following information as is known at the time when contacting Alberta Environment. Follow up the above verbal report with a written report of the environmental emergency to Alberta Environment as soon as is practicable under the circumstances.

**Written Release Report (Non-Registered)**

A written report of the environmental emergency should be submitted to Alberta Environment as soon as is practicable under the circumstances. Reports are required to be submitted no later than 30 days after the release.		A facility or person that is not registered in the E2 Online reporting system must submit a written report regarding an environmental emergency through the following public link <a href="https://pollution-waste.canada.ca/spill-reporting">https://pollution-waste.canada.ca/spill-reporting</a> .	
Date of Report:		Date and Time Release:	
Name of Person in Charge:		Address of Person in Charge:	
Phone # of Person in Charge:			
Location of Release (LSD, facility, etc.):			
Name of Substance Released:		UN# of Substance Released:	
Composition of the Substance Released:		Concentration:	Total Weight:
Quantity or Estimated Quantity of Release:		Total Quantity of Substance Prior to Release:	
Means of Containment Before Release:		Duration of Release and Release Rate:	
Means of containment (from which substance was released and a description of its condition):			
Number of deaths and injuries resulting from the environmental emergency:			
Sequence of Events Before and After the Emergency (include cause if known):			
Names of Agencies Notified or On-Scene at the Time of the Release:			

Measures Taken to Protect the Public:			
Notification to any member of the public adversely affected by the environmental emergency:			
Measures to be Taken to Prevent a Similar Release:			
Name of Person Filling Out Report:		Title:	
Signature of Person Filling Out Report:			Date of Report:
How was Spill Report Sent? <input type="checkbox"/> Email <input type="checkbox"/> Fax <input type="checkbox"/> Post <input type="checkbox"/> Other			

**Notification and Communication to the Public**

NorthRiver has created a Public Information Pamphlet (PIP) to discuss the following:

- the possibility that the environmental emergency could occur,
- the potential effects of the environmental emergency on the environment and on human life or health, considering the substance, the activity the substance is used, and the facility and surrounding area features.
- the measures that will be taken to protect the environment and human life or health.
- the means of communications if the environmental emergency occurs.

The PIP was provided to any surface developments within the CEPA EPZ/HPZ as well as mailed out to Area Users (i.e., Oil and Gas Operators, Railways, Trapper, Guides & Outfitters, Grazing Leases, and Forestry Management Units). Emergency contact information was gathered for the surface developments within the CEPA EPZ and has been included within this plan.

The Public Protection Group Supervisor is responsible for initiating and managing public protection measures, with information and guidance concerning the actions that could be taken to reduce the potential harm to the environment and danger to human life or health, including an explanation of how those actions may help to reduce the harm or danger. (See [Section 3.5](#) for additional roles and responsibilities.)

Notification and continued communication with the public if an environmental emergency involving the release of a substance can be found in the Crisis Communication [Section 6.0](#). Additionally, Roles and Responsibilities would be assigned to the Public Protection Group Supervisor and Information Officer.

The Information Officer will develop a communication strategy to ensure information and releases are appropriate, consistent, accurate, and timely. See [Section 4.6](#) for additional roles and responsibilities.

### Notification and Communication to Local Authorities

Notification and confirmation of the local authorities' roles can be found in the Tupper Main field section & Subsection 10.1.11.

#### Authority Roles Coordination

Type of Agency	Agency Name	Provided Specific Roles	Provided Generic Roles	Notes
RHA	<b>Health Emergency Management BC, North (HEMBC)</b> Dawson Creek Health Unit Owen Brokenshire, Coordinator			This agency is contacted by NorthRiver Midstream and provided with the latest stakeholder pamphlet and their role and responsibilities to ensure up to date information regarding operations in their area.
Local Authority	<b>Peace River Regional District – Dawson Creek</b> Sean Cairns, Protective Services Manager			This agency is contacted by NorthRiver Midstream and provided with the latest stakeholder pamphlet and their role and responsibilities to ensure up to date information regarding operations in their area.
RHA	<b>Alberta Health Services, North Zone 5</b> Shane Hussey, Northern Zone 5 Director, Environmental Public Health			This agency is contacted by NorthRiver Midstream and provided with the latest stakeholder pamphlet and their role and responsibilities to ensure up to date information regarding operations in their area.
Local Authority	<b>County of Grande Prairie No. 1</b> Trevor Grant - Fire Chief			This agency is contacted by NorthRiver Midstream and provided with the latest stakeholder pamphlet and their role and responsibilities to ensure up to date information regarding operations in their area.

All mutual aid role confirmation and supporting documentation is available upon request.

Physical Properties		General Description																				
Chemical Formula	C <sub>3</sub> H <sub>8</sub>	<p>A colorless gas with a faint petroleum-like odor. It is shipped as a liquefied gas under its vapor pressure. For transportation it may be stenched. Contact with the unconfined liquid can cause frostbite by evaporative cooling. Easily ignited. The vapors are heavier than air and a flame can flash back to the source of leak very easily. The leak may be either a liquid or vapor leak. The vapors can asphyxiate by the displacement of air. Under prolonged exposure to fire or heat the containers may rupture violently and rocket.</p> <table border="1"> <thead> <tr> <th>NFPA Diamond</th> <th>Hazard</th> <th>Value</th> <th>Description</th> </tr> </thead> <tbody> <tr> <td rowspan="4"> </td> <td>Health</td> <td>2</td> <td>Can cause temporary incapacitation or residual injury.</td> </tr> <tr> <td>Flammability</td> <td>4</td> <td>Burns readily. Rapidly or completely vaporizes at atmospheric pressure and normal ambient temperature.</td> </tr> <tr> <td>Instability</td> <td>0</td> <td>Normally stable, even under fire conditions.</td> </tr> <tr> <td>Special</td> <td></td> <td></td> </tr> </tbody> </table>				NFPA Diamond	Hazard	Value	Description		Health	2	Can cause temporary incapacitation or residual injury.	Flammability	4	Burns readily. Rapidly or completely vaporizes at atmospheric pressure and normal ambient temperature.	Instability	0	Normally stable, even under fire conditions.	Special		
NFPA Diamond	Hazard					Value	Description															
	Health					2	Can cause temporary incapacitation or residual injury.															
	Flammability					4	Burns readily. Rapidly or completely vaporizes at atmospheric pressure and normal ambient temperature.															
	Instability					0	Normally stable, even under fire conditions.															
	Special																					
Flash Point	-156°F																					
Lower Explosive Limit (LEL)	2.1%																					
Upper Explosive Limit (LEL)	9.5%																					
Autoignition Temperature	842°F																					
Melting Point	-305.9°F																					
Vapor Pressure	9823 mm Hg																					
Vapor Density (Air = 1)	1.5																					
Boiling Point	-43.8°F at 760 mm Hg																					
Water Solubility	0.01%																					
IDLH (as Propane). Based on 10% of lower explosive limit. (NIOSH, 2016)	2100 ppm																					

**ECCC Hazard Category**

**CAS # 74-98-6**

**UN# 1978**

**TC ERG Guide # 115**

Information on this page is from CAMEO Chemicals, NIOSH Pocket Guide to Chemical Hazards, Environment and Climate Change Canada and the Transport Canada Emergency Response Guidebook

**POTENTIAL HAZARDS**

**FIRE OR EXPLOSION**

- EXTREMELY FLAMMABLE.
- Will be easily ignited by heat, sparks or flames.
- Will form explosive mixtures with air.
- Vapors from liquefied gas are initially heavier than air and spread along ground.
- Vapors may travel to source of ignition and flash back.
- Cylinders exposed to fire may vent and release flammable gas through pressure relief devices.
- Containers may explode when heated.
- Ruptured cylinders may rocket.

**HEALTH**

- Vapors may cause dizziness or asphyxiation without warning.
- Some may be irritating if inhaled at high concentrations.
- Contact with gas or liquefied gas may cause burns, severe injury and/or frostbite.
- Fire may produce irritating and/or toxic gases.

**PUBLIC SAFETY**

- As an immediate precautionary measure isolate spill or leak area for at least 100 meters (330 feet) in all directions
- Keep unauthorized personnel away.
- Stay upwind, uphill and/or upstream.
- Many gases are heavier than air and will spread along the ground and collect in low or confined areas (sewers, basements, tanks, etc.).

**PROTECTIVE CLOTHING**

- Wear positive pressure self-contained breathing apparatus (SCBA).
- Structural firefighters' protective clothing provides thermal protection but only limited chemical protection.
- Always wear thermal protective clothing when handling refrigerated/cryogenic liquids.

**PUBLIC SAFETY**

**EVACUATION - Immediate precautionary measure**

- Isolate spill or leak area for at least 100 meters (330 feet) in all directions.

**Large Spill**

- Consider initial downwind evacuation for at least 800 meters (1/2 mile).

**Fire**

- If tank, rail car or tank truck is involved in a fire, ISOLATE for 1600 meters (1 mile) in all directions; also, consider initial evacuation for 1600 meters (1 mile) in all directions.

**EMERGENCY RESPONSE**

**FIRE**

- DO NOT EXTINGUISH A LEAKING GAS FIRE UNLESS LEAK CAN BE STOPPED.

**Small Fire**

- Dry chemical or CO<sub>2</sub>.

**Large Fire**

- Water spray or fog.
- If it can be done safely, move undamaged containers away from the area around the fire.

**Fire Involving Tanks**

- Fight fire from maximum distance or use unmanned master stream devices or monitor nozzles.
- Cool containers with flooding quantities of water until well after fire is out.
- Do not direct water at source of leak or safety devices; icing may occur.
- Withdraw immediately in case of rising sound from venting safety devices or discoloration of tank.
- ALWAYS stay away from tanks engulfed in fire.
- For massive fire, use unmanned master stream devices or monitor nozzles; if this is impossible, withdraw from area and let fire burn.

**EMERGENCY RESPONSE**

**SPILL OR LEAK**

- ELIMINATE all ignition sources (no smoking, flares, sparks or flames) from immediate area.
- All equipment used when handling the product must be grounded.
- Do not touch or walk through spilled material.
- Stop leak if you can do it without risk.
- If possible, turn leaking containers so that gas escapes rather than liquid.
- Use water spray to reduce vapors or divert vapor cloud drift. Avoid allowing water runoff to contact spilled material.
- Do not direct water at spill or source of leak.
- Prevent spreading of vapors through sewers, ventilation systems and confined areas.
- Isolate area until gas has dispersed.


**CAUTION:** When in contact with refrigerated/cryogenic liquids, many materials become brittle and are likely to break without warning.

**FIRST AID**

- Call 911 or emergency medical service.
- Ensure that medical personnel are aware of the material(s) involved and take precautions to protect themselves.
- Move victim to fresh air if it can be done safely.
- Give artificial respiration if victim is not breathing.
- Administer oxygen if breathing is difficult.
- Remove and isolate contaminated clothing and shoes.
- Clothing frozen to the skin should be thawed before being removed.
- In case of contact with liquefied gas, thaw frosted parts with lukewarm water.
- In case of burns, immediately cool affected skin for as long as possible with cold water. Do not remove clothing if adhering to skin.
- Keep victim calm and warm.

**PROPANE**

*Facility Overview Plot Plan*




**TUPPER MAIN PLANT  
SAFETY EQUIPMENT LEGEND**

	SELF CONTAINED BREATHING APPARATUS
	FIRST AID
	EYEWASH STATION
	MUSTER AREA
	STRETCHER
	SHOWER & EYEWASH STATION
	FIRE EXTINGUISHER




Twp 76  
Twp 75  
Twp 74



- NorthRiver Wells**
- Gas
  - Oil
  - Standing
  - Injection
  - Suspended Gas
  - Suspended Oil
  - Water
  - Bottom Hole
  - Well EPZ
  - Discontinued
  - Sour Gas
  - Natural Gas / Fuel Gas
  - Oil
  - Water
  - HVP / LVP
  - Block Valves
  - Pipeline HPZ
  - Major Transmission Lines
- NorthRiver Pipelines**
- Injection Point
  - Meter Station
  - Pump Station
  - Satellite
  - Facility EPZ
  - Storage HPZ
- NorthRiver Facilities**
- Battery
  - Compressor Station
  - Gas Plant
  - Gathering Point
  - Injection Plant
  - Meter Station
  - Pump Station
  - Satellite
  - Facility EPZ
  - Storage HPZ
- Transportation**
- High Grade Roads
  - Resource Roads
  - Low Grade / Seasonal
  - Secondary Highway
  - Primary Highway
  - Radio Controlled Roads
  - Railways
  - Dead Ends
  - Locked Gates
  - Roadblocks
  - Bridge
- Residents**
- Surface Development
  - Occupied
  - Sensitive
  - Business
  - Cabin
  - Occupied Part-Time
  - Vacant
  - Campground
  - Cemetery
  - Church
  - Community Hall
  - Farm / Ranch
  - Grain Bin
  - Gravel Pit
  - School
  - Shop
  - Tower
  - Fire Tower
  - Work Camp
  - Hospitals
  - Reception Centre
  - Stars Air Ambulance
- Other Symbols**
- Urban Area
  - Hydrology
  - Intermittent Waterbody
  - Permanent Waterbody
  - Airfields
  - Municipal District
  - Health Region
  - RCMP
  - WCSS Cooperative
  - AER Boundary
  - Parks
  - First Nations
  - Trapper Boundaries
  - Grazing Reserves
  - Water Control Point
  - Critical Water Control Point
  - Contours (m)
  - Egress Area
  - FMA
  - WMU
- Other Operator Wells and Pipelines represented in BROWN.**

Map Created by DM May 26, 2022  
Revised by LN February 24, 2023



Datum: NAD 83  
Projection: UTM Zone 11  
Mapscale: 1:36 000

NorthRiver Midstream Inc.  
**Tupper Main**  
Emergency Planning Zone Map



**Notes**  
Location of residence in LSD is approximate. Well and Pipeline information is provided by IHS and must be considered approximate.  
**Surface Developments**  
Surface developments outside an EPZ have not been verified.

**Contact Information - British Columbia**  
BC OGC - EMBIC: 1-800-663-3456  
Local Authority - Peace River Regional District: 1-800-670-7773  
RCMP Detachment - Dawson Creek RCMP: 250-784-3700

**Contact Information - Alberta**  
Alberta Energy Regulator - AER: 1-800-222-6514  
Local Authority - County of Grande Prairie No 1: 780-532-9727  
RCMP Detachment - Beaverlodge RCMP: 780-354-2955  
Alberta Health Services - North Zone: 911

**E2 Plan Appendix - Training Records Summary**

<b>Training Type</b>	<b>Hazard Category</b>	<b>Emergency Scenario (WC, AWC or C)</b>	<b>Site Location</b>	<b>Date</b>

Worst Case (WC), Alternate Worst Case (AWC) and third scenario C.  
Official training records can be provided upon request.

## 10.2 Tupper Main CER Regulated Pipeline

### 10.2.1 Contact Information

All incidents, accidents and occurrences as defined by the Onshore Pipeline Regulations (OPR), the Canada Labour Code, and the Transportation Safety Board (TSB) Regulations should be reported.

#### CALL

For emergencies involving inter-provincial or cross border pipelines, the CER is the Regulatory Authority.

In the event of a CER regulated pipeline emergency, call the TSB's 24-hour hotline (collect calls accepted). The TSB will contact the CER to notify them of the incident.

**1-819-997-7887**

#### ONLINE REPORTING

Report all events on the CER's Online Event Reporting System.

This system is intended for use by regulated companies to provide notification to the Canada Energy Regulator (CER) and Transportation Safety Board (TSB) of various events that are defined in regulation including incidents, unauthorized activities, and operations and maintenance activities.

**<https://apps.cer-rec.gc.ca/ERS/Home/Index/>**

### 10.2.2 Tupper Main CER Telephone Directory

**NorthRiver 24-Hour Emergency Number**  
**1-844-667-8477**

**NorthRiver Main Number**  
**587-747-6500**

Field Office			
Telephone Number		[REDACTED]	
Address		[REDACTED]	
Name	Position	Office	Cell
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

### Alberta Government Agencies

Resource	Contact	Office	Cell/24 Hour
Alberta Energy Regulator	Energy and Environmental Emergency 24-Hour Response Line	--	1-800-222-6514
	Inquiry Line	--	1-855-297-8311
	24/7 Media Centre	--	1-855-474-6356
	Northwest Field Operations - Grande Prairie	1-780-538-5138	1-800-222-6514
County of Grande Prairie No. 1	Trevor Grant - Fire Chief (County of GP Fire Service)	1-780-532-9722	1-780-532-9727
Saddle Hills County	Brice Daly, Manager of Protective Services	1-780-864-3760	Duty officer Cell: 1-780-864-0439
RCMP - Beaverlodge Detachment	NCO In Charge	1-780-354-2955	911
Alberta Health Services	Province-wide	<a href="mailto:epd@ahs.ca">epd@ahs.ca</a>	811 / 911 Provincial Number: 1-833-476-4743
Alberta Health Services, North Zone 5	Shane Hussey, Northern Zone 5 Director, Environmental Public Health	1-833-476-4743	811 / 911

Resource	Contact	Office	Cell/24 Hour
Alberta Emergency Management Agency	Province-wide	1-780-422-9000	1-866-618-2362
	Meghan Thomas, Team Lead, Alberta Emergency Alert	1-780-644-4447	1-780-996-2062
Alberta Emergency Management Agency, Northwest Region	Alan Stebbing, Emergency Management Field Officer	Cell: 1-587-783-9201 Email: <a href="mailto:Alan.Stebbing@gov.ab.ca">Alan.Stebbing@gov.ab.ca</a>	24-Hour: 1-866-618-2362
	Chris Graham, Emergency Management Field Officer	Cell: 1-825-993-4235 Email: <a href="mailto:Chris.Graham@gov.ab.ca">Chris.Graham@gov.ab.ca</a>	24-Hour: 1-866-618-2362
Alberta Environment and Parks - Energy & Environment Response Line	Energy & Environment Response Line	--	1-800-222-6514
	Peace Region (Peace River)	1-780-624-7133	1-800-222-6514
Alberta Agriculture and Forestry Report a Wildfire	Ag-Info Centre Province-wide	-- --	310-FARM (3276) 310-FIRE (3473)
Alberta Occupational Health and Safety	Province-wide	1-866-415-8690	1-866-415-8690
Alberta Edge (Environment and Dangerous Goods Emergencies)	Province-wide	1-780-422-9600	1-800-272-9600
Highway Maintenance Contractors	Ledcor Highways Ltd.	1-866-453-3267	1-866-453-3267
Utility Safety Partners	Province-wide	1-800-242-3447	--
Poison & Drug Information Service	Province-wide	--	1-800-332-1414
Alberta Boilers Safety Association (ABSA)	Edmonton	--	1-780-437-9100
Government of Alberta Toll-Free Dialing	Province-wide	--	310-0000 then 10 digit number or 0 for Operator
Government of Canada - DFO (Department of Fisheries and Ocean)	Province-wide	--	1-800-889-8852
Environment and Climate Change Canada	Canada-wide	1-800-668-6767	--
CN Railway Co. - Police Service	Canada-wide	--	1-800-465-9239
CP Railway - Police Service	Canada-wide	--	1-800-716-9132
CANUTEC TDG - Emergency Reporting Line	Canada-wide	--	1-888-226-8832 *666 Cell Phone
Transportation Safety Board (CER Regulated Emergencies)	Canada-wide	--	1-819-997-7887
NAV Canada - Notice to Airmen	Canada-wide	--	1-866-992-7433

**British Columbia Government Agencies**

Resource	Contact	Office	Cell/24 Hour
Emergency Management BC – EMBC	Emergency Coordination Centre 1st call in a Level 1 or greater emergency. The EMBC will forward on the emergency notification onto the BCER On-Call Duty Officer.	--	1-800-663-3456
	North East Region	1-250-612-4172	1-800-663-3456
British Columbia Energy Regulator	Non-Emergency Office Line	1-250-794-5200	Emergency notification received through EMBC
Peace River Regional District (Zone B-C-D-E)	Protective Services Coordinator	Direct: 1-250-784-3222 Reception: 1-250-784-3200	1-800-670-7773
RCMP - Dawson Creek Detachment	NCO In Charge	1-250-784-3700	911
Health Emergency Management BC, North (HEMBC)	Dawson Creek Health Unit	--	1-855-554-3622
Ministry of Environment & Climate Change Strategy - Peace Region	Peace Region Office	1-250-787-3411	1-800-663-3456
	Environmental Emergency Response Officer (Peace Region)	1-250-262-9285	1-800-663-3456
Ministry of Forests - Peace Natural Resource District	Peace Forest District – Dawson Creek	1-250-784-1200	--
	Resource Manager - Dawson Creek	1-250-795-4178	--
WorkSafe BC	Occupational Safety Officer - Fort St. John	1-250-785-1283	--
	24 Hour Number	--	1-888-621-7233 (SAFE)
Ministry of Transportation and Infrastructure – Peace District	Peace District Office	1-250-787-3237	--
	District Manager - Dawson Creek Area	1-778-576-1108	1-250-261-3077
Argo Road Maintenance (South Peace) Inc.	South Peace – Service Area 21	1-800-663-7623	1-800-663-7623
Drug and Poison Information Centre	Province-wide	1-604-682-5050	1-800-567-8911
Report a Wildfire	Province-wide	1-250-565-6716 (PG Fire Centre)	1-800-663-5555 *5555 Cell Phone
Technical Safety BC	Province-wide	1-866-566-7233	--

Resource	Contact	Office	Cell/24 Hour
BC Hydro	Province-wide	1-888-POWERON (1-888-769-3766) *49376 Cell Phone	--
Environmental Emergency Reporting Line	Province-wide	--	1-800-663-3456
Public Services and Procurement Canada - BC Alaska Highway Maintenance	Province-wide	1-250-774-6956	--
Government of Canada - DFO (Department of Fisheries and Ocean)	Province-wide	--	1-800-889-8852
Environment and Climate Change Canada	Canada-wide	1-800-668-6767	--
CN Railway Co. - Police Service	Canada-wide	--	1-800-465-9239
CP Railway - Police Service	Canada-wide	--	1-800-716-9132
CANUTEC TDG - Emergency Reporting Line	Canada-wide	--	1-888-226-8832 *666 Cell Phone
Transportation Safety Board (CER Regulated Emergencies)	Canada-wide	--	1-819-997-7887
NAV Canada - Notice to Airmen	Canada-wide	--	1-866-992-7433

### Emergency Services

Contact	Location	Telephone
<b>Emergency Response Assistance Plan (ERAP)</b>		
Emergency Response Assistance Canada ERAP # ERP 2-0010-083	Canada-wide	1-800-265-0212
<b>Ambulance - Municipal</b>		
BC Ambulance Service	BC-wide	1-800-461-9911 (where 911 not available)
Alberta Health Services - Emergency Dispatch (SAT Phones)	Alberta-wide	1-780-624-3911
Alberta Health Services - EMS	Alberta-wide	911
<b>Ambulance - Oilfield</b>		
HSE Integrated	AB / BC wide	1-888-346-8260
Safety Boss	AB / BC wide	1-800-882-4967
911 Industrial Response	Grande Prairie	1-866-694-9111
<b>Air Ambulance</b>		
Alberta Central Air (ACA) - Medivac Flight Services	Grande Prairie	1-780-814-5888
BCAS Provincial Air Ambulance Coordination Centre	BC-wide	1-250-785-2079 or 911
<b>STARS</b> 115 Landing Site Number Tupper Main Gas Plant a-21-B/93-P-09	AB / BC-wide	1-888-888-4567 or 1-403-299-0932
<b>Hospitals</b>		
Dawson Creek & District Hospital	Dawson Creek	1-250-782-8501
Beaverlodge Municipal Hospital	Beaverlodge	1-780-354-2136
Taylor Medical Clinic	Taylor	1-250-789-6772
<b>Fire Fighters - Municipal</b>		
Tomslake Fire Department*	Tomslake, BC	1-250-784-3890
County of Grande Prairie Fire Department*	Grande Prairie, AB	1-780-532-9727
Pouce Coupe Fire Hall	Pouce Coupe	1-250-786-5794
Wildfire Management Branch Report Wildfires line	Fort St. John	1-800-663-5555 *5555 from a cell phone
<b>Fire Fighters - Oilfield</b>		
HSE Integrated	AB / BC wide	1-888-346-8260
Trojan Safety Services Ltd.	Fort St. John	1-250-785-9557
Safety Boss	AB / BC wide	1-800-882-4967

On the BC side, portions of the EPZ fall under Tomslake coverage. The rest of the BC field does NOT have fire coverage from any local fire department. These fires must be handled by NorthRiver Midstream, mutual aid partners, or contract oilfield fire fighting services. Local fire departments will only respond to motor vehicle accidents and medical emergencies unless specifically dispatched by EMBC or the Local Authority. On the AB side, the EPZ falls under Grande Prairie Fire Department coverage.

**Industry Support Services**

Contact	Location	Telephone
<b>Air Quality Monitoring Equipment</b>		
HSE Integrated	Grande Prairie	1-780-532-2088
Ember Medical & Safety Ltd.	Grande Prairie	1-780-933-0668
Trojan Safety Services Ltd. - BC	Fort St. John	1-250-785-9557
<b>Backhoes</b>		
H.F. Nodes Construction	Pouce Coupe	1-250-786-5474
Reg Norman Trucking Ltd.	Dawson Creek	1-250-782-2778
OCL Group Inc.	Dawson Creek	1-778-949-5023
<b>Communication Equipment (Radio/Telephones)</b>		
North Peace Communications Ltd.	Dawson Creek	1-250-782-6664
Epscan Communications	Dawson Creek	1-250-782-9656
Whitetail Energy Services Inc.	Dawson Creek	1-844-782-9524
<b>Construction Company</b>		
H.F. Nodes Construction	Pouce Coupe	1-250-786-5474
Klassen Bros Construction	Pouce Coupe	1-780-957-3760
OCL Group Inc.	Dawson Creek	1-778-949-5023
<b>Cranes / Picker Services</b>		
SI's Oilfield Hauling Ltd.	Dawson Creek	1-250-784-5533
Northwell Oilfield Hauling (09) Inc.	Dawson Creek	1-250-795-5000
Hurst Anchors & Rentals Ltd.	Dawson Creek	1-250-784-1887
<b>Grief Counsellor</b>		
Peace Counselling	Dawson Creek	1-778-864-0560
Life Compass Counselling Services	Dawson Creek	1-250-719-7844
Burden Bearers Counselling Center	Grande Prairie	1-780-539-5225
<b>Helicopters</b>		
Ridge Rotors	Tumbler Ridge	1-877-242-4211
Mustang Helicopters Inc.	Grande Prairie	1-780-882-9182
Gemini Heli Ltd	Grande Prairie	1-780-539-4354
<b>Hotels / Potential Reception Centres</b>		
Grand Marshal Inn	Hythe	1-780-356-2151
Pomeroy Inn & Suites	Dawson Creek	1-866-782-3577
Northwinds Lodge	Dawson Creek	1-250-782-9181
<b>Radio Stations</b>		
890 AM CJDC - Bell Media Inc.	Dawson Creek	1-250-782-3341
104.1 Peace FM	Dawson Creek	1-250-784-2002
CHRX-FM-1 95.1 FM - Bell Media	Dawson Creek	1-250-785-6634
<b>Safety Equipment / Personnel</b>		
Total Oilfield Rentals Ltd.	Dawson Creek	1-250-719-0505
HSE Integrated	Grande Prairie	1-780-532-2088
Herc Equipment Rental	Grande Prairie	1-780-538-9499
<b>Spill Response / Environmental Services</b>		
Vertex Resource Group Ltd.	Dawson Creek	1-250-719-0353
Parkland Geotechnical Ltd.	Grande Prairie	1-780-539-5102
Badger Daylighting	Grande Prairie	1-780-538-2777

Contact	Location	Telephone
<b>Supply Stores</b>		
P.C. Oilfield Construction Supplies Ltd.	Dawson Creek	1-250-782-5134
Mas-Pro	Clairmont	1-780-832-9899
Gregg Distributors Ltd.	Clairmont	1-780-567-2238
<b>Tank Rentals</b>		
SI's Oilfield Hauling Ltd.	Dawson Creek	1-250-784-5533
B & C Trucking Inc.	Dawson Creek	1-250-219-6055
Whitetail Energy Services Inc.	Dawson Creek	1-844-782-9524
<b>Tank Trucks</b>		
Swamp Donkey Inc.	Dawson Creek	1-250-219-8370
CEDA West Services	Dawson Creek	1-250-784-5151
Wilmar Oilfield Pressure Services Ltd.	Beaverlodge	1-780-518-6964
<b>Vac and Steam Trucks</b>		
Swamp Donkey Inc.	Dawson Creek	1-250-219-8370
CANVAC Oil Field Services	Dawson Creek	1-250-784-7066
Vertex Resource Group Ltd.	Dawson Creek	1-250-719-0353
<b>Well Control Equipment</b>		
Safety Boss	Alberta / BC -wide	1-800-882-4967
Hellfire Suppression Services Inc.	Alberta / BC-wide	1-877-846-4499
Halliburton Boots & Coots	Alberta / BC-wide	1-800-BLOWOUT (256-9688) 1-281-931-8884
<b>Wellsite Accommodations</b>		
Longhorn Oilfield Services	Dawson Creek	1-855-855-7353
Total Oilfield Rentals Ltd.	Dawson Creek	1-250-719-0505
Vertex Resource Group Ltd.	Dawson Creek	1-250-719-0353

**Note:** The above listed corporate entities are subject to change without notice. Information regarding support services is accurate at time of printing.

### 10.2.3 Area Summary

In the event of an incident (reported from an external source and/or confirmed by a drop in pressure), the internal and external notifications would be initiated by the Incident Commander. Simultaneously, an operator would be sent out to shut down the manual control valves on the CER line (please see associated map). The operator would first travel to the Compressor to perform a shutdown; this would be followed by manually closing the valve on the compressor site, then travelling to the downstream side of the pipeline to shut down the other associated valve. The maximum time for a Company operator to reach the compressor would be 20 minutes; the compressor side valve could be reached within two minutes after shutting down the compressor, and there would be an additional ten minutes required to travel to and manually close the downstream side valve. Both control points are easily accessible from the road.

As the gas is sweet and there are no surface developments in the EPZ, the operator would then immediately contact his/her supervisor, who would then update the area's Supervisor and the TSB, and then work with internal support and the outside agencies to determine a plan of action for resolving the source of the release.

Pipeline Information	
Licensed Maximum Operating Pressure	13000 kPa
Licensed H <sub>2</sub> S Concentrations	0% H <sub>2</sub> S
Emergency Planning Zones	0.0 km
Maximum H <sub>2</sub> S Release Volumes	0 m <sup>3</sup>

**Hazard Summary**

Tupper Main CER Field Area – Hazard Summary					
Hazardous Product	General Description	Health Effects	Downwind Evacuation	Fire	HPZ Public Safety (immediate precautionary measures)
Methane	<ul style="list-style-type: none"> <li>Often referred to as "sweet gas".</li> <li>Flammable.</li> <li>Lighter than air.</li> <li>At room temperature and standard pressure, methane is a colorless, odorless gas.</li> <li>It is the simplest alkane and the main component of natural gas.</li> </ul>	<ul style="list-style-type: none"> <li>Vapors may cause dizziness or asphyxiation without warning.</li> <li>Some may be irritating if inhaled at high concentrations.</li> <li>Contact with gas or liquefied gas may cause burns, severe injury and/or frostbite.</li> <li>Fire may produce irritating and/or toxic gases.</li> </ul>	<p><b>Large Spill</b> Consider initial downwind evacuation for at least 800 metres (1/2 mile)</p>	<p>If tank, rail car or tank truck is involved in a fire, isolate for 1600 metres (1 mile) in all directions; also, consider initial evacuation for 1600 metres (1 mile) in all directions.</p>	<p>100 m (330 ft)</p>
Methane, compressed					
Natural gas, compressed					
Propane	<ul style="list-style-type: none"> <li>Extremely Flammable – will be easily ignited by heat, sparks or flames.</li> <li>Colourless</li> <li>Denser than air.</li> <li>When odourized has a sulphur type odour. Non-odourized has a slight hydrocarbon odour.</li> <li>A by-product of natural processing and petroleum refining, it is commonly used as a fuel for engines, oxy-gas torches, portable stoves, and residential central heating. Propane is one of a group of liquefied petroleum gases (LPG).</li> </ul>	<ul style="list-style-type: none"> <li>Vapours may cause dizziness or asphyxiation without warning.</li> <li>Some may be irritating if inhaled at high concentrations.</li> <li>Contact with gas or liquefied gas may cause burns, severe injury and/or frostbite.</li> <li>Fire may produce irritating and /or toxic gases.</li> </ul>	<p><b>Large Spill</b> Consider initial downwind evacuation for at least 800 metres (1/2 mile)</p>	<p>If tank, rail car or tank truck is involved in a fire, isolate for 1600 metres (1 mile) in all directions; also, consider initial evacuation for 1600 metres (1 mile) in all directions.</p>	<p>100 m (330 ft)</p>
Butane					
Liquefied Petroleum Gas (LPG)					
Petroleum Crude Oil	<ul style="list-style-type: none"> <li>Brown to black.</li> <li>Viscous liquid.</li> <li>May contain or release poisonous hydrogen sulfide gas.</li> <li>Extremely flammable liquid and vapour</li> </ul>	<ul style="list-style-type: none"> <li>Inhalation or contact with material may irritate or burn skin and eyes.</li> <li>Fire may produce irritating, corrosive and/or toxic gases.</li> <li>Vapors may cause dizziness or suffocation.</li> </ul>	<p><b>Large Spill</b> Consider initial downwind evacuation for at least 300 metres (1000 ft).</p>	<p>If tank, rail car or tank truck is involved in a fire, isolate for 800 metres (1/2 mile) in all directions; also, consider initial evacuation for 800 metres (1/2 mile) in all directions.</p>	<p>50 m (150 ft)</p>

Tupper Main CER Field Area – Hazard Summary					
<p>Hydrogen Sulphide (H<sub>2</sub>S)</p>	<ul style="list-style-type: none"> <li>Flammable – explosive when mixed with air.</li> <li>Forms SO<sub>2</sub> when combusted.</li> <li>Rotten egg smell at low concentrations.</li> <li>Inhibits olfactory senses at high concentrations.</li> <li>Heavier than air.</li> <li>Will tend to disperse slower in sheltered or low-lying areas.</li> <li>Extremely toxic.</li> </ul>	<ul style="list-style-type: none"> <li>Toxic; extremely hazardous.</li> <li>May be fatal if inhaled or absorbed through skin.</li> <li>Initial odour may be irritating or foul and may deaden your sense of smell.</li> <li>Contact with gas or liquefied gas may cause burns, severe injury and/or frostbite.</li> <li>Fire will produce irritating, corrosive and/or toxic gases.</li> </ul>	<p><b>Small Spill – Day</b> Consider initial downwind evacuation for at least 0.1 km. (100 m)</p> <p><b>Small Spill – Night</b> Consider initial downwind evacuation for at least 0.4 km (400 m)</p> <p><b>Large Spill – Day</b> Consider initial downwind evacuation for at least 2.1 km (2100 m)</p> <p><b>Large Spill – Night</b> Consider initial downwind evacuation for at least 5.4 km (5400 m)</p>	<p>If tank, rail car or tank truck is involved in a fire, isolate for 1600 metres (1 mile) in all directions; also, consider initial evacuation for 1600 metres (1 mile) in all directions.</p>	<p>100 m (330 ft)</p>
<p>Petroleum sour crude oil, flammable, toxic</p>	<ul style="list-style-type: none"> <li>Rotten egg smell at low concentrations.</li> <li>Inhibits olfactory senses at high concentrations.</li> <li>Brown to black.</li> <li>Viscous liquid.</li> <li>May contain or release poisonous hydrogen sulfide gas.</li> <li>Extremely flammable liquid and vapour</li> </ul>	<ul style="list-style-type: none"> <li>Toxic; extremely hazardous.</li> <li>May be fatal if inhaled or absorbed through skin.</li> <li>Initial odour may be irritating or foul and may deaden your sense of smell.</li> <li>Contact with gas or liquefied gas may cause burns, severe injury and/or frostbite.</li> <li>Fire will produce irritating, corrosive and/or toxic gases.</li> <li>Inhalation or contact with material may irritate or burn skin and eyes.</li> <li>Fire may produce irritating, corrosive and/or toxic gases.</li> <li>Vapors may cause dizziness or suffocation.</li> </ul>	<p><b>Small Spill – Day</b> Consider initial downwind evacuation for at least 0.1 km. (100 m)</p> <p><b>Small Spill – Night</b> Consider initial downwind evacuation for at least 0.2 km (200 m)</p> <p><b>Large Spill – Day</b> Consider initial downwind evacuation for at least 0.5 km (500 m)</p> <p><b>Large Spill – Night</b> Consider initial downwind evacuation for at least 0.7 km (700 m)</p>	<p>If tank, rail car or tank truck is involved in a fire, isolate for 800 metres (1/2 mile) in all directions; also, consider initial evacuation for 800 metres (1/2 mile) in all directions.</p>	<p>100 m (330 ft)</p>

*Facilities - Hazardous Products*

Tupper Main Gas Plant A-021-B/093-P-09							
		Latitude	Longitude	Easting	Northing		
UTM Zone 11 NAD83		55.518750	-120.128125	--	--		
STARS Landing Site Number				ERAP Number			
115				ERAP 2-0010-083			
Type	Capacity	Substance	United Nations (UN) ID Number	Transport Canada ER Guide Number	Downwind Evacuation	Fire	HPZ Public Safety (immediate precautionary measures)
Tank	2x 500 gallons	Propane	1075 / 1978	115 – Gases (Flammable)	Large Spill - 800 metres (1/2 mile)	1600 metres (1 mile)	200 m (660 ft)
	2x 1001 gallons						
Tank	2x 845 gallons	Condensate	1267	128 – Flammable Liquids (Water-Immiscible)	Large Spill - 300 metres (1000 feet)	800 metres (1/2 mile)	1200 m (3940 ft)
Tank	400 bbl	Ethylene Oil	1267	128 – Flammable Liquids (Water-Immiscible)	Large Spill - 300 metres (1000 ft)	800 metres (1/2 mile)	50 m (150 ft)
	2x 1000 gallons						
Tank	250 bbl	Compressor Oil	1267	128 – Flammable Liquids (Water-Immiscible)	Large Spill - 300 metres (1000 ft)	800 metres (1/2 mile)	50 m (150 ft)
Tank	1200 liter	Waste Oil	1267	128 – Flammable Liquids (Water-Immiscible)	Large Spill - 300 metres (1000 ft)	800 metres (1/2 mile)	50 m (150 ft)
Tank	500 gallons	Diesel Oil	1267	128 – Flammable Liquids (Water-Immiscible)	Large Spill - 300 metres (1000 ft)	800 metres (1/2 mile)	50 m (150 ft)
Tank	5x 2000 bbl	Produced Water	1993	128 – Flammable Liquids (Water-Immiscible)	Large Spill - 300 metres (1000 feet)	800 metres (1/2 mile)	50 m (150 ft)

### *Shutdown of Production Pipes and Pipelines Procedure*

The following is a general shutdown procedure, when the pipeline is put back into service this procedure will be reviewed to ensure it is applicable.

Pipelines may require periodic, temporary or emergency shutdowns throughout their lifetimes. Shutdowns may occur for several reasons, scheduled maintenance, required modifications or emergency repairs.

Prior to shutdown, the pipeline shall be purged of sour gas. The following procedure shall be followed.

1. All sour tie-ins shall be closed and locked out.
2. The pipeline will be pigged with sweet gas to purge sour gas and liquids from the pipeline.
3. Once the pigging is complete and the pipeline is purged of sour gas the pipeline may be shutdown.
4. All tie-in block valves must be locked out.
5. The valves at 12-11-001-10W2 and Tableland CDP Block Valve must be manually closed.
  - Review of Lock-out/Tag-out procedures
  - Review of a site-specific isolation procedure
  - Review of LEL, Oxygen and H<sub>2</sub>S acceptable levels
  - Review or emergency response and egress plans and muster points
  - Document shutdown in company log and identify any anomalies
6. After the initial purge, the pipeline shall be flared to atmospheric pressure at the selected flare location.

The pipeline will be considered shutdown when the pipeline has been blown down to atmospheric pressure at the selected flare stack. Each shutdown shall be recorded in the company operations log.

Pipelines that have not seen normal production flow for a period longer than 1 month are considered long term shutdown. If a shutdown is longer than 12 months, it must be moved to a discontinued state.

### *Geography and Area Use*

The Tupper Main field is heavily populated with residences and recreational users. The area primarily consists of oil and gas activities, agricultural activities and recreational activities including logging/hauling.

The area surrounding NorthRiver's Tupper Main operations include active cutblocks and range tenures, the grazing season runs from mid-May to the end of October. The Tupper Main field lies in the Boreal White and Black Spruce Bio geoclimatic Zone in the Peace River District. Topography consists of gently to strongly rolling on the till uplands, with long slopes on the lacustrine plains. Vegetation consists predominantly of trembling aspen, balsam poplar, white spruce and willows.

The Tupper Main field includes the Swan Lake Provincial Park and Campground and the Tomslake Sudeten Heritage Park. The Swan Lake Provincial Park and Campground (82 hectares) is in the east of the Tupper Main Gas Plant, accessible via Highway 2. The

Campground is operational from May 10th to September 11<sup>th</sup> (annually). Recreational activities at the park include canoeing, cycling, hiking, scuba diving, swimming, water skiing and windsurfing. There is also a boat launch and dock that is open year-round. Swan Lake is also popular with local anglers. Sport fish include walleye, northern pike, yellow perch and burbot. Northern pike spawn in the spring among lakeshore weeds.

The Sudeten Heritage Park (5 hectares), operated by Tomslake and District Recreation Commission, is situated 4 km west of Swan Lake Provincial Park and Campground. Sudeten often functions as an overflow camping site for Swan Lake Provincial Park during weekends and holidays. Sudeten includes a recreational camping and picnicking area for local and regional residents.

### *Highways / Area Roads / Railways*

Highway 52 (Heritage Highway) runs north / south through the Tupper Main EPZ.

There are several petroleum development roads in the area. The roads are a combination of pavement and gravel and not all are all-weather roads. Access to the area is dependent on weather.

### *Creeks / Rivers / Lakes*

There are numerous waterbodies flowing through the Tupper Main & CER Pipeline field area including Tupper River, Swan Lake, Keering Lake, Albright Lake, Chain Lakes, Ray Lake, Updike Lake, Updike Creek, Little Tupper Creek, Tupper Creek, Bordet Creek and a few unnamed rivers and creeks.

In the event of an emergency near a waterbody, NorthRiver will determine if they need to call WCSS to aid in response activities.

### *10.2.4 Public Summary*

Tupper Main Operations Area	
Number of First Nations:	None
Number of Rights Holders:	4 BC Area Trappers 4 AB Area Trappers 1 BC Guides & Outfitters 2 AB WMU Guides & Outfitters 2 Cutblocks / Woodlots 4 BC Range Tenures 10 AB Grazing Leases 18 Non-Resident Landowners
Number of Oil & Gas operators:	40
Number of Other Area Users:	3
Other surface facilities that were noted:	None

### *First Nations*

There are no First Nations near NorthRiver Midstream operations in the Tupper Main field.

*Rights Holders*

*Area Trappers (BC)*

Trapline #	Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

*Area Trappers (AB)*

Trapline #	Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

*Guides & Outfitters (BC)*

ID #	Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

*Guides & Outfitters (AB)*

WMU 357 - Beaverlodge				
Name	Location	Telephone	Planning Zone	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	

WMU 357 - Beaverlodge			
Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
WMU 358 - Saddle Hills			
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

*Cutblocks/Woodlots*

Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

*Range Tenure (BC)*

Name	Location	Telephone	Planning Zone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

\*Significant attempts were made to locate information for all licensees.







*School Contacts*

Schools and School Divisions	Contact	Location	Telephone
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

### 10.2.5 Risk Assessment

#### Purpose

Risk assessment is a method for analyzing the probability and impact of failure on personnel, the public, the facility, the environment, and/or NorthRiver's reputation. Utilizing the Hazard, Risk and Vulnerability Assessment Matrix during the response to an emergency will help to ensure the incident is managed within NorthRiver risk tolerances.

The nature of the hazard(s) will influence the responses that are implemented by the Site Operations Section Chief and the Incident Commander. NorthRiver risk management during response to any incident is based on the following:

- Activities that present an extreme risk to workers, responders, and public must be limited to only situations where there is a potential to save endangered lives. Life Safety is the number one priority in every incident; this includes the safety of responders.
- Where there is no possibility to save lives, personnel should not attempt extreme risk operations.
- Activities to protect the environment or property are recognized as inherent risks to the safety of response personnel and actions should be taken to reduce or avoid these risks.

The Incident Commander is responsible for the overall coordination and direction of all activities and has the primary responsibility to evaluate the risk to on-site personnel with respect to the purpose and potential results of their actions in each situation. In situations where the risk to personnel is excessive, activities should be limited to defensive and protective operations.

The Site Operations Section Chief has the primary responsibility to evaluate the risk to on-site personnel with respect to the purpose and potential results of their actions in each situation. In situations where the risk to personnel is excessive, activities should be limited to defensive and protective operations.

#### Determining Risk

There are four steps in assessing the risk of an activity or process (see Hazard, Risk and Vulnerability Assessment Matrix):

1. Identify the risk or concern: Describe the risk or concern.
2. Assess the impact: The potential consequence of an incident is defined in terms of impact to people, the environment, operational assets, and the company's reputation.
3. Assess the Probability: The probability of occurrence is estimated in a range from Remote to Frequent.
4. Plot risk level and take action: Risk is categorized in terms of:
  - Critical - the activities must stop until risk controls have been implemented to reduce the risk to a lower level.
  - High - extensive risk controls must be immediately implemented.
  - Moderate - risk controls are required.
  - Low - some risk controls are justified.

### *Hazard Identification*

NorthRiver Emergency Response Plans are BC Energy Regulator Emergency Management Regulation compliant 'all hazards' ERPs covering production operations. Although written and employing an 'all hazards' approach, the focus of these plans are upstream petroleum production operations.

Under Canadian Standards Association (CSA) Z1600-08, organizations are required to identify and monitor hazards that can have an impact on their operations or areas of responsibility. Organizations are mandated to consider the impact of natural, technological hazards and human-caused.

Hazards and risks for NorthRiver were identified and vulnerabilities were assessed by NorthRiver Emergency Response Planning section personnel using the Hazard, Risk and Vulnerability Assessment Matrix. As per the Risk Assessment process, staff evaluated information to facilitate the assignment of both probability and impact scores to the three categories of hazards. The combined scores were then plotted on the Risk Matrix so that the Risk Potential/Level could be determined, and appropriate ERP procedures developed where necessary.

**Hazard, Risk and Vulnerability Analysis**

**Step 1 – Assess the Impact**

Level	People	Environment	Assets	Reputation
<b>4 Critical</b>	<ul style="list-style-type: none"> <li>Fatality</li> <li>Long-term health impact</li> <li>Permanent disability</li> <li>Life altering injury or illness</li> <li>Evacuation of a facility and community</li> <li>Action from / activist involving weapons</li> </ul>	<ul style="list-style-type: none"> <li>Severe long-term environmental damage</li> <li>Wide-spread impacts to sensitive environments, wildlife and/or major bodies of water</li> <li>Significant off lease/site groundwater impacts</li> </ul>	<ul style="list-style-type: none"> <li>One-month facility/equipment outage</li> <li>Production, equipment, property, motor vehicle loss and or damage greater than \$10 million</li> <li>Terrorist attack/attempt</li> </ul>	<ul style="list-style-type: none"> <li>Action resulting in regulatory and/or legal prosecution or suspension of operations</li> <li>Prolonged national/international media attention</li> <li>Sustained widespread stakeholder public protest</li> </ul>
<b>3 High</b>	<ul style="list-style-type: none"> <li>Short term health impact</li> <li>Lost time injury or illness</li> <li>Evacuation of facility and immediate area</li> <li>Violent action from landowner/ activist</li> </ul>	<ul style="list-style-type: none"> <li>Severe short-term environmental damage</li> <li>Localized on lease groundwater impacts</li> <li>Significant off lease/site surface impacts</li> </ul>	<ul style="list-style-type: none"> <li>One-week facility/equipment outage</li> <li>Production, equipment, property, motor vehicle loss and or damage greater than \$1 million</li> <li>Substantial loss from theft/ vandalism</li> </ul>	<ul style="list-style-type: none"> <li>Regulatory and/or legal action resulting in fines or punitive action</li> <li>Prolonged national/regional media attention</li> <li>Prolonged local/regional stakeholder public protest</li> </ul>
<b>2 Moderate</b>	<ul style="list-style-type: none"> <li>Medical aid injury or illness</li> <li>Restricted work/modified duties</li> <li>Evacuation of job site</li> <li>Specific threat from landowner/ activist</li> </ul>	<ul style="list-style-type: none"> <li>Moderate environmental damage</li> <li>No groundwater impacts</li> <li>Localised off lease/site surface impacts</li> <li>Immediate clean-up</li> </ul>	<ul style="list-style-type: none"> <li>Short term (less than one week) facility/equipment outage</li> <li>Production, equipment, property, motor vehicle loss and or damage greater than \$100,000</li> <li>Major property crime</li> </ul>	<ul style="list-style-type: none"> <li>Regulatory and/or legal action resulting in administrative response</li> <li>Brief local/regional media attention</li> <li>Brief local public protest</li> </ul>
<b>1 Low</b>	<ul style="list-style-type: none"> <li>First aid injury or illness</li> <li>Implied threat from landowner/ activist</li> </ul>	<ul style="list-style-type: none"> <li>Minor environmental damage on surface impacts</li> </ul>	<ul style="list-style-type: none"> <li>Negligible production loss</li> <li>Protection, equipment, property, motor vehicle loss and/or damage less than \$100,000</li> <li>Minor property crime</li> </ul>	<ul style="list-style-type: none"> <li>No regulatory action anticipated</li> <li>Brief or no media attention</li> <li>Brief or no public attention</li> </ul>

**Step 2 – Determine the Probability**

Level	Description	Likelihood
<b>4 Frequent</b>	Event is expected to occur in most circumstances.	One or more occurrences per year.
<b>3 Likely</b>	Event will probably occur at home time based on current practices.	One occurrence every 1-5 years.
<b>2 Unlikely</b>	Event should occur at some time based on current practices	One occurrence ever 5-20 years
<b>1 Remote</b>	Event could occur at some time based on current practices	One in the life of the facility

**Step 3 – Determine the Risk Level**

	<b>4 Critical</b>			
	<b>3 High</b>			
<b>Impact</b>	<b>2 Moderate</b>			
	<b>1 Low</b>			
	<b>1 Remote</b>	<b>2 Unlikely</b>	<b>3 – Likely</b>	<b>4 Frequent</b>

**Probability**  
Impact x Probability = Risk Level

**Step 4 – Risk Level**

**Critical – STOP activities. Work cannot proceed until risk is reduced to a lower level.**

**High – Extensive risk controls/mitigation measures must be implemented, and possible corporate approval is required to allow work to proceed. Efforts to reduce risk to a MEDIUM or LOW level should be undertaken.**

**Moderate- Risk controls/mitigation measures must be implemented to allow work to proceed. Efforts to reduce risk to a LOW level should be undertaken.**

**Low – Some risk controls/mitigation measures may be justified. Represents an acceptable level of risk.**

**Step 5 – Take Action**

Ensure all Risks are understood, controlled, and communicated prior to starting work.

**Hazard Risk Analysis**

The chart below identifies the high-risk hazards that are present at the Tupper Main CER area of Operations:

Risk Level	Hazards	Controls
<b>Critical</b>	None Identified	N/A
<b>High</b>	None Identified	N/A
<b>Moderate</b>	Fire: Industrial/Facility	Section 7.21 - Facility Fires
	Release: Chemical (e.g. produced water, cleaning agents)	Section 7.16 – Liquids Release
	Release: Gas (Sweet)	Section 7.11 Sweet Gas (Hydrocarbon) Release
	Release: Gas (Sour)	Section 7.10 Sour Gas Release
	Fire: Wildland/Grass/Forest	Section 7.20 – General Fire Response
	Flood	Sub-Section 7.31.5 - Floods
	Release: Liquid Product	Section 7.16 – Liquids Release, Section 7.17 Spill Contingency Plan
	Excessive Runoff from Facility	Section 7.17 Spill Contingency Plan
<b>Low</b>	Medical Event (Slips, Trips, First Aid, Heart Attack, etc.)	Section 7.28 – Injury/Fatality
	Transportation/Vehicle Incident: On Site	Section 7.25 – Transportation Incident
	Transportation/Vehicle Incident: Off Site Involving Company/Contractor Personnel	Section 7.25 – Transportation Incident
	Weather: Lightning Strike	Section 7.31.4 – Lightning
	Weather: Extreme Cold	Section 7.31.1 – Severe Weather Safety
	Threat or Suspicious Activity	Section 7.34 – Bomb Threat
	Disgruntled Landowner/Employee/Contractor/Vendor	Section 7.33 - Site Security
	Weather: Extreme Heat	Section 7.30.1 – Severe Weather Safety
	Wildlife Bites/Attacks	Section 7.32 – Animal Attacks
	Intruder/Squatter	Section 7.33 - Site Security
	Landslide	Section 7.31.6 – Seismicity
	Seismic Event: Earthquake	Section 7.31.6 – Seismicity
	Weather: Tornado	Section 7.31.3 - Tornadoes
	Prolonged Power Outage	Refer to Business Continuity Plan


### 10.2.6 Spill Support Services

#### WCSS – Coop 5

Area	Chairman	Contact Information
WCSS Emergency 24-Hour Number		1-866-541-8888
[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]

Equipment Storage Location	Custodian	Contact Information	Equipment	Transport Requirements
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]


Equipment Storage Location	Custodian	Contact Information	Equipment	Transport Requirements
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]



## WCSS – Coop 9

Area	Chairman	Contact Information
WCSS Emergency 24-Hour Number		1-866-541-8888
[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]

Equipment Storage Location	Custodian	Contact Information	Equipment	Transport Requirements
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]



### Waterway Control Points

There is 1 waterway control point. These waterway control points are all accessible by road to allow for rapid deployment of spill control equipment.

Control Point	LSD	Latitude	Longitude
TUP-02	d-54-A / 93-P-9	55.547917	-120.040625

### 10.2.7 CER Regulated Assets

LICENSE	REGULATORY CODE	LICENSE	LINE	SUBSTANTIATION CATEGORY	STATUS CODE	FROM	FROM FACILITY	PIPELINE TYPE (C/S/ED/OPEN FLOW/H)	GPS COORDINATES (UTM NAD 83)	TO	TO FACILITY	PIPELINE TYPE (C/S/ED/OPEN FLOW/H)	GPS COORDINATES (UTM NAD 83)	MOP (RPA)	OD (mm)	WT (mm)	LICENSED H-S CONTENT (m³/Meter)	LENGTH (KM)	MDT (°C)	VOLUME OF PRELIME (m³)	Volume of Gas @ Standard Conditions (m³)	Gas Volume Factor (GVF) (m³/m³)	COMPRESS (Z)	BEHAVIOR H-S RELEASE VOLUME (m³)	CUMULATIVE H-S RELEASE VOLUME (m³)	EPZ (KM)	FAZ (KM)	SET BACK LEVEL	CANULIC INITIAL ISOLATION ZONE (MI)	INITIAL ISOLATION HZ (MI)	ASSIGNED HZ* (KM)
<b>CER ASSETS - BC</b>																															
ENBRIDGE G AND P CANADA PIPELINES INC	AC-001-X3-M207-03-2008	83061	Z-A	NS	APPROVED	A-671-B/029-P-00	GP	-		D-051-1063-P-00	PL	ESD	10 N 899772-8150348	13000	323.8	10.3	0	11.75	5	na	na	na	na	0	0	0.000	0.000	na	0.103	0.277	0.277
ENBRIDGE G AND P CANADA PIPELINES INC	AC-003-X3-M207-03-2008	30061	Z-B	NS	APPROVED	D-061-1093-P-00	PL	ESD	10 N 898672-8150348	D-061-1093-P-00	PL	-		13000	323.8	10.3	0	0.45	5	na	na	na	na	0	0	0.000	0.000	na	0.100	0.162	0.162
<b>CER ASSETS - AB</b>																															
NORTH RIVER MIDSTREAM G AND P CANADA PIPELINES INC	AL-004-X3-M207-03-2008	83061	001	NS	APPROVED	02-00-075-13W6	PL			14-07-074-12W6	PL	ESD	11 N 326333-0142912	13000	323.8	10.3	0	10.00	5	na	na	na	na	0	0	0.000	0.000	na	0.100	0.268	0.268

**Notes:** \* HZ or Hazard Planning Zones are based on the In-situ Remedial Action Measures - CANUTEC 2020 Emergency Response Guidebook  
 \*\* Assigned HZ is the highest value from calculated EPZ and Canulic Initial Isolation Zone  
 Substrate Category Codes: CO - Gaseous, DS - Fuel Gas, FM - Fresh Water, HWP - HWP Products, LV - LVP Products, MG - Miscellaneous Gases, ML - Miscellaneous Liquids, NG - Natural Gas, OE - Oil Effluent, OG - Sour Natural Gas, DW - Soft Water, MP - Multiphase, PW - Production Water  
 Status Codes: A - Abandoned, ACT - Active, N - Not Constructed, D - Discontinued, DEACT - Decommissioned, O - Operating, P - To be constructed, R - Reinstated  
 Facility Codes: B - Battery, BE - Blow End, CP - Chemical Plant, CS - Compressor Station, GP - Gas Plant, IP - Injection / Disposal Facility, MR - Meter / Regulation Station, MS - Meter Station, PP - Petrochemical Plant, PL - Pipeline  
 PT - Pump Station, R - Road, RP - Railway, RS - Regulator Station, S - Saddle, ST - Storage Tank, TP - Tank Farm, WF - Well, H - Header  
 Valve Codes: BV - Block Valve, CV - Check Valve, ESD - Emergency Shutdown Valve, MV - Manual Valve, -- No Valve

### 10.2.8 Supporting Information Table

The table below indicates the location of CER supporting documentation in this emergency response plan.


Supporting Information	ERP Section
CER Distribution	Forward: Distribution List
CER Roles and Responsibilities	Jurisdictional Requirements: Canadian Federal Government – Section 9
CER Definitions of Incident Reporting	Jurisdictional Requirements: Canadian Federal Government – Section 9
CER Detailed Incident Report	Jurisdictional Requirements: Canadian Federal Government – Section 9
Notification Requirements for Key Government Agencies and Local Resources	Applicable Jurisdiction – Section 9
TSB Roles and Responsibilities	Jurisdictional Requirements: Canadian Federal Government – Section 9

### 10.2.9 Maps

Area maps on following page:




Twp 76  
Twp 75  
Twp 74



- |  |  |
|--|--|
| <p><b>NorthRiver Wells</b></p> <ul style="list-style-type: none"> <li>Gas</li> <li>Oil</li> <li>Standing</li> <li>Injection</li> <li>Suspended Gas</li> <li>Suspended Oil</li> <li>Water</li> <li>Bottom Hole</li> <li>Well EPZ</li> <li>Discontinued</li> <li>Sour Gas</li> <li>Natural Gas / Fuel Gas</li> <li>Oil</li> <li>Water</li> <li>HVP / LVP</li> <li>Block Valves</li> <li>Pipeline HPZ</li> <li>Major Transmission Lines</li> </ul> <p><b>NorthRiver Pipelines</b></p> <ul style="list-style-type: none"> <li>Injection Point</li> <li>Meter Station</li> <li>Pump Station</li> <li>Satellite</li> <li>Facility EPZ</li> <li>Storage HPZ</li> </ul> <p><b>NorthRiver Facilities</b></p> <ul style="list-style-type: none"> <li>Battery</li> <li>Compressor Station</li> <li>Gas Plant</li> <li>Gathering Point</li> <li>Injection Plant</li> <li>Meter Station</li> <li>Pump Station</li> <li>Satellite</li> <li>Facility EPZ</li> <li>Storage HPZ</li> </ul> <p><b>Transportation</b></p> <ul style="list-style-type: none"> <li>High Grade Roads</li> <li>Resource Roads</li> <li>Low Grade / Seasonal</li> <li>Secondary Highway</li> <li>Primary Highway</li> <li>Radio Controlled Roads</li> <li>Railways</li> <li>Dead Ends</li> <li>Locked Gates</li> <li>Roadblocks</li> <li>Bridge</li> </ul> | <p><b>Residents</b></p> <ul style="list-style-type: none"> <li>Surface Development</li> <li>Occupied</li> <li>Sensitive</li> <li>Business</li> <li>Cabin</li> <li>Occupied Part-Time</li> <li>Vacant</li> <li>Campground</li> <li>Cemetery</li> <li>Church</li> <li>Community Hall</li> <li>Farm / Ranch</li> <li>Grain Bin</li> <li>Gravel Pit</li> <li>School</li> <li>Shop</li> <li>Tower</li> <li>Fire Tower</li> <li>Work Camp</li> <li>Hospitals</li> <li>Reception Centre</li> <li>Stars Air Ambulance</li> </ul> <p><b>Other Symbols</b></p> <ul style="list-style-type: none"> <li>Urban Area</li> <li>Hydrology</li> <li>Intermittent Waterbody</li> <li>Permanent Waterbody</li> <li>Airfields</li> <li>Municipal District</li> <li>Health Region</li> <li>RCMP</li> <li>WCSS Cooperative</li> <li>AER Boundary</li> <li>Parks</li> <li>First Nations</li> <li>Trapper Boundaries</li> <li>Grazing Reserves</li> <li>Water Control Point</li> <li>Critical Water</li> <li>Control Point</li> <li>Contours (m)</li> <li>Egress Area</li> <li>FMA</li> <li>WMU</li> </ul> |
|--|--|

Other Operator Wells and Pipelines represented in BROWN.

Map Created by DM May 26, 2022 Revised by LN February 24, 2023



Datum: NAD 83  
Projection: UTM Zone 11  
Mapscale: 1:36 000

NorthRiver Midstream Inc.  
**Tupper Main**  
Emergency Planning Zone Map



**Notes**  
Location of residence in LSD is approximate. Well and Pipeline information is provided by IHS and must be considered approximate.  
**Surface Developments**  
Surface developments outside an EPZ have not been verified.

**Contact Information - British Columbia**  
BC OGC - EMBIC: 1-800-663-3456  
Local Authority - Peace River Regional District: 1-800-670-7773  
RCMP Detachment - Dawson Creek RCMP: 250-784-3700

**Contact Information - Alberta**  
Alberta Energy Regulator - AER: 1-800-222-6514  
Local Authority - County of Grande Prairie No 1: 780-532-9727  
RCMP Detachment - Beaverlodge RCMP: 780-354-2955  
Alberta Health Services - North Zone: 911


## 11.0 FORMS

### 11.1 Initial emergency Response Forms

#### 11.1.1 Form A1

This form is used at the outset of an incident to record critical information informing key personnel to ensure a rapid and appropriate response.

Incident Details <i>To be completed by the person involved or notified</i>	
Report taken by	Date / Time
Name of person calling	Caller Telephone
Incident Location (LSD / NTS)	
Event Summary	
Agencies Notified	<input type="checkbox"/> Yes Who? <input type="checkbox"/> No
Event Status	<input type="checkbox"/> Incident contained or controlled <input type="checkbox"/> Intermittent control possible <input type="checkbox"/> Imminent control possible <input type="checkbox"/> Incident is uncontrolled
Site Type	<input type="checkbox"/> Well <input type="checkbox"/> Pipeline <input type="checkbox"/> Tank Farm/Storage <input type="checkbox"/> Battery/Plant/Facility <input type="checkbox"/> Other _____
Incident Type	<input type="checkbox"/> Sour Gas Release <input type="checkbox"/> Sweet Gas Release <input type="checkbox"/> Pipeline Break <input type="checkbox"/> Security (theft, threat, terrorism) <input type="checkbox"/> Loss of Containment <input type="checkbox"/> Fire/Explosion <input type="checkbox"/> Worker Injury/Fatality <input type="checkbox"/> Vehicle/Transportation <input type="checkbox"/> Liquid Spill <input type="checkbox"/> Other _____
Impacts	
Public Health and Safety	<input type="checkbox"/> Could be jeopardized <input type="checkbox"/> Is jeopardized
Public Protection Measures Taken	<input type="checkbox"/> Notification <input type="checkbox"/> Evacuation <input type="checkbox"/> Shelter-in-place <input type="checkbox"/> Roadblocks
Worker Injuries	<input type="checkbox"/> First Aid <input type="checkbox"/> Hospitalized <input type="checkbox"/> Fatality <input type="checkbox"/> Other _____
Distance to nearest surface development	_____ km Distance to nearest urban centre _____ km
Details	
Release Impact	<input type="checkbox"/> On-Lease <input type="checkbox"/> Off-Lease Product _____ Amount _____
Gas Readings	H <sub>2</sub> S _____ SO <sub>2</sub> _____ LEL _____ Other _____
Distance to nearest watercourse	_____ km Weather Conditions



Details		
---------	--	--

<b>Media Involvement?</b>	<input type="checkbox"/> Yes <input type="checkbox"/> No	<b>Regulator Involvement?</b>	<input type="checkbox"/> Yes <input type="checkbox"/> No	<b>Public Affairs/Community Relations Issues?</b>	<input type="checkbox"/> Yes <input type="checkbox"/> No
---------------------------	--	-------------------------------	--	---	--

Details
---------


**Notes / Instructions Provided:**

--

## 11.2 Jurisdictional Forms

### 11.2.1 Alberta Forms

#### Release Report



Initial verbal notification of the release to the AER is required prior to completing this release report

General Information		
AER FIS incident no.:	EDGE reference no.:	
Date AER notified:	Time: <input type="checkbox"/> p.m. <input type="checkbox"/> a.m.	AER contact:
Type of report:	Projected date for final report:	
Incident date:	Time: <input type="checkbox"/> p.m. <input type="checkbox"/> a.m.	Incident location: W
Licensee/Company name:		
Licence no.:	Public lands disposition no.:	
EPEA approval no.:	Scheme/Permit approval no.:	Other AER approval no.:
Form completed by:		Phone number:

Release Volume Details					
If volumes change from what was initially reported, then verbal notification to the AER is required.					
Released Substance*	Volume released	Free Fluids recovered	Shipped to (waste receiver) *	Licence/ approval no.*	Location
	m <sup>3</sup>	m <sup>3</sup>			W
	m <sup>3</sup>	m <sup>3</sup>			W
	m <sup>3</sup>	m <sup>3</sup>			W
Gas	10 <sup>3</sup> m <sup>3</sup>				
Release rate:	Duration of release:				
*If the released substance is "Emulsion" the crude oil, produced water, and gas must all be reported					
*Refer to ST107 for the list of AER approved oilfield waste management (WM) facilities					

Waste Recovery Volume Details				
Waste substance	Volume recovered	Shipped to (waste receiver) *	Licence/ approval no.*	Location
Excavated soil/solids removed	m <sup>3</sup>			W
	m <sup>3</sup>			W
Contaminated surface water and/or snow removed	m <sup>3</sup>			W
	m <sup>3</sup>			W
Washwater and/or freshwater used	m <sup>3</sup>			W
	m <sup>3</sup>			W
Vegetation/crop bagged and/or removed	m <sup>3</sup>			W
	m <sup>3</sup>			W
*Refer to ST107 for the list of AER approved oilfield waste management (WM) facilities				
Contaminated soils storage: <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> On site <input type="checkbox"/> Off site – If off site, enter location:				W
On-site waste treatment: <input type="checkbox"/> Yes <input type="checkbox"/> No				Waste Treatment Description:

Release Containment Details			
<input type="checkbox"/> Within well/facility lease boundary – Contained to working surface of lease boundary: <input type="checkbox"/> Yes <input type="checkbox"/> No			
<input type="checkbox"/> Outside well/facility lease boundary			
Release contained by berm: <input type="checkbox"/> Yes <input type="checkbox"/> No		Release contained by liner: <input type="checkbox"/> Yes <input type="checkbox"/> No      Liner type (Directive 055):	
Release onto land/soil: <input type="checkbox"/> Yes <input type="checkbox"/> No		Surface soil type:	Subsurface soil type:

Release Site Details			
Land jurisdiction type:	Environment affected:	Area affected:	m <sup>2</sup>
<input type="checkbox"/> Within public lands disposition boundary		<input type="checkbox"/> Outside public lands disposition boundary – TFA number:	
Distance to closest water body:	m	Distance to nearest town:	km      Name of nearest town:
Distance to closest water well:	m	Distance to nearest permanent dwelling:	km

Release Impacts Details		
Incident/release H <sub>2</sub> S concentration:	Unit of measurement: <input type="checkbox"/> % <input type="checkbox"/> ppm <input type="checkbox"/> mol/kmol	
Wildlife/livestock affected:	Equipment loss:	
Emergency response plan (ERP) activated: <input type="checkbox"/> Yes <input type="checkbox"/> No		
<input type="checkbox"/> Public affected	<input type="checkbox"/> Public evacuation	<input type="checkbox"/> Number evacuated:
<input type="checkbox"/> Landowner notified*	<input type="checkbox"/> Leaseholder notified*	
<input type="checkbox"/> WH&S notified*	Number of injuries:	Number of fatalities:
<a href="#">*Provide details in Additional Notifications box</a>		

Pipeline Details (fill in for AER licensed-pipeline incident)		
<a href="#">Pipeline is not to be returned to service without permission from the AER. See <a href="http://www.aer.ca">www.aer.ca</a> for definitions for incident type and cause.</a>		
Incident type:		Incident cause:
Licence number:	Line number:	Installation cause (if applicable):
Start location:    W	End location:    W	ABSA registration number (if applicable):
Associated facility location:    W	Associated facility licence number:	
<input type="checkbox"/> Test failure <input type="checkbox"/> Retest segment <input type="checkbox"/> Pipeline repair pretested <input type="checkbox"/> Cathodic protection		
Type of external coating:		<input type="checkbox"/> Corrosion mitigation/monitoring program:
Normal operating pressure:	kPa	Maximum operating pressure      kPa
Date line shut in:	Pipeline returned to service: <input type="checkbox"/> No <input type="checkbox"/> Yes	Date:

Clean-up/Remediation Details		
<a href="#">All releases must be remediated or managed in a matter satisfactory to the AER.</a>		
Clean-up status:	Final clean-up/remediation completion date:	
<input type="checkbox"/> In-situ remediation implemented		
Remediation guidelines used (choose all applicable):		
<input type="checkbox"/> Tier 1 <input type="checkbox"/> Tier 2 <input type="checkbox"/> SST <input type="checkbox"/> SCARG <input type="checkbox"/> CCME <input type="checkbox"/> Exposure control		
Method of subsurface delineation:	Confirmatory samples taken: <input type="checkbox"/>	Number of samples:
Remediation certificate applied for: <input type="checkbox"/> Yes <input type="checkbox"/> No		
Environmental contractor:	Phone number:	

Additional Incident Notification Details			
Name of agency/landowner	Person notified / reference no.	Phone number	Date

Incident Details
<p><b>Submit photos of the incident and clean-up/remediation to the AER. Fill in all text boxes below:</b></p> <p><b>Detailed description of circumstances leading up to the release:</b></p> <p><b>How release was identified:</b></p> <p><b>Steps/procedures taken to minimize, control, or stop release:</b></p> <p><b>Steps taken to contain release:</b></p> <p><b>If release was on lease steps taken to ensure no migration off lease (including subsurface migration):</b></p> <p><b>Description of how release volume(s) was determined and verified (include any calculations used):</b></p> <p><b>How the affected area was determined (include any calculations used):</b></p> <p><b>Description of environmental impact:</b></p> <p><b>Clean-up operation details:</b></p> <p><b>Remediation operation details</b></p> <p><b>Release cause:</b></p> <p><b>Description of root cause:</b></p> <p><b>Steps/procedures taken to prevent similar future releases:</b></p> <p><b>Additional comments:</b></p>



the pressure equipment safety authority

AB-097  
2016-08-11

# ACCIDENT REPORTING FORM

## Head Office

**ABSA, the pressure equipment safety authority**  
9410 20th Avenue  
Edmonton, AB T6N 0A4  
Telephone: (780) 437-9100  
Fax: (780) 437-7787

## Grande Prairie District Office

**ABSA, the pressure equipment safety authority**  
#203, 10109 97 Avenue  
Grande Prairie, AB T8V 0N5  
Telephone: (780) 538-9922  
Fax: (780) 538-9400

## Fort McMurray District Office

**ABSA, the pressure equipment safety authority**  
30C Suncor Energy Industrial Campus  
Keyano College  
160 MacKenzie Boulevard  
Ft McMurray, AB T9H 4B8  
Telephone: (780) 714-3067  
Fax: (780) 714-2380

## Calgary District Office

**ABSA, the pressure equipment safety authority**  
Deerfoot Atria South  
Suite 380, 6715 - 8 Street NE Calgary, AB T2E 7H7  
Telephone: (403) 291-7070  
Fax: (403) 291-4545

## Lethbridge District Office

**ABSA, the pressure equipment safety authority**  
Unit 19, 1274 - 3 Ave South  
Lethbridge, AB T1J 0J9  
Telephone: (403) 394-1011  
Fax: (403) 329-0089

## Medicine Hat District Office

**ABSA, the pressure equipment safety authority**  
#103, 346-3rd Street S.E.  
Medicine Hat, AB T1A 0G7  
Telephone: (403) 529-3514  
Fax: (403) 529-3632

## Red Deer District Office

**ABSA, the pressure equipment safety authority**  
#304, 4406 Gaetz Avenue  
Red Deer, AB T4N 3Z6  
Telephone: (403) 341-6677  
Fax: (403) 341-3377

**A**ccidents do occur. And when they do, the result is injury, loss of life or damage to property. Keeping accidents to a minimum, especially where boilers, pressure vessels and pressure piping systems are concerned should be everyone's safety objective. But when a boiler, pressure vessel or pressure piping system accident does occur, the owner or the person in charge must report the accident to ABSA, the pressure equipment safety authority.

The first step is to telephone the nearest ABSA office listed on this page. Until an ABSA Safety Codes Officer completes an investigation of the accident scene, or the ABSA Safety Codes Officer advises otherwise, nothing should be touched or removed from the accident site or the surrounding area, unless it is absolutely necessary to prevent further injury, loss of life or property damage.

The ABSA Safety Codes Officer will investigate an accident scene and file a report. However, Section 35 of the Pressure Equipment Safety Regulation under the Safety Codes Act requires that, as soon as possible, the owner or person in charge must also send a full report in writing to the Administrator. This report is required whenever injury, death or property damage results from an accident involving boilers, pressure vessels, power plants, heating plants, pressure plants or pressure piping systems.

For your convenience, a format for completing this written accident report is provided on the following pages. Your report may be in a different format however, the report must include the required information.

To report an accident, or to obtain further information about ABSA, the pressure equipment safety authority, please contact one of the offices listed.

# ACCIDENT REPORT

To be completed by the owner or person in charge whenever injury, loss of life or property damage results from an accident involving a boiler, pressure vessel or pressure piping system. (Please Print).

## Contact Information

Name of owner/person in charge: \_\_\_\_\_  
Title: \_\_\_\_\_  
Mailing address: \_\_\_\_\_  
Telephone number: \_\_\_\_\_  
Email address: \_\_\_\_\_

Chief Inspector/Management  
Representative (if applicable)

Name: \_\_\_\_\_  
Mailing address: \_\_\_\_\_  
Telephone Number: \_\_\_\_\_  
Email address: \_\_\_\_\_

Site Contact:

Name: \_\_\_\_\_  
Phone Number: \_\_\_\_\_

## Synopsis of Accident

Name and address of plant: \_\_\_\_\_  
Type of Plant: \_\_\_\_\_  
Specific location of accident: \_\_\_\_\_  
Date of accident: \_\_\_\_\_  
Time: \_\_\_\_\_

**Name of Victims**  
(if possible, please describe injuries or cause of death.)

**Damage to Property**  
(list all pressure equipment involved including title description of items, "A" Number, model number, CRN, service, description, severity of damage, etc.)

**Description of Accident**  
Brief plant description, chronological sequence of events; clear understanding of what happened; root cause; preventative measures taken.  
(Sequence of event before, during and after the event).

**Supporting Material**  
Please list all appropriate drawings, sketches, photographs signed statements, Engineer Reports, Root Cause Analysis, etc., that you have included with this report.

**Notification**

The following relevant authorities have been notified

**Probable Cause of Accident**

List major contributing causes in order of their importance.

**Actions and Preventative Measure Taken by Owner**

Steps to prevent occurrences of similar accidents.

**Accident Notification Details**

Reported to ABSA by: \_\_\_\_\_

Name of ABSA Contact: \_\_\_\_\_

Date and Time of Notification: \_\_\_\_\_

**When completed, this form should be sent to:**

Administrator (Chief Inspector)  
ABSA, the pressure equipment safety authority  
9410 20th Avenue  
Edmonton, AB T6N 0A4



# ELECTRICAL INCIDENT REPORT FORM

LOCAL FILE NUMBER \_\_\_\_\_  
DATE \_\_\_\_\_

<b>DETAILS OF ACCIDENT</b>	Human Fatality	<input type="checkbox"/> Yes <input type="checkbox"/> No	Human Injury	<input type="checkbox"/> Yes <input type="checkbox"/> No	Animal Fatality	<input type="checkbox"/> Yes <input type="checkbox"/> No	
	Date of Accident			Time of Day			
	Exact Location of Accident						
			LSD	Section	Township	Range	West of
	Name of Person Injured or Involved		Occupation		Age	Phone No.	
	Address					Postal Code	
	Description of Injury (if any)						
	Employer					Phone No.	
	Address					Postal Code	
	Description of Accident (state facts only)						

<b>ELECTRICAL EQUIPMENT INVOLVED</b>	Description of Electrical Equipment Involved in Accident (including power lines)	
	-	
	Voltage (to gnd. or 0-0?)	
Owner of Equipment	Operator of Equipment (if different from owner)	

<b>OTHER EQUIPMENT INVOLVED</b>	Description of Other Equipment Involved in Accident	
	-	
	License No. of Equipment (if applicable)	Make and/or Type of Equipment (if applicable)
	Owner of Equipment	Phone No.
	Address	Postal Code
	Operator of Equipment	Phone No.
Address	Postal Code	

Reported By	Firm Name	Location	Phone No.
-------------	-----------	----------	-----------

**SUBMIT COPIES TO:**  
 Technical Administrator for the Electrical Discipline  
 16<sup>th</sup> Floor, 10155 – 102 Street, Edmonton, Alberta T5J 4L4  
 Email: [safety.services@gov.ab.ca](mailto:safety.services@gov.ab.ca) Fax: 780-427-8686 Phone: 1-866-421-6929



11.2.2 British Columbia Forms

B.C. Minor Incident Notification Report



<p><b>FORM A</b>  <b>MINOR INCIDENT NOTIFICATION FORM</b></p> <p>Physical Address: 6534 Airport Road,          Fort St. John, B.C. V1J 4M6          Mailing Address: Bag 2, Fort St. John, B.C. V1J 2B0          Phone: (250) 794-5200          emp@bc-er.ca</p>
--

*This form is to be used for incidents which do not meet BCER Level 1, 2, or 3 Classification*

*Minor incidents must be reported to the Commission within **24-hours** through the Commission's Online Minor Incident Reporting System, operated through KERMIT.*

MISCELLANEOUS INFORMATION		A
Risk Score: (attach risk matrix)	DGIR #:	
Incident Date (YYYY-MM-DD):	Incident Time (24-hour clock): <input type="checkbox"/> PST <input type="checkbox"/> MST	
INFORMATION OF PERSON REPORTING INCIDENT		B
Permit Holder Name:	Reported by (name):	
Phone Number:	Alternate Number:	
Email:	Fax Number:	
INCIDENT DETAILS		C
SITE TYPE		D
Select only one type		
<input type="checkbox"/> Well (Active)	<input type="checkbox"/> Well (Abandoned/Suspended)	<input type="checkbox"/> Remote Sump
<input type="checkbox"/> Battery/Plant/Facility	<input type="checkbox"/> Tank Farm/Storage	<input type="checkbox"/> Pipeline
<input type="checkbox"/> Riser (Pipeline)	<input type="checkbox"/> Well (Drilling & Completions):	Rig Name:
<input type="checkbox"/> Road or Road Structure Name:	Location on road:	
<input type="checkbox"/> Other (specify):		

Updated: 08-September-2017  
 Effective: 01-October-2017



<b>PROJECT (PIPELINES) (A UTM location must be filled out in the Location Section)</b>	
Projection Location: NTS From _____ - _____ - _____ / _____ - _____ - _____	
NTS To _____ - _____ - _____ / _____ - _____ - _____	
DLS From _____, SEC _____, TWP _____, RGE _____ W6M	
DLS To _____, SEC _____, TWP _____, RGE _____ W6M	
Project #:	Pipeline Segment #:
Pipeline Installation ID#	Installation Type:
<b>OTHER LOCATION</b> Any asset that does not apply to above such as a road, remote sump, borrow pit, etc. (A UTM location must be filled out in the Location Section).	
Location Type:	Location Description:
<b>LOCATION</b>	
Location of asset: NTS _____ - _____ - _____ / _____ - _____ - _____ or	
DLS _____, SEC _____, TWP _____, RGE _____ W6M	
UTM (NAD 83 Zone): _____ m easting _____ m northing	
GPS: Latitude:	Longitude:
<b>AREA INFORMATION</b>	
<b>I</b>	
Land Type: <input type="checkbox"/> Private Land <input type="checkbox"/> Crown Land	Field Name:
Access: <input type="checkbox"/> ATV <input type="checkbox"/> Helicopter <input type="checkbox"/> Four-wheel drive <input type="checkbox"/> Two-wheel drive <input type="checkbox"/> Unknown	
Name of road the asset is located on:	
Km where the incident occurred:	
Distance to nearest residence/public facility:	Nearest City/Town/Public Camp:
<b>CAUSE</b>	
<b>J</b>	
Check all that apply	
<input type="checkbox"/> Third Party	<input type="checkbox"/> Manufacturing Defect
<input type="checkbox"/> Employee (procedural, behavioral)	<input type="checkbox"/> Corrosion (internal, external)
<input type="checkbox"/> Geological	<input type="checkbox"/> Natural (weather, flood, fire)
<input type="checkbox"/> Unknown at this time. Explain:	<input type="checkbox"/> Failure (materials, mechanical, equipment, system)
<input type="checkbox"/> Other Factors (specify):	<input type="checkbox"/> Over Pressuring Equipment
<b>CAUSE/REMEDIAL ACTIONS</b>	
<b>K</b>	
Describe the cause and remedial actions in more detail:	

Weather				L
Weather Conditions	<input type="checkbox"/> clear	<input type="checkbox"/> cloudy	<input type="checkbox"/> other (specify):	
Wind Direction From:	<input type="checkbox"/> N	<input type="checkbox"/> NE	<input type="checkbox"/> NW	<input type="checkbox"/> E <input type="checkbox"/> SE <input type="checkbox"/> S <input type="checkbox"/> SW <input type="checkbox"/> W
Wind Strength:	<input type="checkbox"/> calm	<input type="checkbox"/> moderate	<input type="checkbox"/> strong	<input type="checkbox"/> gusty
Temperature:	°C			
Comments:				
NOTIFICATION				M
What government agencies has the permit holder notified:				
<input type="checkbox"/> EMBC	<input type="checkbox"/> Ministry of Environment & Climate Change Strategy	<input type="checkbox"/> Ministry of Transportation and Infrastructure		
<input type="checkbox"/> Public Works	<input type="checkbox"/> WorkSafeBC	<input type="checkbox"/> Local Health Authority		
<input type="checkbox"/> Regional/Municipal Authority	<input type="checkbox"/> RCMP	<input type="checkbox"/> Ministry of Forests, Lands, Natural Resource Operations & Rural Development		
<input type="checkbox"/> Canada Energy Regulator	<input type="checkbox"/> Other (specify):			
INFORMATION FOR SPILLS ONLY				N
Is spill off lease? <input type="checkbox"/> Yes <input type="checkbox"/> No				
Spill Material Type:				
<input type="checkbox"/> Corrosive	<input type="checkbox"/> Emulsion (oil, gas, water)	<input type="checkbox"/> Liquid Hydrocarbon (crude, oil, diesel, fuel)		
<input type="checkbox"/> Methanol	<input type="checkbox"/> Non-Toxic Gases (Nitrogen, Carbon Dioxide, Inert Gases)	<input type="checkbox"/> Non-Toxic Liquids		
<input type="checkbox"/> Saltwater	<input type="checkbox"/> Sour Natural Gas	<input type="checkbox"/> Sour Liquid	<input type="checkbox"/> Sweet Natural Gas	
<input type="checkbox"/> Toxic Gas	<input type="checkbox"/> Toxic Liquid	<input type="checkbox"/> Fresh Water	<input type="checkbox"/> Other (specific):	
Amount Spilled:	<input type="checkbox"/> bbl or <input type="checkbox"/> m <sup>3</sup> or <input type="checkbox"/> litre			
Does Material contain any H <sub>2</sub> S? <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Unknown				
If yes, how much? ppm				
Has spill been cleaned up? <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A				
Date of Clean Up/Proposed Clean Up: (mmm dd, yyyy) if applicable				
Estimated Cost of Clean Up: \$ if applicable				
				O
<b>PLEASE NOTE:</b>				
"All incidents involving a pipeline must submit a <u>Form D: Permit Holder Post Incident Report Form</u> within 60 days by email to <a href="mailto:EMP@bc-er.ca">EMP@bc-er.ca</a> . A Permit Holder Post Incident Report Form may be required to be submitted for other minor incidents upon request by a Commission employee."				
The form can be found on the Commission's website.				
Permit Holder Post Incident Report Required: <input type="checkbox"/> Yes <input type="checkbox"/> No				

Updated: 08-September-2017  
Effective: 01-October-2017

 <p>BCER BRITISH COLUMBIA ENERGY REGULATOR</p>	<p><b>FORM C</b> <b>EMERGENCY INCIDENT FORM</b> British Columbia Energy Regulator 6534 Airport Road Fort St. John BC V1J 4M6 Phone: (250) 794-5200 emp@bc-er.ca</p>
---	---

**This is an internal Commission document provided to Industry for reference purposes only.**

This document outlines the information that will be requested by Commission emergency management staff following any Level 1, 2 or 3 incident, as defined in the Emergency Management Matrix available on the Commission's website.



BRITISH COLUMBIA ENERGY REGULATOR

**FORM C  
EMERGENCY INCIDENT FORM**

British Columbia Energy Regulator  
6534 Airport Road  
Fort St. John BC V1J 4M6  
Phone: (250) 794-5200  
emp@bc-er.ca

This form is to be used for emergencies which meet BCER Level 1, 2, or 3 Classification.

**The emergency must be reported to the Commission within 1 hour of the incident.**

British Columbia Energy Regulator 24-hour Emergency Number: 1-250-794-5200

EMBC 24-hour Emergency Number: 1-800-663-3456

**MISCELLANEOUS INFORMATION**

DGIR #	Ledger Number:	Kermit Number:
Incident Date (YYYY-MM-DD):	Incident Time (24-hour clock): <input type="checkbox"/> PST <input type="checkbox"/> MST	
Received Date (YYYY-MM-DD):	Received Time (24-hour clock): <input type="checkbox"/> PST <input type="checkbox"/> MST	

**INFORMATION OF PERSON REPORTING INCIDENT TO BCER**

Permit Holder Name:	Reported by (name):	
Phone Number:	Alternate Number:	
Email:	Fax Number:	

**INCIDENT DETAILS**

--

Updated: 01-Nov-2017

Effective: 01-Dec-2017

LEVEL OF EMERGENCY		
Risk Score: (attach risk matrix) <input type="checkbox"/> Level 1 <input type="checkbox"/> Level 2 <input type="checkbox"/> Level 3		
<input type="checkbox"/> Informed company they must contact the BCER to downgrade or stand down the level.		
SITE TYPE (Select one only)		
<input type="checkbox"/> Well (Active)	<input type="checkbox"/> Well (Abandoned/Suspended)	<input type="checkbox"/> Remote Sump
<input type="checkbox"/> Well (Drilling & Completions): Rig Name:		
<input type="checkbox"/> Battery/Plant/Facility	<input type="checkbox"/> Tank Farm/Storage	<input type="checkbox"/> Pipeline
<input type="checkbox"/> Riser (Pipeline)		
<input type="checkbox"/> Road or Road Structure: Name:		Location on road:
<input type="checkbox"/> Other – Specify:		
INCIDENT TYPE (check all that apply)		
<input type="checkbox"/> Spill (releases and discharges)	<input type="checkbox"/> Fire/Explosion	<input type="checkbox"/> Drilling Kick
<input type="checkbox"/> Worker Injury	<input type="checkbox"/> Security (theft, threat, sabotage, terrorism)	<input type="checkbox"/> Induced Seismicity
<input type="checkbox"/> Well Bore Communication	<input type="checkbox"/> Pipeline Boring	<input type="checkbox"/> Vehicle
<input type="checkbox"/> Equipment/Structural Damage		
<input type="checkbox"/> Other – Specify:		
ACTIVITY (check all that apply)		
<input type="checkbox"/> Construction (road, lease, pipeline, facility)	<input type="checkbox"/> Drilling/Exploration	<input type="checkbox"/> Waste Management
<input type="checkbox"/> Processing (natural gas, petroleum liquids, other)	<input type="checkbox"/> Well Fracturing	<input type="checkbox"/> Servicing
<input type="checkbox"/> Repair	<input type="checkbox"/> Flaring (emergency)	<input type="checkbox"/> Well Testing
<input type="checkbox"/> Pressure testing	<input type="checkbox"/> Transportation	
<input type="checkbox"/> Other – Specify:		
CONSEQUENCE OR IMPACTS (check all that apply. If none, leave blank)		
<input type="checkbox"/> Worker Safety (fatality, injuries)	<input type="checkbox"/> Property (government, public, private)	<input type="checkbox"/> Economic (loss of and/or damage to equipment or infrastructure, loss of production, work stoppage)
<input type="checkbox"/> Other – Specify:		
AREA INFORMATION		
Land Type: <input type="checkbox"/> Private Land <input type="checkbox"/> Crown Land	Field Name:	
Area Type: <input type="checkbox"/> Forest <input type="checkbox"/> Muskeg <input type="checkbox"/> Farmland <input type="checkbox"/> Residential <input type="checkbox"/> Other		



### NOTIFICATION

What government agencies has the permit holder notified?

<input type="checkbox"/> EMBC	<input type="checkbox"/> Ministry of Environment & Climate Change Strategy	<input type="checkbox"/> Ministry of Transportation and Infrastructure
<input type="checkbox"/> Public Works	<input type="checkbox"/> WorkSafe BC	<input type="checkbox"/> Local Health Authority
<input type="checkbox"/> Regional/Municipal Authority	<input type="checkbox"/> RCMP	<input type="checkbox"/> Ministry of Forest
<input type="checkbox"/> Canada Energy Regulator		<input type="checkbox"/> Other – Specify

Permit Holder instructed to call:

### MATERIAL INFORMATION

Is spill off lease?  Yes  No

Spill Material Type:  Corrosive Acid  Emulsion (oil, gas, water)

Fresh Water  Liquid Hydrogen (crude, oil diesel, fuel)  Methanol

Non-Toxic Gases (Nitrogen, Carbon Dioxide, Inert Gases)  Non-Toxic Liquids  Saltwater

Sour Natural Gas  Sour Liquid (H<sub>2</sub>S)  Sweet Natural Gas  Toxic Gas  Toxic Liquid

Other

### GAS

Does material contain any H<sub>2</sub>S?  Yes  No  Unknown  N/A

If yes, how much? ppm

Gas Rate: _____ 10 <sup>3</sup> m <sup>3</sup> d or mmcf	Gas Volume: _____ 10 <sup>3</sup> m <sup>3</sup> or mmscf
--	---

Can you hear/smell gas? <input type="checkbox"/> Yes <input type="checkbox"/> No	Propane/NGLs/LPSs? <input type="checkbox"/> Yes <input type="checkbox"/> No
--	---

### LIQUID

Does material contain any H<sub>2</sub>S (oil, water, condensate)?  Yes  No  Unknown  N/A

If yes, how much? ppm

Liquid Rate: _____ m <sup>3</sup> d or BPD	Liquid Volume: _____ m <sup>3</sup> or bbls or litres
--	---

Other (describe):

Has spill been cleaned up?  Yes  No  N/A

Date of Clean Up/Proposed Clean-Up: (mmm dd, yyyy)

Estimated Cost of Clean-Up: \$

### SAFETY ISSUES

Emergency Planning Zone Size: \_\_\_\_\_ km

Are responders in danger?  Unknown  No  Yes

Are public in danger?  Unknown  No  Yes

First Nations Band Affected:  No  Yes Name of Band: \_\_\_\_\_

Public safety actions taken:

Evacuation  Sheltering (**Instruct Permit holder to contact Local Authority**)

Roadblocks  Do you need, or do you have a Closure Order? (**Instruct Permit holder to contact MOT up to mile 82 on Alaska Highway or Public Works from 82 north on Alaska highway for any public roads and the BCER for Petroleum Development Resource roads, or Ministry of Forestry for forestry roads**)

Do you need, or do you have a NOTAM?

Have you conducted a Transient Survey?

Any Media Releases must be done in conjunction with BCER

Have you or do you need to dispatch a Mobile Air Quality Monitoring (**Instruct Permit holder to contact Health Authority if public are involved**)

Have you or will you need to Ignite?

Have you notified all tenure holders? Non-resident landowners/Trapper/Guide-Outfitters/Range Allotments/Grazing Lease

### ASSETS

#### GEOPHYSICAL PROGRAM (A UTM location is required)

Geophysical #:

Program Name:

Client Name:

UTM (NAD 83): \_\_\_\_\_ m easting \_\_\_\_\_ m northing

(Place on the program that incident happened REQUIRED)

#### SITE (On lease equipment, wells, or facilities). Fill information in for asset with incident.

Location of asset: NTS \_\_\_\_\_ - \_\_\_\_\_ - \_\_\_\_\_ / \_\_\_\_\_ - \_\_\_\_\_ - \_\_\_\_\_ or  
DLS \_\_\_\_\_, SEC \_\_\_\_\_, TWP \_\_\_\_\_, RGE \_\_\_\_\_ W6M

BCER Site #:

Site Detail (on lease equipment):

#### WELL

Well Authorization #:

Status of well:

Depth/Perforation: \_\_\_\_\_ m KB

Wellbore Fluid Density: \_\_\_\_\_ kg/m<sup>3</sup>



**OTHER LOCATION**

(Any asset that does not apply to above such as a road, remote sump, borrow pit, etc)  
(A UTM location must be filled out in the Location Section).

Location Type:		Location Description:	
Location of asset:	NTS _____ - _____ - _____ / _____ - _____ - _____ or DLS _____, SEC _____, TWP _____, RGE _____ W6M		
UTM (NAD 83):	m easting	m northing	REQUIRED
GPS: Latitude:	Longitude:		

**B.C. Post-Incident Report**

	<p><b>FORM D</b> <b>PERMIT HOLDER POST INCIDENT REPORT</b></p> <p>Must be submitted by the permit holder within 60 days for:                      1. Level 1, 2 or 3 emergency incident*: complete Part A-P; or                      2. Any pipeline incident, including a minor incident: complete Part A-U                      *Note: in addition to the above a permit holder may be required to complete and submit a "Form D" when requested by a representative of the Commission.</p> <p><b>This report and accompanying documentation must be emailed electronically to EMP@bc-er.ca</b></p>
DGIR # (if known)	
BCER Incident # (if known)	

**PART A – PERMIT HOLDER**

Permit holder Name	
Permit holder Address	
Contractor(s) Names(s)	
Contractor(s) Address	

**PART B – TIME, WEATHER, AND LOCATION OF INCIDENT**

Well Authorization or Facility #:	NTS/DLS Location		
Incident Date (YYYY/MM/DD)	Incident Time Hour (24-hr system & time zone)		
Duration of Incident			
Weather:	Temperature °C	(precipitation)	(wind speed & wind direction from)

**PART C – SPILLS AND RELEASES**

<input type="checkbox"/> Sweet gas <input type="checkbox"/> LVP <input type="checkbox"/> HVP <input type="checkbox"/> Toxic substance <input type="checkbox"/> Sour gas <input type="checkbox"/> Produced water <input type="checkbox"/> Oil <input type="checkbox"/> Other			
Name of product/substance		SDS Sheet or CAS# (spills only)	
Volume spilled/released	m <sup>3</sup>	Volume recovered	m <sup>3</sup>
Was there a fire? <input type="checkbox"/> Yes <input type="checkbox"/> No		Was there an explosion? <input type="checkbox"/> Yes <input type="checkbox"/> No	
Was anyone directly exposed to the spill product? <input type="checkbox"/> Yes <input type="checkbox"/> No		Was medical treatment required? <input type="checkbox"/> Yes <input type="checkbox"/> No (if yes, complete Part H)	

**PART D – ORIGIN OF INCIDENT**

Facility involved	<input type="checkbox"/> Battery Site <input type="checkbox"/> Processing Battery <input type="checkbox"/> Satellite Battery <input type="checkbox"/> Compressor Dehydrator <input type="checkbox"/> Compressor Station <input type="checkbox"/> Gas Dehydrator <input type="checkbox"/> Gas Processing Plant <input type="checkbox"/> Gas Sales Meter <input type="checkbox"/> Injection Station <input type="checkbox"/> Disposal Station <input type="checkbox"/> LNG Facility <input type="checkbox"/> Oil Sales Meter <input type="checkbox"/> Tank Terminal <input type="checkbox"/> Test Facility <input type="checkbox"/> Water Hub <input type="checkbox"/> Other Related Facility (specify):		
Site Equipment involved	<input type="checkbox"/> On Lease Pipe <input type="checkbox"/> Valve <input type="checkbox"/> Pressure relief device <input type="checkbox"/> Fitting <input type="checkbox"/> Compressor <input type="checkbox"/> Pump <input type="checkbox"/> Pressure vessel <input type="checkbox"/> Tank <input type="checkbox"/> Instrumentation <input type="checkbox"/> Other (specify):		
Well site incident involved	<input type="checkbox"/> Wellhead failure <input type="checkbox"/> BOP <input type="checkbox"/> Kick <input type="checkbox"/> Drilling Equipment <input type="checkbox"/> Servicing Equipment <input type="checkbox"/> Casing <input type="checkbox"/> Other (specify):		

**PART E – EQUIPMENT MALFUNCTION/FAILURE**

Equipment	Manufacturer	Model #
Manufactured Date:	Installed Date:	Certification Date:

Will there be or has there been any third-party analysis of equipment failure (if applicable)?  Yes  No

If yes, please describe:

**PART F – ESTIMATE OF TOTAL INCIDENT COST** *Provide total cost estimate including repair, clean-up and restoration*

\$

**PART G – REPAIR DESCRIPTION** *Provide description of all necessary repairs as a result of the incident and include date of return to service*

**PART H – INJURY AND FATALITY DESCRIPTIONS**

Affiliation			Fatality or injury description (as per WorkSafeBC definitions)		
<input type="checkbox"/> Company employee	<input type="checkbox"/> Contractor	<input type="checkbox"/> Public	<input type="checkbox"/> Minor Injury	<input type="checkbox"/> Major Injury	<input type="checkbox"/> Fatality
<input type="checkbox"/> Company employee	<input type="checkbox"/> Contractor	<input type="checkbox"/> Public	<input type="checkbox"/> Minor Injury	<input type="checkbox"/> Major Injury	<input type="checkbox"/> Fatality
<input type="checkbox"/> Company employee	<input type="checkbox"/> Contractor	<input type="checkbox"/> Public	<input type="checkbox"/> Minor Injury	<input type="checkbox"/> Major Injury	<input type="checkbox"/> Fatality
<input type="checkbox"/> Company employee	<input type="checkbox"/> Contractor	<input type="checkbox"/> Public	<input type="checkbox"/> Minor Injury	<input type="checkbox"/> Major Injury	<input type="checkbox"/> Fatality
<input type="checkbox"/> Company employee	<input type="checkbox"/> Contractor	<input type="checkbox"/> Public	<input type="checkbox"/> Minor Injury	<input type="checkbox"/> Major Injury	<input type="checkbox"/> Fatality

**IMMEDIATE INCIDENT CAUSE OF SERIOUS INJURY** *(Immediate Cause—means unsafe acts or unsafe conditions)*

- Defective/inadequate safety devices, tools or equipment
- Improper loading or placement
- Congested work area/disorderly workplace
- Other (specify)
- Improper operation of safety devices, tools or equipment
- Hazardous environment (gases, dust, smoke, fumes or vapours)

**PART I – NARRATIVE OF INCIDENT** *Provide a complete description of the incident, including conditions and events leading up to, and following, the incident. Attach any additional information that may supplement the narrative such as 1) drawing of the incident site; 2) photographs; 3) schematics; 4) maps; 5) reports (drilling, servicing, metallurgical, NDT, inspection, pressure test, etc.); 6) List any fluids associated to incident (environmental reports etc.)*

*Attach additional sheets of narrative as required.*

**PART J – INCIDENT RESPONSE** Describe how the Emergency Response Plan was implemented and outline applicable steps taken to:

- Provide for the safety and health of all responders
- Save lives
- Reduce suffering
- Protect public health
- Protect government infrastructure
- Protect property
- Protect the environment
- Reduce economic and social losses

Empty space for describing the implementation of the Emergency Response Plan and applicable steps taken.

**PART K – WITNESS INFORMATION**

<i>Name</i>	<i>Phone No.</i>

**PART L – INCIDENT CAUSES** *Identify all causes contributing to the incident; more than one cause may be assigned to the incident*

- Third Party                       External Corrosion                       Internal Corrosion                       Human Error                       Over Pressuring Equipment  
 Equipment Failure                       Geological                       Manufacturing Defect

Additional comments on selected basic cause:

**PART M – CORRECTIVE ACTION(S)** *Provide an outline of the steps taken to prevent a similar incident; OR, explain if no corrective action was necessary*

**PART N – NAME OF PERSON CONDUCTING A COMPANY INCIDENT INVESTIGATION**

Name	Title
Address	
Telephone number	Fax number

**PART O – NAMES OF OTHER AGENCIES INVESTIGATING INCIDENT**

Agency	Agency
Telephone number	Telephone number
Contact name	Contact name
Agency	Agency
Telephone number	Telephone number
Contact name	Contact name

**PART P – NAME AND TITLE OF COMPANY REPRESENTATIVE FILING REPORT**

Name	Title	
Signature	Company	
Address		
Date (YYYY/MM/DD HH)	Telephone number	Fax Number

**ADDITIONAL INFORMATION REQUIRED: PIPELINE INCIDENTS ONLY**

**PART Q – PIPELINE INFORMATION**

Pipeline Project #

CSA Class Location     1     2     3     4

Location of Incident(s) on pipeline using Latitude & Longitude or UTM (Preferred):

**PART R – IMMEDIATE CAUSE Check all applicable causes  
Check the box for the incident cause and check one of the sub-causes as defined in CSA Z662-2007 Annex H**

PRIMARY CAUSE	SUB CAUSE
<input type="checkbox"/> Corrosion	<input type="checkbox"/> Internal <input type="checkbox"/> External
<input type="checkbox"/> Cracking	<input type="checkbox"/> stress corrosion cracking <input type="checkbox"/> hydrogen induced <input type="checkbox"/> mechanical damage <input type="checkbox"/> corrosion fatigue <input type="checkbox"/> fatigue
<input type="checkbox"/> External interference	<input type="checkbox"/> third party <input type="checkbox"/> vandalism <input type="checkbox"/> company employee or contractor
<input type="checkbox"/> Material manufacturing or construction	<input type="checkbox"/> defective weld <input type="checkbox"/> defective other joint <input type="checkbox"/> defective pipe body <input type="checkbox"/> wrinkle or buckle
<input type="checkbox"/> Weather & geotechnical failure	<input type="checkbox"/> heavy rains or floods <input type="checkbox"/> freeze-thaw <input type="checkbox"/> construction or undermining <input type="checkbox"/> earthquake <input type="checkbox"/> slope movement <input type="checkbox"/> lightning <input type="checkbox"/> wildfire
<input type="checkbox"/> Equipment malfunction/failure	
<input type="checkbox"/> Incorrect operational procedure	
<input type="checkbox"/> Other (specify)	

**PART S – LINE PIPE DATA**

Type of failure:

Nominal diameter (mm)	Wall thickness (mm)	Date of manufacture
Weld process	SMYS (MPa)	
Pipe specifications <input type="checkbox"/> Z 245 <input type="checkbox"/> Other (specify)	Pipe location <input type="checkbox"/> Below ground <input type="checkbox"/> Above ground	
Maximum operating pressure (kPa)	Pressure at time of incident (kPa)	
Latest pressure test date	Maximum test pressure (kPa)	Test duration (hrs)

**PART T – CORROSION FAILURES**

Corrosion location <input type="checkbox"/> Internal <input type="checkbox"/> External	Circumferential position looking downstream (mark on diagram below) 
Type of corrosion (specify): Type of coating:	

**PART U – FAILURES DUE TO EXTERNAL LOAD OR NATURAL FORCES**

<input type="checkbox"/> Damage by operator or its contractor <input type="checkbox"/> Damage by other parties <input type="checkbox"/> Vandalism <input type="checkbox"/> Pre-loading <input type="checkbox"/> Earth movement <input type="checkbox"/> Lightning/Fire <input type="checkbox"/> Other (specify):	
Name of Contractor/Other Party	
Address	
Phone	Name of representative

**For Commission Use Only**

Incident No.	Date Received	Reviewer
--------------	---------------	----------

Reviewer's Commends and any actions taken:



505 Sixth Street, Suite 200, New Westminster, BC V3L 0E1  
Toll free: 1-866-566-7233 Website: [www.safetyauthority.ca](http://www.safetyauthority.ca)

## Incident Reporting Form

Note: The information on this form is collected to administer the provisions of the BC Safety Standards Act and section 26 of the Freedom of Information and Protection of Privacy Act. If you have questions about the collection, use, or disclosure of this information, contact the Records, Information & Privacy Analyst at 1-866-566-7233.

### Instructions for Use

For incidents involving the following technologies:

- |   |   |
|---|---|
| <input type="checkbox"/> Amusement Rides                          | <input type="checkbox"/> Passenger Ropeways |
| <input type="checkbox"/> Boilers, Pressure Vessels, Refrigeration | <input type="checkbox"/> Elevating Devices  |
| <input type="checkbox"/> Electrical                               | <input type="checkbox"/> Gas                |

**Note:** For all Amusement Rides and Passenger Ropeways incidents (Level I, II, and III):

1. Call 1-866-566-7233 to report the incident
2. Complete form below:
  1. save the form to your computer
  2. upload the form as an attachment to an email
  3. send to [incidents@safetyauthority.ca](mailto:incidents@safetyauthority.ca)
3. You may also save a copy for your records.

### EMERGENCY RESPONSE

For an incident requiring IMMEDIATE emergency response:  
**(ambulance, fire, and/or police) CALL 911**

### LEVEL I & II INCIDENTS

An incident involving serious injuries or damages (Level I & II incidents) must be reported immediately to the Technical Safety BC by:

**Telephone: 1-866-566-7233**

### LEVEL III INCIDENTS

An incident involving minor injuries/damages or no injuries/damages (Level III incidents) must be reported within 24-hours to the Technical Safety BC by:

**Email: [incidents@safetyauthority.ca](mailto:incidents@safetyauthority.ca)**

or

**Telephone: 1-866-566-7233**

Technical Safety BC is working towards going paperless! Participate by signing up for email correspondence.



## Incident Reporting Form

Note: The information on this form is collected to administer the provisions of the BC Safety Standards Act and section 26 of the Freedom of Information and Protection of Privacy Act. If you have questions about the collection, use, or disclosure of this information, contact the Records, Information & Privacy Analyst at 1-866-566-7233.

Date Reported: \_\_\_\_\_

Time Reported: \_\_\_\_\_

### DETAILS

Date Incident Occurred: \_\_\_\_\_

Time Incident Occurred: \_\_\_\_\_

Address/Location of Incident:

Type of Premises: \_\_\_\_\_

If other, please specify: \_\_\_\_\_

Technology Involved: \_\_\_\_\_

Incident Description:

Incident Cause:

Description of Injuries

Description of Damages:

Number of People Injured: \_\_\_\_\_

Equipment/Property Damage:  Yes  No

Number of Fatalities: \_\_\_\_\_

Product/Equipment still in service:  Yes  No

Hospitalization Required:  Yes  No

Name of Contractor / FSR: \_\_\_\_\_

Unit Number: \_\_\_\_\_

Contractor / FSR Phone Number: \_\_\_\_\_

Permit Number: \_\_\_\_\_

### Notifier's Information:

Name: \_\_\_\_\_

By submitting this form, I give consent to Technical Safety BC to verify and disclose the information provided on this form for the purposes consistent with the administration of the Safety Standards Act.

Organization: \_\_\_\_\_

Contact Phone Number: \_\_\_\_\_

Technical Safety BC is working towards going paperless! Participate by signing up for email correspondence.

**BC Wildfire Emergency Contact Information**



BRITISH COLUMBIA | BC Wildfire Service

For all users: Please refer to the [Wildfire Act](#) and [Wildfire Regulation](#) for statutory responsibilities, obligations and requirements.

**INFORMATION ABOUT THE ACTIVITY**

Date

Form

Completed:

<b>Worksite Details (manned facilities only e.g. staff on site &gt; 4 hrs/day)</b>			
Project Name		Project Number	
Physical location of activity (helpful if map attached, or attach additional information as necessary)		Type of Activity	
		Specify:	
		Format for Lat & Long: Degrees[space] Minutes[.Decimal] (e.g. 125 15 20)	
		Lat	Long
UDO ID (UDO information to be completed by BCWS)			
Duration of Activities (enter date(s) for appropriate period only)			
Temporary	Start	End	
Intermittent	Dates	Permanent	Start Date
<b>Company Contact Information (INCLUDING sub-contractors - add additional pages if necessary)</b> (For more than one temporary activity taking place, one central contact and number would be sufficient information provided)			
24 hr Company Emergency Line(s) #			
Company Name			
Contact	Phone	E-mail	
Alternate 24 hr Contact Name and Phone(s)			
Company Name			
Contact	Phone	E-mail	
<b>Other Key Emergency Contact(s) # – List contractors and sub-contractors (attach additional pages as necessary)</b>			
Company Name		Phone	
Contact	Phone	E-mail	
<b>List of industrial activities (OPTIONAL to complete – as specified in the <a href="#">Wildfire Regulation</a>)</b>			
<input type="checkbox"/> Any high-risk activity as defined in the <a href="#">Wildfire Regulation</a>			
<b>Operating equipment or machinery in relation to forest management during:</b>		<b>Operating equipment or machinery in relation to activities other than forest management during:</b>	
<input type="checkbox"/> road construction, road maintenance and road deactivation <input type="checkbox"/> timber harvesting, including sorting logs <input type="checkbox"/> mechanical modification of forest debris and debris piling <input type="checkbox"/> silviculture treatments <input type="checkbox"/> portable wood chipping, milling, processing or manufacturing <input type="checkbox"/> other (specify) _____		<input type="checkbox"/> debris piling <input type="checkbox"/> road construction, road maintenance or road deactivation <input type="checkbox"/> rock drilling <input type="checkbox"/> mining operations <input type="checkbox"/> railway operations <input type="checkbox"/> utility transmission operations <input type="checkbox"/> portable wood chipping, milling, processing or manufacturing <input type="checkbox"/> other (specify) _____	
<b>Fire Emergency Contact Information</b>			
<b>Forest Fire Reporting: 1-800-663-5555 or * 5555</b> on most cellular networks			
<b>Fire Centre Contact Information</b> (know which fire centre is local to your activities) See <a href="#">Map</a> .			
Fire Centre	E-mail Form to:	Office Phone	
Coastal	<a href="mailto:BCWS.COFCDispatch@gov.bc.ca">BCWS.COFCDispatch@gov.bc.ca</a>	250-951-4222	
Southeast	<a href="mailto:BCWS.SEFCDDispatch@gov.bc.ca">BCWS.SEFCDDispatch@gov.bc.ca</a>	250-365-4040	
Kamloops	<a href="mailto:BCWS.KFCDispatch@gov.bc.ca">BCWS.KFCDispatch@gov.bc.ca</a>	250-554-7701	
Cariboo	<a href="mailto:BCWS.CARFCDispatch@gov.bc.ca">BCWS.CARFCDispatch@gov.bc.ca</a>	250-989-2600	
Prince George	<a href="mailto:BCWS.PGFCDispatch@gov.bc.ca">BCWS.PGFCDispatch@gov.bc.ca</a>	250-565-6126	
Northwest	<a href="mailto:BCWS.NWFCDDispatch@gov.bc.ca">BCWS.NWFCDDispatch@gov.bc.ca</a>	250-847-6633	
BC Wildfire Management Branch Website: <a href="http://bcwildfire.ca">http://bcwildfire.ca</a>			

Complete this form and submit electronically to the appropriate Fire Centre.



11.3 ICS Forms

ICS 201 - Incident Briefing

<b>DETAILS</b>	Incident:	
	Date:	
	Time (0-2400 hrs):	Time Zone:
	Prepared by (Name and Position):	Signature:
<b>MAP SKETCH</b>		
<b>SITUATION SUMMARY AND SAFETY BRIEFING</b>		

PAGE 1 OF 4







*ICS 202 - Incident Objectives*

<b>DETAILS</b>	Incident:	
	Date:	
	Time (0-2400 hrs):	Time Zone:
	Operational Period (Date/Time)	Date From: _____ Date To: _____ Time From: _____ Time To: _____
	Prepared by (Planning Section Chief):	Signature: _____
	Approved by (Incident Commander):	Signature: _____
<b>GENERAL CONTROL OBJECTIVES FOR THE INCIDENT</b>	(Include alternatives)	
<b>WEATHER FORECAST</b>		
<b>GENERAL SAFETY MESSAGE</b>		
<b>ATTACHMENTS</b>	<input type="checkbox"/> ICS 203 - Organization List <input type="checkbox"/> Medical Plan (ICS 206) <input type="checkbox"/> _____ <input type="checkbox"/> ICS 204 - Assignment List <input type="checkbox"/> ERP Map <input type="checkbox"/> _____ <input type="checkbox"/> _____	

ICS 203 - Organization Assignment List

<b>DETAILS</b>	Incident:				
	Date:				
	Time (0-2400 hrs):		Time Zone:		
	Operational Period (Date/Time)		Date From: _____	Date To: _____	
			Time From: _____	Time To: _____	
Prepared by (Planning Section Chief):		Signature:			
<b>INCIDENT COMMAND STAFF</b>	Incident Commander		<b>OPERATIONS SECTION</b>	Operations Section Chief	
	Deputy IC			a. Staging Area Manager	
	Safety Officer			b. Public Protection Group Supervisor	
	Liaison Officer			Roadblock Team	
	Unified Commander(s)			Rover Evacuation Team	
				Air Monitoring Team	
		Reception Team			
		Telephone Team			
		c. On-Site Group Supervisor			
		Fire Control Team			
		Isolation Repair Team			
		Spill Response Team			
		Site Security Team			
		Ignition Team			
		d. Additional Support			
		e. Additional Services			
<b>AGENCY/ ORGANIZATION REPRESENTATIVES</b>	Agency/Organization	Representative			
<b>PLANNING SECTION</b>	Planning Section Chief				
	Engineering				
	Human Resources				
	Legal				
<b>LOGISTICS SECTION</b>	Logistics Section Chief		<b>EOC / FINANCE / ADMIN SECTION</b>	Finance/Admin Section Chief	
				Business Impact Support	
	b. Additional Services				
	PAGE 1 OF 1				
	PAGE 1 OF 1				





ICS 206 - Medical Plan

<b>DETAILS</b>	Incident:									
	Date:									
	Time (0-2400 hrs):								Time Zone:	
	Operational Period (Date/Time)			Date From: _____			Date To: _____			
				Time From: _____			Time To: _____			
	Prepared by (Safety Officer):					Signature: _____			Date/Time	
Approved by (Incident Commander):					Signature: _____			Date/Time		
<b>INCIDENT MEDICAL AID STATION</b>	<b>Medical Aid Stations</b>		<b>Location</b>			<b>Contact (number or frequency)</b>		<b>Paramedics</b>		
								<b>Yes</b>	<b>No</b>	
								<input type="checkbox"/>	<input type="checkbox"/>	
								<input type="checkbox"/>	<input type="checkbox"/>	
								<input type="checkbox"/>	<input type="checkbox"/>	
								<input type="checkbox"/>	<input type="checkbox"/>	
<b>TRANSPORTATION</b>	<b>Ambulance Service</b>		<b>Location</b>			<b>Contact (number or frequency)</b>		<b>Level of Serv.</b>		
								<b>ALS</b>	<b>BLS</b>	
								<input type="checkbox"/>	<input type="checkbox"/>	
								<input type="checkbox"/>	<input type="checkbox"/>	
								<input type="checkbox"/>	<input type="checkbox"/>	
								<input type="checkbox"/>	<input type="checkbox"/>	
<b>HOSPITALS</b>	<b>Hospital Name</b>	<b>Address (lat/long if helipad)</b>	<b>Travel Time</b>		<b>Contact (number or frequency)</b>	<b>Helipad</b>		<b>Burn Centre</b>		
			<b>Air</b>	<b>Ground</b>		<b>Yes</b>	<b>No</b>	<b>Yes</b>	<b>No</b>	
						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
<b>SPECIAL MEDICAL EMERGENCY PROCEDURES</b>										

ICS 207 - Incident Organization Chart

<b>DETAILS</b>	Incident:		
	Date:		
	Time (0-2400 hrs):		Time Zone:
	Operational Period (Date/Time)	Date From: _____ Time From: _____	Date To: _____ Time To: _____
	Prepared by (Name & Position):		Signature





ICS 208 - Safety Message / Plan

<b>DETAILS</b>	Incident:	
	Date:	
	Time (0-2400 hrs):	Time Zone:
	Operational Period (Date/Time)	Date From: _____ Date To: _____ Time From: _____ Time To: _____
	Prepared by (Site Safety Officer):	Signature: _____
<b>SAFETY MESSAGE/EXPANDED SAFETY MESSAGE, SAFETY PLAN, SITE SAFETY PLAN</b>		
<b>SAFETY PLAN</b>	Site Safety Plan Required? Yes <input type="checkbox"/> No <input type="checkbox"/> Approved Site Safety Plan(s) located at: _____	
		PAGE 1 OF 1

ICS 209 - Incident Status Summary

<b>DETAILS</b>	*Incident Name:		Incident No:			
	*Report Version Check one box on left): <input type="checkbox"/> Initial Rpt# <input type="checkbox"/> Update (if used) <input type="checkbox"/> Final		*Incident Commander(s) & Agency or Organization		Incident Management Organization  *Incident Start Date/Time Date:  Time:	
	Current Incident Size or Area Involved (Use unit label – e.g. 'sq km', 'city block')	% Contained	*Incident Definition	Incident Complexity Level		*For Time Period From Date/Time:  To Date/Time:
		Completed				
<b>APPROVAL &amp; ROUTING INFORMATION</b>	*Prepared by:		ICS Position:		Signature:	
	Approved by:		ICS Position:		Signature:	
	*Date/Time Submitted:					
	*Primary Location, Organization, or Agency Sent To:					
<b>INCIDENT LOCATION INFORMATION</b>	*Province/Territory		*County, Regional/Rural Municipality, Regional/Municipal District		*City	
	Unit or Other		*Incident Jurisdiction		Incident Location Ownership (if different than jurisdiction)	
	Longitude	Latitude	Datum		Legal Description (twp, range, section)	
	*Short location or area description (list all affected areas or a reference point)				*UTM Coordinates	
	Note any electronic geospatial data included or attached (indicate data format, content, and collection time information and labels)					
<b>INCIDENT SUMMARY</b>	*Significant events for the time period reported (summarize significant progress made, evacuations, incident growth, etc.)					
	Primary materials or hazards involved (hazardous chemicals, fuel types, infectious agents, radiation, etc.)					
	Damage Assessment Information (summarize damage and/or restriction of use or availability to residential or commercial property, natural resources, critical infrastructure and key resources, etc.)	Structural Summary	# Threatened (72 hrs)	# Damaged	# Destroyed	
		Single Residences				
		Non-residential Commercial Property				
Other Structures Minor						
Other						
*required when applicable					PAGE 1 OF 4	

<b>DETAILS</b>	*Incident Name:			Incident No:		
	<b>*Public Status Summary</b>	<b># This Reporting Period</b>	<b>Total # To Date</b>	<b>*Responder Status Summary</b>	<b># This Reporting Period</b>	<b>Total # To Date</b>
<b>ADDITIONAL INCIDENT DECISION SUPPORT INFORMATION</b>	Indicate number of Stakeholders (public) below			Indicate number of responders below		
	Fatalities			Fatalities		
	With Injuries/Illness			With Injuries/Illness		
	Trapped/In Need of Rescue			Trapped/In Need of Rescue		
	Missing (note if estimated)			Missing (note if estimated)		
	Evacuated (note if estimated)			Evacuated (note if estimated)		
	Sheltering in Place (note if estimated)			Sheltering in Place (note if estimated)		
	In Reception Centres (note if estimated)			In Reception Centres (note if estimated)		
	Total # Stakeholders (Public) Affected			Total Responders Affected		
	Life, Safety, and Health Status/Threat Remarks			<b>Life, Safety, and Health Threat Mgmt</b>		<b>Check if active</b>
				No likely threat		<input type="checkbox"/>
				Potential Future Threat		<input type="checkbox"/>
				Mass notifications in progress		<input type="checkbox"/>
				Mass notifications completed		<input type="checkbox"/>
				No evacuation(s) imminent		<input type="checkbox"/>
				Planning for evacuation		<input type="checkbox"/>
				Planning for shelter-in-place		<input type="checkbox"/>
Evacuation(s) in progress				<input type="checkbox"/>		
Shelter-in-Place in Progress				<input type="checkbox"/>		
Area restriction in effect				<input type="checkbox"/>		
				<input type="checkbox"/>		
				<input type="checkbox"/>		
				<input type="checkbox"/>		
Weather Concerns (synopsis of current and predicted weather, discuss related factors that may cause concern)					<input type="checkbox"/>	
					<input type="checkbox"/>	
					<input type="checkbox"/>	
					<input type="checkbox"/>	
					<input type="checkbox"/>	
					<input type="checkbox"/>	
<b>Project Incident Activity, Potential, Movement, Escalation, or Spread and influencing factors during the next operational period and in 12-, 24-, 48-, and 72-hour timeframes</b>						
12 hours						
24-hours						
48 hours						
72 hours						
Anticipated after 72 hours						
Objectives (define planned end-state for incident)						

\*required when applicable

<b>DETAILS</b>	<b>*Incident Name:</b>	<b>Incident No:</b>
	<b>CURRENT INCIDENT THREAT SUMMARY AND RISK INFORMATION IN 12-, 24-, 48-, AND 72-HOUR TIMEFRAMES AND BEYOND</b> Summarize primary incident threats to life, property, communities and community stability, residences, health care facilities, other critical infrastructure and key resources, commercial facilities, natural and environmental resources, cultural resources, and continuity of operations and/or business. Identify corresponding incident-related potential economic or cascading impacts.	
<b>ADDITIONAL INCIDENT DECISION SUPPORT INFORMATION (continued)</b>	12 hours	
	24-hours	
	48 hours	
	72 hours	
	Anticipated after 72 hours	
	<b>Critical Resource Needs in 12-, 24-, 48-, and 72-hour timeframes and beyond to meet critical incident objectives.</b> List resource category, kind, and/or type, and amount needed, in priority order:	
	12 hours	
	24-hours	
	48 hours	
	72 hours	
	Anticipated after 72 hours	
	<b>Strategic discussion: explain in relation to overall strategy, constraints, and current available information to:</b> 1) critical resource needs identified above, 2) the Incident Action Plan and management objectives, 3) anticipated results. Explain major problems and concerns such as operational challenges, incident management problems, and social, political, economic, or environmental concerns or impacts.	
	Planned Actions for Next Operational Period	
	Projected final incident size/area (Use Unit Label – e.g., “sq km”)	
	Anticipated Incident Management Completion Date	
	Projected Significant Resource Demobilization Start Date	
Estimated Incident Costs to Date		
Projected Final Incident Cost Estimate		
Remarks (or continuation of any blocks above – list block number in notation)		

\*required when applicable



ICS 211 - Check-In List

<b>DETAILS</b>	Incident Name:	Incident Number (if assigned):	Check-In Location										Start Date/Time						
			<input type="checkbox"/> OSCP <input type="checkbox"/> ICP <input type="checkbox"/> Staging Area <input type="checkbox"/> EOC <input type="checkbox"/> Hel base <input type="checkbox"/> Other _____										Date:						
	Prepared by (Name & Position):											Signature		Time:					
CHECK-IN INFORMATION (use reverse of form for remarks or comments)	List Personnel (overhead) by Agency & Name – OR List Resources by the Following Format							LDW	Order Request Number	Date/Time Check-In	Leader's Name	Total Number of Personnel	Contact Information	Home Unit/ Base	Departure Point	Method of Travel	Incident Assignment	Other Qualifications	Sent to Resource Unit
	P/T	AGENCY	CAT.	KIND	TYPE	ST/TF	Resource Name or ID #												
	Remarks or Comments																		

ICS 214 - Activity Log

<b>DETAILS</b>	Incident:		
	Date:		
	Time (0-2400 hrs):		Time Zone:
	Operational Period (Date/Time)	Date From: _____ Time From: _____	Date To: _____ Time To: _____
	Prepared by:	ICS Position:	Signature:
<b>PERSONNEL ASSIGNED</b>	<b>Name</b>	<b>ICS Position</b>	<b>Command Centre (OSCP, ICP, EOC)</b>
<b>ACTIVITY LOG</b>	<b>Time</b>	<b>Major Events</b>	



ICS 215 - Operational Planning Worksheet

DETAILS	Incident:																					
	Date:																					
	Time (0-2400 hrs):								Time Zone:													
	Operational Period (Date/Time)						Date From: _____			Date To: _____												
							Time From: _____			Time To: _____												
Prepared by (Site Operations Section Chief):										Signature												
OPERATIONAL PLANNING	Branch	Division, Group, or Other	Work Assignment & Special Instructions	Resources														Overhead Position(s)	Special Equipment & Supplies	Reporting Location	Requested Arrival Time	
				Req.																		
				Have																		
				Need																		
				Req.																		
				Have																		
				Need																		
				Req.																		
				Have																		
				Need																		
				Req.																		
				Have																		
				Need																		
<b>Total Resources Required</b>																						
<b>Total Resources – Have on Hand</b>																						
<b>Total Resources Need to Order</b>																						
																	Page:					

ICS 215a - Incident Action Safety Plan Analysis

<b>DETAILS</b>	Incident:		
	Date:		
	Time (0-2400 hrs):		Time Zone:
	Operational Period (Date/Time)	Date From: _____ Time From: _____	Date To: _____ Time To: _____
	Prepared by (Site Safety Officer):	Name: _____	Signature: _____
	Prepared by (Site Operations Section Chief):	Name: _____	Signature: _____
<b>INCIDENT ACTION SAFETY PLAN</b>	<b>Incident Area</b>	<b>Hazards/Risks</b>	<b>Mitigations</b>

**ICS 221 - Demobilization Checkout**

<b>DETAILS</b>	Incident Name/Number:		Date/Time:			Demob Number:	
	Prepared by (Site Planning Section Chief or EOC Planning Chief):					Signature	
	Approved by (Incident Commander):					Signature	
	Unit/Personnel Released:						
	Transportation Type/Number:						
	Actual Release Date/Time:					Manifest Completed <input type="checkbox"/> Yes <input type="checkbox"/> No	
	Destination:		Notify	ICP <input type="checkbox"/>	Agency <input type="checkbox"/>	Region <input type="checkbox"/>	Area <input type="checkbox"/>
		Name					
		Date					
<b>UNIT/PERSONNEL</b>	You and your resources have been released subject to Sign-Off from the following: Planning Section Chief - Check the appropriate box						
	<b>LOGISTICS SECTION</b>			<b>COMMENTS</b>			
	<input type="checkbox"/> Logistics Section Chief						
	<input type="checkbox"/> a. Additional Support						
	<input type="checkbox"/>						
	<input type="checkbox"/>						
	<input type="checkbox"/> b. Additional Services						
	<input type="checkbox"/>						
	<b>PLANNING SECTION</b>						
	<input type="checkbox"/> Planning Section Chief						
	<input type="checkbox"/>						
	<input type="checkbox"/> Engineering						
	<input type="checkbox"/> Human Resources						
	<input type="checkbox"/> Legal						
	<b>OPERATIONS SECTION</b>						
<input type="checkbox"/> Operations Section Chief							
<input type="checkbox"/> Staging Area Manager							
<input type="checkbox"/> Public Protection Group Supervisor							
<input type="checkbox"/> Roadblock Team							
<input type="checkbox"/> Rover Evacuation Team							

<b>DETAILS</b>	<b>Incident Name/Number:</b>	<b>Date/Time:</b>	<b>Demob Number:</b>
	Prepared by (Site Planning Section Chief or EOC Planning Chief):		Signature
	Approved by (Incident Commander):		Signature
<b>UNIT/PERSONNEL Continued</b>	<input type="checkbox"/> Air Monitoring Team		
	<input type="checkbox"/> Reception Team		
	<input type="checkbox"/> Telephone Team		
	<input type="checkbox"/> On-Site Group Supervisor		
	<input type="checkbox"/> Fire Control Team		
	<input type="checkbox"/> Isolation Repair Team		
	<input type="checkbox"/> Spill Response Team		
	<input type="checkbox"/> Site Security Team		
	<input type="checkbox"/> Ignition Team		
	<input type="checkbox"/> a. Additional Support		
	<input type="checkbox"/>		
	<input type="checkbox"/> b. Additional Services		
	<input type="checkbox"/>		
	<b>FINANCE / ADMIN SECTION</b>		
	<input type="checkbox"/> Finance/Admin Section Chief		
	<input type="checkbox"/> Business Impact Support		
	<b>EMERGENCY OPERATIONS CENTRE (EOC)</b>		
	<input type="checkbox"/> EOC Director		
	<input type="checkbox"/> Operations and Technical Support		
	<input type="checkbox"/> Regulatory/Government Liaison		
<b>REMARKS:</b>			

*ICS 230 – Daily Meeting Schedule*

<b>DETAILS</b>	Incident: _____				
	Operational Period (Date/Time)		Date From: _____	Date To: _____	
			Time From: _____	Time To: _____	
	Prepared by (Planning Chief): _____		Signature: _____		Date/Time: _____
<b>MEETING SCHEDULE</b>	<b>Date/Time</b>	<b>Meeting Name</b>	<b>Purpose</b>	<b>Attendees</b>	<b>Location</b>



11.4 ERP Forms

*Environmental Monitoring Record*

<b>DETAILS</b>	Incident:									
	Date:									
	Time (0-2400 hrs):							Time Zone:		
	Completed by:							Response Team Position:		

<b>ENVIRONMENTAL MONITORING RECORD</b>	Time	Location of Sample:	LEL (%)	O <sub>2</sub> (%)	H <sub>2</sub> S (ppm)	SO <sub>2</sub> (ppm)	Other	Temp. (C/F°)	Wind Conditions		
									From	Speed (km/h/mph)	

*Notification Record*

<b>DETAILS</b>	Incident:			
	Date:			
	Time (0-2400 hrs):			Time Zone:
	Completed by:			
<b>INCIDENT COMMANDER</b>		<b>Who was notified?</b>	<b>Date/Time</b>	<b>Who did notification?</b>
	Supervisor:			
	Ambulance:			
	Police:			
	Fire Department:			
	Forestry Service:			
	Local Authority:			
	Prime Contractor:			
	Area Stakeholder:			
	Other:			
<b>EOC OPERATIONS CHIEF</b>		<b>Who was notified?</b>	<b>Date/Time</b>	<b>Who did notification?</b>
	Executive Team:			
	President:			
	Disaster Services:			
	Regulatory Authority:			
	Workplace Health and Safety Authority:			
	Health Authority:			
	Hospital/Health Care Facility:			
	Environmental Agency:			
	Other:			

*Roadblock Checkpoint Record*

<b>DETAILS</b>	Incident:						
	Date:						
	Time (0-2400 hrs):					Time Zone:	
	Completed by:					Response Team Position:	
<b>ROADBLOCK CHECKPOINT RECORD</b>	Vehicle Type	Licence Plate Number & Province/State	Name of Driver (if available)	Number of People in Vehicle	Time Entering EPZ	Time Exiting EPZ	Comments (Record all vehicles turned away)
Page:							

**Note:** The licensee has the responsibility to protect the public but without the assistance of the police cannot legally prevent the public from entering the secured area. If someone insists on going through the roadblock, ask him or her for emergency contact numbers, this may encourage the driver to stop.

*Spill/Release Written Report Form*

<b>DETAILS</b>	Incident:							
	Date of Notification:							
	Time of Notification (0-2400 hrs):						Time Zone:	
	Completed by:				Phone Number:			
<b>DISCOVERY</b>	Name of person who discovered release:				Phone number:			
	Date of Release (Estimate if necessary):				Time of Release (Estimate if necessary):			
	Date Release Discovered:				Time Release Discovered:			
<b>LOCATION</b>	Nearest Town/Road Intersection:							
	Directions:							
	Facility Name (any signs indicating well name, rig number, etc.?):							
	LSD, if known:							
	Additional Location Information:							
<b>WEATHER CONDITIONS</b>	Temperature °C							
	Wind speed and direction:							
	Precipitation:							
<b>SPILL/RELEASE</b>	Name of product/substance:							
	Volume (m³)/Quantity (bbl) Spilled/Released:				Volume/Quantity Recovered:			
	<input type="checkbox"/> Sweet gas	<input type="checkbox"/> LVP	<input type="checkbox"/> HVP	<input type="checkbox"/> Toxic substance	<input type="checkbox"/> Sour gas	<input type="checkbox"/> Produced water	<input type="checkbox"/> Oil	<input type="checkbox"/> Other
	Was there a fire? <input type="checkbox"/> Yes <input type="checkbox"/> No				Was there an explosion? <input type="checkbox"/> Yes <input type="checkbox"/> No			

		Yes	No	Details
<b>RELEASE INFORMATION</b>	Is the health or safety of any individuals (residences, communities, etc.) in imminent danger?	<input type="checkbox"/>	<input type="checkbox"/>	
	Are any specially designated environmental areas (wetland, preserves, etc.) in imminent danger?	<input type="checkbox"/>	<input type="checkbox"/>	
	Was any waterway affected?	<input type="checkbox"/>	<input type="checkbox"/>	If yes, provide name of waterway:
	Was release contained? If no, describe dimensions of release (length, width depth). If yes, describe containment (within firewall, booms, etc.).	<input type="checkbox"/>	<input type="checkbox"/>	
	Description of release and impacts, including wells and/or facilities involved, and the source of release (stuffing box rubber on well head burned up, internal corrosion on flow line, etc.):			
<b>RESPONSE ACTIONS</b>	<b>Resource</b>	<b>Contractor/Equipment</b>		<b>Estimated Cost</b>
	List contractors summoned to assist in containment:			\$
				\$
				\$
	List contractors summoned to assist in clean-up:			\$
				\$
				\$
	List special clean-up equipment used:			\$
				\$
	Describe remedial action taken and current status:			
Page:				

# STARS<sup>®</sup>

Site Number \_\_\_\_\_  
Location \_\_\_\_\_

## Remote Site Landing Zone Reference Card

In the event of a **SITE EMERGENCY**  
**PHONE the STARS Emergency Link Centre<sup>®</sup>**

**TOLL FREE**  
**1-888-888-4567**

**OR**


**DIRECT**  
**403-299-0932**

### BE PREPARED WITH THE FOLLOWING INFORMATION

1. STARS Site Number
2. Location of site (Legal Land Description or GPS)
3. Contact phone number at the site
4. Known hazards on-site
5. If applicable, is there a monitor on-site confirming the presence of H<sub>2</sub>S

### SAFETY GUIDELINES

- the landing zone should be on level ground, (less than 5% slope) at least 36 x 36 metres (120 x 120 ft) and more, if possible, to include a safety zone
- check for loose debris in landing zone  
**THIS IS OF VITAL IMPORTANCE**
- ensure no one approaches the helicopter  
STARS crew will approach you when safe to do so
- everyone should be at least 30 metres from landing zone during landing and takeoff, due to possibility of injury from loose debris caused by rotor downwash
- movement around aircraft is to be in safe areas only
- if necessary, provide road blocks approximately 500 metres on either side of the landing zone



### PRE-LANDING CHECKLIST

The STARS Emergency Link Centre will require the following information from the site:

TERRAIN	LANDING ZONE MARKINGS	HAZARDS
level or sloping	4 turbo flares or strobe flares (no chemical flares)	signs
type of surface	4 highway cones (days only)	vehicles
dust, loose snow,	Extra strobes, flares, or cones on upwind side	trees
rocks, bushes,		equipment
stumps, etc.		wires



**Telephone Checklist for Threatening Calls**

<b>DETAILS</b>	Date:																									
	Time (0-2400 hrs):	Time Zone:																								
	Completed by:																									
<b>CALL DETAILS</b>	<b>When a threat is received:</b> <ul style="list-style-type: none"> <li>• Have someone listen in on the call and have call traced, if possible.</li> <li>• Listen.</li> <li>• Be calm and courteous.</li> <li>• Do not interrupt the caller.</li> <li>• Obtain as much information as you can.</li> </ul>																									
	<b>Questions to ask for bomb threats:</b> <ul style="list-style-type: none"> <li>• When is the bomb going to explode?</li> <li>• Where is it right now?</li> <li>• Why did you place the bomb?</li> <li>• What does it look like?</li> <li>• What will cause it to explode?</li> <li>• What is your name and address?</li> </ul>																									
	<b>Exact wording of the threat:</b>																									
	<b>BACKGROUND SOUNDS</b> <table border="0"> <tr> <td><input type="checkbox"/> Street Noises</td> <td><input type="checkbox"/> PA System</td> <td><input type="checkbox"/> Motor</td> <td><input type="checkbox"/> Animal noises</td> </tr> <tr> <td><input type="checkbox"/> Local</td> <td><input type="checkbox"/> Crockery</td> <td><input type="checkbox"/> Music</td> <td><input type="checkbox"/> Office machinery</td> </tr> <tr> <td><input type="checkbox"/> Clear</td> <td><input type="checkbox"/> Long distance</td> <td><input type="checkbox"/> Voices</td> <td><input type="checkbox"/> House noises</td> </tr> <tr> <td><input type="checkbox"/> Factory</td> <td><input type="checkbox"/> Static</td> <td><input type="checkbox"/> Booth</td> <td><input type="checkbox"/> Other</td> </tr> </table>		<input type="checkbox"/> Street Noises	<input type="checkbox"/> PA System	<input type="checkbox"/> Motor	<input type="checkbox"/> Animal noises	<input type="checkbox"/> Local	<input type="checkbox"/> Crockery	<input type="checkbox"/> Music	<input type="checkbox"/> Office machinery	<input type="checkbox"/> Clear	<input type="checkbox"/> Long distance	<input type="checkbox"/> Voices	<input type="checkbox"/> House noises	<input type="checkbox"/> Factory	<input type="checkbox"/> Static	<input type="checkbox"/> Booth	<input type="checkbox"/> Other								
	<input type="checkbox"/> Street Noises	<input type="checkbox"/> PA System	<input type="checkbox"/> Motor	<input type="checkbox"/> Animal noises																						
<input type="checkbox"/> Local	<input type="checkbox"/> Crockery	<input type="checkbox"/> Music	<input type="checkbox"/> Office machinery																							
<input type="checkbox"/> Clear	<input type="checkbox"/> Long distance	<input type="checkbox"/> Voices	<input type="checkbox"/> House noises																							
<input type="checkbox"/> Factory	<input type="checkbox"/> Static	<input type="checkbox"/> Booth	<input type="checkbox"/> Other																							
<b>THREATENING LANGUAGE</b> <table border="0"> <tr> <td><input type="checkbox"/> Well spoken (educated)</td> <td><input type="checkbox"/> Foul</td> <td><input type="checkbox"/> Irrational</td> </tr> <tr> <td><input type="checkbox"/> Message being read by threat maker</td> <td><input type="checkbox"/> Taped</td> <td><input type="checkbox"/> Incoherent</td> </tr> </table>		<input type="checkbox"/> Well spoken (educated)	<input type="checkbox"/> Foul	<input type="checkbox"/> Irrational	<input type="checkbox"/> Message being read by threat maker	<input type="checkbox"/> Taped	<input type="checkbox"/> Incoherent																			
<input type="checkbox"/> Well spoken (educated)	<input type="checkbox"/> Foul	<input type="checkbox"/> Irrational																								
<input type="checkbox"/> Message being read by threat maker	<input type="checkbox"/> Taped	<input type="checkbox"/> Incoherent																								
<b>CALLER DETAILS</b>	Distinguishing accent:																									
	Age:	Sex:																								
	Length of call:	Number called:																								
	<b>CALLER'S VOICE</b> <table border="1"> <tr> <td><input type="checkbox"/> Calm</td> <td><input type="checkbox"/> Angry</td> <td><input type="checkbox"/> Excited</td> <td><input type="checkbox"/> Slow</td> </tr> <tr> <td><input type="checkbox"/> Rapid</td> <td><input type="checkbox"/> Soft</td> <td><input type="checkbox"/> Loud</td> <td><input type="checkbox"/> Laughter</td> </tr> <tr> <td><input type="checkbox"/> Crying</td> <td><input type="checkbox"/> Normal</td> <td><input type="checkbox"/> Distinct</td> <td><input type="checkbox"/> Slurred</td> </tr> <tr> <td><input type="checkbox"/> Nasal</td> <td><input type="checkbox"/> Stutter</td> <td><input type="checkbox"/> Lisp</td> <td><input type="checkbox"/> Raspy</td> </tr> <tr> <td><input type="checkbox"/> Deep</td> <td><input type="checkbox"/> Ragged</td> <td><input type="checkbox"/> Clearing throat</td> <td><input type="checkbox"/> Deep breathing</td> </tr> <tr> <td><input type="checkbox"/> Cracking</td> <td><input type="checkbox"/> Disguised</td> <td><input type="checkbox"/> Accent</td> <td><input type="checkbox"/> Familiar</td> </tr> </table>		<input type="checkbox"/> Calm	<input type="checkbox"/> Angry	<input type="checkbox"/> Excited	<input type="checkbox"/> Slow	<input type="checkbox"/> Rapid	<input type="checkbox"/> Soft	<input type="checkbox"/> Loud	<input type="checkbox"/> Laughter	<input type="checkbox"/> Crying	<input type="checkbox"/> Normal	<input type="checkbox"/> Distinct	<input type="checkbox"/> Slurred	<input type="checkbox"/> Nasal	<input type="checkbox"/> Stutter	<input type="checkbox"/> Lisp	<input type="checkbox"/> Raspy	<input type="checkbox"/> Deep	<input type="checkbox"/> Ragged	<input type="checkbox"/> Clearing throat	<input type="checkbox"/> Deep breathing	<input type="checkbox"/> Cracking	<input type="checkbox"/> Disguised	<input type="checkbox"/> Accent	<input type="checkbox"/> Familiar
	<input type="checkbox"/> Calm	<input type="checkbox"/> Angry	<input type="checkbox"/> Excited	<input type="checkbox"/> Slow																						
	<input type="checkbox"/> Rapid	<input type="checkbox"/> Soft	<input type="checkbox"/> Loud	<input type="checkbox"/> Laughter																						
	<input type="checkbox"/> Crying	<input type="checkbox"/> Normal	<input type="checkbox"/> Distinct	<input type="checkbox"/> Slurred																						
	<input type="checkbox"/> Nasal	<input type="checkbox"/> Stutter	<input type="checkbox"/> Lisp	<input type="checkbox"/> Raspy																						
<input type="checkbox"/> Deep	<input type="checkbox"/> Ragged	<input type="checkbox"/> Clearing throat	<input type="checkbox"/> Deep breathing																							
<input type="checkbox"/> Cracking	<input type="checkbox"/> Disguised	<input type="checkbox"/> Accent	<input type="checkbox"/> Familiar																							
If familiar, who did it sound like:																										
<b>NOTES</b>																										
		Page:																								


**Report call immediately to your supervisor, corporate security, or administrative services.**

11.5 Stakeholder Forms

Stakeholder Contact Record

<b>DETAILS</b>	Incident:						
	Date:						
	Time (0-2400 hrs):				Time Zone:		
	Completed by:				Response Team Position:		
<b>STAKEHOLDER CONTACT RECORD</b>	<b>Resident ID</b>	<b>Name</b>	<b>Shelter in Place or Evacuate</b>	<b>Number of People</b>		<b>Assistance or Transportation Required</b>	<b>Comments</b>
				<b>Inside</b>	<b>Outside</b>		
						Page:	

Notice of Evacuation




**Notice of Evacuation**  
for  
\_\_\_\_\_  
(Location)

\_\_\_\_\_(Company) has experienced a \_\_\_\_\_ at the above mentioned facility, which has created an emergency in the area.  
As a safety precaution we have implemented our Emergency Response Plan. Please proceed immediately out of the area by the most direct route.  
To ensure your safety please check-in with our Reception Centre Representative at the \_\_\_\_\_(Reception Centre) of \_\_\_\_\_(City), \_\_\_\_\_(Phone).

If you have access to a telephone please call our Evacuation Team Leader immediately at \_\_\_\_\_(Phone).

\_\_\_\_\_(Company)Representatives have secured the hazardous area with road blocks. If you have any questions or concerns contact our head office at \_\_\_\_\_.




**Notice of Evacuation**  
for  
\_\_\_\_\_  
(Location)

\_\_\_\_\_(Company) has experienced a \_\_\_\_\_ at the above mentioned facility, which has created an emergency in the area.  
As a safety precaution we have implemented our Emergency Response Plan. Please proceed immediately out of the area by the most direct route.  
To ensure your safety please check-in with our Reception Centre Representative at the \_\_\_\_\_(Reception Centre) of \_\_\_\_\_(City), \_\_\_\_\_(Phone).

If you have access to a telephone please call our Evacuation Team Leader immediately at \_\_\_\_\_(Phone).

\_\_\_\_\_(Company)Representatives have secured the hazardous area with road blocks. If you have any questions or concerns contact our head office at \_\_\_\_\_.



**Notice of Evacuation**  
for  
\_\_\_\_\_  
(Location)

\_\_\_\_\_(Company) has experienced a \_\_\_\_\_ at the above mentioned facility, which has created an emergency in the area.  
As a safety precaution we have implemented our Emergency Response Plan. Please proceed immediately out of the area by the most direct route.  
To ensure your safety please check-in with our Reception Centre Representative at the \_\_\_\_\_(Reception Centre) of \_\_\_\_\_(City), \_\_\_\_\_(Phone).

If you have access to a telephone please call our Evacuation Team Leader immediately at \_\_\_\_\_(Phone).

\_\_\_\_\_(Company)Representatives have secured the hazardous area with road blocks. If you have any questions or concerns contact our head office at \_\_\_\_\_.

Reception Centre Registration Form (to be filled out by evacuees)

<b>DETAILS</b>	Incident:					
	Date:					
	Time (0-2400 hrs):				Time Zone:	
	Completed by:					
<b>EVACUEE INFORMATION</b>	Last Name		First Name		Middle Initial:	
	Sex:	Age:	Address:			
	City:		Province:		Phone Number:	
<b>EVACUATED FAMILY MEMBERS</b>	<b>First Name</b>	<b>Middle Initial</b>	<b>Last Name</b>	<b>Relationship to above</b>	<b>Gender</b>	<b>Age</b>
<b>ALTERNATE CONTACT INFO</b>						
<b>SPECIAL MEDICAL NEEDS</b>						
<b>ADDITIONAL INFO</b>						
<b>CHECK IN/OUT</b>	Arrival Time:				Departure Time:	

*Evacuee Expense Claim Form*

<b>DETAILS</b>	Incident:		
	Date:		
<b>EVACUEE INFORMATION</b>	Last Name	First Name	Middle Initial:
	Address:		Phone Number:
	City:	Province:	Postal Code:
	Location of Residence, Business, etc.		
<b>EXPENSES</b>	Accommodation:	\$	Details:
	Meals	\$	Details:
	Other Reasonable Expenses:	\$	Details:
	Other:	\$	Details:
	Other:	\$	Details:
	Other:	\$	Details:
		<b>Total:</b>	
	Evacuee Signature:		
<b>ADMINISTRATION</b>	Company Contact:	Company Phone Number:	
	Approved by:		

11.6 Media Forms

Preliminary Media Statement

Date:(YY/MM/DD)	Responder Name:
Responder Position:	Responder Phone No.:

**This is the information I can give you so far:**

At \_\_\_\_\_ (time - 0-2400 hrs) \_\_\_\_\_ on (date),  
a(n) \_\_\_\_\_ (fire, explosion, gas release, spill) occurred at the Company's  
\_\_\_\_\_ (location name) site, located \_\_\_\_\_ (distance) kilometres  
\_\_\_\_\_ (east / west / north / south) of \_\_\_\_\_(nearest town or city).

Presently, \_\_\_\_\_ (number of personnel) workers are being treated for injuries. The names and condition of the injured cannot be released until their families have been contacted.

The \_\_\_\_\_ (well site, plant, pipeline, office, drilling location) has been  
\_\_\_\_\_ (shutdown, isolated, or is still flowing) .

Company staff have been activated and are directing emergency response procedures to protect the public, our workers and the environment.

The cause of the \_\_\_\_\_ (fire, explosion, gas release, spill) is not yet known and no estimate of damage is available. As information becomes available, news releases will be issued from the Information Officer.

Any further inquiries should be directed to the Information Officer, who will issue a press release at a later time.

Contact:

\_\_\_\_\_ (Name): \_\_\_\_\_ (Phone)

Note: Only the Information Officer designated by the EOC Director is to provide any specific information to the public or the media.







## 12.0 APPENDIX

### 12.1 Properties of Hydrogen Sulphide (H<sub>2</sub>S)

H<sub>2</sub>S gas (also commonly referred to as sour gas) is naturally occurring, colourless, flammable, and toxic and is slightly heavier than air. At very low concentrations, it has an offensive odour (similar to rotten eggs), but at higher concentrations or with prolonged exposure it deadens the sense of smell. Concentrations of H<sub>2</sub>S are generally measured in parts per million (ppm). 1 ppm means that there is one part of H<sub>2</sub>S gas in one million parts of air (1% H<sub>2</sub>S gas concentration equals 10,000 ppm). It affects people differently depending on concentration and length of exposure.

Concentration (ppm)	Health Effects
0.01 - 0.3	Odour threshold
1-20	Offensive odour, possible nausea, tearing of the eyes or headaches with prolonged exposure
20-50	Nose, throat and lung irritation; digestive upset and loss of appetite; sense of smell starts to become fatigued; acute conjunctivitis may occur (pain, tearing and light sensitivity)
100-200	Severe nose, throat and lung irritation; ability to smell odour completely disappears.
250-500	Pulmonary edema (buildup of fluid in the lungs)
500	Severe lung irritation, excitement, headache, dizziness, staggering, sudden collapse (knockdown), unconsciousness and death within a few hours, loss of memory for the period of exposure
500-1000	Respiratory paralysis, irregular heartbeat, collapse and death without rescue.
>1000	Rapid collapse and death

### 12.2 Properties of Sulphur Dioxide (SO<sub>2</sub>)

SO<sub>2</sub> gas is a colourless, non-flammable, non-explosive gas, and has a pungent odour such as a burning match. SO<sub>2</sub> is a by-product from the combustion of hydrogen sulphide and would only be present if the source of H<sub>2</sub>S was ignited.


In its normal state SO<sub>2</sub> is heavier than air, however during the combustion process, the heat from the fire will carry the SO<sub>2</sub> and smoke upwards resulting in rapid dispersion and low concentration values.

Toxicity Information	
Concentration (ppm)	Effects
2	<ul style="list-style-type: none"> <li>8-hour exposure limit</li> </ul>
3 – 5	<ul style="list-style-type: none"> <li>Odour detection threshold</li> </ul>
5	<ul style="list-style-type: none"> <li>15-minute exposure limit</li> </ul>
6 – 50	<ul style="list-style-type: none"> <li>Exposure for 5 to 15 minutes irritates the eyes and may irritate the respiratory system (e.g. choking and coughing)</li> <li>Possible nosebleed under extended exposure</li> </ul>
50 – 100	<ul style="list-style-type: none"> <li>Irritation increase may become unbearable and vision impossible</li> </ul>
Over 100	<ul style="list-style-type: none"> <li>Immediately dangerous to life</li> <li>Immediate feeling of suffocation</li> </ul>

### 12.3 Legal Survey Description (LSD) Reference Tool (Alberta)

- Each township (6 mile x 6 mile) is divided into 36 sections (1 mile x 1 mile)
- Each section is divided into 16 legal sub-divisions (LSD)
- Each section is divided into four quarters (N.W., N.E., S.W., and S.E.)

The numbering of sections and LSDs is shown below:



- Townships increase in number from South to North starting at the Canada - USA border.
- Ranges increase in number from East to West within a Meridian. A Range is one Township wide (6 miles).
- Meridians run from the North Pole to the South Pole and are spaced every four degrees. The principal Meridian in Canada originates in Central Manitoba and increases West or East from there.
- Legal land description is listed in the following order:

	LSD	Section	Township	Range	Meridian
Example:	02	01	38	09	West of the 4th


## 12.4 National Topographic System (NTS) Reference Tool

Based on the national topographic series map numbering system terms as follows:

- Primary Quadrangle:** A 4° x 8° in geodetic latitude and longitude (e.g. Primary Quadrangle 93).
- Lettered Quadrangle:** 1/16 of a Primary Quadrangle 1° in latitude by 2° in longitude, lettered A to P (e.g. 93-P).
- N.T.S. Grid Area:** 1/16 of Lettered Quadrangle 15' in latitude by 30' in longitude, numbered 1 to 16 (e.g. 93-P-9).
- Block:** An area 1/12 of an NTS map 5' in latitude by 7'30" in longitude, lettered A to L (e.g. H/93-P-9).
- Unit:** A block is divided into 100 numbered parts, 10 to a side, each part called a unit and has a latitudinal extent of 30" and longitudinal extent of 45" (e.g. 29-H/93-P-9).
- Quarter Section:** ¼ of a Unit, lettered a to d (e.g. a-29-H/93-P-9).

The area contained by a unit decreases to the north from 86.016 HA at 48° latitude to 64.782 HA at 60° latitude.

Example: a-29-H/94-P-9



### 12.5 HVP - Proposed EPZ Distances for Selected Diameters

Pipeline Size		Ethane, Propane, and Butane Mix (no Ethylene)	Ethylene
3"	88.9 mm	250 m	250 m
4"	114.3 mm	300 m	350 m
6"	168.3 mm	500 m	550 m
8"	219.1 mm	700 m	750 m
10"	273.1 mm	900 m	1000 m
12"	323.9 mm	1100 m	1200 m
16"	403.4 mm	1600 m	1600 m

CAPP Companion Planning Guide to ERCB Directive 071, July 2008

### 12.6 Conversion Table

<b>H<sub>2</sub>S</b>	10 moles	1%	10,000 ppm	14,000 mg/m <sup>3</sup>
<b>Pressure</b>	1 PSI	6.895 kPa	1 kPa	0.15 PSI
<b>Length</b>	1 inch	2.54 cm	1 cm	0.39 inches
	1 foot	0.31 m	1 m	3.281 feet
	1 yard	0.914 m	1 m	1.09 yards
	1 mile	1.609 km	1 km	0.62 miles
	1 mile	5280 feet	-	-
	1 mile	1760 yards	-	-
	1 km	1000 m		
<b>Volume</b>	1 litre	0.22 gallon (imp)	1 gallon (imp)	4.546 litres
	1 barrel	42 gallon (US)	1 gallon (US)	0.024 barrels
	1 barrel	0.16 cubic metres	1 cubic metre	6.29 barrels
	1 cubic metre	35.31 cubic ft	1 cubic ft	0.028 cubic metres
	1 cubic yard	0.76 cubic metre	1 cubic metre	1.31 cubic yards
	1 gallon (US)	0.83 gallon (imp)	1 gallon (imp)	1.2 gallon (US)
	1 gallon (US)	3.785 litres	1 litre	0.26 gallon (US)
	1 sq mile	2.59 sq km	1 sq km	0.39 sq miles
	1 cu inch	16.39 cu cm	1 cu cm	0.06 cu inches
<b>Weight</b>	1 pound	0.454 kg	1 kg	2.2 pounds
	1 ton	2000 pounds	1 pound	0.0005 tons
	1 ton	907 kg	-	-
	1 tonne	1.102 tons	1 ton	0.907 tonnes
<b>Area</b>	1 acre	.404 hectare	1 hectare	2.471 acres
	1 section	640 acres	-	-
	¼ section	160 acres	-	-
	1 LSD	40 acres	-	-
<b>Temperature</b>	0° Celsius	32° Fahrenheit	0° Fahrenheit	-18° Celsius
<b>Other</b>	1 dek	10 <sup>3</sup> m <sup>3</sup>	-	-

## 12.7 NATO Phonetic Alphabet

Letter	Code word
A	Alpha
B	Bravo
C	Charlie
D	Delta
E	Echo
F	Foxtrot
G	Golf
H	Hotel
I	India
J	Juliet
K	Kilo
L	Lima
M	Mike

Letter	Code word
N	November
O	Oscar
P	Papa
Q	Quebec
R	Romeo
S	Sierra
T	Tango
U	Uniform
V	Victor
W	Whiskey
X	X-ray
Y	Yankee
Z	Zulu
- (hyphen)	Dash

## 12.8 Glossary

$10^3\text{m}^3$ ( $\text{e}^3\text{m}^3$ ):	1000 cubic metres per day.
Absolute Open Flow:	The rate at which a well would produce against a zero sandface back pressure.
Adjacent to:	For the purpose of this plan, refers to the immediate 25 metres.
Adverse Effect:	The impairment of or damage to the environment, human health or safety, or property.
Agency:	A division of government with a specific function offering a particular kind of assistance. Agencies are defined as jurisdictional (having statutory responsibility for incident management) or as assisting or cooperating (providing resources or other assistance).
Air Quality Monitoring:	The measurement of atmospheric concentrations of a gas such as $\text{H}_2\text{S}$ or $\text{SO}_2$ .
ALS	An abbreviation for Advance Life Support.
Auto-Ignition Temperature:	All NGL products are flammable and will flash at extremely low temperatures. An open flame or spark is not necessary to cause ignition. Any hot surface which exceeds the auto-ignition temperature of a product can cause a fire if the vapours reaching the hot surface are within their flammable range.
Battery:	A group of tanks in the gathering system, they receive oil directly from the wells.
bbbl:	An abbreviation for barrel.
BLS	An abbreviation for Basic Life Support.

---

Boiling Liquid Expanding Vapour Explosion (BLEVE):	A boiling liquid expanding vapour explosion is usually associated with natural gas liquids and high vapour pressure liquids. This is a type of explosion that can occur when a vessel containing a pressurized liquid is ruptured.
Booster Pump:	A small pump that pulls product from the source of supply and pumps it into the suction, or input of the main pump unit.
Businesses:	Industrial operators, retail suppliers, service providers, trappers, loggers and other entities who normally operate within the EPZ, but do not necessarily reside in the EPZ.
Camp:	A geographical site equipped and staffed to provide sleeping, food, water, and sanitary services to personnel.
Ceiling – Recommended Exposure Limit:	The concentration that should not be exceeded during any part of the working exposure. An employee’s exposure to a hazardous substance shall at no time exceed the ceiling value.
CER	Canada Energy Regulator
Chain of Command:	A series of command, control, executive, or management positions in hierarchical order of authority.
Command Staff:	In an incident management organization, the Command Staff consists of the Incident Command and the special staff positions of Officer, Chief and other positions as required, who report directly to the Incident Commander. They may have assistants as needed.
Condensate:	The liquid formed by the condensation of a vapour or gas; specifically, the hydrocarbon liquid separated from natural gas because of changes in temperature and pressure when the gas from the reservoir was delivered to the surface separators.
Control Valve:	A valve that will automatically maintain a predetermined pressure upstream or downstream of the valve or will maintain a controlled flow rate through the valve.
Emergency Operations Centre (EOC):	Focal point for the communication of support functions provided by Head Office personnel and (potentially) contract specialists. They should provide advice, direction and logistical support to the Site Command personnel.
Downstream:	With reference to a pumping station, indicates the discharge side of that station.
Emergency Planning Zone (EPZ):	An EPZ is a geographical area surrounding a well, pipeline, or facility containing hazardous product that requires specific emergency response planning by the licensee.
Emergency Response Plan (ERP):	A comprehensive plan to protect the public that includes criteria for assessing an emergency situation and procedures for mobilizing response personnel and agencies and establishing communication and coordination among the parties.

---

Emergency Shutdown Valve (ESD):	A valve that blocks the passage of material from both directions and can automatically close when the amount of material passing through the valve exceeding allowable limits.
ERAC:	An abbreviation for Emergency Response Assistance Canada. A not-for-profit emergency preparedness and response organization who develops, implements and responds to Emergency Response Assistance Plans (ERAPs) for more than 300 Plan Participant Members of ERAC.
ERAP:	An ERAP or Emergency Response Assistance Plan is a plan that describes what is to be done in the event of a transportation accident involving certain higher risk dangerous goods. The ERAP is required by the Transportation of Dangerous Goods Regulations (TDGR) for dangerous goods that require special expertise and response equipment to respond to an incident. The plan is intended to assist local emergency responders by providing them with technical experts and specially trained and equipped emergency response personnel at the scene of an incident.
Explosive Limit:	Each gaseous hydrocarbon substance has a minimum lower explosive limit (LEL) and a maximum upper explosive limit (UEL) percentage in the air below or above which combustion will not take place. Explosive limit and flammability limit are used interchangeable. The terms 'too lean' and 'too rich' are used for levels outside of the explosive range.
Facility:	Any building, structure, installation, equipment or appurtenance over which the Regulatory Authority has jurisdiction and that is connected to or associated with the recovery, development, production, handling, processing, treatment or disposal of hydrocarbon-based resources or any associated substances or wastes. This term does not refer to or include wells or pipelines.
Field Separator:	A vessel in the oil and gas field for separating gas, hydrocarbon liquid, and water from each other.
Flammability Limit:	<p>The lower flammability limit is the minimum percentage volume of a combustible gas in an air mixture that will support combustion at certain pressure and temperature conditions.</p> <p>The higher flammability limit is the maximum percentage volume of a combustible gas in an air mixture that will support combustion at certain pressure and temperature conditions.</p> <p>Note: Data for flammability limits is often published for standard atmospheric and temperature conditions. Refer to the Safety Data Sheet (SDS) for specific product information.</p>
Flaring/Venting:	The controlled burning (flare) or release (vent) of natural gas that can't be processed for sale or use because of technical or economic reasons.

---

Flash Point:	The lowest temperature at which vapours over a volatile combustible substance will ignite when exposed to an external source of ignition (and will continue to burn after the source is removed).
Flexibility:	A principle of ICS that provides a consistent and adjustable framework within which government and private entities at all levels can work together to manage domestic incidents, regardless of their cause, size, location, or complexity. This flexibility applies across all phases of the incident management: prevention, preparedness, response, recovery, and mitigation.
Flow Rate:	The speed in which the product is flowing, computed in cubic metres per second (m <sup>3</sup> /s).
Gathering System:	The network of pipelines, pumps, tanks and other equipment that carry oil and gas to a processing plant or to other separation equipment.
Government Emergency Operations Centre (GEOC):	An operations centre with the capacity to accommodate representatives from each government department.
Hazard:	A situation with potential to cause harm to persons, property, or the environment.
High Vapour Pressure (HVP):	HVP products have a vapour pressure greater than 240 kPa at a temperature of 38° C (34.8 psig at 100 °F). They include ethane, propane, butane, and pentanes plus either as individual products or as a mixture. A leak from a vessel or pipe containing HVP products can result in a BLEVE.
High Vapour Pressure (HVP) Pipeline:	A pipeline system conveying hydrocarbons mixtures or hydrocarbon mixtures in the liquid or quasi-liquid state with a vapour pressure greater than 100 kPa absolute at 38°C, as determined using the Reid method. Some examples are liquid ethane, ethylene, propane, butanes, and pentanes plus.
Hazard Planning Zone (HPZ):	<p>Hazard planning distances are used to identify a geographical area (a hazard planning zone) within which persons, property or the environment may be affected by an emergency. The combined geographic areas of hazard planning zones are used by the applicant or permit holder to identify an EPZ where immediate response actions are required in the event of an emergency.</p> <p>The HPZ has been determined by CANUTEC as the area that requires immediate precautionary measures whereby the spill or leak is to be isolated in all directions for the specified distance.</p>
Hydrogen Sulphide (H <sub>2</sub> S):	A naturally occurring gas found in a variety of geological formations and also formed by the natural decomposition of organic matter in the absence of oxygen. H <sub>2</sub> S is colourless, heavier than air, and extremely toxic. In small concentrations it has a rotten egg smell and causes eye and throat irritation.

---

Hydrogen Sulphide (H <sub>2</sub> S) Release Rate:	The rate at which the sour gas escapes into the atmosphere is calculated for sour gas wells. The rate is usually given in cubic metres per second (m <sup>3</sup> /s). The size of the EPZ is calculated based on the H <sub>2</sub> S release rate.
Hydrogen Sulphide (H <sub>2</sub> S) Release Volume:	The volume of sour gas that escapes into the atmosphere is calculated for facilities that have a defined retention volume. It is usually defined in cubic metres (m <sup>3</sup> ). EPZ sizes are calculated using the volume of gas that may be released from a facility.
Ignition Team:	A two person team assigned the responsibility of igniting a sour gas plume.
Incident:	An unexpected occurrence or event that requires action by emergency response personnel to prevent or minimize the impacts on the safety and health of people as well as on property and the environment.
Incident Action Plan (IAP):	An Incident Action Plan formally documents incident goals, operations period objectives and the response strategy defined by incident command during emergency response planning.
Incident Classification:	A system that examines the risk level to members of the public following an incident and assigns a level of emergency based on the consequence of the incident and the likelihood of the incident escalating.
Incident Command System (ICS):	The incident command system is a standardized response protocol. It is a combination of facilities, equipment, personnel, procedures and communications operating with a common organization structure with responsibility for the management of assigned resources to effectively accomplish stated objectives pertaining to the incident.
Incident Commander:	The Incident Commander role should be assigned to the most experienced company supervisor or representative at the incident site. The Incident Commander has the responsibility to manage the on-site activities and the implementation of a safe and effective tactical response.
Incident Objectives:	Statements of guidance and direction necessary for selecting the appropriate strategy and tactical direction of resources. Incident objectives are based on realistic expectations of what can be accomplished when all allocated resources have been effectively deployed. Incident objectives must be achievable and measurable, yet flexible enough to allow strategic and tactical alternatives.
Joint Venture Partner:	Two companies working together to combine resources to complete a capital project.
Kick:	A situation where the formation pressure exceeds the static pressure in the well bore allowing formation fluid to enter.
Km:	An abbreviation for kilometre; a unit of length in the metric system, equal to one thousand metres.

---

kPa:	An abbreviation for kilopascal; it is a measure of force per unit area, defined as one newton per square metre. One kilopascal is about 1% of atmospheric pressure.
Leader:	The ICS title for an individual responsible for a Task Force, Strike Team, or functional unit.
Liaise:	A form of communication for establishing and maintaining mutual understanding and cooperation.
Licensee:	A term used to designate the responsible duty holder (e.g. licensee, operator, company, and applicant).
Liquefied Petroleum Gas (LPG):	Mixture of heavier, gaseous hydrocarbons (butane and propane), liquefied as a portable source of energy.
Local Authority:	Council of a city, town, village, or municipal district. An improvement district or special area. The Settlement Council or a settlement under the Métis Settlements Act. The Band Council of an Indian Band if an agreement has been entered into with the Government of Canada in which it is agreed that the Band Council is a local authority for the purposes of the Disaster Services Act.
Local State of Emergency:	A local state of emergency is authorized for a limited period of time and limited geographical area by members of the municipal authority (city, town, municipal district or county). A local state of emergency grants extraordinary powers to the authorities such as forcibly removing public from an area or preventing the public from entry into a designated area.
Logistics:	Providing resources, material support and other services to support incident management.
Lower Explosive/Flammable Limit (LEL/LFL):	The lowest concentration of gas of vapour (per cent by volume in air) that burns or explodes if an ignition source is present at ambient temperatures.
m <sup>3</sup> :	An abbreviation for cubic metres.
MAWP:	An abbreviation for “maximum actual or allowable working pressure”.
Maximum Operating Pressure (MOP):	The maximum licensed operating pressure for a vessel or pipeline.
mcf:	An abbreviation for one thousand cubic feet of gas.
Mercaptans:	A sulphur containing organic compound with the general formula RSH where R is any radical, especially ethyl mercaptan, C <sub>2</sub> H <sub>5</sub> SH.
Mmcf:	An abbreviation for one million cubic feet of gas.

---

mSv/h	<p>The sievert (symbol: Sv) is a derived unit of ionizing radiation dose in the International System of Units (SI). It is a measure of the health effect of low levels of ionizing radiation on the human body.</p> <p>In the SI system, a millisievert (mSv) is defined as "the average accumulated background radiation dose to an individual for 1 year, exclusive of radon, in the United States." 1 mSv is the dose produced by exposure to 1 milligray (mG) of radiation.</p>
Mobile Air Monitoring Unit:	Personnel with sophisticated portable equipment capable of tracking substances such as H <sub>2</sub> S or SO <sub>2</sub> and of measuring very low (ppb) atmospheric concentrations.
MOU:	An abbreviation for Memorandum of Understanding.
Multi-Agency Incident:	An incident where one or more agencies assist a jurisdictional agency or agencies. May be single or Unified Command.
Municipal Emergency Operations Centre (MEOC):	The centre from which responsible municipal officials manage and support operations within their jurisdiction. The MEOC personnel will formulate protective actions and provide public information. The centre should have adequate workspace, maps, status boards, and communications capability.
Mutual Aid Understanding:	An understanding between two or more public and (or) private parties, such as oil and gas companies, service companies, and local authorities that defines each party's commitment to provide aid and support during an incident.
Natural Gas Liquid (NGL):	These are hydrocarbons liquefied under pressure in field facilities or in gas processing plants. Natural gas liquids include ethane, propane, butanes and pentanes plus, and normally occur as a mixture of these compounds.
Notice to Airmen (NOTAM):	This is a notice issued by Transport Canada. A NOTAM restricts access to airspace in a defined area. NOTAMs are generally issued through the nearest flight service station.
Odour Complaint:	A member of the public has submitted either a written or verbal complaint of an odour problem due to a gas release or venting incident.
Off-Site:	The area beyond the asset property boundary.
OHS:	An abbreviation for Occupational Health and Safety.
Oil Spill Containment and Recovery Unit (OSCAR):	A trailer or truck style unit which contains recovery equipment to assist in spill containment and recovery.
On-Site:	The area within the asset property boundary.
On-Site Command Post (OSCP):	An emergency operations centre established in the immediate vicinity of the incident to provide immediate and direct response to the emergency and initially staffed by company personnel.
Operating Personnel:	Refers to the people working in a given field area.

---

---

Operations Section:	The section responsible for all tactical incident operations. In ICS, it normally includes subordinate branches, divisions, and/or groups.
Parts Per Million (ppm):	The unit for measuring the concentration of a particular substance equal to one (1) unit combined with 999,999 other units.
Personal Consultation:	Consultation through face-to-face visits or telephone conversations with identified parties and providing the required information packages.
Personal Protective Equipment (PPE):	Safety equipment used for an individual's protection.
Plain Language:	Common terms and definitions that can be understood by individuals for all responder disciplines. The intent of plain language is to ensure the clear and accurate communication of information during the incident.
Planning Section:	Responsible for the collection, evaluation, and dissemination of operational information related to the incident, and for the preparation and for the documentation of the Incident Action Plan. This section also maintains information on the current and forecasted situation and on the status of resources assigned to the incident.
Plume:	An elongated mobile column of gas or smoke. The term plume is often used to describe the area in which hazardous gas, such as sour gas, disperses into the atmosphere from a facility, well or pipeline. Eventually gases will dilute (with distance away from the source) to concentrations that are not considered hazardous. Plumes are generally elongated shapes that are oriented downwind of the point of the gas release.
ppb:	An abbreviation for parts per billion.
Preparedness:	The range of deliberate, critical tasks and activities necessary to build, sustain, and improve the operational capability to prevent, protect against, respond to, and recover from domestic incidents. Preparedness is a continuous process. Preparedness involves efforts at all levels of government and between government, the private sector and non-government organizations to identify threats and determine vulnerabilities and required resources. Preparedness is operationally focused on establishing guidelines, protocols, and standards for planning, training and exercises, personnel qualification and certification, equipment certification, and publication management.
Public:	Individuals (or groups of people) who may be impacted by an emergency. Example: employees, contractors, nearby residents, emergency response organizations, regulatory agencies, the media, appointed or elected officials, visitors, customers, etc.
Pump Unit:	Consists of an electric motor or engine connected to a centrifugal pump, either directly as in the case of constant speed units, or through a fluid drive, as in the variable speed pump units.

---

Reception Centre:	A centre established to register evacuees for emergency shelter, to assess their needs, and, if temporary shelter is not required because evacuees will stay elsewhere, to ascertain where they can be contacted.
Regional Emergency Operations Centre (REOC):	An operations centre established in a suitable off-site location near the emergency to manage the large-scale aspects of the emergency response. It is manned jointly by government and industry personnel.
Regulatory Authority:	The local petroleum Regulatory Authority will participate in the emergency response to all situations involving or threatening oilfield wells, production facilities, or pipelines.
Relief System:	The system for safely relieving excess pressure to avoid exceeding equipment design pressure.
Residence:	A dwelling that is occupied full time or part time.
Response:	Activities that address the short term, direct effects of an incident. Response includes immediate actions to save lives, protect property, and meet basic human needs. Response also includes the execution of emergency operations plans and incident mitigation activities designed to limit the loss of life, personal injury, property damage, and other unfavourable outcomes.
Roadblock Team:	Operator or Contract personnel responsible for controlling access to the EPZ.
Rover:	Individual responsible for assisting the evacuation of the Emergency Planning Zone.
Safety Officer:	A member of the Command Staff responsible for monitoring and assessing safety hazards or unsafe situations and for developing measures for ensuring personnel safety.
SCADA:	Acronym for Supervisory Control and Data Acquisition.
SCBA:	Acronym for Self Contained Breathing Apparatus.
Serious Injury:	Can be defined as any of the following: <ul style="list-style-type: none"><li>• An injury that results in death.</li><li>• A fracture or crush of a major bone.</li><li>• Penetrating injury to eye, head, neck, chest, abdomen or groin.</li><li>• Amputation other than a portion of a finger or toe.</li><li>• Severe haemorrhaging - internal or external.</li><li>• Third degree burn or any other degree burn with complications.</li><li>• Unconsciousness.</li><li>• An injury that results in paralysis (permanent loss of function or sense).</li></ul>
SDS:	Acronym for Safety Data Sheets. A Safety Data Sheet (SDS) is a document that contains information on the potential hazards (health, fire, reactivity and environmental) and how to work safely with a chemical product.

---

Shelter in Place:	The use of a structure and its indoor atmosphere to temporarily separate individuals from a hazardous outdoor atmosphere. It entails closing all household doors, windows and vents and taking immediate shelter in a readily accessible location that puts as much indoor air and mass between the individual and the hazardous outside air, such as a basement or centrally located medium to small room, and trying to make it as airtight as possible by shutting off all ventilation/HVAC systems and extensively sealing the shelter's doors and windows from all outside air contaminants with damp towels, or if available, plastic sheeting and adhesive tape.
SITREP:	An abbreviation for Situation Report.
Solution Gas:	Gas that originates from the liquid phase in an oil reservoir.
Sour:	Liquids and gases are said to be "sour" if they contain hydrogen sulphide (H <sub>2</sub> S), carbon dioxide (CO <sub>2</sub> ), and/or mercaptans over a specified level.
Sour Gas:	Natural gas, including solution gas, containing hydrogen sulphide (H <sub>2</sub> S).
Sour Gas Facility:	Any facility that produces, processes, or transports sour gas.
Span of Control:	The number of individuals a supervisor is responsible for, usually expressed as a ratio of supervisors to individuals. Under ICS an appropriate span of control is between 1:3 and 1:7 with 1:5 being established as optimum.
Spill:	Means a release or discharge of a substance into the natural environment.
Special Needs:	Those persons for whom early response actions must be taken because they require evacuation assistance, requested early notification, do not have telephones, require transportation assistance, have a language or comprehension barrier, or have specific medical needs. Special needs also include those who decline to give information during the public consultation process and any residences or businesses where contact cannot be made.
Staging Area:	Location established where the resources can be placed while awaiting a tactical assignment. The Operations Section manages Staging Areas.
Stakeholders:	Industry activities often affect surrounding areas and populations. People with an interest in these activities are considered stakeholders. They may include nearby landowners, municipalities, Indigenous communities, recreational land users, other industries, environmental groups, governments and regulators.
Substance:	Any matter that is capable of being dispersed in the environment and that is capable of causing transformations in the environment.
Sulphur:	A yellow, non-metallic chemical element. In its elemental state, it has a crystalline or amorphous form. In many gas streams, sulphur may be found in volatile sulphur compounds, e.g. hydrogen sulphide,

---

	sulphur oxides, mercaptans, carbonyl sulphide. Reduction of their concentration levels is necessary for corrosion control and, in many cases, necessary for health and safety reasons.
Sulphur Dioxide (SO <sub>2</sub> ):	A colorless, water soluble, suffocating gas formed by burning sulphur in air; also used in the manufacture of sulphuric acid. SO <sub>2</sub> has a pungent smell similar to a burning match. SO <sub>2</sub> is extremely toxic at higher concentrations. The molecular weight of SO <sub>2</sub> is heavier than air; however, typical releases are related to combustion, which makes the gaseous mixture lighter than air (buoyant).
Surface Development:	Dwellings that are occupied full time or part time publicly used development, public facilities, including campgrounds and places of business, and any other surface development where the public may gather on a regular basis. Surface development includes residences immediately adjacent to the EPZ and those from which dwellers are required to egress through the EPZ.
Sump:	An underground tank located at each pump station used to catch products that leak through valves, meters, pump units, seal housing, etc.
Sweet:	Gas containing essentially no objectionable sulphur compounds. Also, the term sweet is used to describe treated gas leaving a sweetening unit.
Tabletop Exercise:	An informal exercise generally used to review resource allocation, roles and procedures for emergency response. It also serves to orientate new personnel to emergency operations without the stress and time constraints of a full scale exercise.
Technical Specialist:	Personnel with special skills that can be used anywhere within the ICS organization.
Telephoner(s):	Personnel assigned the responsibility to contact the area residents and/or users in the event of an Emergency.
Transient:	A person who is temporarily in the response zones (examples: camper, cross-country skier, and hunter).
Trapper:	Holder of a licensed and registered trapline for the purpose of hunting and trapping fur-bearing animals.
Uncontrolled Flow:	A release of product that the licensee cannot shut off at the licensee's discretion.
Unified Command:	The Unified Command is a structure that brings together the "Incident Commanders" of all major organizations involved in the incident in order to coordinate an effective response while at the same time carrying out their own jurisdictional responsibilities. The Unified Command links the organizations responding to the incident and provides a forum for these entities to make consensus decisions.
Urban Center:	A city, town, new town, village, summer village, hamlet, with no fewer than 50 separate buildings, each of which must be an occupied

---

	dwelling or any similar development the AER may designate as an urban centre.
Vapour Density:	A measure of the weight of the gas compared to air (air = 1).
Vapour Pressure:	The pressure exerted by the vapour when the rate of evaporation is equal to the rate of condensation of the vapour. All NGL products have vapour pressure greater than atmospheric pressure air and therefore have to be kept under pressure or else they will vaporize.
Well Servicing:	The maintenance procedures performed on a producing or injecting well after the well has been completed and operations have commenced. Well servicing activities are generally conducted to maintain or enhance well productivity or injectivity.
Workovers:	The process of re-entering an existing well to perform remedial action that will restore or improve the productivity or injectivity of the target formation.